



24640

BLACK & VEATCH Waste Science, Inc.

400 Northridge Road, Suite 350, Atlanta, Georgia 30350, (404) 594-2500, Fax: (404) 587-2930

US EPA -- Region IV
Site Inspections
Work Assignment No. 12

BVWS Project 52012.329
August 10, 1994

Mr. Narindar Kumar
Chief, Site Assessment Section
U.S. Environmental Protection Agency
345 Courtland Street, NE
Atlanta, Georgia 30365

Subject: Draft Site Inspection Prioritization
Kennon (Genesco) Site
Brentwood, Williamson County, TN
EPA ID No. TND981473515

Dear Mr. Kumar:

Enclosed please find one copy of the Draft Site Inspection
Prioritization for Kennon (Genesco) Site in Brentwood, Williamson
County, Tennessee. If you have any questions, please contact
me at 404/643-2320.

Very truly yours,

BLACK & VEATCH Waste Science, Inc.

Paul Moisa for

Victor Blix
Project Manager

fw
Enclosure

cc: Doug Thompson, EPA PO, w/o enclosures
Deborah Davidson, EPA CO, w/o enclosures
Earl Bozeman, EPA WAM, w/o enclosures

REC'D

AUG 11 1994

W



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION IV

345 COURTLAND STREET, N.E.
ATLANTA, GEORGIA 30365

4WD-WPB

AUG 11 1994

Victor Blix
Black & Veatch Waste Science, Inc.
400 Northridge Road, Suite 350
Atlanta, GA 30350

RE: Site Inspection Prioritization

Site Name: Kennon (Genesco)

EPA ID#: TND981473515

Dear Mr. Blix:

I have reviewed the SIP report on the above referenced site and made the following decision:

- ☒ Report acceptable as is and will serve as final SIP for the site. Please send me an additional copy of the report and references.
- ☐ Site reconnaissance, additional documentation and/or HRS scoring scenarios required. See comments section for details.
- ☐ Field sampling is needed at this site. See comments section for details.
- ☐ Report needs revisions as indicated in comments section. Please revise and submit final no later than ____/____/____.

Comments:

Send 2 copies of the final SIP.

If you have any questions regarding this matter, please contact me at 347-5059 ext. 6149.

Sincerely,

Robert P. Mory
Site Assessment Manager

cc:

Earl Bozeman, WAM
Doug Thompson, PO
Debbie Davidson, CO

C-92-6-4-11

U.S. Environmental Protection Agency
Kennon (Genesco) Site
Work Assignment 12

July 21, 1994

Mr. Narindar Kumar, Chief
Site Assessment Section
U.S. Environmental Protection Agency
345 Courtland Street, N.E.
Atlanta, Georgia 30365

Subject: Site Inspection Prioritization
Kennon (Genesco) Site
Brentwood, Williamson County, Tennessee
EPA ID TND981473515

WJH: C-92-6-4-11

Dear Mr. Kumar:

Halliburton NUS Corporation has been tasked by BLACK & VEATCH Waste Science, Inc., under U.S. Environmental Protection Agency (EPA) Contract 68-W9-0055, to conduct a Site Inspection Prioritization at the Kennon (Genesco) Site in Brentwood, Williamson County, Tennessee. In accordance with the Kennon Site scope of work, a preliminary Hazard Ranking System (HRS) score was prepared to determine the need for future activities at the site.

The Kennon Site is located off Split Log Road in a rural area east of Brentwood in Williamson County, Tennessee (Refs. 1, 2). The geographic coordinates of the site are 35°57'22" north latitude and 86°46'27" west longitude (Refs. 2, 3). The 10-acre site is located on a 150-acre tract of farmland owned by Emmett and Rose Kennon. The site is currently undergoing remediation. Phosphate was mined on the farmland property between 1972 and 1974, and one pit was left unreclaimed. In 1978, this mine pit and four additional trenches were used for the disposal of industrial wastes, consisting of organic solvents, adhesives, and organic fillers from General Adhesives, which at that time was a division of Genesco, Inc. (Ref. 4, p. 1). These contaminants included acetone, methyl ethyl ketone, toluene, 1,1,1-trichloroethane, trichloroethylene, and various other organics (Ref. 1).

The site was discovered in 1985 when Genesco officials learned of the previous disposal activity and notified the Tennessee Department of Environment and Conservation (TDEC). The State began a sampling investigation of springs and wells in the area and learned that contamination had indeed spread to a nearby spring (the Hackett Spring), and to onsite monitoring wells (Ref. 4,

Mr. Narindar Kumar
U.S. Environmental Protection Agency
C-92-64-11
July 21, 1994 - page two

p. 1). They then instigated remedial action at the site. The first steps were to build a silt fence to prevent contaminated sediment from leaving the property and to provide an alternate water supply to residents in the area who used private wells as their potable water source. Genesco has cooperated with the State in all actions concerning this site (Ref. 4, p. 1).

At the present time, the site is still undergoing remediation. Genesco hired Geraghty and Miller to perform the remediation tasks. A subsurface drain was designed and installed in 1989 to intercept the flow of groundwater, and the water is treated by the City of Brentwood Sewer System. Large mechanical screens were used from June 1990 to September 1991 to separate semi-solid and solid adhesive wastes from the soils. Bioremediation is also presently being performed. The site is being remediated in accordance with TDEC Order 86-3013, issued March 5, 1986 (Ref. 4, p. 1).

A preliminary HRS score for the Kennon Site was calculated using the Site Inspection Worksheets. Pathways evaluated include groundwater migration, surface water migration, soil exposure, and air migration. A worst case scenario was used to determine a maximum potential score for the site. This score reflects a waste quantity of 10 based on 800 drums of material (Ref. 1). Maximum waste characteristic values were used for all pathways.

The City of Brentwood supplies potable water to the residents in the area of the Kennon site. As previously stated, some residents were using private wells as their water source but since work began at this site, water lines have been installed (Ref. 4, p. 1). The City of Brentwood obtains water from Metro Nashville and Harpeth Valley Utilities. Both systems obtain water from intakes on the Cumberland River (Ref. 5, p. 2).

Surface water from the site flows into an unnamed intermittent stream which is actually located on site. This stream flows approximately 0.5 mile southwest until it enters the Little Harpeth River. The Little Harpeth River flows south until it empties into Clovercroft Lake (Ref. 2). The Little Harpeth River is a small to moderate stream. Flow rates are unavailable for this water body. The surface water intakes on the Cumberland River are not connected with the surface water pathway of this site (Ref. 2). There are no endangered or threatened species along the surface water pathway (Ref. 6). The Little Harpeth River is used for recreational fishing, and Clovercroft Lake is used for both recreation and fishing (Ref. 7). A topographic analysis of the vicinity identifies no wetlands (Ref. 2). However, wetland maps for this area are currently unavailable.

The Kennon site is located in a rural portion of Williamson County. The nearest city is Brentwood, approximately 1.5 miles northwest of the site. There are no schools or day-care centers within 1 mile of the site. The nearest residence is approximately 0.5 mile to the northwest (Ref. 2). The population within a 4-mile radius of the site is approximately 19,317

Mr. Narindar Kumar
U.S. Environmental Protection Agency
C-92-6-4-11
July 21, 1994 - page three

persons, distributed as follows: 0.5 - 1 mile: 7 persons; 1 - 2 miles: 434 persons; 2 - 3 miles: 11,707 persons, 3 - 4 miles: 7,169 persons (Refs. 2, 8, 9). One threatened plant, the Price's potato-bean (Apios priceana), and one endangered plant, the leafy prairie clover (Dalea foliosa), have been identified in Williamson County (Ref. 6).

HRS SCORING SUMMARY


Sgw	=	0
Ssw	=	.04
Sso	=	0
Sa	=	.07

OVERALL SCORE = 0.04

Due to low targets and ongoing remedial work, no further action is recommended for the Kennon (Genesco) site.

Attached are additional references collected during this investigation. If you have any questions or comments, please contact Victor Blix at (404) 594-2500.

Very truly yours,



Teresa Sawyer
Project Manager

TS/gwb

Enclosures

cc: Philip A. Blackwell
File

REFERENCES

1. Potential Hazardous Waste Site, Site Inspection Report (EPA Form 2070-13) for the Kennon (Genesco) Site in Brentwood, Williamson County, Tennessee. Prepared by Thomas A. Moss, Tennessee Department of Health and Environment, Superfund Division, May 12, 1987.
2. U.S. Geological Survey, 7.5 minute series Topographic Quadrangle Maps of Tennessee: Franklin 1981, Nolensville 1957 (Photorevised (PR) 1979), Antioch 1968 (PR 1983), Oak Hill 1968 (PR 1983), scale 1:24,000.
3. Latitude and Longitude Calculation Worksheet #1 for the Kennon Site. Prepared by Teresa Sawyer, Halliburton NUS Corporation, June 7, 1994.
4. After-Action Report including Air Monitoring Program, Water Monitoring Program, and Site Security Program for the Kennon Site in Brentwood, Tennessee. Prepared by Mosley and Associates, Inc., January 1993. Revised December 1993.
5. Brenda Apple, Tennessee Department of Environment and Conservation, Superfund Division, Public Drinking Water Systems in Middle Tennessee, December 18, 1992.
6. U.S. Fish and Wildlife Service, Endangered and Threatened Species of the Southeastern United States (Atlanta, Georgia). 1993.
7. James Brian, Tennessee Wildlife Resources Agency, telephone conversation with Teresa Sawyer, Halliburton NUS Corporation, June 13, 1994. Subject: Fishing and recreation near the Kennon site.
8. U.S. Environmental Protection Agency, Graphical Exposure Modeling System (GEMS) Data Base. Compiled from U.S. Bureau of the Census (1980).
9. Teresa Sawyer, Halliburton NUS Corporation, memorandum to file for Kennon Site, June 13, 1994. Subject: Population of the City of Brentwood.

Site Name: The Kennon Site

Location: Brentwood, Williamson County, Tennessee

GROUND WATER MIGRATION PATHWAY SCORESHEET

FACTOR CATEGORIES AND FACTORS

	<u>Likelihood of Release to an Aquifer</u>	<u>Maximum Value</u>	<u>Value Assigned</u>
1.	Observed Release	550	<u>550</u>
2.	Potential to Release		
2a.	Containment	10	<u>-</u>
2b.	Net Precipitation	10	<u>-</u>
2c.	Depth to Aquifer	5	<u>-</u>
2d.	Travel Time	35	<u>-</u>
2e.	Potential to Release [(lines 2a x (2b + 2c + 2d))]	500	<u>-</u>
3.	Likelihood of Release (higher of lines 1 or 2e)	550	<u>550</u>
<u>Waste Characteristics</u>			
4.	Toxicity/Mobility	a	<u>10</u>
5.	Hazardous Waste Quantity	a	<u>10</u>
6.	Waste Characteristics	100	<u>3</u>
<u>Targets</u>			
7.	Nearest Well	50	<u>0</u>
8.	Population		
8a.	Level I Concentrations	b	<u>0</u>
8b.	Level II Concentrations	b	<u>0</u>
8c.	Potential Contamination	b	<u>0</u>
8d.	Population (lines 8a + 8b + 8c)	b	<u>0</u>
9.	Resources	5	<u>0</u>
10.	Wellhead Protection Area	20	<u>0</u>
11.	Targets (lines 7 + 8d + 9 + 10)	b	<u>0</u>
<u>Ground Water Migration Score for an Aquifer</u>			
12.	Aquifer Score [(lines 3 x 6 x 11)/82,500] ^c	100	<u>0</u>
<u>Ground Water Migration Pathway Score</u>			
13.	Pathway Score (S_{GW}), (highest value from line 12 for all aquifers evaluated) ***	100	<u>0</u>

a Maximum value applies to waste characteristics category.

b Maximum value not applicable.

c Do not round to the nearest integer

Site Name: The Kennon Site

Location: Brentwood, Williamson County, Tennessee

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET

<u>Factor Categories and Factors</u>		<u>Maximum Value</u>	<u>Value Assigned</u>
DRINKING WATER THREAT			
<u>Likelihood of Release</u>			
1.	Observed Release	550	<u>0</u>
2.	Potential Release by Overland Flow		
2a.	Containment	10	<u>10</u>
2b.	Runoff	25	<u>1</u>
2c.	Distance to Surface Water	25	<u>6</u>
2d.	Potential to Release by Overland Flow [(lines 2a x (2b + 2c))]	500	<u>70</u>
3.	Potential to Release by Flood		
3a.	Containment (Flood)	10	<u>10</u>
3b.	Flood Frequency	50	<u>0</u>
3c.	Potential to Release by Flood (lines 3a x 3b)	500	<u>0</u>
4.	Potential to Release (lines 2d + 3c, subject to a maximum of 500)	500	<u>70</u>
5.	Likelihood to Release (higher of lines 1 and 4)	550	<u>70</u>
<u>Waste Characteristics</u>			
6.	Toxicity/Persistence	a	<u>4.0</u>
7.	Hazardous Waste Quantity	a	<u>10</u>
8.	Waste Characteristics	100	<u>2</u>
<u>Targets</u>			
9.	Nearest Intake	50	<u>0</u>
10.	Population		
10a.	Level I Concentrations	b	<u>0</u>
10b.	Level II Concentrations	b	<u>0</u>
10c.	Potential Contamination	b	<u>0</u>
10d.	Population (lines 10a + 10b + 10c)	b	<u>5</u>
11.	Resources	5	<u>0</u>
12.	Targets (lines 9 + 10d + 11)	b	<u>5</u>
<u>Drinking Water Threat Score</u>			
13.	Drinking Water Threat Score ([(lines 5 x 8 x 12)/82,500, subject to a maximum of 100])	100	<u>0.01</u>

a Maximum value applies to waste characteristics category.

b Maximum value not applicable.

c Do not round to nearest integer.

Site Name: The Kennon Site

Location: Brentwood, Williamson County, Tennessee

**SURFACE WATER, OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET
(continued)**

	<u>Factor Categories and Factors</u>	<u>Maximum Value</u>	<u>Value Assigned</u>
HUMAN FOOD CHAIN THREAT			
<u>Likelihood of Release</u>			
14.	Likelihood of Release (same value as line 5)	550	<u>70</u>
<u>Waste Characteristics</u>			
15.	Toxicity/Persistence/Bioaccumulation	a	<u>2 x 10⁴</u>
16.	Hazardous Waste Quantity	a	<u>10</u>
17.	Waste Characteristics	1,000	<u>18</u>
<u>Targets</u>			
18.	Food Chain Individual	50	<u>0</u>
19.	Population		
19a.	Level I Concentrations	b	<u>0</u>
19b.	Level II Concentrations	b	<u>-</u>
19c.	Potential Human Food Chain Contamination	b	<u>2</u>
19c.	Population (lines 19a + 19b + 19c)	b	<u>2</u>
20.	Targets (lines 18 + 19d)		<u>2</u>
<u>Human Food Chain Threat Score</u>			
21.	Human Food Chain Threat Score ([(lines 14 x 17 x 20)/82,500, subject to a maximum of 100])	100	<u>0.03</u>
ENVIRONMENTAL THREAT			
<u>Likelihood of Release</u>			
22.	Likelihood of Release (same value as line 5)	550	<u>70</u>
<u>Waste Characteristics</u>			
23.	Ecosystem Toxicity/Persistence/Bioaccumulation	a	<u>2 x 10⁴</u>
24.	Hazardous Waste Quantity	a	<u>10</u>
25.	Waste Characteristics	1,000	<u>18</u>
26.	Sensitive Environments		
26a.	Level I Concentrations	b	<u>0</u>
26b.	Level II Concentrations	b	<u>0</u>
26c.	Potential Contamination	b	<u>0</u>
26d.	Sensitive Environments (lines 26a + 26b + 26c)	b	<u>0</u>

a Maximum value applies to waste characteristics category.

b Maximum value not applicable.

c Do not round to nearest integer.

Site Name: The Kennon Site

Location: Brentwood, Williamson County, Tennessee

**SURFACE WATER, OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET
(concluded)**

	<u>Factor Categories and Factors</u>	<u>Maximum Value</u>	<u>Value Assigned</u>
	<u>Targets</u>		
27.	Targets (value from line 26d)		<u>0</u>
	<u>Environmental Threat Score</u>		
28.	Environmental Threat Score ([lines 22 x 25 x 27]/82,500, subject to a maximum of 60)	60	<u>0</u>
SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE FOR A WATERSHED			
29.	Watershed Score ^c (lines 13 + 21 + 28, subject to a maximum of 100)	100	<u>0.03</u>
SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE			
30.	Component Score (S_{OF}) ^c (Highest score from line 29 for all watersheds evaluated, subject to a maximum of 100)	100	<u>0.03</u>

-
- a Maximum value applies to waste characteristics category.
b Maximum value not applicable.
c Do not round to the nearest integer.

Site Name: The Kennon Site

Location: Brentwood, Williamson County, Tennessee

SOIL EXPOSURE PATHWAY SCORESHEET

<u>Factor Categories and Factors</u>		<u>Maximum Value</u>	<u>Value Assigned</u>
RESIDENT POPULATION THREAT			
<u>Likelihood of Exposure</u>			
1.	Likelihood of Exposure	550	<u>550</u>
<u>Waste Characteristics</u>			
2.	Toxicity	a	<u>10⁴</u>
3.	Hazardous Waste Quantity	a	<u>10</u>
4.	Waste Characteristics	100	<u>18</u>
<u>Targets</u>			
5.	Resident Individual	50	<u>0</u>
6.	Resident Population		
6a.	Level I Concentrations	b	<u>0</u>
6b.	Level II Concentrations	b	<u>0</u>
6c.	Resident Population (lines 6a + 6b)	b	<u>0</u>
7.	Workers	15	<u>0</u>
8.	Resources	5	<u>0</u>
9.	Terrestrial Sensitive Environments	c	<u>0</u>
10.	Targets (lines 5 + 6c + 7 + 8 + 9)	b	<u>0</u>
<u>Resident Population Threat Score</u>			
11.	Resident Population Threat (Lines 1 x 4 x 10)/82,500	b	<u>0</u>
NEARBY POPULATION THREAT			
<u>Likelihood of Exposure</u>			
12.	Attractiveness/Accessibility	100	<u>5</u>
13.	Area of Contamination	100	<u>8</u>
14.	Likelihood of Exposure	500	<u>25</u>
<u>Waste Characteristics</u>			
15.	Toxicity	a	<u>10⁴</u>
16.	Hazardous Waste Quantity	a	<u>10</u>
17.	Waste Characteristics	100	<u>18</u>

a Maximum value applies to waste characteristics category.

b Maximum value not applicable.

c Do not round to the nearest integer.

Site Name: The Kennon Site

Location: Brentwood, Williamson County, Tennessee

SOIL EXPOSURE PATHWAY SCORESHEET
(concluded)

<u>Factor Categories and Factors</u>	<u>Maximum Value</u>	<u>Value Assigned</u>
<u>Targets</u>		
18. Nearby Individual	1	<u>0</u>
19. Population Within 1 Mile	b	<u>.002</u>
20. Targets (lines 18 + 19)	b	<u>.002</u>
<u>Nearby Population Threat Score</u>		
21. Nearby Population Threat (lines 14 x 17 x 20)	b	<u>0.9</u>
SOIL EXPOSURE PATHWAY SCORE		Nearby Population <u>2</u> Threat: (Default Value)
22. Soil Exposure Pathway Score ^d (S ₅), (lines [11 + 21], subject to a maximum of 100)	100	<u>0.00</u>

-
- a Maximum value applies to waste characteristics category.
b Maximum value not applicable.
c No specific maximum value applies to the factor. However, pathway score based solely on sensitive environments is limited to maximum of 60.
d Do not round to the nearest integer.

Site Name: The Kennon Site

Location: Brentwood, Williamson County, Tennessee

AIR MIGRATION PATHWAY SCORESHEET

Factor Categories and Factors

	<u>Likelihood of Release</u>	<u>Maximum Value</u>	<u>Value Assigned</u>
1.	Observed Release	550	<u>0</u>
2.	Potential to Release		
2a.	Gas Potential to Release	500	<u>500</u>
2b.	Particulate Potential to Release	500	<u>500</u>
2c.	Potential to Release (higher of lines 2a and 2b)	500	<u>500</u>
3.	Likelihood of Release (higher of lines 1 and 2c)	a	<u>500</u>

Waste Characteristics

4.	Toxicity/Mobility	a	<u>1</u>
5.	Hazardous Waste Quantity	a	<u>10</u>
6.	Waste Characteristics	100	<u>2</u>

Targets

7.	Nearest Individual	50	<u>1</u>
8.	Population		
8a.	Level I Concentrations	b	<u>0</u>
8b.	Level II Concentrations	b	<u>0</u>
8c.	Potential Contamination	b	<u>4.81</u>
8d.	Population (lines 8a + 8b + 8c)	b	<u>4.81</u>
9.	Resources	5	<u>0</u>
10.	Sensitive Environments		
10a.	Actual Contamination	c	<u>0</u>
10b.	Potential Contamination	c	<u>0</u>
10c.	Sensitive Environments (lines 10a + 10b)	c	<u>0</u>
11.	Targets (lines 7 + 8d + 9 + 10c)	b	<u>5.81</u>

Air Migration Pathway Score

12.	Pathway Score (S_a) [(Lines 3 x 6 x 11)/82,500] ^d	100	<u>0.07</u>
-----	---	-----	-------------

a Maximum value applies to waste characteristics category.

b Maximum value not applicable.

c No specific maximum value applies to the factor. However, pathway score based solely on sensitive environments is limited to maximum of 60.

d Do not round to the nearest integer.

SITE INSPECTION WORKSHEETS

CERCLIS IDENTIFICATION NUMBER

TND981473515

SITE LOCATION			
SITE NAME: LEGAL, COMMON, OR DESCRIPTIVE NAME OF SITE Kennon Site			
STREET ADDRESS, ROUTE, OR SPECIFIC LOCATION IDENTIFIER 2111 Long Road / Wilson Park			
CITY Kerrwood	STATE TN	ZIP CODE 	TELEPHONE ()
COORDINATES: LATITUDE and LONGITUDE 35° 57' 22" 86° 46' 27"		TOWNSHIP, RANGE, AND SECTION 	

OWNER/OPERATOR IDENTIFICATION					
OWNER Emmett Kennon			OPERATOR SAME		
OWNER ADDRESS 2934 Sidco Drive			OPERATOR ADDRESS 		
CITY Nashville			CITY 		
STATE TN	ZIP CODE 37204	TELEPHONE ()	STATE 	ZIP CODE 	TELEPHONE ()

SITE EVALUATION		
AGENCY/ORGANIZATION Hollibuton NUG Ship		
INVESTIGATOR TERESA SANCHEZ		
CONTACT LOFTON MARK		
ADDRESS 6275E WET HILL RD BLVD		
CITY DUBLIN GEORGIA	STATE GEORGIA	ZIP CODE 30037
TELEPHONE (404) 413 0965		

GENERAL INFORMATION

Site Description and Operational History: Provide a brief description of the site and its operational history. State the site name, owner, operator, type of facility and operations, size of property, active or inactive status, and years of waste generation. Summarize waste treatment, storage, or disposal activities that have or may have occurred at the site; note whether these activities are documented or alleged. Identify all source types and prior spills, floods, or fires. Summarize highlights of the PA and other investigations. Cite references.

The 10-acre site is located on a 150-acre tract of farmland owned by Emmett and Rose Kennon.

The site is currently undergoing remediation. Phosphate was mined on the farmland property between 1972 and 1974, and one pit was left unreclaimed. In 1978, this mine pit and four additional trenches were used for the disposal of industrial wastes, consisting of organic solvents, adhesives, and organic fillers from General Adhesives, which at that time was a division of Genesco Inc. (Ref. 4).

Genesco corporate officials learned of the disposal activities in 1985, at which time the Tennessee Department of Environmental and Conservation (TDEC), formerly known as the Tennessee Department of Health and Environment (TDHE), was notified, and a series of investigations and remedial activities were begun under the supervision and direction of TDEC (Ref. 4).

During the initial stage, a silt fence was constructed to prevent contaminated sediment from leaving the property, and an alternative water supply was provided to residents in the area. Soil sampling and geophysical surveys were conducted in the disposal areas, and monitor wells were constructed on site by consultant personnel. Domestic wells and springs were sampled by the TDHE, and the US Geological Survey (USGS) conducted a study of the regional groundwater flow system. In 1986, the city of Brentwood extended the city water lines into this area of Williamson County to provide city water to residents in the surrounding area, with Genesco participating in the funding thereof (Ref. 4).

Geraghty and Miller, Inc. (G&M) was retained by Genesco to collect and analyze all of the existing data and to prepare a plan of investigation of the site. During 1987, that plan was implemented. From the data obtained during the site investigation in 1987, it was concluded that the hydrogeologic system at the site is composed of three basic units. The uppermost unit (the shallow aquifer) includes a granular saprolite zone at the base of the weathering residuum and the weathered upper few feet of the bedrock. This is underlain by the Hermitage Aquitard, which is a confining zone. The Carter's Formation, which is the third unit, underlies both the hydrogeologic systems noted above and is a massive limestone formation (Ref. 4).

The groundwater flow in the shallow aquifer is toward the southwest and is largely controlled by topography. Groundwater contamination was found to be restricted to the shallow aquifer and confined to a relatively small area on the Kennon property immediately adjacent to the disposal area. Based upon the data collected, it was determined that it was unlikely that any contaminants had migrated off of the Kennon property (Ref. 4).


Work plans, investigation reports and remedial design documents were prepared during 1986 to 1990 to address the onsite contaminants and were implemented in 1989 through 1991. The site is being remediated in accordance with TDEC order, No. 86-3013, issued March 5, 1986. A Hazard Evaluation and Remedial Alternatives (HE&RA) study was conducted to identify the media of concern (groundwater, adhesive waste, contaminated soils) and the optimum treatment and disposal alternatives (Ref. 4).

The selected groundwater remedial method was Remedial Alternative 1 of the HE&RA, which was comprised of a subsurface drain. The subsurface collection drain was designed and installed in November 1989 to intercept the flow of groundwater. Intercepted groundwater is removed from the site and treated through the city of Brentwood sewer system at a treatment facility operated by the Metropolitan Government of Nashville and Davidson County. Large mechanical screens were used from June 1990 to September 1991 to separate semi-solid and solid adhesive wastes from the soils. Excavated adhesive wastes were removed from the site and incinerated. The remaining soils were processed through the screens several times prior to the bioremediation phase of the project (Ref. 4).

A treatability study was conducted by G&M at the site in 1990. The study determined that an adapted indigenous aerobic bacteria population was present in the soils, which could be used to convert the residual contamination present in the soils to carbon dioxide. Baseline soil sampling was conducted in 1990 and 1991, and the site was terraced into a series of surface water holding cells in order to promote the bioremediation effort. Soil and groundwater sampling takes place on a scheduled basis, to ensure that bioremediation continues in an effective manner. Bioremediation is anticipated to continue until approximately the year 2002, but closure of the site will not be completed until a comprehensive sampling analysis has been conducted to ensure that the soil and groundwater cleanliness meets the applicable regulations (Ref. 4).

GENERAL INFORMATION (continued)

Site Sketch: Provide a sketch of the site. Indicate all pertinent features of the site and nearby environments including sources of wastes, areas of visible and buried wastes, buildings, residences, access roads, parking areas, fences, fields, drainage patterns, water bodies, vegetation, wells, sensitive environments, and other features.



GENERAL INFORMATION (continued)

Source Descriptions: Describe all sources at the site. Identify source type and relate to waste disposal operations. Provide source dimensions and the best available waste quantity information. Describe the condition of sources and all containment structures. Cite references.

SOURCE TYPES

Landfill: A man-made (by excavation or construction) or natural hole in the ground into which wastes have come to be disposed by backfilling, or by contemporaneous soil deposition with waste disposal.

Surface Impoundment: A natural topographic depression, man-made excavation, or diked area, primarily formed from earthen materials (lined or unlined) and designed to hold an accumulation of liquid wastes, wastes containing free liquids, or sludges not backfilled or otherwise covered; depression may be wet with exposed liquid or dry if deposited liquid has evaporated, volatilized or leached; structures that may be described as lagoon, pond, aeration pit, settling pond, tailings pond, sludge pit; also a surface impoundment that has been covered with soil after the final deposition of waste materials (i.e., buried or backfilled).

Drum: A portable container designed to hold a standard 55-gallon volume of wastes.

Tank and Non-Drum Container: Any device, other than a drum, designed to contain an accumulation of waste that provides structural support and is constructed primarily of fabricated materials (such as wood, concrete, steel, or plastic); any portable or mobile device in which waste is stored or otherwise handled.

Contaminated Soil: An area or volume of soil onto which hazardous substances have been spilled, spread, disposed, or deposited.

Pile: Any non-containerized accumulation above the ground surface of solid, non-flowing wastes; includes open dumps. Some types of waste piles are:

- **Chemical Waste Pile:** A pile consisting primarily of discarded chemical products, by-products, radioactive wastes, or used or unused feedstocks.
- **Scrap Metal or Junk Pile:** A pile consisting primarily of scrap metal or discarded durable goods (such as appliances, automobiles, auto parts, batteries, etc.) composed of materials containing hazardous substances.
- **Tailings Pile:** A pile consisting primarily of any combination of overburden from a mining operation and tailings from a mineral mining, beneficiation, or processing operation.
- **Trash Pile:** A pile consisting primarily of paper, garbage, or discarded non-durable goods containing hazardous substances.

Land Treatment: Landfarming or other method of waste management in which liquid wastes or sludges are spread over land and tilled, or liquids are injected at shallow depths into soils.

Other: Sources not in categories listed above.

GENERAL INFORMATION (continued)

Source Description: Include description of containment per pathway for ground water (see HRS Table 3-2), surface water (see HRS Table 4-2), and air (see HRS Tables 6-3 and 6-9).

Hazardous Waste Quantity (HWQ) Calculation: SI Tables 1 and 2 (See HRS Tables 2-5, 2-6, and 5-2).

800 drums of adhesives and other
volatile organics

Attach additional pages, if necessary

HWQ =

SI TABLE 1: HAZARDOUS WASTE QUANTITY (HWQ) SCORES FOR SINGLE SOURCE SITES AND FORMULAS FOR MULTIPLE SOURCE SITES

		Single Source Sites (assigned HWQ scores)	
(Column 1)	(Column 2)	(Column 3)	(Column 4)
TIER	Source Type	HWQ = 10	HWQ = 100
A Hazardous Constituent Quantity	N/A	HWQ = 1 if Hazardous Constituent Quantity data are complete HWQ = 10 if Hazardous Constituent Quantity data are not complete	>100 to 10,000 lbs
B Hazardous Wastestream Quantity	N/A	≤ 500,000 lbs	>500,000 to 50 million lbs
C Volume	Landfill	≤ 6.75 million ft ³ ≤ 250,000 yd ³	>6.75 million to 675 million ft ³ >250,000 to 25 million yd ³
	Surface impoundment	≤ 6,750 ft ³ ≤ 250 yd ³	>6,750 to 675,000 ft ³ >250 to 25,000 yd ³
	Drums	≤ 1,000 drums	>1,000 to 100,000 drums
	Tanks and non-drum containers	≤ 50,000 gallons	>50,000 to 5 million gallons
	Contaminated soil	≤ 6.75 million ft ³ ≤ 250,000 yd ³	>6.75 million to 675 million ft ³ >250,000 to 25 million yd ³
	Pile	≤ 6,750 ft ³ ≤ 250 yd ³	>6,750 to 675,000 ft ³ >250 to 25,000 yd ³
	Other	≤ 6,750 ft ³ ≤ 250 yd ³	>6,750 to 675,000 ft ³ >250 to 25,000 yd ³
D Area	Landfill	≤ 340,000 ft ² ≤ 7.8 acres	>340,000 to 34 million ft ² >7.8 to 780 acres
	Surface impoundment	≤ 1,300 ft ² ≤ 0.029 acres	>1,300 to 130,000 ft ² >0.029 to 2.9 acres
	Contaminated soil	≤ 3.4 million ft ² ≤ 78 acres	> 3.4 million to 340 million ft ² > 78 to 7,800 acres
	Pile	≤ 1,300 ft ² ≤ 0.029 acres	>1,300 to 130,000 ft ² >0.029 to 2.9 acres
	Land treatment	≤ 27,000 ft ² ≤ 0.62 acres	>27,000 to 2.7 million ft ² >0.62 to 62 acres

1 ton = 2,000 pounds = 1 cubic yard = 4 drums = 200 gallons

TABLE 1 (CONTINUED)

Single Source Sites (assigned HWQ scores)		Multiple Source Sites		
(Column 5)	(Column 6)	(Column 7) Divisors for Assigning Source WQ Values	(Column 2) Source Type	(Column 1) TIER
HWQ = 10,000	HWQ = 1,000,000			
>10,000 to 1 million lbs	> 1 million lbs	lbs + 1	N/A	A Hazardous Constituent Quantity
>50 million to 5 billion lbs	> 5 billion lbs	lbs + 5,000	N/A	B Hazardous Wastestream Quantity
>675 million to 67.5 billion ft ³ >25 million to 2.5 billion yd ³ >675,000 to 67.5 million ft ³ >25,000 to 2.5 million yd ³ >100,000 to 10 million drums >5 million to 500 million gallons	> 67.5 billion ft ³ > 2.5 billion yd ³ > 67.5 million ft ³ > 2.5 million yd ³ > 10 million drums > 500 million gallons	ft ³ + 67,500 yd ³ + 2,500 ft ³ + 67.5 yd ³ + 2.5 drums + 10 gallons + 500	Landfill Surface Impoundment Drums Tanks and non-drum containers Contaminated Soil Pile Other	C Volume
>34 million to 3.4 billion ft ² >780 to 78,000 acres >130,000 to 13 million ft ² >2.9 to 290 acres > 340 million to 34 billion ft ² > 7,800 to 780,000 acres > 130,000 to 13 million ft ² > 2.9 to 290 acres >2.7 million to 270 million ft ² >62 to 6,200 acres	> 3.4 billion ft ² >78,000 acres > 13 million ft ² > 290 acres > 34 billion ft ² > 780,000 acres > 13 million ft ² > 290 acres > 270 million ft ² > 6,200 acres	ft ² + 3,400 acres + 0.078 ft ² + 13 acres + 0.00029 ft ² + 34,000 acres + 0.78 ft ² + 13 acres + 0.00029 ft ² + 270 acres + 0.0062	Landfill Surface Impoundment Contaminated Soil Pile Land Treatment	D Area

1 ton = 2,000 pounds = 1 cubic yard = 4 drums = 200 gallons

HAZARDOUS WASTE QUANTITY (HWQ) CALCULATION

For each migration pathway, evaluate HWQ associated with sources that are available (i.e., incompletely contained) to migrate to that pathway. (Note: If *Actual Contamination Targets* exist for ground water, surface water, or air migration pathways, assign the calculated HWQ score or 100, whichever is greater, as the HWQ score for that pathway.) For each source, evaluate HWQ for one or more of the four tiers (SI Table 1; HRS Table 2-5) for which data exist: constituent quantity, wastestream quantity, source volume, and source area. Select the tier that gives the highest value as the source HWQ. Select the source volume HWQ rather than source area HWQ if data for both tiers are available.

Column 1 of SI Table 1 indicates the quantity tier. Column 2 lists source types for the four tiers. Columns 3, 4, 5, and 6 provide ranges of waste amount for sites with only one source, corresponding to HWQ scores at the tops of the columns. Column 7 provides formulas to obtain source waste quantity values at sites with multiple sources.

1. Identify each source type.
2. Examine all waste quantity data available for each source. Record constituent quantity and waste stream mass or volume. Record dimensions of each source.
3. Convert source measurements to appropriate units for each tier to be evaluated.
4. For each source, use the formulas in the last column of SI Table 1 to determine the waste quantity value for each tier that can be evaluated. Use the waste quantity value obtained from the highest tier as the quantity value for the source.
5. Sum the values assigned to each source to determine the total site waste quantity.
6. Assign HWQ score from SI Table 2 (HRS Table 2-6).

Note these exceptions to evaluate soil exposure pathway HWQ (see HRS Table 5-2):

- The divisor for the area (square feet) of a landfill is 34,000.
- The divisor for the area (square feet) of a pile is 34.
- Wet surface impoundments and tanks and non-drum containers are the only sources for which volume measurements are evaluated for the soil exposure pathway.

SI TABLE 2: HWQ SCORES FOR SITES

Site WQ Total	HWQ Score
0	0
1 ^a to 100	1 ^b
> 100 to 10,000	100
> 10,000 to 1 million	10,000
> 1 million	1,000,000

^a If the WQ total is between 0 and 1, round it to 1.

^b If the hazardous constituent quantity data are not complete, assign the score of 10.

Q. 1

Ground Water Observed Release Substances Summary Table

On SI Table 4, list the hazardous substances associated with the site detected in ground water samples for that aquifer. Include only those substances directly observed or with concentrations significantly greater than background levels. Obtain toxicity values from the Superfund Chemical Data Matrix (SCDM). Assign mobility a value of 1 for all observed release substances regardless of the aquifer being evaluated. For each substance, multiply the toxicity by the mobility to obtain the toxicity/mobility factor value; enter the highest toxicity/mobility value for the aquifer in the space provided.

Ground Water Actual Contamination Targets Summary Table

If there is an observed release at a drinking water well, enter each hazardous substance meeting the requirements for an observed release by well and sample ID on SI Table 5 and record the detected concentration. Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For MCL and MCLG benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the population using the well as a Level I target. If these percentages are less than 100% or all are N/A, evaluate the population using the well as a Level II target for that aquifer.

GROUND WATER PATHWAY GROUND WATER USE DESCRIPTION

Describe Ground Water Use within 4 Miles of the Site:

Describe generalized stratigraphy, aquifers, municipal and private wells

The city of Brentwood supplies potable water to the residents in the area of the Kennon site.

As previously stated, some residents were using private wells as their water source but since

work began at this site, water lines have been installed (Ref. 4) The city of Brentwood obtains

water from Metro Nashville and Harpeth Valley Utilities. Both systems obtain water from

intakes in the Cumberland River (Ref. 5)

Show Calculations of Ground Water Drinking Water Populations for each Aquifer:

Provide apportionment calculations for blended supply systems.

County average number of persons per household: _____ Reference _____

GROUND WATER PATHWAY WORKSHEET

LIKELIHOOD OF RELEASE	Score	Data Type	Refs
1. OBSERVED RELEASE: If sampling data or direct observation support a release to the aquifer, assign a score of 550. Record observed release substances on SI Table 4.	550		
2. POTENTIAL TO RELEASE: Depth to aquifer: <u>30</u> feet. If sampling data do not support a release to the aquifer, and the site is in karst terrain or the depth to aquifer is 70 feet or less, assign a score of 500; otherwise, assign a score of 340. Optionally, evaluate potential to release according to HRS Section 3.	0	H	1
LR = <u>550</u>			

TARGETS

Are any wells part of a blended system? Yes <u> </u> No <u>X</u> If yes, attach a page to show apportionment calculations.			
3. ACTUAL CONTAMINATION TARGETS: If analytical evidence indicates that any target drinking water well for the aquifer has been exposed to a hazardous substance from the site, evaluate the factor score for the number of people served (SI Table 5). Level I: <u> </u> people x 10 = <u> </u> Level II: <u> </u> people x 1 = <u> </u> Total =	0	H	14.5
4. POTENTIAL CONTAMINATION TARGETS: Determine the number of people served by drinking water wells for the aquifer or overlying aquifers that are not exposed to a hazardous substance from the site; record the population for each distance category in SI Table 6a or 6b. Sum the population values and multiply by 0.1.	0	H	14.5
5. NEAREST WELL: Assign a score of 50 for any Level I Actual Contamination Targets for the aquifer or overlying aquifer. Assign a score of 45 if there are Level II targets but no Level I targets. If no Actual Contamination Targets exist, assign the Nearest Well score from SI Table 6a or 6b. If no drinking water wells exist within 4 miles, assign 0.	0	H	4.5
6. WELLHEAD PROTECTION AREA (WHPA): If any source lies within or above a WHPA for the aquifer, or if a ground water observed release has occurred within a WHPA, assign a score of 20; assign 5 if neither condition applies but a WHPA is within 4 miles; otherwise assign 0.	0	H	4.5
7. RESOURCES: Assign a score of 5 if one or more ground water resource applies; assign 0 if none applies. <ul style="list-style-type: none"> Irrigation (5 acre minimum) of commercial food crops or commercial forage crops Watering of commercial livestock Ingredient in commercial food preparation Supply for commercial aquaculture Supply for a major or designated water recreation area, excluding drinking water use 	0	H	4.5
POT TO RELEASE	Sum of Targets	T=	0

A Net 10
B Net 10 3
C Depth to Aquifer 3
D Total 35

SI TABLE 6 (From HRS TABLE 3-12): VALUES FOR POTENTIAL CONTAMINATION GROUND WATER
TARGET POPULATIONS

SI Table 6a: Other Than Karst Aquifers

Distance from Site	Pop.	Nearest Well (choose highest)	Population Served by Wells within Distance Category												Pop. Value	Rel.
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1000	1001 to 3000	3001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000		
0 to $\frac{1}{4}$ mile	()	20	4	17	53	164	522	1,633	5,214	16,325	52,137	163,246	521,360	1,632,455	()	11.5
$> \frac{1}{4}$ to $\frac{1}{2}$ mile	()	18	2	11	33	102	324	1,013	3,233	10,122	32,325	101,213	323,243	1,012,122	()	
$> \frac{1}{2}$ to 1 mile	()	9	1	5	17	52	167	523	1,669	5,224	16,684	52,239	166,835	522,385	()	
> 1 to 2 miles	()	5	0.7	3	10	30	94	294	939	2,939	9,385	29,384	93,845	293,842	()	
> 2 to 3 miles	()	3	0.5	2	7	21	68	212	678	2,122	6,778	21,222	67,777	212,219	()	
> 3 to 4 miles	()	2	0.3	1	4	13	42	131	417	1,306	4,171	13,060	41,709	130,596	()	✓
Nearest Well = ()															Sum = ()	

C-16

SI TABLE 6 (From HRS TABLE 3-12): VALUES FOR POTENTIAL CONTAMINATION GROUND WATER
TARGET POPULATIONS (continued)

SI Table 6b: Karst Aquifers

Distance from Site	Pop.	Nearest Well (choose highest)	Population Served by Wells within Distance Category												Pop. Value	Ref.
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1000	1001 to 3000	3001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000		
0 to $\frac{1}{4}$ mile		20	4	17	53	164	522	1,633	5,214	16,325	52,137	163,246	521,360	1,632,455		
$> \frac{1}{4}$ to $\frac{1}{2}$ mile		20	2	11	33	102	324	1,013	3,233	10,122	32,325	101,213	323,243	1,012,122		
$> \frac{1}{2}$ to 1 mile		20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227		
> 1 to 2 miles		20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227		
> 2 to 3 miles		20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227		
> 3 to 4 miles		20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227		
Nearest Well =															Sum =	

C-17

GROUND WATER PATHWAY WORKSHEET (concluded)

WASTE CHARACTERISTICS	Score	Data Type	Does not Apply																						
8. If any Actual Contamination Targets exist for the aquifer or overlying aquifers, assign the calculated hazardous waste quantity score or a score of 100, whichever is greater; if no Actual Contamination Targets exist, assign the hazardous waste quantity score calculated for sources available to migrate to ground water.	10	H																							
9. Assign the highest ground water toxicity/mobility value from SI Table 3 or 4.	10	H																							
10. Multiply the ground water toxicity/mobility and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below: (from HRS Table 2-7) <table border="1" style="margin: 10px auto; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Product</th> <th style="text-align: center;">WC Score</th> </tr> </thead> <tbody> <tr><td>0</td><td style="text-align: center;">0</td></tr> <tr><td>>0 to <10</td><td style="text-align: center;">1</td></tr> <tr><td>10 to <100</td><td style="text-align: center;">2</td></tr> <tr><td>100 to <1,000</td><td style="text-align: center;">3</td></tr> <tr><td>1,000 to < 10,000</td><td style="text-align: center;">6</td></tr> <tr><td>10,000 to <1E + 05</td><td style="text-align: center;">10</td></tr> <tr><td>1E + 05 to <1E + 06</td><td style="text-align: center;">18</td></tr> <tr><td>1E + 06 to <1E + 07</td><td style="text-align: center;">32</td></tr> <tr><td>1E + 07 to <1E + 08</td><td style="text-align: center;">56</td></tr> <tr><td>1E + 08 or greater</td><td style="text-align: center;">100</td></tr> </tbody> </table>	Product	WC Score	0	0	>0 to <10	1	10 to <100	2	100 to <1,000	3	1,000 to < 10,000	6	10,000 to <1E + 05	10	1E + 05 to <1E + 06	18	1E + 06 to <1E + 07	32	1E + 07 to <1E + 08	56	1E + 08 or greater	100	3		
Product	WC Score																								
0	0																								
>0 to <10	1																								
10 to <100	2																								
100 to <1,000	3																								
1,000 to < 10,000	6																								
10,000 to <1E + 05	10																								
1E + 05 to <1E + 06	18																								
1E + 06 to <1E + 07	32																								
1E + 07 to <1E + 08	56																								
1E + 08 or greater	100																								
WC =	3																								

Multiply LR by T and by WC. Divide the product by 82,500 to obtain the ground water pathway score for each aquifer. Select the highest aquifer score. If the pathway score is greater than 100, assign 100.

GROUND WATER PATHWAY SCORE:


$$\frac{LR \times T \times WC}{82,500}$$

<div style="font-size: 2em; margin: 0;">0</div> <div style="font-size: 0.8em; margin-top: 5px;">(Maximum of 100)</div>
--

SURFACE WATER PATHWAY

Sketch of the Surface Water Migration Route:

Sketch of the Surface Water Migration Route. Label all surface water bodies. Include runoff route and drainage direction, probable point of entry, and 15-mile target distance limit. Mark sample locations, intakes, fisheries, and sensitive environments. Indicate flow directions, tidal influence, and rate.



SURFACE WATER PATHWAY

Surface Water Observed Release Substances Summary Table

On SI Table 7, list the hazardous substances detected in surface water samples for the watershed, which can be attributed to the site. Include only those substances in observed releases (direct observation) or with concentration levels significantly above background levels. Obtain toxicity, persistence, bioaccumulation potential, and ecotoxicity values from SCDM. Enter the highest toxicity/persistence, toxicity/persistence/bioaccumulation, and ecotoxicity/persistence/ecobioaccumulation values in the spaces provided.

- TP = Toxicity x Persistence
- TPB = TP x bioaccumulation
- ETPB = EP x bioaccumulation (EP = ecotoxicity x persistence)

Drinking Water Actual Contamination Targets Summary Table

For an observed release at or beyond a drinking water intake, on SI Table 8 enter each hazardous substance by sample ID and the detected concentration. For surface water sediment samples detecting a hazardous substance at or beyond an intake, evaluate the intake as Level II contamination. Obtain benchmark, cancer risk, and reference dose concentrations for each substance from SCDM. For MCL and MCLG benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages of the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the population served by the intake as a Level I target. If the percentages are less than 100% or all are N/A, evaluate the population served by the intake as a Level II target.

[illegible]

Intake ID: _____ Sample Type _____ Level I _____ Level II _____ Population Served _____ References _____

Sample ID	Hazardous Substance	Conc. (µg/L)	Benchmark Conc. (MCL or MCLG)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RfD	% of RfD
Highest Percent					Sum of Percents		Sum of Percents	

Intake ID:	Sample Type	Level I	Level II	Population Served	References
------------	-------------	---------	----------	-------------------	------------

Sample ID	Hazardous Substance	Conc. (µg/L)	Benchmark Conc. (MCL or MCLG)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RfD	% of RfD
			Highest Percent		Sum of Percents		Sum of Percents	

SURFACE WATER PATHWAY LIKELIHOOD OF RELEASE AND DRINKING WATER THREAT WORKSHEET

LIKELIHOOD OF RELEASE- OVERLAND/FLOOD MIGRATION

	Score	Data Type	Refs												
1. OBSERVED RELEASE: If sampling data or direct observation support a release to surface water in the watershed, assign a score of 550. Record observed release substances on SI Table 7.	0	H	1,4												
2. POTENTIAL TO RELEASE: Distance to surface water: _____ (feet) If sampling data do not support a release to surface water in the watershed, use the table below to assign a score from the table below based on distance to surface water and flood frequency.															
<table border="1"> <tr> <td>Distance to surface water <2500 feet</td> <td align="center">500</td> </tr> <tr> <td>Distance to surface water >2500 feet, and:</td> <td></td> </tr> <tr> <td> Site in annual or 10-yr floodplain</td> <td align="center">500</td> </tr> <tr> <td> Site in 100-yr floodplain</td> <td align="center">400</td> </tr> <tr> <td> Site in 500-yr floodplain</td> <td align="center">300</td> </tr> <tr> <td> Site outside 500-yr floodplain</td> <td align="center">100</td> </tr> </table>	Distance to surface water <2500 feet	500	Distance to surface water >2500 feet, and:		Site in annual or 10-yr floodplain	500	Site in 100-yr floodplain	400	Site in 500-yr floodplain	300	Site outside 500-yr floodplain	100			
Distance to surface water <2500 feet	500														
Distance to surface water >2500 feet, and:															
Site in annual or 10-yr floodplain	500														
Site in 100-yr floodplain	400														
Site in 500-yr floodplain	300														
Site outside 500-yr floodplain	100														
Optionally, evaluate surface water potential to release according to HRS Section 4.1.2.1.2	30	H	1,2												

LR =

70

LIKELIHOOD OF RELEASE GROUND WATER TO SURFACE WATER MIGRATION

	Score	Data Type	Refs
1. OBSERVED RELEASE: If sampling data or direct observation support a release to surface water in the watershed, assign a score of 550. Record observed release substances on SI Table 7.			
NOTE: Evaluate ground water to surface water migration only for a surface water body that meets all of the following conditions:			
1) A portion of the surface water is within 1 mile of site sources having a containment factor greater than 0.			
2) No aquifer discontinuity is established between the source and the above portion of the surface water body.			
3) The top of the uppermost aquifer is at or above the bottom of the surface water.			
Elevation of top of uppermost aquifer _____			
Elevation of bottom of surface water body _____			
2. POTENTIAL TO RELEASE: Use the ground water potential to release. Optionally, evaluate surface water potential to release according to HRS Section 3.1.2.			

LR =

Not to release
by accident

Not to release
by flood

10
1
10

10
10
8

70

**SURFACE WATER PATHWAY
LIKELIHOOD OF RELEASE AND DRINKING WATER THREAT WORKSHEET
(CONTINUED)**

DRINKING WATER THREAT TARGETS	Score	Data Type	Rels																
<p>Record the water body type, flow, and number of people served by each drinking water intake within the target distance limit in the watershed. If there is no drinking water intake within the target distance limit, assign 0 to factors 3, 4, and 5.</p> <table border="1" style="width: 100%; border-collapse: collapse; margin: 10px 0;"> <thead> <tr> <th style="width: 25%;">Intake Name</th> <th style="width: 25%;">Water Body Type</th> <th style="width: 25%;">Flow</th> <th style="width: 25%;">People Served</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table> <p>Are any intakes part of a blended system? Yes _____ No _____ If yes, attach a page to show apportionment calculations.</p> <p>3. ACTUAL CONTAMINATION TARGETS: If analytical evidence indicates a drinking water intake has been exposed to a hazardous substance from the site, list the intake name and evaluate the factor score for the drinking water population (SI Table 8).</p> <hr/> <p>Level I: _____ people x 10 = _____ Level II: _____ people x 1 = _____ Total =</p>	Intake Name	Water Body Type	Flow	People Served													0	H	145
Intake Name	Water Body Type	Flow	People Served																
<p>4. POTENTIAL CONTAMINATION TARGETS: Determine the number of people served by drinking water intakes for the watershed that have not been exposed to a hazardous substance from the site. Assign the population values from SI Table 9. Sum the values and multiply by 0.1.</p>	0	H	145																
<p>5. NEAREST INTAKE: Assign a score of 50 for any Level I Actual Contamination Drinking Water Targets for the watershed. Assign a score of 45 if there are Level II targets for the watershed, but no Level I targets. If no Actual Contamination Drinking Water Targets exist, assign a score for the intake nearest the PPE from SI Table 9. If no drinking water intakes exist, assign 0.</p>	0	H	145																
<p>6. RESOURCES: Assign a score of 5 if one or more surface water resource applies; assign 0 if none applies.</p> <ul style="list-style-type: none"> • Irrigation (5 acre minimum) of commercial food crops or commercial forage crops • Watering of commercial livestock • Ingredient in commercial food preparation • Major or designated water recreation area, excluding drinking water use 	5	H	145																
SUM OF TARGETS T=	5																		

SI TABLE 9 (From HRS Table 4-14): DILUTION-WEIGHTED POPULATION VALUES FOR POTENTIAL CONTAMINATION FOR SURFACE WATER MIGRATION PATHWAY

Type of Surface Water Body	Pop.	Nearest Intake	Number of people									Pop. Value
			0	1 to 10	11 to 30	31 to 100	101 to 300	301 to 1,000	1,001 to 3,000	3,001 to 10,000	10,001 to 30,000	
Minimal Stream (<10 cfs)		20	0	4	17	53	164	522	1,633	5,214	16,325	
Small to moderate stream (10 to 100 cfs)		2	0	0.4	2	5	16	52	163	521	1,633	
Moderate to large stream (> 100 to 1,000 cfs)		0	0	0.04	0.2	0.5	2	5	16	52	163	
Large Stream to river (>1,000 to 10,000 cfs)		0	0	0.004	0.02	0.05	0.2	0.5	2	5	16	
Large River (> 10,000 to 100,000 cfs)		0	0	0	0.002	0.005	0.02	0.05	0.2	0.5	16	
Very Large River (>100,000 cfs)		0	0	0	0	0.001	0.002	0.005	0.02	0.05	0.2	
Shallow ocean zone or Great Lake (depth < 20 feet)		0	0	0	0.002	0.005	0.02	0.05	0.2	0.5	2	
Moderate ocean zone or Great Lake (Depth 20 to 200 feet)		0	0	0	0	0.001	0.002	0.005	0.02	0.05	0.2	
Deep ocean zone or Great Lake (depth > 200 feet)		0	0	0	0	0	0.001	0.003	0.008	0.03	0.08	
3-mile mixing zone in quiet flowing river (≥ 10 cfs)		10	0	2	9	26	82	261	817	2,607	8,163	
Nearest Intake =												Sum =

References

SURFACE WATER PATHWAY

Human Food Chain Actual Contamination Targets Summary Table

On SI Table 10, list the hazardous substances detected in sediment, aqueous, sessile benthic organism tissue, or fish tissue samples (taken from fish caught within the boundaries of the observed release) by sample ID and concentration. Evaluate fisheries within the boundaries of observed releases detected by sediment or aqueous samples as Level II, if at least one observed release substance has a bioaccumulation potential factor value of 500 or greater (see SI Table 7). Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For FDAAL benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate this portion of the fishery as subject to Level I concentrations. If the percentages are less than 100% or all are N/A, evaluate the fishery as a Level II target.

Sensitive Environment Actual Contamination Targets Summary Table

On SI Table 11, list each hazardous substance detected in aqueous or sediment samples at or beyond wetlands or a surface water sensitive environment by sample ID. Record the concentration. If contaminated sediments or tissues are detected at or beyond a sensitive environment, evaluate the sensitive environment as Level II. Obtain benchmark concentrations from SCDM. For AWQC/AALAC benchmarks, determine the highest percentage of benchmark of the substances detected in aqueous samples. If benchmark concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage equals or exceeds 100%, evaluate that part of the sensitive environment subject to Level I concentrations. If the percentage is less than 100%, or all are N/A, evaluate the sensitive environment as Level II.

SI TABLE 10: HUMAN FOOD CHAIN ACTUAL CONTAMINATION TARGETS FOR WATERSHED

Fishery ID: _____ Sample Type _____ Level I _____ Level II _____ References _____

Sample ID	Hazardous Substance	Conc. (mg/kg)	Benchmark Concentration (FDAAL)	% of Benchmark	Cancer Risk Concentration	% of Cancer Risk Concentration	RIID	% of RIID
Highest Percent					Sum of Percents		Sum of Percents	

SI TABLE 11: SENSITIVE ENVIRONMENT ACTUAL CONTAMINATION TARGETS FOR WATERSHED

Environment ID: _____ Sample Type _____ Level I _____ Level II _____ Environment Value _____

C-27

Sample ID	Hazardous Substance	Conc.. (µg/L)	Benchmark Concentration (AWQC or AALAC)	% of Benchmark	References
Highest Percent					

Environment ID: _____ Sample Type _____ Level I _____ Level II _____ Environment Value _____

Sample ID	Hazardous Substance	Conc.. (µg/L)	Benchmark Concentration (AWQC or AALAC)	% of Benchmark	References
Highest Percent					

SURFACE WATER PATHWAY (continued) HUMAN FOOD CHAIN THREAT WORKSHEET

HUMAN FOOD CHAIN THREAT TARGETS	Score	Data Type	Ref's										
<p>Record the water body type and flow for each fishery within the target distance limit. If there is no fishery within the target distance limit, assign a score of 0 at the bottom of this page.</p>													
<p>Fishery Name <u>Little Harpeth River</u> Water Body _____ Flow _____ cfs</p> <p>Species _____ Production _____ lbs/yr</p> <p>Species _____ Production _____ lbs/yr</p> <p>Fishery Name _____ Water Body <u>Claycraft Lake</u> Flow _____ cfs</p> <p>Species _____ Production _____ lbs/yr</p> <p>Species _____ Production _____ lbs/yr</p> <p>Fishery Name _____ Water Body _____ Flow _____ cfs</p> <p>Species _____ Production _____ lbs/yr</p> <p>Species _____ Production _____ lbs/yr</p>													
<p>FOOD CHAIN INDIVIDUAL</p> <p>7. ACTUAL CONTAMINATION FISHERIES:</p> <p>If analytical evidence indicates that a fishery has been exposed to a hazardous substance with a bioaccumulation factor greater than or equal to 500 (SI Table 10), assign a score of 50 if there is a Level I fishery. Assign 45 if there is a Level II fishery, but no Level I fishery.</p> <p>8. POTENTIAL CONTAMINATION FISHERIES:</p> <p>If there is a release of a substance with a bioaccumulation factor greater than or equal to 500 to a watershed containing fisheries within the target distance limit, but there are no Level I or Level II fisheries, assign a score of 20.</p> <p>If there is no observed release to the watershed, assign a value for potential contamination fisheries from the table below using the lowest flow at all fisheries within the target distance limit:</p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Lowest Flow</th> <th>FCI Value</th> </tr> </thead> <tbody> <tr> <td><10 cfs</td> <td>20</td> </tr> <tr> <td>10 to 100 cfs</td> <td>2</td> </tr> <tr> <td>>100 cfs, coastal tidal waters, oceans, or Great Lakes</td> <td>0</td> </tr> <tr> <td>3-mile mixing zone in quiet flowing river</td> <td>10</td> </tr> </tbody> </table> <p align="right">FCI Value = <u>2</u></p>				Lowest Flow	FCI Value	<10 cfs	20	10 to 100 cfs	2	>100 cfs, coastal tidal waters, oceans, or Great Lakes	0	3-mile mixing zone in quiet flowing river	10
Lowest Flow	FCI Value												
<10 cfs	20												
10 to 100 cfs	2												
>100 cfs, coastal tidal waters, oceans, or Great Lakes	0												
3-mile mixing zone in quiet flowing river	10												
<p>SUM OF TARGETS T =</p>		<p><u>2</u></p>											

SURFACE WATER PATHWAY (continued) ENVIRONMENTAL THREAT WORKSHEET

When measuring length of wetlands that are located on both sides of a surface water body, sum both frontage lengths. For a sensitive environment that is more than one type, assign a value for each type.

ENVIRONMENTAL THREAT TARGETS	Score	Data Type	Refs																																			
<p>Record the water body type and flow for each surface water sensitive environment within the target distance (see SI Table 12). If there is no sensitive environment within the target distance limit, assign a score of 0 at the bottom of the page.</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 30%;">Environment Name</th> <th style="width: 30%;">Water Body Type</th> <th style="width: 40%;">Flow</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td>cfs</td></tr> <tr><td> </td><td> </td><td>cfs</td></tr> <tr><td> </td><td> </td><td>cfs</td></tr> <tr><td> </td><td> </td><td>cfs</td></tr> <tr><td> </td><td> </td><td>cfs</td></tr> </tbody> </table>	Environment Name	Water Body Type	Flow			cfs			cfs			cfs			cfs			cfs	0	H	6																	
Environment Name	Water Body Type	Flow																																				
		cfs																																				
		cfs																																				
		cfs																																				
		cfs																																				
		cfs																																				
<p>9. ACTUAL CONTAMINATION SENSITIVE ENVIRONMENTS: If sampling data or direct observation indicate any sensitive environment has been exposed to a hazardous substance from the site, record this information on SI Table 11, and assign a factor value for the environment (SI Tables 13 and 14).</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 20%;">Environment Name</th> <th style="width: 20%;">Environment Type and Value (SI Tables 13 & 14)</th> <th style="width: 20%;">Multiplier (10 for Level I, 1 for Level II)</th> <th style="width: 40%;">Product</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td>x</td><td>=</td></tr> <tr><td> </td><td> </td><td>x</td><td>=</td></tr> <tr><td> </td><td> </td><td>x</td><td>=</td></tr> <tr><td> </td><td> </td><td>x</td><td>=</td></tr> <tr> <td colspan="3" style="text-align: right;">Sum =</td> <td> </td> </tr> </tbody> </table>	Environment Name	Environment Type and Value (SI Tables 13 & 14)	Multiplier (10 for Level I, 1 for Level II)	Product			x	=			x	=			x	=			x	=	Sum =																	
Environment Name	Environment Type and Value (SI Tables 13 & 14)	Multiplier (10 for Level I, 1 for Level II)	Product																																			
		x	=																																			
		x	=																																			
		x	=																																			
		x	=																																			
Sum =																																						
<p>10. POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;">Flow</th> <th style="width: 15%;">Dilution Weight (SI Table 12)</th> <th style="width: 20%;">Environment Type and Value (SI Tables 13 & 14)</th> <th style="width: 10%;">Pot. Cont.</th> <th style="width: 45%;">Product</th> </tr> </thead> <tbody> <tr><td>cfs</td><td>x</td><td>x</td><td>0.1</td><td>=</td></tr> <tr><td>cfs</td><td>x</td><td>x</td><td>0.1</td><td>=</td></tr> <tr><td>cfs</td><td>x</td><td>x</td><td>0.1</td><td>=</td></tr> <tr><td>cfs</td><td>x</td><td>x</td><td>0.1</td><td>=</td></tr> <tr><td>cfs</td><td>x</td><td>x</td><td>0.1</td><td>=</td></tr> <tr> <td colspan="4" style="text-align: right;">Sum =</td> <td> </td> </tr> </tbody> </table>	Flow	Dilution Weight (SI Table 12)	Environment Type and Value (SI Tables 13 & 14)	Pot. Cont.	Product	cfs	x	x	0.1	=	cfs	x	x	0.1	=	cfs	x	x	0.1	=	cfs	x	x	0.1	=	cfs	x	x	0.1	=	Sum =					0	H	2
Flow	Dilution Weight (SI Table 12)	Environment Type and Value (SI Tables 13 & 14)	Pot. Cont.	Product																																		
cfs	x	x	0.1	=																																		
cfs	x	x	0.1	=																																		
cfs	x	x	0.1	=																																		
cfs	x	x	0.1	=																																		
cfs	x	x	0.1	=																																		
Sum =																																						
T =	0																																					

SI TABLE 12 (HRS Table 4-13):
SURFACE WATER DILUTION WEIGHTS

Type of Surface Water Body		Assigned Dilution Weight
Descriptor	Flow Characteristics	
Minimal stream	< 10 cfs	1
Small to moderate stream	10 to 100 cfs	0.1
Moderate to large stream	> 100 to 1,000 cfs	0.01
Large stream to river	> 1,000 to 10,000 cfs	0.001
Large river	> 10,000 to 100,000 cfs	0.0001
Very large river	> 100,000 cfs	0.00001
Coastal tidal waters	Flow not applicable; depth not applicable	0.001- 0.0001
Shallow ocean zone or Great Lake	Flow not applicable; depth less than 20 feet	0.001- 0.0001
Moderate depth ocean zone or Great Lake	Flow not applicable; depth 20 to 200 feet	0.0001- 0.00001
Deep ocean zone or Great Lake	Flow not applicable; depth greater than 200 feet	0.000005
3-mile mixing zone in quiet flowing river	10 cfs or greater	0.5

SI TABLE 13 (HRS TABLE 4-23):
SURFACE WATER AND AIR SENSITIVE ENVIRONMENTS VALUES

SENSITIVE ENVIRONMENT	ASSIGNED VALUE
Critical habitat for Federal designated endangered or threatened species Marine Sanctuary National Park Designated Federal Wilderness Area Ecologically important areas identified under the Coastal Zone Wilderness Act Sensitive Areas identified under the National Estuary Program or Near Coastal Water Program of the Clean Water Act Critical Areas identified under the Clean Lakes Program of the Clean Water Act (subareas in lakes or entire small lakes) National Monument (air pathway only) National Seashore Recreation Area National Lakeshore Recreation Area	100
Habitat known to be used by Federal designated or proposed endangered or threatened species National Preserve National or State Wildlife Refuge Unit of Coastal Barrier Resources System Coastal Barrier (undeveloped) Federal land designated for the protection of natural ecosystems Administratively Proposed Federal Wilderness Area Spawning areas critical for the maintenance of fish/shellfish species within a river system, bay, or estuary Migratory pathways and feeding areas critical for the maintenance of anadromous fish species within river reaches or areas in lakes or coastal tidal waters in which the fish spend extended periods of time Terrestrial areas utilized by large or dense aggregations of vertebrate animals (semi-aquatic foragers) for breeding National river reach designated as recreational	75
Habitat known to be used by State designated endangered or threatened species Habitat known to be used by a species under review as to its Federal endangered or threatened status Coastal Barrier (partially developed) Federally designated Scenic or Wild River	50
State land designated for wildlife or game management State designated Scenic or Wild River State designated Natural Area Particular areas, relatively small in size, important to maintenance of unique biotic communities	25
State designated areas for the protection of maintenance of aquatic life under the Clean Water Act	5
Wetlands See SI Table 14 (Surface Water Pathway) or SI Table 23 (Air Pathway)	

SI TABLE 14 (HRS TABLE 4-24): SURFACE WATER
WETLANDS FRONTAGE VALUES

Total Length of Wetlands	Assigned Value
Less than 0.1 mile	0
0.1 to 1 mile	25
Greater than 1 to 2 miles	50
Greater than 2 to 3 miles	75
Greater than 3 to 4 miles	100
Greater than 4 to 8 miles	150
Greater than 8 to 12 miles	250
Greater than 12 to 16 miles	350
Greater than 16 to 20 miles	450
Greater than 20 miles	500

SURFACE WATER PATHWAY (concluded)
WASTE CHARACTERISTICS, THREAT, AND PATHWAY SCORE SUMMARY

WASTE CHARACTERISTICS	Score																														
14. If an Actual Contamination Target (drinking water, human food chain, or environmental threat) exists for the watershed, assign the calculated hazardous waste quantity score, or a score of 100, whichever is greater.	10																														
15. Assign the highest value from SI Table 7 (observed release) or SI Table 3 (no observed release) for the hazardous substance waste characterization factors below. Multiply each by the surface water hazardous waste quantity score and determine the waste characteristics score for each threat.																															
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>Substance Value</th> <th>HWO</th> <th>Product</th> </tr> </thead> <tbody> <tr> <td>Drinking Water Threat Toxicity/Persistence</td> <td align="center">4.0</td> <td align="center">x</td> <td align="center">10 = 40</td> </tr> <tr> <td>Food Chain Threat Toxicity/Persistence Bioaccumulation</td> <td align="center">2×10^4</td> <td align="center">x</td> <td align="center">10 = 2×10^5</td> </tr> <tr> <td>Environmental Threat Ecotoxicity/Persistence/ Ecobioaccumulation</td> <td align="center">2×10^4</td> <td align="center">x</td> <td align="center">10 = 2×10^5</td> </tr> </tbody> </table>		Substance Value	HWO	Product	Drinking Water Threat Toxicity/Persistence	4.0	x	10 = 40	Food Chain Threat Toxicity/Persistence Bioaccumulation	2×10^4	x	10 = 2×10^5	Environmental Threat Ecotoxicity/Persistence/ Ecobioaccumulation	2×10^4	x	10 = 2×10^5	<p align="center">WC Score (from Table) (Maximum of 100)</p> <table border="1" style="width:100%; border-collapse: collapse;"> <tbody> <tr> <td align="center">2</td> <td align="right"><small>max = 100</small></td> </tr> <tr> <td align="center">18</td> <td align="right"><small>max = 1000</small></td> </tr> <tr> <td align="center">18</td> <td align="right"><small>max = 1000</small></td> </tr> </tbody> </table>	2	<small>max = 100</small>	18	<small>max = 1000</small>	18	<small>max = 1000</small>								
	Substance Value	HWO	Product																												
Drinking Water Threat Toxicity/Persistence	4.0	x	10 = 40																												
Food Chain Threat Toxicity/Persistence Bioaccumulation	2×10^4	x	10 = 2×10^5																												
Environmental Threat Ecotoxicity/Persistence/ Ecobioaccumulation	2×10^4	x	10 = 2×10^5																												
2	<small>max = 100</small>																														
18	<small>max = 1000</small>																														
18	<small>max = 1000</small>																														
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Product</th> <th>WC Score</th> </tr> </thead> <tbody> <tr><td>0</td><td align="center">0</td></tr> <tr><td>>0 to <10</td><td align="center">1</td></tr> <tr><td>10 to <100</td><td align="center">2</td></tr> <tr><td>100 to <1,000</td><td align="center">3</td></tr> <tr><td>1,000 to <10,000</td><td align="center">6</td></tr> <tr><td>10,000 to <1E + 05</td><td align="center">10</td></tr> <tr><td>1E + 05 to <1E + 06</td><td align="center">18</td></tr> <tr><td>1E + 06 to <1E + 07</td><td align="center">32</td></tr> <tr><td>1E + 07 to <1E + 08</td><td align="center">56</td></tr> <tr><td>1E + 08 to <1E + 09</td><td align="center">100</td></tr> <tr><td>1E + 09 to <1E + 10</td><td align="center">180</td></tr> <tr><td>1E + 10 to <1E + 11</td><td align="center">320</td></tr> <tr><td>1E + 11 to <1E + 12</td><td align="center">560</td></tr> <tr><td>1E + 12 or greater</td><td align="center">1000</td></tr> </tbody> </table>	Product	WC Score	0	0	>0 to <10	1	10 to <100	2	100 to <1,000	3	1,000 to <10,000	6	10,000 to <1E + 05	10	1E + 05 to <1E + 06	18	1E + 06 to <1E + 07	32	1E + 07 to <1E + 08	56	1E + 08 to <1E + 09	100	1E + 09 to <1E + 10	180	1E + 10 to <1E + 11	320	1E + 11 to <1E + 12	560	1E + 12 or greater	1000	
Product	WC Score																														
0	0																														
>0 to <10	1																														
10 to <100	2																														
100 to <1,000	3																														
1,000 to <10,000	6																														
10,000 to <1E + 05	10																														
1E + 05 to <1E + 06	18																														
1E + 06 to <1E + 07	32																														
1E + 07 to <1E + 08	56																														
1E + 08 to <1E + 09	100																														
1E + 09 to <1E + 10	180																														
1E + 10 to <1E + 11	320																														
1E + 11 to <1E + 12	560																														
1E + 12 or greater	1000																														

SURFACE WATER PATHWAY THREAT SCORES

Threat	Likelihood of Release (LR) Score	Targets (T) Score	Pathway Waste Characteristics (WC) Score (determined above)	Threat Score $\frac{LR \times T \times WC}{82,500}$
Drinking Water	70	5	2	(maximum of 100) 0.01
Human Food Chain	70	2	18	(maximum of 100) 0.03
Environmental	70	0	18	(maximum of 60) 0

SURFACE WATER PATHWAY SCORE
 (Drinking Water Threat + Human Food Chain Threat + Environmental Threat)

(maximum of 100)
0.04

SOIL EXPOSURE PATHWAY

If there is no observed contamination (e.g., ground water plume with no known surface source), do not evaluate the soil exposure pathway. Discuss evidence for no soil exposure pathway.

Soil Exposure Resident Population Targets Summary

For each property (duplicate page 35 as necessary):

If there is an area of observed contamination on the property and within 200 feet of a residence, school, or day care center, enter on Table 15 each hazardous substance by sample ID. Record the detected concentration. Obtain cancer risk, and reference dose concentrations from SCDM. Sum the cancer risk and reference dose percentages for the substances listed. If cancer risk or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the residents and students as Level I. If both percentages are less than 100% or all are N/A, evaluate the targets as Level II.

SI TABLE 15: SOIL EXPOSURE RESIDENT POPULATION TARGETS

Residence ID: _____ Level I _____ Level II _____ Population _____

Sample ID	Hazardous Substance	Conc. (mg/kg)	Cancer Risk Concentration	% of Cancer Risk Conc.	RfD	% of RfD	Toxicity Value	References
			Highest Percent		Sum of Percents		Sum of Percents	

Residence ID: _____ Level I _____ Level II _____ Population _____

Sample ID	Hazardous Substance	Conc. (mg/kg)	Cancer Risk Concentration	% of Cancer Risk Conc.	RfD	% of RfD	Toxicity Value	References
			Highest Percent		Sum of Percents		Sum of Percents	

C-35

Residence ID: _____ Level I _____ Level II _____ Population _____

Sample ID	Hazardous Substance	Conc. (mg/kg)	Cancer Risk Concentration	% of Cancer Risk Conc.	RfD	% of RfD	Toxicity Value	References
			Highest Percent		Sum of Percents		Sum of Percents	

SOIL EXPOSURE PATHWAY WORKSHEET RESIDENT POPULATION THREAT

LIKELIHOOD OF EXPOSURE

	Score	Data Type	Refs
1. OBSERVED CONTAMINATION: If evidence indicates presence of observed contamination (depth of 2 feet or less), assign a score of 550; otherwise, assign a 0. Note that a likelihood of exposure score of 0 results in a soil exposure pathway score of 0.	550		4

LE = 550

TARGETS

<p>2. RESIDENT POPULATION: Determine the number of people living or attending school or day care on a property with an area of observed contamination and whose residence, school, or day care center, respectively, is on or within 200 feet of the area of observed contamination.</p> <p>Level I: _____ people x 10 = _____</p> <p>Level II: _____ people x 1 = _____</p> <p style="text-align: right;">Sum = _____</p>													
<p>3. RESIDENT INDIVIDUAL: Assign a score of 50 if any Level I resident population exists. Assign a score of 45 if there are Level II targets but no Level I targets. If no resident population exists (i.e., no Level I or Level II targets), assign 0 (HRS Section 5.1.3).</p>													
<p>4. WORKERS: Assign a score from the table below for the total number of workers at the site and nearby facilities with areas of observed contamination associated with the site.</p> <table border="1" style="margin: 10px auto; width: 60%; text-align: center;"> <thead> <tr> <th>Number of Workers</th><th>Score</th></tr> </thead> <tbody> <tr> <td>0</td><td>0</td></tr> <tr> <td>1 to 100</td><td>5</td></tr> <tr> <td>101 to 1,000</td><td>10</td></tr> <tr> <td>>1,000</td><td>15</td></tr> </tbody> </table>	Number of Workers	Score	0	0	1 to 100	5	101 to 1,000	10	>1,000	15			
Number of Workers	Score												
0	0												
1 to 100	5												
101 to 1,000	10												
>1,000	15												
<p>5. TERRESTRIAL SENSITIVE ENVIRONMENTS: Assign a value for each terrestrial sensitive environment (SI Table 16) in an area of observed contamination.</p> <table border="1" style="margin: 10px auto; width: 60%;"> <thead> <tr> <th>Terrestrial Sensitive Environment Type</th><th>Value</th></tr> </thead> <tbody> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </tbody> </table> <p style="text-align: right;">Sum = _____</p>	Terrestrial Sensitive Environment Type	Value											
Terrestrial Sensitive Environment Type	Value												
<p>6. RESOURCES: Assign a score of 5 if any one or more of the following resources is present on an area of observed contamination at the site; assign 0 if none applies.</p> <ul style="list-style-type: none"> • Commercial agriculture • Commercial silviculture • Commercial livestock production or commercial livestock grazing 													

Total of Targets T=

0

SI TABLE 16 (HRS TABLE 5-5): SOIL EXPOSURE PATHWAY
TERRESTRIAL SENSITIVE ENVIRONMENT VALUES

TERRESTRIAL SENSITIVE ENVIRONMENT	ASSIGNED VALUE
Terrestrial critical habitat for Federal designated endangered or threatened species National Park Designated Federal Wilderness Area National Monument	100
Terrestrial habitat known to be used by Federal designated or proposed threatened or endangered species National Preserve (terrestrial) National or State terrestrial Wildlife Refuge Federal land designated for protection of natural ecosystems Administratively proposed Federal Wilderness Area Terrestrial areas utilized by large or dense aggregations of animals (vertebrate species) for breeding	75
Terrestrial habitat used by State designated endangered or threatened species Terrestrial habitat used by species under review for Federal designated endangered or threatened status	50
State lands designated for wildlife or game management State designated Natural Areas Particular areas, relatively small in size, important to maintenance of unique biotic communities	25

SOIL EXPOSURE PATHWAY WORKSHEET NEARBY POPULATION THREAT

LIKELIHOOD OF EXPOSURE		Score	Data Type	Ref
7. Attractiveness/Accessibility (from SI Table 17 or HRS Table 5-6)	Value <u>5</u>			
Area of Contamination (from SI Table 18 or HRS Table 5-7)	Value <u>80</u>			
Likelihood of Exposure (from SI Table 19 or HRS Table 5-8)				

note: if there is no area of
observed contamination,
LE = 0.

LE = 25

TARGETS		Score	Data Type	Ref
8. Assign a score of 0 if Level I or Level II resident individual has been evaluated or if no individuals live within 1/4 mile travel distance of an area of observed contamination. Assign a score of 1 if nearby population is within 1/4 mile travel distance and no Level I or Level II resident population has been evaluated.		0		
9. Determine the population within 1 mile travel distance that is not exposed to a hazardous substance from the site (i.e., properties that are not determined to be Level I or Level II); record the population for each distance category in SI Table 20 (HRS Table 5-10). Sum the population values and multiply by 0.1.		.002		

T = .002

**SI TABLE 17 (HRS TABLE 5-6):
ATTRACTIVENESS/ACCESSIBILITY VALUES**

Area of Observed Contamination	Assigned Value
Designated recreational area	100
Regularly used for public recreation (for example, vacant lots in urban area)	75
Accessible and unique recreational area (for example, vacant lots in urban area)	75
Moderately accessible (may have some access improvements—for example, gravel road) with some public recreation use	50
Slightly accessible (for example, extremely rural area with no road improvement) with some public recreation use	25
Accessible with no public recreation use	10
Surrounded by maintained fence or combination of maintained fence and natural barriers	5
Physically inaccessible to public, with no evidence of public recreation use	0

SI TABLE 18 (HRS TABLE 5-7): AREA OF CONTAMINATION FACTOR VALUES

Total area of the areas of observed contamination (square feet)	Assigned Value
≤ to 5,000	5
> 5,000 to 125,000	20
> 125,000 to 250,000	40
> 250,000 to 375,000	60
> 375,000 to 500,000	80
> 500,000	100

C-40

SI TABLE 20 (HRS TABLE 5-10): DISTANCE-WEIGHTED POPULATION VALUES
FOR NEARBY POPULATION THREAT

Travel Distance Category (miles)	Pop.	Number of people within the travel distance category												Pop. Value
		0	1 to 10	11 to 30	31 to 100	101 to 300	301 to 1,000	1,001 to 3,000	3,001 to 10,001	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	
Greater than 0 to $\frac{1}{4}$	0	0	0.1	0.4	1.0	4	13	41	130	408	1,303	4,081	13,034	
Greater than $\frac{1}{4}$ to $\frac{1}{2}$	0	0	0.05	0.2	0.7	2	7	20	65	204	652	2,041	6,517	
Greater than $\frac{1}{2}$ to 1	7	0	0.02	0.1	0.3	1	3	10	33	102	326	1,020	3,258	
Reference(s) <u>2</u>														Sum = <u>100</u>

SOIL EXPOSURE PATHWAY WORKSHEET (concluded)

WASTE CHARACTERISTICS

10	Assign the hazardous waste quantity score calculated for soil exposure <i>HRS Section 5.1.2.2 and HRS Table 5-2</i>	10
11	Assign the highest toxicity value from SI Table 16 <i>3 or</i> <i>for the soil exposure pathway</i>	10 ⁴
12	Multiply the toxicity and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below:	WC = 18

Product	WC Score
0	0
>0 to <10	1
10 to <100	2
100 to <1,000	3
1,000 to <10,000	6
10,000 to <1E + 05	10
1E + 05 to <1E + 06	18
1E + 06 to <1E + 07	32
1E + 07 to <1E + 08	56
1E + 08 or greater	100

RESIDENT POPULATION THREAT SCORE:

(Likelihood of Exposure, Question 1;
Targets = Sum of Questions 2, 3, 4, 5, 6)

550 x 0 x 2
LE X T X WC
-82,500-

0

NEARBY POPULATION THREAT SCORE:

(Likelihood of Exposure, Question 7;
Targets = Sum of Questions 8, 9)

550 x 0.2 x 18
LE X T X WC
-82,500-

0.9

SOIL EXPOSURE PATHWAY SCORE:

Resident Population Threat + Nearby Population Threat \div 82,500

0.00

(Maximum of 100)

AIR PATHWAY

Air Pathway Observed Substances Summary Table

On SI Table 21, list the hazardous substances detected in air samples of a release from the site. Include only those substances with concentrations significantly greater than background levels. Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For NAAQS/NESHAPS benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter *N/A* for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate targets in the distance category from which the sample was taken and any closer distance categories as Level I. If the percentages are less than 100% or all are *N/A*, evaluate targets in that distance category and any closer distance categories that are not Level I as Level II.

SI TABLE 21: AIR PATHWAY OBSERVED RELEASE SUBSTANCES

Sample ID: _____ Level I _____ Level II _____ Distance from Sources (mi) _____ References _____

Hazardous Substance	Conc. ($\mu\text{g}/\text{m}^3$)	Gaseous Particulate	Benchmark Conc. (NAAQS or NESHAPS)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RfD	% of RfD
Highest Toxicity/Mobility			Highest Percent		Sum of Percents		Sum of Percents	

Sample ID: _____ Level I _____ Level II _____ Distance from Sources (mi) _____ References _____

C-43

Hazardous Substance	Conc. ($\mu\text{g}/\text{m}^3$)	Toxicity/Mobility	Benchmark Conc. (NAAQS or NESHAPS)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RfD	% of RfD
Highest Toxicity/Mobility			Highest Percent		Sum of Percents		Sum of Percents	

Sample ID: _____ Level I _____ Level II _____ Distance from Sources (mi) _____ References _____

Hazardous Substance	Conc. ($\mu\text{g}/\text{m}^3$)	Toxicity/Mobility	Benchmark Conc. (NAAQS or NESHAPS)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RfD	% of RfD
Highest Toxicity/Mobility			Highest Percent		Sum of Percents		Sum of Percents	

AIR PATHWAY WORKSHEET

LIKELIHOOD OF RELEASE	Score	Data Type	Refs
1. OBSERVED RELEASE: If sampling data or direct observation support a release to air, assign a score of 550. Record observed release substances on SI Table 21.			
2. POTENTIAL TO RELEASE: If sampling data do not support a release to air, assign a score of 500. Optionally, evaluate air migration gaseous and particulate potential to release (HRS Section 6.1.2).	500	H	1.4
LR = 500			

TARGETS

<p>3. ACTUAL CONTAMINATION POPULATION: Determine the number of people within the target distance limit subject to exposure from a release of a hazardous substance to the air.</p> <p style="margin-left: 40px;">a) Level I: _____ people x 10 = _____</p> <p style="margin-left: 40px;">b) Level II: _____ people x 1 = _____ Total = _____</p>																					
	0	H	1.4																		
<p>4. POTENTIAL TARGET POPULATION: Determine the number of people within the target distance limit not subject to exposure from a release of a hazardous substance to the air, and assign the total population score from SI Table 22. Sum the values and multiply the sum by 0.1.</p>																					
	4.81	H	8.9																		
<p>5. NEAREST INDIVIDUAL: Assign a score of 50 if there are any Level I targets. Assign a score of 45 if there are Level II targets but no Level I targets. If no Actual Contamination Population exists, assign the Nearest Individual score from SI Table 22.</p>																					
	1	H	8.9																		
<p>6. ACTUAL CONTAMINATION SENSITIVE ENVIRONMENTS: Sum the sensitive environment values (SI Table 13) and wetland acreage values (SI Table 23) for environments subject to exposure from the release of a hazardous substance to the air.</p> <table border="1" style="width: 100%; margin-top: 10px;"> <tr> <th style="width: 80%;">Sensitive Environment Type</th><th style="width: 20%;">Value</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr> <th>Wetland Acreage</th><th>Value</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>	Sensitive Environment Type	Value									Wetland Acreage	Value									
Sensitive Environment Type	Value																				
Wetland Acreage	Value																				
	0	H	2.6																		
<p>7. POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS: Use SI Table 24 to evaluate sensitive environments not subject to exposure from a release.</p>																					
	0	H	1.4																		
<p>8. RESOURCES: Assign a score of 5 if one or more air resources apply within 1/2 mile of a source; assign a 0 if none applies.</p> <ul style="list-style-type: none"> • Commercial agriculture • Commercial silviculture • Major or designated recreation area 																					
	0	H	1.4																		
T = 5.81																					
		H																			

SI TABLE 22 (From HRS TABLE 6-17): VALUES FOR POTENTIAL CONTAMINATION AIR TARGET POPULATIONS

Distance from Site	Pop.	Nearest Individual (choose highest)	Number of People within the Distance Category												Pop Value
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1,000	1,001 to 3,000	3,001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000	
On a source	0	20	4	17	53	164	522	1,633	5,214	16,325	52,137	163,246	521,360	1,632,455	0
0 to $\frac{1}{4}$ mile	0	*	1	4	13	41	131	408	1,304	4,081	13,034	40,812	130,340	408,114	0
$> \frac{1}{4}$ to $\frac{1}{2}$ mile	0	2	0.2	0.9	3	9	28	88	282	882	2,815	8,815	28,153	88,153	0
$> \frac{1}{2}$ to 1 mile	7	①	0.06	0.3	0.9	3	8	26	83	261	834	2,612	8,342	26,119	0.06
> 1 to 2 miles	434	0	0.02	0.09	0.3	0.8	③	8	27	83	266	833	2,659	8,326	3
> 2 to 3 miles	11,707	0	0.009	0.04	0.1	0.4	1	4	12	③8	120	375	1,199	3,755	38
> 3 to 4 miles	7,169	0	0.005	0.02	0.07	0.2	0.7	2	⑦	28	73	229	730	2,285	7
Nearest Individual =															Sum =
															4806

References

8.9

* Score = 20 if the Nearest Individual is within $\frac{1}{8}$ mile of a source; score = 7 if the Nearest Individual is between $\frac{1}{8}$ and $\frac{1}{4}$ mile of a source.

SI TABLE 23 (HRS TABLE
6-18): AIR PATHWAY
VALUES FOR WETLAND
AREA

Wetland Area	Assigned Value
< 1 acre	0
1 to 50 acres	25
> 50 to 100 acres	75
> 100 to 150 acres	125
> 150 to 200 acres	175
> 200 to 300 acres	250
> 300 to 400 acres	350
> 400 to 500 acres	450
> 500 acres	500

SI TABLE 24: DISTANCE WEIGHTS AND
CALCULATIONS FOR AIR PATHWAY POTENTIAL
CONTAMINATION SENSITIVE ENVIRONMENTS

Distance	Distance Weight	Sensitive Environment Type and Value (from SI Tables 13 and 20) ²³	Product
On a Source	0.10	x	
		x	
0 to 1/4 mile	0.025	x	
		x	
		x	
1/4 to 1/2 mile	0.0054	x	
		x	
		x	
1/2 to 1 mile	0.0016	x	
		x	
		x	
1 to 2 miles	0.0005	x	
		x	
		x	
2 to 3 miles	0.00023	x	
		x	
		x	
3 to 4 miles	0.00014	x	
		x	
		x	
> 4 miles	0	x	
Total Environments Score =			0

AIR PATHWAY (concluded)

WASTE CHARACTERISTICS

<p>9. If any Actual Contamination Targets exist for the air pathway, assign the calculated hazardous waste quantity score or a score of 100, whichever is greater; if there are no Actual Contamination Targets for the air pathway, assign the calculated HWO score for sources available to air migration. <u>All sources must meet the minimum size requirement of 0.5 (1-RS 6.1.2.1.2)</u></p>	10																						
<p>10. Assign the highest air toxicity/mobility value from SI Table 21.</p>	1.0																						
<p>11. Multiply the air pathway toxicity/mobility and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below:</p> <table border="1" style="margin: 10px auto; border-collapse: collapse; text-align: center;"> <thead> <tr> <th style="padding: 2px 10px;">Product</th> <th style="padding: 2px 10px;">WC Score</th> </tr> </thead> <tbody> <tr><td style="padding: 2px 10px;">0</td><td style="padding: 2px 10px;">0</td></tr> <tr><td style="padding: 2px 10px;">>0 to <10</td><td style="padding: 2px 10px;">1</td></tr> <tr><td style="padding: 2px 10px;">10 to <100</td><td style="padding: 2px 10px;">2</td></tr> <tr><td style="padding: 2px 10px;">100 to <1,000</td><td style="padding: 2px 10px;">3</td></tr> <tr><td style="padding: 2px 10px;">1,000 to <10,000</td><td style="padding: 2px 10px;">6</td></tr> <tr><td style="padding: 2px 10px;">10,000 to <1E + 05</td><td style="padding: 2px 10px;">10</td></tr> <tr><td style="padding: 2px 10px;">1E + 05 to <1E + 06</td><td style="padding: 2px 10px;">18</td></tr> <tr><td style="padding: 2px 10px;">1E + 06 to <1E + 07</td><td style="padding: 2px 10px;">32</td></tr> <tr><td style="padding: 2px 10px;">1E + 07 to <1E + 08</td><td style="padding: 2px 10px;">56</td></tr> <tr><td style="padding: 2px 10px;">1E + 08 or greater</td><td style="padding: 2px 10px;">100</td></tr> </tbody> </table>	Product	WC Score	0	0	>0 to <10	1	10 to <100	2	100 to <1,000	3	1,000 to <10,000	6	10,000 to <1E + 05	10	1E + 05 to <1E + 06	18	1E + 06 to <1E + 07	32	1E + 07 to <1E + 08	56	1E + 08 or greater	100	<p style="font-size: 24px;">WC = 2</p>
Product	WC Score																						
0	0																						
>0 to <10	1																						
10 to <100	2																						
100 to <1,000	3																						
1,000 to <10,000	6																						
10,000 to <1E + 05	10																						
1E + 05 to <1E + 06	18																						
1E + 06 to <1E + 07	32																						
1E + 07 to <1E + 08	56																						
1E + 08 or greater	100																						

AIR PATHWAY SCORE:


$$\frac{LR \times LE \times T \times WC}{82,500}$$


<div style="font-size: 24px; margin: 0;">0.07</div> <div style="font-size: 10px; margin: 0;">(maximum of 100)</div>

SITE SCORE CALCULATION		S	S ²
GROUND WATER PATHWAY SCORE (S _{GW})		0	0
SURFACE WATER PATHWAY SCORE (S _{SW})		.04	.0016
SOIL EXPOSURE (S _S)		0	0
AIR PATHWAY SCORE (S _A)		.07	.0049
SITE SCORE $\sqrt{\frac{S_{GW}^2 + S_{SW}^2 + S_S^2 + S_A^2}{4}} =$			0.04

COMMENTS

Reference 1

 POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT PART 1 - SITE LOCATION AND INSPECTION INFORMATION		I. IDENTIFICATION	
		01 STATE TN	02 SITE NUMBER D 981473515
II. SITE NAME AND LOCATION			
01 SITE NAME (Legal, Common, or Descriptive Name of Site) Kennon (Genesco) Site		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Split Log Road	
03 CITY Brentwood	04 STATE TN	05 ZIP CODE 37027	06 COUNTY Williamson *
09 COORDINATES LATITUDE 35 57 25 LONGITUDE 86 45 44		10 TYPE OF OWNERSHIP (Check all that apply) <input checked="" type="checkbox"/> A PRIVATE <input type="checkbox"/> B FEDERAL <input type="checkbox"/> C STATE <input type="checkbox"/> D COUNTY <input type="checkbox"/> E MUNICIPAL <input type="checkbox"/> F OTHER	
III. INSPECTION INFORMATION			
01 DATE OF INSPECTION 1, 14, 86 MONTH DAY YEAR	02 SITE STATUS <input type="checkbox"/> ACTIVE <input checked="" type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1978 1978 UNKNOWN BEGINNING YEAR ENDING YEAR	
04 AGENCY PERFORMING INSPECTION (Check all that apply): <input type="checkbox"/> A EPA <input type="checkbox"/> B EPA CONTRACTOR <input type="checkbox"/> C MUNICIPAL <input type="checkbox"/> D MUNICIPAL CONTRACTOR <input checked="" type="checkbox"/> E STATE <input type="checkbox"/> F STATE CONTRACTOR <input type="checkbox"/> G OTHER			
05 CHIEF INSPECTOR Charles Powers	06 TITLE Field Coordinator	07 ORGANIZATION Superfund	08 TELEPHONE NO. (615) 741-6287
09 OTHER INSPECTORS Ronnie Bowers	10 TITLE Environmental Specialist	11 ORGANIZATION Superfund	12 TELEPHONE NO. (615) 741-6287
			()
			()
			()
			()
13 SITE REPRESENTATIVES INTERVIEWED Wayne McCoy	14 TITLE Consultant-Edge	15 ADDRESS 4301 Hillsboro Rd.; Nash.	16 TELEPHONE NO. (615) 383-3588
Ralph Mosely	Genesco	Genesco Park; Nashville	(615) 367-7314
			()
			()
			()
			()
17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION	19 WEATHER CONDITIONS	
IV. INFORMATION AVAILABLE FROM			
01 CONTACT Charles Powers	02 OF (Agency/Organization) TDH&E/Superfund		03 TELEPHONE NO. (615) 741-6287
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Thomas A. Moss	05 AGENCY TDH&E	06 ORGANIZATION Superfund	07 TELEPHONE NO. (615) 741-6287
			08 DATE 5 12 87



- I HIGHLY VOLATILE
- J EXPLOSIVE
- K REACTIVE
- L INCOMPATIBLE
- M NOT APPLICABLE

FD-302 (Rev. 11-27-60)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE TN 02 SITE NUMBER 981473515

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A GROUNDWATER CONTAMINATION 02 ☒ OBSERVED (DATE 1/28/86) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED 410 04 NARRATIVE DESCRIPTION

Hackett Spring sampling shows contamination. Population in area not on public water approximately 410. Site is in Ordovician carbonates with no confining layer for aquifer of concern.

01 ☒ B SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED 0 04 NARRATIVE DESCRIPTION

Seep from site may enter tributary of Little Harpeth River.

01 ☐ C CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

01 ☐ D FIRE EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

01 ☐ E DIRECT CONTACT 02 ☐ OBSERVED (DATE) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

01 ☒ F CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE) ☒ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED Unknown 04 NARRATIVE DESCRIPTION

Seep leaving site. Drums and liquids dumped in pits.

01 ☒ G DRINKING WATER CONTAMINATION 02 ☒ OBSERVED (DATE 1/28/86) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED 410 04 NARRATIVE DESCRIPTION

Hackett Spring sampling shows contamination and is used for drinking water supply. Population within three miles of site not on public water approximately 410.

01 ☐ H WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

01 ☐ I POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D 981473515

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (INCLUDE NUMBER OF SPECIES)

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES
(Spills, Pumps, Standing liquids, Leaking drums)

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED 410

04 NARRATIVE DESCRIPTION

Drums and liquids dumped in pits. By admission of company.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

Drums and liquids dumped in phosphate pits. Site was not a permitted landfill.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED 410

IV. COMMENTS

Residents within a one mile radius of the site have been run municipal water from Brentwood at Genesco's expense.

V. SOURCES OF INFORMATION (CHECK ALL THAT APPLY)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION
01 STATE: TN 02 NUMBER: D 981473515

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A NPDES				
<input type="checkbox"/> B UIC				
<input type="checkbox"/> C AIR				
<input type="checkbox"/> D RCRA				
<input type="checkbox"/> E RCRA INTERIM STATUS				
<input type="checkbox"/> F SPCC PLAN				
<input type="checkbox"/> G STATE (Specify)				
<input type="checkbox"/> H LOCAL (Specify)				
<input type="checkbox"/> I OTHER (Specify)				
<input checked="" type="checkbox"/> J NONE				

III. SITE DESCRIPTION

01 STORAGE/ DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A SURFACE IMPOUNDMENT			<input type="checkbox"/> A INCINERATION	<input type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B PILES			<input type="checkbox"/> B UNDERGROUND INJECTION	
<input type="checkbox"/> C DRUMS, ABOVE GROUND			<input type="checkbox"/> C CHEMICAL/PHYSICAL	
<input type="checkbox"/> D TANK, ABOVE GROUND			<input type="checkbox"/> D BIOLOGICAL	
<input type="checkbox"/> E TANK, BELOW GROUND			<input type="checkbox"/> E WASTE OIL PROCESSING	
<input checked="" type="checkbox"/> F LANDFILL	800	drums	<input type="checkbox"/> F SOLVENT RECOVERY	06 AREA OF SITE
<input type="checkbox"/> G LANDFARM			<input type="checkbox"/> G OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H OPEN DUMP			<input type="checkbox"/> H OTHER (Specify)	
<input type="checkbox"/> I OTHER (Specify)				

07 COMMENTS

Drums and liquids dumped in phosphate pits on site and covered.

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)
☐ A ADEQUATE SECURE ☐ B MODERATE ☐ C INADEQUATE POOR ☒ D INSECURE, UNSOUND DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING LINERS, BARRIERS ETC.

Drums dumped in phosphate pits on site.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE ☐ YES ☒ NO
02 COMMENTS

VI. SOURCES OF INFORMATION (Check all that apply)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I IDENTIFICATION

01 STATE TN 02 SITE NUMBER
D 981473515

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY (Check as applicable)		02 STATUS			03 DISTANCE TO SITE	
	SURFACE	WELL	ENDANGERED	AFFECTED	MONITORED	
COMMUNITY	A <input checked="" type="checkbox"/>	B <input type="checkbox"/>	A <input type="checkbox"/>	B <input type="checkbox"/>	C <input type="checkbox"/>	A <u>> 3</u> (mi)
NON COMMUNITY	C <input type="checkbox"/>	D <input checked="" type="checkbox"/>	D <input type="checkbox"/>	E <input checked="" type="checkbox"/>	F <input type="checkbox"/>	B <u>< 0.25</u> (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)				
<input checked="" type="checkbox"/> A ONLY SOURCE FOR DRINKING <input type="checkbox"/> B DRINKING (Other sources available) COMMERCIAL INDUSTRIAL IRRIGATION (No other water sources available) <input type="checkbox"/> C COMMERCIAL INDUSTRIAL IRRIGATION (Other water sources available) <input type="checkbox"/> D NOT USED UNUSEABLE				
02 POPULATION SERVED BY GROUND WATER <u>410</u>		03 DISTANCE TO NEAREST DRINKING WATER WELL <u>< 0.25</u> (mi)		
04 DEPTH TO GROUNDWATER <u>30</u> (ft)	05 DIRECTION OF GROUNDWATER FLOW <u>Unknown</u>	06 DEPTH TO AQUIFER OF CONCERN <u>30</u> (ft)	07 POTENTIAL YIELD OF AQUIFER <u>Unknown (gpd)</u>	08 SOLE SOURCE AQUIFER <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO

09 DESCRIPTION OF WELLS (including usage, depth, and location relative to buildings and buildings):

Springs and wells within three miles of site used for drinking water. Well depths average approximately 200 feet.

10 RECHARGE AREA <input type="checkbox"/> YES <input type="checkbox"/> NO	COMMENTS	11 DISCHARGE AREA <input type="checkbox"/> YES <input type="checkbox"/> NO	COMMENTS
--	----------	---	----------

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)			
<input checked="" type="checkbox"/> A RESERVOIR, RECREATION DRINKING WATER SOURCE <input type="checkbox"/> B IRRIGATION, ECONOMICALLY IMPORTANT RESOURCES <input type="checkbox"/> C COMMERCIAL INDUSTRIAL <input type="checkbox"/> D NOT CURRENTLY USED			
02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER			
NAME	AFFECTED	DISTANCE TO SITE	
<u>Tributary of Little Harpeth River</u>	<input type="checkbox"/>	<u>0.1</u> (mi)	
<u>Little Harpeth River</u>	<input type="checkbox"/>	<u></u> (mi)	
<u></u>	<input type="checkbox"/>	<u></u> (mi)	

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN			02 DISTANCE TO NEAREST POPULATION <u></u> (mi)
ONE (1) MILE OF SITE A <u></u> NO. OF PERSONS	TWO (2) MILES OF SITE B <u></u> NO. OF PERSONS	THREE (3) MILES OF SITE C <u></u> NO. OF PERSONS	
03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE <u></u>		04 DISTANCE TO NEAREST OFF SITE BUILDING <u></u> (mi)	

05 POPULATION WITHIN VICINITY OF SITE (Provide detailed description of nature of population within 1/2 mile, 1/4 mile, 1/8 mile, 1/16 mile, 1/32 mile, 1/64 mile, 1/128 mile, 1/256 mile, 1/512 mile, 1/1024 mile, 1/2048 mile, 1/4096 mile, 1/8192 mile, 1/16384 mile, 1/32768 mile, 1/65536 mile, 1/131072 mile, 1/262144 mile, 1/524288 mile, 1/1048576 mile, 1/2097152 mile, 1/4194304 mile, 1/8388608 mile, 1/16777216 mile, 1/33554432 mile, 1/67108864 mile, 1/134217728 mile, 1/268435456 mile, 1/536870912 mile, 1/1073741824 mile, 1/2147483648 mile, 1/4294967296 mile, 1/8589934592 mile, 1/17179869184 mile, 1/34359738368 mile, 1/68719476736 mile, 1/137438953472 mile, 1/274877906944 mile, 1/549755813888 mile, 1/1099511627776 mile, 1/2199023255552 mile, 1/4398046511104 mile, 1/8796093022208 mile, 1/17592186044416 mile, 1/35184372088832 mile, 1/70368744177664 mile, 1/140737488355328 mile, 1/281474976710656 mile, 1/562949953421312 mile, 1/1125899906842624 mile, 1/2251799813685248 mile, 1/4503599627370496 mile, 1/9007199254740992 mile, 1/18014398509481984 mile, 1/36028797018963968 mile, 1/72057594037927936 mile, 1/144115188075855872 mile, 1/288230376151711744 mile, 1/576460752303423488 mile, 1/1152921504606846976 mile, 1/2305843009213693952 mile, 1/4611686018427387904 mile, 1/9223372036854775808 mile, 1/18446744073709551616 mile, 1/36893488147419103232 mile, 1/73786976294838206464 mile, 1/147573952589676412928 mile, 1/295147905179352825856 mile, 1/590295810358705651712 mile, 1/1180591620717411303424 mile, 1/2361183241434822606848 mile, 1/4722366482869645213696 mile, 1/9444732965739290427392 mile, 1/18889465931478580854784 mile, 1/37778931862957161709568 mile, 1/75557863725914323419136 mile, 1/151115727451828646838272 mile, 1/302231454903657293676544 mile, 1/604462909807314587353088 mile, 1/1208925819614629174706176 mile, 1/2417851639229258349412352 mile, 1/4835703278458516698824704 mile, 1/9671406556917033397649408 mile, 1/19342813113834066795298816 mile, 1/38685626227668133590597632 mile, 1/77371252455336267181195264 mile, 1/154742504910672534362390528 mile, 1/309485009821345068724781056 mile, 1/618970019642690137449562112 mile, 1/1237940039285380274899124224 mile, 1/2475880078570760549798248448 mile, 1/4951760157141521099596496896 mile, 1/9903520314283042199192993792 mile, 1/19807040628566084398385987584 mile, 1/39614081257132168796771975168 mile, 1/79228162514264337593543950336 mile, 1/158456325028528675187087900672 mile, 1/316912650057057350374175801344 mile, 1/633825300114114700748351602688 mile, 1/1267650600228229401496703205376 mile, 1/2535301200456458802993406410752 mile, 1/5070602400912917605986812821504 mile, 1/10141204801825835211973625643008 mile, 1/20282409603651670423947251286016 mile, 1/40564819207303340847894502572032 mile, 1/81129638414606681695789005144064 mile, 1/162259276829213363391578010288128 mile, 1/324518553658426726783156020576256 mile, 1/649037107316853453566312041152512 mile, 1/1298074214633706907132624082305024 mile, 1/2596148429267413814265248164610048 mile, 1/5192296858534827628530496329220096 mile, 1/10384593717069655257060992658440192 mile, 1/20769187434139310514121985316880384 mile, 1/41538374868278621028243970633760768 mile, 1/83076749736557242056487941267521536 mile, 1/166153499473114484112975882535043072 mile, 1/332306998946228968225951765070086144 mile, 1/664613997892457936451903530140172288 mile, 1/1329227995784915872903807060280344576 mile, 1/2658455991569831745807614120560689152 mile, 1/5316911983139663491615228241121378304 mile, 1/10633823966279326983230456482242756608 mile, 1/21267647932558653966460912964485513216 mile, 1/42535295865117307932921825928971026432 mile, 1/85070591730234615865843651857942052864 mile, 1/170141183460469231731687303715884105728 mile, 1/340282366920938463463374607431768211456 mile, 1/680564733841876926926749214863536422912 mile, 1/1361129467683753853853498429727072845824 mile, 1/2722258935367507707706996859454145691648 mile, 1/5444517870735015415413993718908291383296 mile, 1/10889035741470030830827987437816582766592 mile, 1/21778071482940061661655974875633165533184 mile, 1/43556142965880123323311949751266331066368 mile, 1/87112285931760246646623899502532662132736 mile, 1/174224571863520493293247799005065324265472 mile, 1/348449143727040986586495598010130648530944 mile, 1/696898287454081973172991196020261297061888 mile, 1/1393796574908163946345982392040522594123776 mile, 1/2787593149816327892691964784081045188247552 mile, 1/5575186299632655785383929568162090376495104 mile, 1/11150372599265311570767859136324180752990208 mile, 1/22300745198530623141535718272648361505980416 mile, 1/44601490397061246283071436545296723011960832 mile, 1/89202980794122492566142873090593446023921664 mile, 1/178405961588244985132285746181186892047843328 mile, 1/356811923176489970264571492362373784095686656 mile, 1/713623846352979940529142984724747568191373312 mile, 1/1427247692705959881058285969449495136382746624 mile, 1/2854495385411919762116571938898990272765493248 mile, 1/5708990770823839524233143877797980545530986496 mile, 1/11417981541647679048466287755595961091061972992 mile, 1/22835963083295358096932575511191922182123945984 mile, 1/45671926166590716193865151022383844364247891968 mile, 1/91343852333181432387730302044767688728495783936 mile, 1/182687704666362864775460604089535377456991567872 mile, 1/365375409332725729550921208179070754913983135744 mile, 1/730750818665451459101842416358141509827966271488 mile, 1/1461501637330902918203684832716283019655932542976 mile, 1/2923003274661805836407369665432566039311865085952 mile, 1/5846006549323611672814739330865132078623730171904 mile, 1/11692013098647223345629478661730264157247460343808 mile, 1/23384026197294446691258957323460528314494920687616 mile, 1/46768052394588893382517914646921056628989841375232 mile, 1/93536104789177786765035829293842113257979682750464 mile, 1/187072209578355573530071658587684226515959365500928 mile, 1/374144419156711147060143317175368453031918731001856 mile, 1/748288838313422294120286634350736906063837462003712 mile, 1/1496577676626844588240573268701473812127674924007424 mile, 1/2993155353253689176481146537402947624255349848014848 mile, 1/5986310706507378352962293074805895248510699696029696 mile, 1/11972621413014756705924586149611790497021399392059392 mile, 1/23945242826029513411849172299223580994042798784118784 mile, 1/47890485652059026823698344598447161988085597568237568 mile, 1/95780971304118053647396689196894323976171195136475136 mile, 1/191561942608236107294793378393788647952342390272950272 mile, 1/383123885216472214589586756787577295904684780545900544 mile, 1/766247770432944429179173513575154591809369561091801088 mile, 1/1532495540865888858358347027150309183618739122183602176 mile, 1/3064991081731777716716694054300618367237478244367204352 mile, 1/6129982163463555433433388108601236734474956488734408704 mile, 1/12259964326927110866866776217202473468949912977468817408 mile, 1/24519928653854221733733552434404946937899825954937634816 mile, 1/49039857307708443467467104868809893875799651909875269632 mile, 1/98079714615416886934934209737619787751599303819750539264 mile, 1/196159429230833773869868419475239575503198607639501078528 mile, 1/392318858461667547739736838950479151006397215279002157056 mile, 1/784637716923335095479473677900958302012794430558004314112 mile, 1/1569275433846670190958947355801916604025588861116008628224 mile, 1/3138550867693340381917894711603833208051177722232017256448 mile, 1/6277101735386680763835789423207666416102355444464034512896 mile, 1/12554203470773361527671578846415332832204710888928069025792 mile, 1/25108406941546723055343157692830665664409421777856138051584 mile, 1/50216813883093446110686315385661331328818843555712276103168 mile, 1/100433627766186892221372630771322662657637687111424552206336 mile, 1/200867255532373784442745261542645325315275374222849104412672 mile, 1/401734511064747568885490523085290650630550748445698208825344 mile, 1/803469022129495137770981046170581301261101496891396417650688 mile, 1/1606938044258990275541962092341162602522202993782792835301376 mile, 1/3213876088517980551083924184682325205044405987565585670602752 mile, 1/6427752177035961102167848369364650410088811975131171341205504 mile, 1/12855504354071922204335696738729300820177623950262342682411008 mile, 1/25711008708143844408671393477458601640355247900524685364822016 mile, 1/51422017416287688817342786954917203280710495801049370729644032 mile, 1/102844034832575377634685573909834406561420991602098741459288064 mile, 1/205688069665150755269371147819668813122841983204197482918576128 mile, 1/411376139330301510538742295639337626245683966408394965837152256 mile, 1/822752278660603021077484591278675252491367932816789931674304512 mile, 1/1645504557321206042154969182557350504982735865633579863348609024 mile, 1/3291009114642412084309938365114701009965471731267159726697218048 mile, 1/6582018229284824168619876730229402019930943462534319453394436096 mile, 1/13164036458569648337239753460458804039861886925068638906788872192 mile, 1/26328072917139296674479506920917608079723773850137277813577744384 mile, 1/52656145834278593348959013841835216159447547700274555627155488768 mile, 1/105312291668557186697918027683670432318895095400549111254310977536 mile, 1/210624583337114373395836055367340864637790190801098222508621955072 mile, 1/421249166674228746791672110734681729275580381602196445017243910144 mile, 1/842498333348457493583344221469363458551160763204392890034487820288 mile, 1/1684996666696914987166688442938726917102321526408785780068975640576 mile, 1/3369993333393829974333376885877453834204643052817571560137951281152 mile, 1/6739986666787659948666753771754907668409286105635143120275902562304 mile, 1/13479973333575319897333507543509815336818572211270286240551805124608 mile, 1/26959946667150639794667015087019630673637144422540572481103610249216 mile, 1/53919893334301279589334030174039261347274288845081144962207220498432 mile, 1/107839786668602559178668060348078522694548577690162289924414440996864 mile, 1/215679573337205118357336120696157045389097155380324579848828881993728 mile, 1/431359146674410236714672241392314090778194310760649159697657763987456 mile, 1/862718293348820473429344482784628181556388621521298319395315527974912 mile, 1/1725436586697640946858688965569256363112777243042596638790631055949824 mile, 1/3450873173395281893717377931138512726225554486085193277581262111899648 mile, 1/6901746346790563787434755862277025452451108972170386555162524223799296 mile, 1/13803492693581127574869511724554050904902217944340773110325048447598592 mile, 1/27606985387162255149739023449108101809804435888681546220650096895197184 mile, 1/55213970774324510299478046898216203619608871777363092441300193790394368 mile, 1/110427941548649020598956093796432407239217743554726184882600387580788736 mile, 1/220855883097298041197912187592864814478435487109452369765200775161577472 mile, 1/441711766194596082395824375185729628956870974218904739530401550323154944 mile, 1/883423532389192164791648750371459257913741948437809479060803100646309888 mile, 1/1766847064778384329583297500742918515827483896875618958121606201292619776 mile, 1/3533694129556768659166595001485837031654967793751237916243212402585239552 mile, 1/7067388259113537318333190002971674063309935587502475832486424805170479104 mile, 1/14134776518227074636666380005943348126619871175004951664972849610340958208 mile, 1/28269553036454149273332760011886696253239742350009903329945699220681916416 mile, 1/56539106072908298546665520023773392506479484700019806659891398441363832832 mile, 1/113078212145816597093331040047546785012958969400039613319782796882727665664 mile, 1/226156424291633194186662080095093570025917938800079226639565593765455331328 mile, 1/4523128485832



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

1. IDENTIFICATION

01 STATE/C SITE NUMBER

TN D 981473515

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (check one)

☐ A $10^{-8} - 10^{-6}$ cm/sec ☐ B $10^{-4} - 10^{-6}$ cm/sec ☐ C $10^{-4} - 10^{-2}$ cm/sec ☐ D GREATER THAN 10^{-2} cm/sec

02 PERMEABILITY OF BEDROCK (check one)

☐ A IMPERMEABLE
(less than 10^{-8} cm/sec) ☐ B RELATIVELY IMPERMEABLE
($10^{-8} - 10^{-6}$ cm/sec) ☒ C RELATIVELY PERMEABLE
($10^{-2} - 10^{-4}$ cm/sec) ☐ D VERY PERMEABLE
(greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK

10 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

(ft)

05 SOIL pH

06 NET PRECIPITATION

48 (in)

07 ONE YEAR 24 HOUR RAINFALL

3 (in)

08 SLOPE

SITE SLOPE
4 %

DIRECTION OF SITE SLOPE

SW

TERRAIN AVERAGE SLOPE

4 %

09 FLOOD POTENTIAL

SITE IS IN YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

OTHER

A (mi)

B (mi)

12 DISTANCE TO CRITICAL HABITAT (or endangered species)

(mi)

ENDANGERED SPECIES

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL/STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A (mi)

B (mi)

C (mi)

D (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Site is in rural area on the toe of hill with a number of old farmhouses and newer residences in the vicinity.

VII. SOURCES OF INFORMATION (See SOURCE REFERENCES on C-1500 form) (APPENDIX A/C-1000)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE TN 02 SITE NUMBER D 981473515

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATE OF RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL			
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input type="checkbox"/> GROUND <input type="checkbox"/> AERIAL		02 IN CUSTODY OF _____ <small>(NAME OF ORGANIZATION OR INDIVIDUAL)</small>
03 MAPS <input type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS _____	

V. OTHER FIELD DATA COLLECTED (Provide Narrative Description)

Numerous wells have been sampled within the vicinity of the site as well as pits on site.

VI. SOURCES OF INFORMATION (See Section 1.0 for Guidance) (State the source and date of information)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION
C1 STATE C2 SITE NUMBER
TN D 981473515

II. CURRENT OWNER(S)				PARENT COMPANY (IF APPLICABLE)			
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
Emmett Kennon							
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
2934 Sidco Drive							
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
Nashville		TN	37204				
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
III. PREVIOUS OWNER(S) (Last model previous report)				IV. REALTY OWNER(S) (If applicable, last model previous report)			
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
V. SOURCES OF INFORMATION (Use specific references: e.g., State and Federal agency reports)							
State Superfund Files							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART B - OPERATOR INFORMATION

I. IDENTIFICATION

D1 STATE D2 SITE NUMBER
TN D 981473515

II. CURRENT OPERATOR (Provide information from owner)				OPERATOR'S PARENT COMPANY (if applicable)			
D1 NAME		D2 D+B NUMBER		D1 NAME		D2 D+B NUMBER	
D3 STREET ADDRESS (P.O. Box, RFD, etc.)		D4 SIC CODE		D3 STREET ADDRESS (P.O. Box, RFD, etc.)		D4 SIC CODE	
D5 CITY		D6 STATE	D7 ZIP CODE	D5 CITY		D6 STATE	D7 ZIP CODE
D8 YEARS OF OPERATION		D9 NAME OF OWNER					
III. PREVIOUS OPERATOR(S) (List most recent first; provide only 4 operators maximum)				PREVIOUS OPERATORS' PARENT COMPANIES (if applicable)			
D1 NAME		D2 D+B NUMBER		D1 NAME		D2 D+B NUMBER	
D3 STREET ADDRESS (P.O. Box, RFD, etc.)		D4 SIC CODE		D3 STREET ADDRESS (P.O. Box, RFD, etc.)		D4 SIC CODE	
D5 CITY		D6 STATE	D7 ZIP CODE	D5 CITY		D6 STATE	D7 ZIP CODE
D8 YEARS OF OPERATION		D9 NAME OF OWNER DURING THIS PERIOD					
D1 NAME		D2 D+B NUMBER		D1 NAME		D2 D+B NUMBER	
D3 STREET ADDRESS (P.O. Box, RFD, etc.)		D4 SIC CODE		D3 STREET ADDRESS (P.O. Box, RFD, etc.)		D4 SIC CODE	
D5 CITY		D6 STATE	D7 ZIP CODE	D5 CITY		D6 STATE	D7 ZIP CODE
D8 YEARS OF OPERATION		D9 NAME OF OWNER DURING THIS PERIOD					
D1 NAME		D2 D+B NUMBER		D1 NAME		D2 D+B NUMBER	
D3 STREET ADDRESS (P.O. Box, RFD, etc.)		D4 SIC CODE		D3 STREET ADDRESS (P.O. Box, RFD, etc.)		D4 SIC CODE	
D5 CITY		D6 STATE	D7 ZIP CODE	D5 CITY		D6 STATE	D7 ZIP CODE
D8 YEARS OF OPERATION		D9 NAME OF OWNER DURING THIS PERIOD					
IV. SOURCES OF INFORMATION (City records, interviews, etc.; specify how gathered information reported)							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D 981473515

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	
05 CITY	06 STATE 07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
General Adhesives			
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
6100 Centennial Blvd.			
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
Nashville	TN 37202		
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
Genesco			
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
Genesco Park			
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
Nashville	TN 37202		

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

V. SOURCES OF INFORMATION (Check appropriate reference(s). Do not check more than one source.)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

1 IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 0 981473515

II PAST RESPONSE ACTIVITIES

01 ☐ A WATER SUPPLY CLOSED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ B TEMPORARY WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☒ C PERMANENT WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE 11/86

03 AGENCY Superfund

Brentwood water lines run to residents within one mile of site. Paid for by Genesco.

01 ☐ D SPILLED MATERIAL REMOVED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ E CONTAMINATED SOIL REMOVED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ F WASTE REPACKAGED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ G WASTE DISPOSED ELSEWHERE
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ H ON SITE BURIAL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ I IN SITU CHEMICAL TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ J IN SITU BIOLOGICAL TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ K IN SITU PHYSICAL TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ L ENCAPSULATION
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ M EMERGENCY WASTE TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ N CUTOFF WALLS
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☒ O EMERGENCY DIKING/SURFACE WATER DIVERSION
04 DESCRIPTION

02 DATE 1/86

03 AGENCY Superfund

Genesco had silt fence constructed to limit off site contamination.

01 ☐ P CUTOFF TRENCHES/SUMP
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ Q SUBSURFACE CUTOFF WALL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D 981473515

II PAST RESPONSE ACTIVITIES (continued)

01 ☐ R BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ S CAPPING/COVERING
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ T BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ C GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ V BOTTOM SEALED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ W GAS CONTROL
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ X FIRE CONTROL
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Y LEACHATE TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Z AREA EVACUATED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 1 ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 2 POPULATION RELOCATED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 3 OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE

03 AGENCY

III SOURCES OF INFORMATION (Cite source references, e.g., State log, sampling analysis reports)

State Superfund Files; Geraghty and Miller 1986 Report



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I IDENTIFICATION

C1 STATE	C2 SITE NUMBER
TN	D 981473515

II. ENFORCEMENT INFORMATION

D1 PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☐ NO

D2 DESCRIPTION OF FEDERAL STATE LOCAL REGULATORY/ENFORCEMENT ACTION

III. SOURCES OF INFORMATION (CAP SPECIFIC REFERENCES & D STATE AND REGIONAL REPORTS)

KENNON SITE

Site No. TND 981473575

Reference No. 1

Sampling log

Superfund File

94-508

KENNON SITE (GENESCO)

<u>Date</u>	<u>EVENT</u>
1/15/86	Monitoring well installation begins.
1/22/86	Areas of suspected pits excavated. Samples of water, waste, and soil obtained.
1/24/86	Further excavation of suspected pits to determine extent of dumping. Monitoring well installation continues. Local person informs state personnel of nearby wells and springs being used for drinking water.
1/28/86	Sampling of offsite Hacket Spring and Fletcher Well. Seep below site is also sampled. Full priority pollutants analysis is requested.
1/29/86	Resampled Fletcher Well (previously sampled 1/28/86) due to concern of owner over taking sample from his holding tank.
2/7/86	Resample Hacket Spring after heavy rain.
2/11/86	Sample Hacket Spring for verification of analysis by State Laboratory. Sample Myatt well also.
2/12/86	Sample offsite drinking water sources - Steve Smith Spring, Pewitt Well, Fischer Well, Johnson Well, Stubblefield Spring.
2/13/86	Sample offsite drinking water sources - Glass Well, Levine Well, Sharp Spring, Reece Smith Spring.
2/14/86	Sample offsite drinking water sources - Foster Well, Little Harpeth River at Moores Lane Bridge.
2/17/86	Sample offsite drinking water sources - Hacket Spring at inside Tap, Allen Well, Primm Spring, Sullivan Well, Legieza Well.
2/18/86	Meeting with Genesco Consultants to discuss sampling plans for Shallow Monitoring Wells onsite. Determined areas of soil borings and offsite shallow monitoring wells. Charcoal filter was installed at Hacket's home by Genesco.
2/21/86	Sample Hacket water supply at Tap after installation of the charcoal filter. Split one sample of Monitoring well #8 onsite with Genesco Consultant. Sample spring below Edgar Johnson's home.
2/24/86	Resample Legieza well to verify results with State Laboratory.

<u>Date</u>	<u>Event</u>
2/25/86	Sample offsite drinking water sources - Denny Well, Waggoner Well, Lowe Well, Hackett Creek (above spring), Hackett Creek (below Spring , Little Harpeth (below Hackett Creek), Dickie Well, Beyer Well, Clark Well, Dalton Well. Sampled offsite drinking water sources - Scott Well, Myatt Well, Mallory Well, Howe Well, Carson Spring.
2/26/86	All individuals whose Analysis had been returned were called and informed of these results. Sampled offsite drinking water sources - Turner Well, Clark Well, Burris Well.
2/28/86	Sample offsite drinking water sources - Atkinson Well, Denny Well (resampled), Shaw Well.
3/3/86	Drilling of shallow monitoring wells continue. Genesco consultants are running an Electro Magnetic survey of the site to determine areas of dumping.
3/4/86	Genesco Consultants are running a ground penetrating radar survey. Drill crew is still working. Delivered sample results to residences.
3/5/86	Sample Holt Well.
3/6/86	Talked to several citizens about there wells. (Outside 3 mile radius).
3/7/86	Sample offsite drinking water sources - Mallory Well, Myatt Well, Pewitt Well, Anderson Well.
3/11/86	Sample offsite drinking water sources - Dennison Well, Harmon Well.

RB/lag Customs House #8

KENNON SITE/GENESCO SAMPLING

FAMILY NAME	SPRING/WELL	SAMPLE DATE	RESULTS	REPORT ON FILE
Hackett	Spring	1-28-86	Detected	Yes
		2-7-86	Detected	Yes
		2-11-86	Detected	Yes
		2-17-86	Detected	Yes
		2-21-86	No results yet	
Fletcher	Well	1-29-86	Non-detected	Yes
Myatt	Well	2-11-86	Non-detected	Yes
Smith (Steve)	Spring	2-12-86	Non-detected	Yes
Pewitt	Well	2-12-86	Non-detected	Yes
Fisher	Well	2-16-86	Non-detected	Yes
Johnson	Well	2-16-86	Non-detected	Yes
Stubblefield (Younger & Stubblefield)	Spring	2-12-86	Non-detected	Yes
Glass	Well	2-13-86	Non-detected	Yes
Foster	Well	2-14-86	Non-detected	Yes
Levine	Well	2-13-86	Non-detected	Yes
Sharp/Farrar	Spring	2-13-86	Non-detected	Yes
Smith (Reece)	Spring	2-13-86	Non-detected	Yes
Allen	Well	2-17-86	Non-detected	Yes
Primm	Spring	2-17-86	Non-detected	Yes
Sullivan	Well	2-17-86	Non-detected	Yes
Legieza	Well	2-17-86	Detected	Yes
Little Harpeth	River	2-14-86	Non-detected	Yes

CHRONOLOGY - KENNON (GENESCO SITE)

- May 21, 1985 By a letter dated 5/21/85 signed by Ralph Mosley, Genesco Inc., Genesco Park, Nashville, Tennessee 37202 notified the Division of Solid Waste Management of a chemical waste site once used by a division of Genesco, Inc. (General Adhesives). The site is on a farm owned by Emmett N. Kennon. Genesco, Inc. solicited the assistance and approval of TDHE with respects to certain actions. Genesco indicated that some of the waste was buried in barrels (50 - 80 barrels) and the remainder (44,000 gallons) was poured into a phosphate pit or pits. Genesco, Inc. stated that they believed the waste contained water based adhesives and may have contained acetone, ethyl acetate, hexane, methylene chloride, methylethyl ketone, rubber solvent, toluene, 111-trichlorolthane, trichloroethylene, and organic fillers. Genesco, Inc. expressed the intent to excavate, exhume, analyze and dispose of contaminated materials.
- May 31, 1985 Don Shackleford, Head of Superfund Section, Barry Atnip, Field Coordinator, Superfund, Ralph Mosley, Genesco, and Wayne McCoy, Resource Consultant met to discuss the site. Genesco indicated that they were not sure if they really had a problem or if there was a problem they believed that it possibly was not very extensive. They agreed to submit an investigation plan by August 15, 1985.
- July 2, 1985 Barry Atnip, Coordinator Superfund, Ralph Mosley, Genesco, Ed Wilson and Mark Levy of Geologic Associates, Edgar Johnson (Kennon Foreman) and Emmett Kennon made a vist to the site. This was a preliminary site investigation to visually assess the site. The trip report stated in part that there were no houses near, utility water available to homes in the area and pits were covered and sown in grass.
- August 13, 1985 A proposed plan of investigation dated August 9, 1985 was received.
- August 22, 1985 Barry Atnip, Coordinator, Superfund, Todd Hughes, Geologist, Superfund and Charles Powers, Coordinator, Superfund met to review the proposed plan of investigation. Several revisions were agreed on as being needed.
- August 28, 1985 A letter to Ralph Mosley, Genesco, dated August 28, 1985 signed by Charles H. Powers stating the required revisions of the proposed plan of investigation was mailed.
- September 13, 1985 As requested by Ralph Mosely, Genesco. Todd Hughes, Geologist, Wayne McCoy of Resource Consultants and Charles Powers, Coordinator, Superfund met to discuss the required revisions to the site investigation plan.

September 25, 1985 A revised proposed plan of investigation dated September 20, 1985 was received from Genesco with cover letter from Ralph Mosely to Charles Powers. The plan included all the required revisions.

October 2, 1985 By letter dated October 2, 1984 from Charles Powers, Superfund to Ralph Mosely, Genesco, the revised plan of investigation dated September 20, 1985 was approved.

October 9, 1985 Charles Powers, was notified by phone by Ralph Mosely that Task A and B had been started.

December 12, 1985 Charles Powers, Coordinator, Todd Hughes, Geologist, Ralph Mosely, Genesco, Wayne McCoy Resource Consultants, and Mark Levy of Geologic Associates met for an update on the work. Wayne McCoy stated that Task A and B was completed. They presented a map indicating locations of trenches and proposed locations of wells for installation of piezometers. The start of the well drilling and pit excavation for exact location and testing would start immediately after January 1, 1986.

December 23, 1985 Received from Ralph Mosely, Genesco to Charles Powers, Superfund a ground water monitoring configuration which Todd Hughes had requested.

January 6, 1986 Todd Hughes and Charles Powers sent letter dated January 6, 1986 to Ralph Mosely stating our concerns relative to the kind of pipe proposed to be used and that if the wells were to be used for long term sampling then a different kind of pipe must be used.

January 14, 1986 Charles Powers, Coordinator and Ronnie Bowers, Superfund made a site visit and joined Wayne McCoy of Edge and Ralph Mosely, Genesco. Geologic Associates started drilling the wells.

January 17, 1986 Ronnie Bowers, Superfund and Charles Powers, Superfund made a site visit. We saw Mr. Hobbs of Geologic Associates. Two wells had been completed and a third well started.

January 22, 1986 Excavation of the pits for sampling started. Ronnie Bowers and Todd Hughes collected samples for Superfund. Geologic Associates did sampling for Genesco.

January 27, 1986 Meeting with Genesco, Inc. Don Shackleford, Todd Hughes, Ralph Mosely, Wayne McCoy, Ronnie Bowers, Mark Levy and Charles Powers attended. This was a session of updating. It appeared that the problem was much larger than expected. Sampling was discussed. We became aware that there were wells and springs in the area used for drinking water. An

immediate sampling plan and information to homeowners was initiated. This included immediate samples of Mr. Hackett's and Dr. Fletcher's drinking water.

Ralph Mosely stated that the transport of waste was by Mr. Kennon driver and truck and possibly a vehicle owned or operated by Genesco.

January 28, 1986	Sampling was started on Mr. Hackett's spring. A complete list of water supply sampling and dates are attached. This list is complete up to 2-14-86. Sampling of water supply is continuing as of February 25, 1986.
February 11, 1986	Laboratory report received relative to Hackett's spring. Genesco, Inc. made plan and commitment to furnish bottled water to all households in the area if they wanted the service.
February 13, 1986	State Laboratory verified sample results of Hacketts Spring. Dr. Michael T. Bruner, Assistant Commissioner, Department of Health and Environment issued a press release.
February 18, 1986	A charcoal filter system installed in Hacketts Water supply.
February 19, 1986	An update meeting with the following present: Levy, Seaborg, Kennon, Mosely, McCoy, Shackelford, Roland, Hughes, Powers, Bowers and Ault. Mr. Shackelford stated that we would prepare an order and would attempt to get it through the system in one (1) month. Mr. Kennon, in response to a question, stated that to the best of his knowledge no one else used the site for a dump. A letter signed by James Ault, Director of Superfund dated February 19, 1986 to Mr. Kennon and Ralph Mosely requesting them to respond to us relative to all known responsible parties.
February 24, 1986	Dr. Michael T. Bruner, Assistant Commissioner attended the Brentwood City Commission meeting and presented the state's position.

DS/sdm/CH-8

KENNON SITE GENESCO

TND 981473515

SITE SUMMARY

The Kennon Site (Genesco) is located near the junction of Split Log Road and Wilson Pike east of Brentwood in Williamson County, Tennessee.

The site is on the Kennon farm in an area of old phosphate pits where in 1978 General Adhesives, a subsidiary of Genesco, dumped approximately 800 drums of organic solvents, organic fillers, and adhesives. The pits were then filled. The state was informed of this unregistered landfill by Genesco in 1985. Chemicals detected on site at appreciable levels in 1986 sampling were toluene; tetrachloroethylene; 1,1,1 trichloroethylene; 2 Butanone (Methyl ethyl ketone); xylene; hexane; 1,1,1 trichloroethene; acetone; 1,2 dichloroethane; and benzene.

Several private wells are still in use within three miles of the site and ground water contamination was discovered in early 1986. Residents with wells within a one mile radius (a population of approximately 118) were provided with bottled water at their discretion by Genesco until water lines could be run from Brentwood. Brentwood water is supplied by Metro Nashville and Harpeth Valley Utilities. The total population within three miles on groundwater prior to remedial action of running water lines was 410.

RCRA SUMMARY
KENNON SITE (GENESCO)
TND 981473515

The Kennon Site (Genesco) is a farm with phosphate pits that was used to dump approximately 800 drums of organic solvents, fillers, and adhesives in 1978. The site was never registered as a landfill and did not have a TSD permit.

TAM/ib

Facility name: Kennon Site (Genesco) TND 981473515

Location: Brentwood, Williamson County, Tennessee

EPA Region: IV

Person(s) in charge of the facility: Emmett Kennon
Ralph Mosely, Genesco

Name of Reviewer: Thomas A. Moss Date: 4/30/87

General description of the facility:
 (For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

The Kennon Site (Genesco) is a drum disposal site used by General Adhesives,
a subsidiary of Genesco, in 1978 to dispose of approximately 800 drums of
organic solvents, fillers, water based adhesives by dumping them in phosphate
pits and covering the pits at the site. The aquifer of concern is a car-
bonate, fracture-based, solutionally enlarged aquifer. A population of
approx 410 persons were on private wells within 3 miles of the site prior to
the remedial action of water lines being run.

Scores: $S_M = 25.2$ ($S_{gw} = 43.2$ $S_{sw} = 5.3$ $S_a = NR$)
 $S_{FE} =$ Not Rated
 $S_{DC} =$ Not Rated

FIGURE 1
HRS COVER SHEET

Kennon Site

TND 981473515

Ground Water Route Work Sheet

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)
1 Observed Release	0 (45)	1	45	45	3.1
If observed release is given a score of 45, proceed to line 14.					
If observed release is given a score of 0, proceed to line 2.					
2 Route Characteristics					3.2
Depth to Aquifer of Concern	0 1 2 3	2		6	
Net Precipitation	0 1 2 3	1		3	
Permeability of the Unsaturated Zone	0 1 2 3	1		3	
Physical State	0 1 2 3	1		3	
Total Route Characteristics Score				15	
3 Containment	0 1 2 3	1		3	3.3
4 Waste Characteristics					3.4
Toxicity/Persistence	0 3 6 9 12 (15) 18	1	15	18	
Hazardous Waste Quantity	0 1 2 3 (4) 5 6 7 8	1	4	8	
Total Waste Characteristics Score			19	26	
5 Targets					3.5
Ground Water Use	0 1 2 (3)	3	9	9	
Distance to Nearest Well/Population Served	0 4 6 8 10 12 16 18 (20) 24 24 30 32 35 40	1	20	40	
Total Targets Score			29	49	
6 If line 1 is 45, multiply (45) x (15) x (5)					
If line 2 is 0, multiply (0) x (3) x (1) x (15)					
Divide line 6 by 100 and multiply by 100			24,795	24,795	
Score line 6 by 100 and multiply by 100			43.2	43.2	

FIGURE 2
GROUND WATER SOURCE WORK SHEET

Surface Water Route Work Sheet							
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)		
1 Observed Release	0 45	1	0	45	4.1		
If observed release is given a value of 45, proceed to line 4 . If observed release is given a value of 0, proceed to line 2 .							
2 Route Characteristics					4.2		
Facility Slope and Intervening Terrain	0 1 2 3	1	1	3			
1-yr. 24-hr. Rainfall	0 1 2 3	1	2	3			
Distance to Nearest Surface Water	0 1 2 3	2	4	8			
Physical State	0 1 2 3	1	3	3			
Total Route Characteristics Score			10	15			
3 Containment	0 1 2 3	1	3	3	4.3		
4 Waste Characteristics					4.4		
Toxicity/Persistence	0 3 6 9 12 15 18	1	15	18			
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1	4	8			
Total Waste Characteristics Score			19	26			
5 Targets					4.5		
Surface Water Use	0 1 2 3	3	6	9			
Distance to a Sensitive Environment	0 1 2 3	2	0	6			
Population Served/Distance to Water Intake Downstream	0 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40			
Total Targets Score			6	55			
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			3,420	64,350			
7 Divide line 6 by 64,350 and multiply by 100			$S_{SW} = 5.3$				

FIGURE 7
SURFACE WATER ROUTE WORK SHEET

NOT RATED

Air Route Work Sheet				Kennon Site TND 981473515	
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)
<input type="checkbox"/> Observed Release	0 45	1		45	5.1
Date and Location:					
Sampling Protocol:					
If line <input type="checkbox"/> 1 is 0, the $S_a = 0$. Enter on line <input type="checkbox"/> 5. If line <input type="checkbox"/> 1 is 45, then proceed to line <input type="checkbox"/> 2.					
<input type="checkbox"/> 2 Waste Characteristics					5.2
Reactivity and Incompatibility	0 1 2 3	1		3	
Toxicity	0 1 2 3	3		9	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8	
Total Waste Characteristics Score				20	
<input type="checkbox"/> 3 Targets					5.3
Population Within 4-Mile Radius	{ 0 9 12 15 18 21 24 27 30	1		30	
Distance to Sensitive Environment	0 1 2 3	2		6	
Land Use	0 1 2 3	1		3	
Total Targets Score				39	
<input type="checkbox"/> 4 Multiply <input type="checkbox"/> 1 x <input type="checkbox"/> 2 x <input type="checkbox"/> 3				35.100	
<input type="checkbox"/> 5 Divide line <input type="checkbox"/> 4 by 35.100 and multiply by 100			$S_a =$		

FIGURE 9
AIR ROUTE WORK SHEET

	S	S ²
Groundwater Route Score (S _{gw})	43.2	1866.24
Surface Water Route Score (S _{sw})	5.3	28.09
Air Route Score (S _a)	Not Rated	Not Rated
$S_{gw}^2 + S_{sw}^2 + S_a^2$		1894.33
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		43.5
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M =$		25.2

FIGURE 10
WORKSHEET FOR COMPUTING S_M

NOT RATED

Fire and Explosion Work Sheet		Kennon Site IND 981473515			
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref (Section)
1 Containment	1 3	1		3	7.1
2 Waste Characteristics					7.2
Direct Evidence	0 3	1		3	
Ignitability	0 1 2 3	1		3	
Reactivity	0 1 2 3	1		3	
Incompatibility	0 1 2 3	1		3	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8	
Total Waste Characteristics Score				20	
3 Targets					7.3
Distance to Nearest Population	0 1 2 3 4 5	1		5	
Distance to Nearest Building	0 1 2 3	1		3	
Distance to Sensitive Environment	0 1 2 3	1		3	
Land Use	0 1 2 3	1		3	
Population Within 2-Mile Radius	0 1 2 3 4 5	1		5	
Buildings Within 2-Mile Radius	0 1 2 3 4 5	1		5	
Total Targets Score				24	
4 Multiply 1 x 2 x 3				1,440	
5 Divide line 4 by 1,440 and multiply by 100			SFE =		

FIGURE 11
FIRE AND EXPLOSION WORK SHEET

NOT RATED					
Direct Contact Work Sheet				Kennon Site TND 981473515	
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)
<input type="checkbox"/> 1 Observed Incident	0 45	1		45	8.1
If line <input type="checkbox"/> 1 is 45, proceed to line <input type="checkbox"/> 2 If line <input type="checkbox"/> 1 is 0, proceed to line <input type="checkbox"/> 2					
<input type="checkbox"/> 2 Accessibility	0 1 2 3	1		3	8.2
<input type="checkbox"/> 3 Containment	0 15	1		15	8.3
<input type="checkbox"/> 4 Waste Characteristics Toxicity	0 1 2 3	5		15	8.4
<input type="checkbox"/> 5 Targets					8.5
Population Within a 1-Mile Radius	0 1 2 3 4 5	4		20	
Distance to a Critical Habitat	0 1 2 3	4		12	
Total Targets Score					32
<input type="checkbox"/> 6 If line <input type="checkbox"/> 1 is 45, multiply <input type="checkbox"/> 1 x <input type="checkbox"/> 4 x <input type="checkbox"/> 5 If line <input type="checkbox"/> 1 is 0, multiply <input type="checkbox"/> 2 x <input type="checkbox"/> 3 x <input type="checkbox"/> 4 x <input type="checkbox"/> 5					21,600
<input type="checkbox"/> 7 Divide line <input type="checkbox"/> 6 by 21,600 and multiply by 100				SDC =	

FIGURE 12
DIRECT CONTACT WORK SHEET

**DOCUMENTATION RECORDS
FOR
HAZARD RANKING SYSTEM**

FACILITY NAME: Kennon Site (Genesco) TND 981473515

FACILITY DESCRIPTION: Phosphate pits on farm filled with dumped liquids and drums and covered.

LOCATION: Brentwood, Tennessee

DATE SCORED: April 28, 1987

PERSON SCORING: Thomas A. Moss

PRIMARY SOURCE(S) OF INFORMATION (e.g., EPA region, state, FIT, etc.):

State Superfund Files

FACTORS NOT SCORED DUE TO INSUFFICIENT INFORMATION:

Air, Fire and Explosion, Direct Contact

COMMENTS OR QUALIFICATIONS:

Water lines have been run to houses that were on private wells within a one-mile radius of the site.

GROUND WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected (5 maximum):

Trans-1,2-dichloroethene; toluene; 1,1,-dichloroethane; and 1,1,1-trichloroethane detected in Hackett Spring and on site monitoring wells by State Superfund sampling (Ref. 1, 2) and are known to be toxic (Ref. 3, 4). Background well (Johnson) showed no contamination (Ref. 1, 2).

Rationale for attributing the contaminants to the facility:

Contamination found in monitoring wells on site, no contamination found in background well (Ref. 1).

2 ROUTE CHARACTERISTICS

Depth to Aquifer of Concern

Name/description of aquifer(s) of concern:

The aquifer of concern would be the Ordovician limestone formations (Ref. 5, 6) of the Bigby-Cannon Limestone (70-130 ft. thick), Hermitage Formation (50-150 ft. thick), and Carters Limestone (70 ft. thick). The majority of private wells in the area have depths of 150-350 ft. (Ref. 7) and would be completed in the Hermitage Formation or Carters Limestone (Ref. 5, 6) (50-100 ft. thick). See attachment 2A for further discussion of aquifer of concern.

Depth(s) from the ground surface to the highest seasonal level of the saturated zone (water table(s)) of the aquifer of concern:

N/A

Depth from the ground surface to the lowest point of waste disposal/storage:

N/A

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

N/A

Mean annual lake or seasonal evaporation (list months for seasonal):

N/A

Attachment 2A
Aquifer of Concern

There are no confining layers present within the Bigby-Cannon Limestone, Hermitage Formation, and Carters Limestone. The Bigby-Cannon Limestone contains facies ranging from a microcrystalline limestone facies to medium- and coarse-grained limestone facies (Ref. 5). The Bigby-Cannon has sinkhole development and deep weathering along vertical fractures (Ref. 6). Numerous springs are present in the area (Ref. 2).

The underlying Hermitage Formation consists of a coquina (shell hash) facies with shale partings, a laminated argillaceous limestone facies, and a limestone with shale partings (Ref. 5). The Carters Limestone underlying the Hermitage consists of an upper and lower limestone member of cryptocrystalline to fine-grained limestone with shale partings separated by a thin bentonite clay (Ref. 5). The Carters weathers to a brown plastic clay with some sinkholes (Ref. 6).

Net precipitation (subtract the above figures):

N/A

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

N/A

Permeability associated with soil type:

N/A

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

N/A

* * *

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

N/A

Method with highest score:

N/A

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

1,1-dichloroethene and 1,1-dichloroethane detected in pits A and B and monitoring well #8 on site and not detected in background well (Johnson) by State Superfund sampling (Ref. 1, 2, 8).

Compound with highest score:

1,1-dichloroethene has a toxicity rating of 3 (Ref. 4) and a persistence rating of 2 (Ref. 9).

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

800 drums

Basis of estimating and/or computing waste quantity:

Genesco admission of the dumping of approximately 800 55-gallon barrels of waste material containing organic solvents, organic fillers, and water based adhesives at the site by their subsidiary General Adhesives (Ref. 10).

5 TARGETS

Ground Water Use

Use(s) and aquifer(s) of concern within a 3-mile radius of the facility:

Drinking water with no municipal water presently available (Ref. 11, 12). Genesco paid for lines to be run from Brentwood for the area within a one-mile radius of the site that had no municipal water source.

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

Hackett Spring is used as a drinking water supply by the Hacketts (Ref. 13). Hackett house is on east side of Wilson Pike approximately 1000 ft. north of Split Log Road (Ref. 2, 14, 15).

Distance to above well or building:

Hackett Spring is contaminated (Ref. 1), distance would be considered as zero. Actual distance from the pits is approximately 1500 ft. (Ref. 14, 15).

Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

108 houses not on public water for a population of 410 (Ref. 16).

Kennon Site
TND 981473515

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

None identified (Ref. 17)

Total population served by ground water within a 3-mile radius:

410

SURFACE WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

None identified

Rationale for attributing the contaminants to the facility:

N/A

* * *

2 ROUTE CHARACTERISTICS

Facility Slope and Intervening Terrain

Average slope of facility in percent:

60 ft. in 1800 ft. for 3.3% slope (Ref. 14, 15).

Name/description of nearest downslope surface water:

Unnamed creek entering the Little Harpeth River north of the junction of Wilson Pike and Split Log Road (Ref. 14, 15).

Average slope of terrain between facility and above-cited surface water body in percent:

80 ft. in 1800 ft. for 4% slope (Ref. 14, 15).

Is the facility located either totally or partially in surface water?

No (Ref. 14, 15)

Is the facility completely surrounded by areas of higher elevation?

No (Ref. 14, 15)

1-Year 24-Hour Rainfall in Inches

3 inches (Ref. 9)

Distance to Nearest Downslope Surface Water

0.4 miles from the site to where surface drainage enters unnamed tributary of Little Harpeth River (Ref. 14, 15).

Physical State of Waste

Liquids dumped at site by admission of company (Ref. 10).

* * *

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

Landfill not adequately covered and no diversion system present--drums and liquid emptied into pits and covered with no documentation indicating adequate cap (Ref. 10).

Method with highest score:

Landfill not covered, no diversion system present.

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

1,1-dichloroethene and 1,1-dichloroethane detected in pits A and B and monitoring #8 on site by State Superfund sampling (Ref. 1, 2).

Compound with highest score:

1,1-dichloroethene has a toxicity rating of 3 (Ref. 4) and a persistence rating of 2 (Ref. 9).

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

800 drums

Basis of estimating and/or computing waste quantity:

Genesco admission of the dumping of approximately 800 55-gallon barrels of waste material containing organic solvents, organic fillers, and water-based adhesives at the site by their subsidiary General Adhesives (Ref. 10).

5 TARGETS

Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:

Recreational use of the Little Harpeth River between Split Log Road and Concord Road (Ref. 17).

Is there tidal influence?

No (Ref. 14, 15)

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

None identified (Ref. 14, 15)

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

None identified (Ref. 14, 15)

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

None identified (Ref. 18)

Population Served by Surface Water

Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:

None identified (Ref. 19)

Computation of land area irrigated by above-cited intake(s) and conversion to population (1.5 people per acre):

None identified (Ref. 17)

Kennon Site
TND 981473515

Total population served:

N/A

Name/description of nearest of above water bodies:

N/A

Distance to above-cited intakes, measured in stream miles:

N/A

AIR ROUTE
NOT RATED

1 OBSERVED RELEASE

Contaminants detected:

Date and Location of detection of contaminants:

Methods used to detect the contaminants:

Rationale for attributing the contaminants to the site:

* * *

2 WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

Most incompatible pair of compounds:

Toxicity

Most toxic compound:

Hazardous Waste Quantity

Total quantity of hazardous waste:

Basis of estimating and/or computing waste quantity:

* * *

3 TARGETS

Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

0 to 4 mi 0 to 1 mi 0 to 1/2 mi 0 to 1/4 mi

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

Distance to critical habitat of an endangered species, if 1 mile or less:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Kennon Site
TND 981473515

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

**FIRE AND EXPLOSION
NOT RATED**

1 CONTAINMENT

Hazardous substances present:

Type of containment, if applicable:

* * *

2 WASTE CHARACTERISTICS

Direct Evidence

Type of instrument and measurements:

Ignitability

Compound used:

Reactivity

Most reactive compound:

Incompatibility

Most incompatible pair of compounds:

* * *

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility:

Basis of estimating and/or computing waste quantity:

* * *

3 TARGETS

Distance to Nearest Population

Distance to Nearest Building

Distance to Sensitive Environment

Distance to wetlands:

Distance to critical habitat:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

Population Within 2-Mile Radius

Buildings Within 2-Mile Radius

DIRECT CONTACT
NOT RATED

1 OBSERVED INCIDENT

Date, location, and pertinent details of incident:

* * *

2 ACCESSIBILITY

Describe type of barrier(s):

* * *

3 CONTAINMENT

Type of containment, if applicable:

* * *

4 WASTE CHARACTERISTICS

Toxicity

Compounds evaluated:

Compound with highest score:

* * *

5 TARGETS

Kennon Site
TND 981473515

Population within one-mile radius

Distance to critical habitat (of endangered species)

TAM/ah
Disc--Higgs/GrndW4
SF-12


REFERENCES
KENNON SITE (GENESCO)
TND 981473515

1. Kennon Site Sampling and Event Chronology; State Superfund Sampling Results for Kennon Site (Genesco) with Sample Points for Wells/Springs. See Geraghty and Miller, 1986 for Sampling Locations.
2. Geraghty and Miller (1986): Plan for Investigation of the Kennon Site, Brentwood, Tennessee; prepared for Genesco, Inc., Dec. 1986.
3. G. Hawley, revised (1981): Condensed Chemical Dictionary, Tenth Edition; Van Nostrand Reinhold.
4. N.I. Sax (1984): Dangerous Properties of Industrial Materials, 6th Edition; Van Nostrand Reinhold.
5. (1963) Franklin Quadrangle Geologic Map - GM 63 NE.
6. Beaver Engineering (1977): Bedrock Geology of the Nashville and Middle Tennessee Area.
7. 2/19/87 Letter from Roger W. Lee, U.S. Geological Survey to Todd Hughes, TN Dept. of Health and Environment (Superfund) - Data on Observation Wells.

8. 3/19/86 and 3/24/86 Analytical Reports from Wayne McCoy, Edge to Ronnie Bowers, DSF; Re: Kennon Property Analytical Results. - Background Soil Sample (See Pond Sediment and Hackett Ditch).
9. (1984) Uncontrolled Hazardous Waste Site Ranking System, A Users Manual (HW-10), U.S. E.P.A.
10. 5/21/85 Letter from Ralph Mosely, Genesco to Tom Tiesler, DSWM; RE: Chemical Waste Site Once Used by a Division of Genesco.
11. 2/19/86 Letter from Frank W. Clifton Jr. Brentwood City Manager to Don Shackelford, TN Div. Superfund; Re: Cost Estimates for Water Lines.
12. 7/28/86 Letter from Ralph Mosely, Genesco to Frank W. Clifton, Jr., Brentwood City Manager; Re: Service Connections.
13. 3/16.87 Conversation of Thomas A. Moss, DSF with Ronnie L. Bowers, DSF; Re: Kennon Site (Genesco) Sample Results, Water Use.
14. (1981) Franklin Quadrangle Topographic Map - 63 NE.
15. (1957) Nolensville Quadrangle Topographic Map - 70NW.
16. 4/24/87 TDH&E Memo from Thomas A. Moss, DSF to Kennon Site (Genesco) File; Re: Ground Water Use Survey/House County for 3 Mile Radius.

17. 3/10/87 Telephone Conversation of Thomas A. Moss, DSF with Robin Bowie, Williamson County Soil Conservation Service; Re: Surface and Groundwater Use for Irrigation in the Area of the Genesco Site.
18. 12/19/85 Letter from Robert M. Thatcher, TWRA to Gordon S. Caruthers, DSWM with attachments: Critical Wildlife Habitat of Tennessee.
19. (1978) Water Quality Management Plan for the Lower Cumberland River Basin, TN Division of Water Quality Control.
20. Commissioners Order: Genesco Inc./Emmett & Rose Kennon. Order No. 863013.

TAM/dje SF #5



OVERSIZED

DOCUMENT

Reference 3

LATITUDE AND LONGITUDE CALCULATION WORKSHEET #1
LI USING CUSTOM RULER OR COORDINATOR™

SITE NAME: Kennon Site CERCLIS #: 7ND981473515
 AKA: Genesee SSID: _____
 ADDRESS: Split Log Road / Wilson Pike
 CITY: Brentwood STATE: TN ZIP CODE: 37027

SITE REFERENCE POINT: _____

USGS QUAD MAP NAME: Franklin, TN TOWNSHIP: _____ N/S RANGE: _____ E/W

SCALE: 1:24,000 MAP DATE: _____ SECTION: _____ 1/4 _____ 1/4 _____ 1/4

MAP DATUM: 1927 1983 (CIRCLE ONE) MERIDIAN: _____

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):

LONGITUDE: 86° 45' 00" LATITUDE: 35° 52' 30"

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:

LONGITUDE: 86° 47' 30" LATITUDE: 35° 57' 30"

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

A) ALIGN THE BOTTOM OF THE SCALE WITH BOTTOM OF GRID. ALIGN THE TOP OF THE SCALE WITH THE TOP OF GRID. POSITION EDGE OF RULER OVER SITE REFERENCE POINT WHILE KEEPING TOP AND BOTTOM ALIGNED.

B) READ TICS ON RULER AT 1- OR 0.5-SECOND INTERVALS (INTERPOLATE).

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): _____' _____"

D) ADD TO STARTING LATITUDE: _____° _____' _____" + _____' _____" =

SITE LATITUDE: 35° 57' 22.0"

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)

A) ALIGN THE BOTTOM OF THE SCALE WITH RIGHT SIDE OF GRID. ALIGN THE TOP OF THE SCALE WITH THE LEFT SIDE OF GRID. POSITION EDGE OF RULER OVER SITE REFERENCE POINT WHILE KEEPING TOP AND BOTTOM ALIGNED.

B) READ TICS ON RULER AT 1- or 0.5-SECOND INTERVALS. (INTERPOLATE)

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): _____' _____"

D) ADD TO STARTING LONGITUDE: _____° _____' _____" + _____' _____" =

SITE LONGITUDE: 86° 46' 27.0"INVESTIGATOR: Teresa Sawyer DATE: 6/7/94



Reference 4

232 GENESCO PARK
NASHVILLE, TN 37217

OFFICES: (615) 399-1016
FAX MACHINE: (615) 399-0152
PAGING SERVICE: (615) 664-1813

MOSELY AND ASSOCIATES, INC.

**AFTER-ACTION REPORT
INCLUDING AIR MONITORING PROGRAM,
WATER MONITORING PROGRAM,
AND SITE SECURITY PROGRAM**

Kennon Site - Brentwood, Tennessee

**January 1993
Revised December 1993**

**AFTER-ACTION REPORT
INCLUDING AIR MONITORING PROGRAM,
WATER MONITORING PROGRAM, AND SITE SECURITY PROGRAM
Kennon Site - Brentwood, Tennessee
January 1993
Revised December 1993**

TABLE OF CONTENTS

Introduction	Section 1
<ul style="list-style-type: none">• Background History of Site• Anticipated O&M Costs at Site• Annual Report Information• Long-Term Treatment Criteria	
Air Monitoring Program	Section 2
<ul style="list-style-type: none">• Perimeter Monitoring• Work Area Detection Alarms• Daily Air Samples• Direct Reading Instrumentation	
Air Monitoring Stations	Section 3
<ul style="list-style-type: none">• Location Map and Photographs• Weekly Perimeter Air Monitoring Reports• Daily Air Monitoring Reports	
Water Monitoring Program	Section 4
<ul style="list-style-type: none">• Groundwater Monitoring Plan - Kennon Site• List of Priority Pollutants to be Analyzed• Status, Construction Details and Location of Wells• Groundwater Monitoring Results - TDEC Well Monitoring Program• Groundwater Monitoring Results - City of Brentwood Monitoring Program• Groundwater Monitoring Results - Excavation Monitoring Program• Evacuation Water Samples	
Site Security Program	Section 5
<ul style="list-style-type: none">• Emergency Personnel Listing	

INTRODUCTION

INTRODUCTION
Kennon Site - Brentwood, Tennessee

There are three separate documents comprising this After-Action Report:

- **The Mosely & Associates, Inc. After-Action Report** is a notebook which contains the Introduction and Site History, the Air Monitoring Program, Water Monitoring Program, and Site Security Program.
- **The Geraghty & Miller, Inc. Source Control/Remediation After-Action Report for the Kennon Site** is a separate notebook which contains a brief history of the site activity and reviews the source control remediation activities.
- **The Geraghty & Miller, Inc. Long-Term Soils Management for the Kennon Site Report** is a separate notebook which contains the soils management program for the site.

BACKGROUND HISTORY OF SITE

BACKGROUND HISTORY OF SITE

Kennon Site - Brentwood, Tennessee

The ten acre site undergoing remediation is located in Brentwood, Tennessee on a 150-acre tract of farmland owned by Emmett and Rose Kennon (See Figure 1). Phosphate was mined on the farmland property between 1972 and 1974, from which one pit was left unreclaimed. In 1978, this mine pit and four additional trenches were used for the disposal of industrial wastes, consisting of organic solvents, adhesives, and organic fillers from General Adhesives, which at that time was a division of Genesco Inc.

Genesco corporate officials learned of the disposal activities in 1985, at which time the Tennessee Department of Environment and Conservation (TDEC), formerly known as the Tennessee Department of Health and Environment (TDHE), was notified and a series of investigations and remedial activities were begun under the supervision and direction of TDEC.

During the initial stage, a silt fence was constructed to prevent contaminated sediment from leaving the property and an alternative water supply was provided to residents in the area. Soil sampling and geophysical surveys were conducted in the disposal areas and monitor wells were constructed on-site by consultant personnel. Domestic wells and springs were sampled by the TDHE, and the US Geological Survey (USGS) conducted a study of the regional ground-water flow system. In 1986, the City of Brentwood extended the city water lines into this area of Williamson County to provide city water to residents in the surrounding area, with Genesco participating in the funding thereof.

Geraghty and Miller, Inc. (G&M) was retained by Genesco to collect and analyze all of the existing data and to prepare a plan of investigation of the site. During 1987, that plan was implemented.

From the data obtained during the site investigation in 1987, it was concluded that the hydrogeologic system at the site is composed of three basic units. The uppermost unit (the shallow aquifer) includes a granular saprolite zone at the base of the weathering residuum and the weathered upper few feet of the bedrock. This is underlain by the Hermitage Aquitard, which is a confining zone. The Carter's Formation, which is the third unit, underlies both the hydrogeologic systems noted above and is a massive limestone formation.

The ground water flow in the shallow aquifer is towards the southwest and is largely controlled by topography. Ground water contamination was found to be restricted to the shallow aquifer and confined to a relatively small area on the Kennon property immediately adjacent to the disposal area. Based upon the data collected, it was determined that it was unlikely that any contaminants had migrated off of the Kennon property.

Work plans, investigation reports and remedial design documents were prepared during 1986 to 1990 to address the on site contaminants, and were implemented in 1989 through 1991. The site is being remediated in accordance with TDEC order, No. 86-3013, issued March 5, 1986. A Hazard Evaluation and Remedial Alternatives (HE&RA) study was conducted to identify the media of concern (ground water, adhesive waste, contaminated soils) and the optimum treatment and disposal alternatives.

The selected ground water remedial method was Remedial Alternative 1 of the HE&RA, which was comprised of a subsurface drain (See Figure 2). The subsurface collection drain was designed and installed in November 1989 to intercept the flow of ground water (See Figure 3). Intercepted ground water is removed from the site and treated through the City of Brentwood sewer system at a treatment facility operated by the Metropolitan Government of Nashville and Davidson County.

The selected source control remediation method was outlined in the G&M Source Control Plan of May 1989. The TDEC approved the Source Control Plan in April 1990 and it was implemented during the period of July 1990 through June 1991. Large mechanical screens were used from June 1990 to September 1991 to separate semi-solid and solid adhesive wastes from the soils. Excavated adhesive wastes were removed from the site and incinerated. The remaining soils were processed through the screens several times prior to the bioremediation phase of the project.

A treatability study was conducted by G&M at the site in 1990. The study determined that an adapted indigenous aerobic bacteria population was present in the soils which could be used to convert the residual contamination present in the soils to carbon dioxide.

Baseline soil sampling was conducted in 1990 and 1991, and the site was terraced into a series of surface water holding cells in order to promote the bioremediation effort (See Figures 5 and 6).

Soil and ground water sampling takes place on a scheduled basis to ensure that bioremediation continues in an effective manner.

Bioremediation is anticipated to continue until approximately the year 2002, but closure of the site will not be completed until a comprehensive sampling analysis has been conducted to ensure that the soil and ground water cleanliness meets the applicable regulations.

FIGURE 1




FIGURE 2




FIGURE 3




FIGURE 4

REMOVAL OF SOURCE MATERIAL




FIGURE 5





FIGURE 6

TERRACING PROMOTES PONDING AND INCREASES FLOW THROUGH THE SOILS



ANTICIPATED O&M COSTS AT SITE

KENNON SITE - BRENTWOOD, TENNESSEE

Future Cost Projections

FYE 95 Through FYE 2001 - As of February 9, 1993

I. LONG-TERM COSTS FROM FEBRUARY 1994 - FYE 2001

Geraghty & Miller, Inc.

Annual Costs for Bioremediation, Soil Sampling and Laboratory Analysis @ \$8,000/yr x 7 yrs. \$ 56,000

Bi-Annual Bioremediation/Soil Treatment (\$5,000/application - Incl. contractor x 4 applications) 20,000

Soil Re-Working - Est. in FYE 97 (incl. contractor) 30,000

Mosely & Associates, Inc.

Air & Water Sampling/Regulatory Liaison @ \$20,000/yr x 7 yrs 140,000

Operations & Maintenance (incl contractor @ \$8,000 every other year x 3 yrs) 24,000

TDEC Cost Allocation (\$60,000 - January 95 Payment) 60,000

Other Miscellaneous Costs

Sewer, Utilities, Etc. @ \$18,600/yr x 7 yrs 130,200

II. SITE CLOSURE COSTS - APPROX. FYE 2001

Decontamination of Subsurface Systems (M&A and G&M) 50,000

Certifications for Meeting TDEC ARAR's 50,000

Final Closure Report (G&M) 20,000

Regulatory Liaison (M&A) 30,000

TDEC Cost Allocation (NOTE: Majority of TDEC cost will have already been previously paid) 30,000

FUTURE TOTAL LONG-TERM COSTS \$ 640,200

ANNUAL REPORT INFORMATION

ANNUAL REPORT INFORMATION
Kennon Site - Brentwood, Tennessee

An annual report will be prepared each year summarizing the yearly events including the sampling and soils management activities. Included will be an estimate of the volume of ground water treated and the annual expenditures. Two copies of this report will be submitted to the Division of Superfund (DSF) by March 1st of each year.

The first such report is due March 1, 1994, covering the activities for the calendar year 1993.

LONG-TERM TREATMENT CRITERIA

LONG-TERM TREATMENT CRITERIA
Kennon Site - Brentwood, Tennessee

A necessary omission from the Long-Term Soils Management Program is the reporting of risk-based soil and groundwater Applicable or Relevant and Appropriate Requirements (ARAR's), which are sometimes set by the appropriate regulatory authority as a "level of cleanliness" to which the on-site groundwater and soils are compared when de-listing of the site occurs.

Since the United States Environmental Protection Agency (EPA) has not yet determined the ARARs for sites undergoing remediation, it was felt by TDEC, Genesco and the consultants that the specification of an ARARs number for the soils and groundwater would be premature and somewhat arbitrary. The U.S. EPA continues to develop the ARARs Program and is expected to publish ARARs guidelines well before the bioremediation activities at the site are completed. After each five year period, the bioremediation system's effectiveness in achieving treatment goals through the bioremediation program will be evaluated by comparison with ARAR's published by EPA or TDEC.

AIR MONITORING PROGRAM

AIR MONITORING PROGRAM Kennon Site - Brentwood, Tennessee

Four tasks concerning air monitoring were accomplished on the Kennon site to obtain data concerning the possibility of airborne contaminants from the removal/remediation operations which were being conducted in 1990 and 1991. The air monitoring was accomplished in conjunction with the utilization of a comprehensive weather station located at the site, which measured the barometric pressure, outside temperature, relative humidity, wind direction, and wind speed. This information was accumulated on a continuing basis, during the periods when all source removal/remediation operations were actually conducted.

Perimeter Monitoring

Ten air monitoring stations, located around the property boundary of the Kennon farm, were equipped with 3M passive monitors to detect airborne organic vapors. The monitors were housed in specially-designed air monitoring stations, constructed of untreated redwood and galvanized screen mesh, to protect the monitors from the elements and wildlife. Photographs of the sampling stations, and a location map, are included as attachments to this document.

Monitors were changed out on a weekly basis during the active source removal phase, and on a bi-weekly basis during inactive source removal activities. The monitors were immediately labeled, sealed, and shipped to the Clayton Environmental Laboratories in Novi, Michigan, for a gas chromatograph hydrocarbon scan to determine the total level of hydrocarbons present. Gas chromatography mass spectrophotography analyzation was available in the event that the levels of the total hydrocarbons, on a cumulative, time-weighted average basis, exceeded a level indicative of the presence of hydrocarbons in excess of background levels.

Also included within this document are the results of each of the individual laboratory tests. The total hydrocarbons found on the sample itself, as well as the time-weighted average of milligrams per cubic meter (mg/M³) are reported. At no time were background levels exceeded, showing that no harmful levels of organic vapors crossed the boundaries of the farm. The trace levels that were occasionally reported were attributed to large deposits of cow manure found in the immediate vicinity of the respective monitoring station.

Work Area Detection Alarms

Three Thermoelectron Organic Vapor Monitors (OVMs), which are sophisticated electronic monitoring instruments, were placed in special weather-tight enclosures, were equipped with radio alarm systems and were used daily during the construction process when source material was brought to the surface of the ground. They were placed upwind and downwind from the work area to pick up levels of organic vapors

which might be drifting towards the property line. Should the readings be over a pre-set alarm level (four parts per million [ppm]) the alarm would trip, a radio signal would be sent to the Mosely & Associates site trailer weather station, and an investigation would immediately take place to determine the cause of the indicated high level. In most cases, the alarms came from exhaust fumes from construction or farm equipment. In those isolated cases where the alarm limit was exceeded due to on-site removal activity which did not exceed 10 ppm, immediate steps were taken on-site to contain or remove the generating source.

Daily Air Samples

During the excavation phase of the project, air samples were taken in the source removal area to insure that the source removal activities generated no airborne contaminants in the construction area at the site which may be too small to be noted by other instruments, but which might accumulate over the work day to a level which may be of concern to site workers.

SKC Air Monitoring pumps installed with charcoal tube collection media were mounted approximately five feet above ground in the North, East, South, and West quadrants surrounding the construction area at the site. A fifth pump and charcoal tube was set out in the middle of the construction area.


Each day while source removal activities were underway at the site, five air samples, plus laboratory and/or field blanks were taken in accordance with OSHA, EPA, NIOSH, and AIHA methodology and were sent to Clayton Environmental Laboratories in Novi, Michigan for analysis. This laboratory is accredited by the American Industrial Hygiene Association (AIHA) for this type of analyses.

The attached data shows the results both as the total milligrams of hydrocarbons found in the sample (mg) and a Time-Weighted Average (TWA) in mg/M^3 . In all cases, no time-weighted average organic vapors were present in the construction area in an amount sufficient to cause concern regarding worker or nearby resident health and safety.

Direct Reading Instrumentation

Organic Vapor Monitors and/or Organic Vapor Analyzers (sophisticated, state-of-the-art industrial hygiene instruments), were used continually while excavation activities were taking place. These analyzers enabled Mosely & Associates, Inc. and contractor health and safety personnel to monitor levels of airborne vapors for worker and resident safety during excavation activities. This permitted sources of organic vapors to be covered, contained or treated to prevent the large scale release of those vapors.

These instruments were also used to assist in the qualification and identification of source materials for the presence of organic vapors, and to assist, along with soil and water samples, in the qualification of backfill material.



DRAWING NO:
FL01014-SR1

DRAWN BY:	DATE:
K. C. C. C.	May 31, 1989
CHECKED:	DATE:
C. Duncan	May 3, 89
APPROVED:	DATE:
J. P. K. K.	May 3, 89

 GERAGHTY & MILLER
ENGINEERS, INC.

APPROXIMATE AIR MONITORING LOCATIONS

KENNON SITE
BRENTWOOD, TENNESSEE

WATER MONITORING PROGRAM

WATER MONITORING PROGRAM
Kennon Site - Brentwood, Tennessee

Three separate documents previously submitted to TDEC govern the water monitoring procedures at the Kennon site, their requirements, and the requisite quality assurance procedures, and are reported as a part of the Groundwater Monitoring Plan, January 1993. These documents are described below:

1. **City of Brentwood Sewer Permit:** This permit, Issued Initially on June 1, 1990, renewed on June 1, 1992, and currently expiring on May 31, 1994, requires compliance with Metro Ordinance No. 080-343, which governs wastewater discharge into the sewer system for the Metropolitan Government of Nashville and Davidson County, and into the City of Brentwood sewer system. A copy of the Permit and related requirements is included as Appendix 2 in this section.
2. **Groundwater Monitoring Plan - Geraghty & Miller, Inc., November 1988:** This document covers the initial groundwater monitoring well installation and monitoring of those wells throughout the life of the project. It was previously submitted to the TDEC and approved by them prior to the beginning of the Groundwater Monitoring Program.
3. **Water Sampling Plan, Mosely & Associates, Inc., May 1990:** This plan combined the monitoring requirements from the above two documents, and included increased monitoring procedures for the Source Removal Phase of the project in 1990 and 1991. It was previously submitted and approved by TDEC.

Groundwater Monitoring Plan, Mosely & Associates, Inc., January 1993: This Water Monitoring Plan incorporates all of the quality assurance, sampling, and analytical requirements of the above three documents by reference into this Water Monitoring Plan, and contains the combined water sampling schedule until the site is de-listed by the Tennessee Department of Environment and Conservation. This plan was initially submitted to TDEC in January 1993 and was updated in December 1993 and is included in its entirety in this section of this report.



232 GENESCO PARK
NASHVILLE, TN 37217

OFFICES: (615) 399-1016

FAX MACHINE: (615) 399-0152

PAGING SERVICE: (615) 664-1813

MOSELY AND ASSOCIATES, INC.

**GROUNDWATER MONITORING PLAN
KENNON SITE
BRENTWOOD, TENNESSEE
JANUARY 1993**

Revised December 1993

**GROUNDWATER MONITORING PLAN
KENNON SITE
BRENTWOOD, TENNESSEE
JANUARY 1993
REVISED DECEMBER 1993**

TABLE OF CONTENTS

	<u>Page</u>
Project Description	1
Background Information	2
Sampling Procedures	2
Sampling Safety	3
Sampling Schedules	3
Sampling Schedule - Monitor Wells - Kennon Site	3
Sampling Schedule - City of Brentwood Sewer Sampling Program	3
Sampling Schedule - Source Removal Phase - Groundwater Discharge Monitoring Program	4
Sampling Equipment	4
Field Analysis Procedures	5
Sample Collection Methods	5
Decontamination Procedure	6
Sample Preservation	6
Field Blanks, Rinsate Blanks, Duplicates, Splits	6
Sample Documentation	7
Field Sample Measurements	7
Chain-of-Custody	7
Sample Transfer and Shipment	8
Laboratory Custody Procedures	8
Data Reduction, Validation, Interpreting and Reporting	8

LIST OF APPENDIXES

Wastewater Sampling and Testing Criteria	Appendix 1
City of Brentwood Sewer Permit and Requirements	Appendix 2
Groundwater Sampling Schedule	Appendix 3
Water Sampling Log	Appendix 4
Chain of Custody Record	Appendix 5
Map of Monitoring Well Locations	Appendix 6

**GROUNDWATER MONITORING PLAN
KENNON SITE
JANUARY 1993
Revised December 1993**

1.0 PROJECT DESCRIPTION

Mosely & Associates, Inc. has been retained by Genesco Inc. to provide environmental safety management services in connection with the Kennon site, located near Wilson Pike in Brentwood, Tennessee. One of the specific services of our environmental activities is to collect and arrange to have analyzed samples of groundwater and/or wastewater that is, or may be, conveyed to the City of Brentwood sewer system.

This document reviews the sampling and quality assurance procedures to be taken in accomplishing this task.

Wastewater sampling and analysis is being accomplished for three different phases of the Kennon site project:

1. **MONITOR WELL SAMPLING:** This activity is provided relative to the "GroundWater Monitoring Plan for the Kennon Site, Brentwood, Tennessee, November, 1988", which was prepared by Geraghty & Miller, Inc., Oak Ridge, Tennessee. This plan was approved by TDEC and sets forth the sampling and quality assurance procedures for monitoring the groundwater quality of selected previously-installed monitoring wells inside and outside the bermed area on the Kennon property.

Under this program, sampling is performed on selected monitoring wells on a quarterly basis and the sample results are submitted to the TDEC.

2. **CITY OF BRENTWOOD SEWER SAMPLING:** Specific wastewater sampling for sewer discharge is required by the City of Brentwood Department of Water and Sewerage Services Permit No. 89-001 for the Discharge of Industrial Wastes, issued to Genesco Inc. on June 1, 1989.

Discharge to the sewer is in the form of groundwater collected through the subsurface drain system at the Kennon site, and potentially may contain trace levels of volatile organic compounds (VOC's). A baseline sample and analysis for the priority pollutants - volatiles, and the full "Metro" list is collected and analyzed annually. The priority pollutants list for volatiles is collected and analyzed on a quarterly basis. Beginning in 1994, an analysis for flow, BOD₅, SS, oil and grease, pH, ammonia, iron, zinc, cadmium, and magnesium will also be accomplished on a semi-annual basis, to comply with requirements imposed upon the city of Brentwood by Metro. Results are sent to both the City of Brentwood and to TDEC.

3. **SOURCE REMOVAL PHASE - GROUNDWATER DISCHARGE MONITORING PROGRAM:**
Beginning in the late Spring of 1990, Genesco Inc. entered into the Source Removal/Soil Remediation Phase of the Kennon project. In this phase, groundwater and decontamination rinsate that was collected on site was processed through a solvent-water separator and/or process control unit for use in the soil remediation/bioremediation activities. Excess groundwater was discharged to the City of Brentwood Sewer System. Increased sampling frequency and quality assurance steps for groundwater monitoring were required during that particular phase of the Kennon Site remediation project. The results were sent to both the City of Brentwood and to TDEC.

1.1 **BACKGROUND INFORMATION**

Groundwater monitoring through both the Monitor Well Sampling and Sewer Discharge Programs has been accomplished for several years on this project. Sample results from both programs indicate that contaminants are not present in the monitor wells or sewer discharge, except for trace levels of a few volatile organic compounds. All trace levels of volatile organic compounds found were considerably lower than limitations set forth in the City of Brentwood or Metropolitan Government of Nashville and Davidson County Sewer Use Ordinances.

2.0 **SAMPLING and QUALITY ASSURANCE PROCEDURES**

This section presents the scope and the methodology of sampling activities to accomplish this project. The primary quality assurance objectives for the sampling procedures are : (a) that the samples obtained are representative of the total wastewater stream into the sewer; (b) that a sufficient amount of the sample is taken so that the appropriate analyses may be accomplished by the analytical laboratory; (c) that the proper handling and preservation procedures are followed to maintain the integrity of the sample; and (d) that the sampling procedures are well documented.

References for sampling procedures that will be used include:

- (1) NPDES Compliance Sampling Manual, U.S. Environmental Protection Agency, Office of Water Enforcement, October 1979.
- (2) Sampling Procedures for Hazardous Waste Streams, deVera, et al.
- (3) Safety Manual for Hazardous Waste Site Investigations, U.S. Environmental Protection Agency.
- (4) NIOSH Manual of Analytical Methods, Third Edition, National Institute of Occupational Safety and Health, U.S. Department of Health, Education and Welfare, February, 1984.
- (5) Methods for Chemical Analysis of Municipal and Industrial Wastewater, U.S. Environmental Protection Agency, EPA-600/482-057.
- (6) Occupational Safety and Health Guidance Manual for Hazardous Waste Site Activities, National Institute for Occupational Safety and Health, NIOSH-85-115.

2.1 SAMPLING SAFETY

The Health and Safety Plan, prepared for the Kennon site by Geraghty & Miller, Inc. and contained in the Groundwater Monitoring Plan of November 1988, is used as a guideline for safety procedures to be implemented and followed during sample collection, and includes the following considerations: (a) respiratory protection where required for collecting samples of suspected high concentrations of hazardous materials; (b) protective clothing which may be required during the sampling procedures; (c) contingency plans for emergencies, including a list of telephone numbers for ambulance service, hospital, fire department, police department and poison control; and directions to the nearest medical facility. The necessary protective clothing and safety procedures will be determined by the Site Health and Safety Officer (SHSO) before sampling activities begin.

2.2 SAMPLING SCHEDULES

The sampling schedules for the three (3) water sampling programs at the Kennon site are set forth below:

2.2.1 SAMPLING SCHEDULE - MONITOR WELLS - KENNON SITE

Sampling for Priority Organic Pollutants - Volatiles is accomplished on a quarterly basis at selected monitoring wells, in compliance with the TDEC-approved GroundWater Monitoring Plan published in November, 1988. This list for volatiles is the same as those listed under EPA's Total Toxic Organic-Volatiles list. Sampling and analysis for the full EPA Priority Pollutants list, less pesticides and PCB's, is accomplished at those specified monitoring wells on an annual basis. In conjunction with the sampling and analysis for volatiles for that particular quarter. This is normally accomplished in the fourth quarter of each calendar year.

2.2.2 SAMPLING SCHEDULE - CITY OF BRENTWOOD SEWER SAMPLING

Genesco's sewer discharge permit requires semi-annual sampling and analysis for flow, biochemical oxygen demand (BOD), suspended solids, oil and grease, pH, ammonia, iron, zinc, cadmium and magnesium. In addition, the City of Brentwood verbally requested that the quarterly analysis for volatiles, which is accomplished at the City of Brentwood sewer inlet (Manhole "X"), be provided to them. They likewise have requested that the annual analysis for the sample collected for TDEC at Manhole "X" and analyzed for the full Priority Pollutants List (less pesticides and PCB's) be provided to them. This request has also been, and will continue to be, honored. As previous samples have shown no detectable amounts of these materials, this analysis will be performed annually, will be called the Comprehensive Sample and Analysis, and will include the analysis for parameters collected on a quarterly basis, as outlined below, as well. Should the comprehensive sample taken on an annual basis show a constituent above the regulatory limit, the source will be identified, where possible, and that particular constituent, or class of constituents, will be sampled on a quarterly basis until two consecutive quarterly analyses show that parameter not exceeded.

On a quarterly basis, samples will be collected and analyzed for volatile organics priority pollutants (see attached listing) to ensure that the trace amounts previously found stay well within the criteria for discharge into the City of Brentwood sewer system. These will be analyzed utilizing EPA test method 8240 by a laboratory certified by the State of Tennessee for wastewater analysis.

2.2.3 SAMPLING SCHEDULE - SOURCE REMOVAL PHASE - GROUNDWATER DISCHARGE MONITORING PROGRAM

1. **BASELINE ANALYSIS:** Previous groundwater monitoring on the site has shown no detectable amounts of metals, pesticides, PCB's or cyanides. Also, levels of Biological Oxygen Demand, 5-day (BOD₅), Chemical Oxygen Demand (COD), oil and grease, suspended solids, or pH recorded have not caused a concern over water quality to be discharged into the City of Brentwood sewer system. Only small amounts of certain volatile organic compounds have been found in the groundwater, all of which are projected to easily meet the City of Brentwood/Metropolitan Government of Nashville and Davidson County (METRO) criteria.

During the Source Removal Phase of the site remediation project (from November 1990 through January 1991, and again from April through October 1991, to verify the groundwater quality, a Baseline Sample was collected on the first day that source material was excavated. The Baseline Sample included a laboratory analysis for the parameters shown in the attached table (see the Water Monitoring Results following in this section of this report) and was performed by a laboratory certified by the State of Tennessee for performing wastewater analysis.

2. **MONTHLY ANALYSIS of GROUNDWATER DISCHARGE:** The Baseline Analysis was repeated monthly to ensure that wastewater quality for all baseline parameters remained within the City of Brentwood and METRO limits.
3. **WEEKLY ANALYSIS - VOLATILE ORGANICS:** Since trace amounts of volatile organic compounds have previously been found in the groundwater discharge from this site, samples for the Organic Priority Pollutants - Volatiles, were collected on a weekly basis when excavation was being accomplished to ensure that the sewer discharge remained within the City of Brentwood/METRO limitations.
4. **SAMPLING METHODOLOGY:** Because of the potential presence of Volatile Organic Compounds in the site wastewater, grab samples were collected for all analyses.
5. **SAMPLING SCHEDULE TABLE:** The attached table (see the Groundwater Monitoring Schedule for the Kennon Site following in this section of this report) presents the above sampling schedule and results in tabular form.

2.3 SAMPLING EQUIPMENT

Sampling equipment necessary for the collection of representative wastewater samples for all sampling programs is presented below:

1. Several gallons of distilled water and properly cleaned wash bottles
2. Plastic sheeting or large size garbage bags
3. Bottom filling Teflon or stainless steel bailer with appropriate nautical rope lengths
4. Graduated, glass or Teflon sample collection and quantification containers
5. Appropriate laboratory-prepared sample containers
6. Sample bottle labels, waterproof marking pen
7. pH meter

8. Thermometer
9. Specific conductivity meter
10. Preservatives for water samples (unless already in sample containers)
11. Field data forms, clip board, pen
12. Ice chest and ice or freezer packs
13. Steel measuring tape
14. Flashlight
15. Appropriate collection/holding/reach equipment
16. Clean rags or wipes
17. Laboratory grade detergent

2.4 FIELD ANALYSIS PROCEDURES - ALL SAMPLING PROGRAMS

Analyses of pH, temperature and specific conductance will be made in the field at the time of the sampling because these parameters can change rapidly after the sample is collected. Enough water will be removed from each sampling point to determine the temperature of the water, specific conductivity, and pH. These values will be recorded on a field data sheet and the surplus water dispensed in such a manner so as to avoid potential contamination. Instruments will be calibrated before and after sampling to ensure that the sample collected is representative of the aquifer at that point, or of the wastewater flow.

Samples for volatile organics will be taken in VOA vials and properly filled and inverted to insure the absence of air in the sample container.

Other containers as specified by the Metropolitan Government of Nashville and Davidson County and/or the City of Brentwood will be utilized, where directed. Immediately after the sample is collected with either a bailer or with another type sample collection device, it will be transferred to the sample containers containing the appropriate preservatives.

2.5 SAMPLE COLLECTION METHODS

Sampling will be conducted in the sewer man-hole, monitoring well or lift station as specified by the sampling plan. Sample collection containers or a bailer are to be used to obtain the sample which will then be poured into the laboratory-supplied container. Such collection container or bailer will be decontaminated as specified below prior to sample collection. A "clean capture" methodology will be used to prohibit contamination of the collection container from the walls of the sewer pipe, flume or holding tank itself.

For monitoring well samples, a stainless steel or Teflon bailer will be utilized for purging approximately three well volumes of standing water in well casings, as well as for the collection of the sample itself. The pH and specific conductance of the purged water will be tested periodically to ensure that the sample is representative of the aquifer and is not affected by the conditions at the well. If consistent readings of these parameters are obtained over the purging period, it will be assumed that the evacuation of standing water in the well is adequate.

The VOC sample will be collected with the same bailer used for purging the well, and bailers will be carefully decontaminated as specified below between each sampling location.

For monitoring sewer discharge samples and process tank samples, either a stainless steel or

Teflon bailer or special glass or stainless steel collection container will be used for collecting the wastewater or sewer samples. Samples will be poured from the collection containers into the sample containers without making direct contact between the two vessels. Sample containers will be immediately labeled and appropriate notations made in the Water Sampling Log as shown in this section of this report.

2.5.1 DECONTAMINATION PROCEDURE

Bailers and other sample collection containers will be rinsed with tap or distilled water, washed with a laboratory-grade detergent solution, rinsed with distilled water, and allowed to air dry. The bailers and other sample collection containers will be wrapped in aluminum foil for transportation between sample locations. The use of organic solvents such as acetone or isopropyl alcohol for decontamination will not be utilized due to the risk of introducing false positives into the analysis protocols.

2.6 SAMPLE PRESERVATION

The attached table (immediately following this section of this report) presents the wastewater sampling and testing considerations, including the type and quantity of preservatives, for a wide range of constituents which include those being sampled at this location. In most cases, the containers are prepared by the analytical laboratory and the preservatives also furnished by them for the specific sampling being accomplished. Samples will be maintained at the required temperature by transporting them in special containers which contain either ice or ice packs specifically made for such refrigeration purposes.

2.7 FIELD BLANKS, RINSATE BLANKS, DUPLICATES, SPLITS

The following information applies to the use of field blanks, rinsate blanks, duplicates and splits, for all sampling programs.

2.7.1 FIELD BLANKS

One (1) Field Blank will be obtained during each daily sampling event for Volatile Organic Compounds, by pouring laboratory-supplied, purged water for VOA sample blanks into a VOA vial. It will be labeled, handled and transported with the other VOA samples collected that day. The laboratory will perform the same analysis on the VOA Field Blank as the other VOA samples collected, to determine if contamination of samples in transportation or a systematic laboratory error may have occurred.

2.7.2 RINSATE BLANKS

Where sample collection containers or a bailer is used at more than one sample location during a daily sampling event, one sample of the rinsate from that container or bailer will be collected in a VOA vial and will be analyzed with the other samples, to determine if the decontamination process adequately cleaned the sample collection container or bailer. If more than one decontamination method is used, or more than one supply of laboratory-grade detergent is utilized in the decontamination process, a rinsate blank will be obtained each time the method or detergent is changed.

2.7.3 DUPLICATES

Each VOA sample will be collected in duplicate VOA vials, to allow for a margin of error in either

sampling or laboratory personnel's handling of VOA vials. If the first VOA vial is successfully analyzed, its duplicate will not be analyzed.

2.7.4 SPLITS

If samples are to be split with a regulatory agency or other authorized personnel, both samples will be collected at the same time and will be marked or tagged so that each may be identified as a split of the other.

If different sample collection containers or bailers are utilized to obtain the samples, both parties' Water Sampling Logs will be noted as such.

3.0 SAMPLE DOCUMENTATION

The following sets forth the sample documentation criteria.

3.0.1 FIELD SAMPLE MEASUREMENTS

The field samples to be collected can be classified into two categories: (a) in-situ measurements, and (b) laboratory measurements:

1. IN-SITU MEASUREMENTS:

These measurements are made immediately after the sample has been collected. The data will be recorded directly onto the Water Sampling Log form as shown in the attached Exhibit 2-1, along with identifying information on sampling conditions and location. In-situ measurements include the following: pH, temperature and conductivity.

2. LABORATORY MEASUREMENTS:

Samples collected and preserved in the field to be shipped to the appropriate laboratory for chemical analyses are specified as laboratory measurements. Identifying information on sampling conditions and location of sample will be recorded as indicated above, together with a record of the required analyses for each of the samples collected.

3.0.2 CHAIN-OF-CUSTODY

Documentation of sample custody is an important part of field and laboratory operations when samples are needed for regulatory agencies or for litigation. Chain of custody procedures will document sample possession from the time of collection to disposal, in accordance with guidelines established in the EPA Safety Manual for Hazardous Waste Site Investigations (September, 1980). In order to document sample custody, the following Chain of Custody procedures will be followed. For the purpose of these procedures, a sample is considered in custody if it is:

- (1) in actual possession of the responsible person;
- (2) in view, after being in physical possession;
- (3) locked so that no one can tamper with it, after having been in physical custody or possession; or

- (4) in a secured area, restricted to authorized personnel.

Each field sample collected will be identified by a sample tag or label on the container itself which is filled out using water-resistant ink. Included on the tag or label, which is usually supplied by the laboratory, are the sample identification number, date, time and location of sample collection, designation of the sample (whether grab, pumped, or composite), the type of sample and preservative, if any, and any pertinent remarks. The signature of the sampler will also be included on the tag or label.

This information will be recorded on the Water Sampling Log form along with any in-situ measurement data and field observations. After collection and identification, the sample will be maintained under the chain of custody procedures as specified elsewhere in this document. If the sample collected is to be split with a governmental or regulatory agency, then the appropriate sample receiver will be indicated on the split sample tag which is affixed to the container containing the split sample and on the sampling log.

3.1 SAMPLE TRANSFER AND SHIPMENT

The following guidelines will be followed in transferring and shipping samples:

1. With the shipping record prepared for each laboratory, samples will be properly packaged for shipment and dispatched to the appropriate laboratory for analysis. Shipping containers will be properly secured for shipment and will be affixed with signature seals if an individual other than the sampler will be delivering the samples to the analytical laboratory.
2. When transferring possession of samples, the individual relinquishing the sample and the new custodian of the sample will sign the record and will note the date and time. A copy of the signed record will be made by the previous custodian and sent to the receiving laboratory to allow tracking of sample possession. All Change of Custody of samples must be a person-to-person exchange of both custody documents and samples. A copy of custody documents will be returned by the laboratory performing the analysis after the samples have been received, and again with the final data package.

3.2 LABORATORY CUSTODY PROCEDURES

General guidelines describing methods for laboratory sample custody are contained in the QA/QC documentation of the analytical laboratory selected to analyze the samples, and may be provided upon request.

4.0 DATA REDUCTION, VALIDATION, INTERPRETATION AND REPORTING

The reduction of the laboratory data, validation of the procedures utilized, the interpretation of the results and the reporting of the results to the client or to the regulatory agency will be accomplished as directed by the client. Laboratory validation data from the laboratory performing the analysis will accompany the report where such validation is necessary.

WASTEWATER SAMPLING AND TESTING CRITERIA

MOSELY & ASSOCIATES, INC.
WASTEWATER SAMPLING AND TESTING CRITERIA

Parameter Name	Container ¹	Preservation Technique ^{2,3}	Max. Holding Time ⁴	Sample Vol. Recommended
Bacterial Tests:				
Coliform, fecal and total	P, G	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵	8 Hours	150 ml
Fecal streptococci	P, G	Same as Above	8 Hours	150 ml
Inorganic Tests:				
Acidity	P, G	Cool, 4°C	14 days	250 ml
Alkalinity	P, G	Cool, 4°C	14 days	250 ml
Ammonia	P, G	Cool, 4°C, H ₂ SO ₄ to pH < 2	28 days	500 ml
Biochemical oxygen demand	P, G	Cool, 4°C	48 hours	500 ml
Bromide	P, G	None Required	28 days	300 ml
Biochemical oxygen demand, carbonaceous	P, G	Cool, 4°C	48 hours	500 ml
Chemical oxygen demand	P, G	Cool, 4°C, H ₂ SO ₄ to pH < 2	28 days	100 ml
Chloride	P, G	None Required	28 days	200 ml
Chlorine, total residual	P, G	None Required	Analyze Immediately	200 ml
Color	P, G	Cool, 4°C	48 hours	250 ml
Cyanide, total and amenable to chlorination	P, G	Cool, 4°C, NaOH to pH > 12, 0.8g/l ascorbic acid	14 days ⁶	1,000 ml
Fluoride	P	None Required	28 days	100 ml
Hardness	P, G	HNO ₃ to pH < 2, H ₂ SO ₄ to pH < 2	6 months	100 ml
Hydrogen Ion (pH)	P, G	None Required	Analyze Immediately	100 ml
Kjeldahl and organic nitrogen	P, G	Cool, 4°C, H ₂ SO ₄ to pH < 2	28 days	500 ml
Chromium VI	P, G	Cool, 4°C	24 days	500 ml
Mercury ⁷	P, G	HNO ₃ to pH < 2	28 days	500 ml
Metals ⁷ , except Chromium VI and mercury	P, G	HNO ₃ to pH < 2	6 months	500 ml
Nitrate	P, G	Cool, 4°C	48 hours	500 ml
Nitrate-nitrite	P, G	Cool, 4°C, H ₂ SO ₄ to pH < 2	28 days	500 ml
Nitrite	P, G	Cool, 4°C	48 hours	500 ml
Oil and Grease	G	Cool, 4°C, H ₂ SO ₄ to pH < 2	28 days	1000 ml
Organic carbon	P, G	Cool, 4°C, HCl or H ₂ SO ₄ to pH < 2	28 days	100 ml
Orthophosphate	P, G	Filter Immediately, Cool 4°C	48 hours	200 ml
Oxygen, Dissolved Probe	G Bottle & Top	None Required	Analyze Immediately	Not Applicable
Phenols	G only	Cool, 4°C, H ₂ SO ₄ to pH < 2	28 days	500 ml
Phosphorus (elemental)	P, G	Cool, 4°C	48 hours	2000 ml
Phosphorus, total	P, G	Cool, 4°C, H ₂ SO ₄ to pH < 2	28 days	500 ml
Residue, total	P, G	Cool, 4°C	7 days	500 ml
Residue, Filterable	P, G	Cool, 4°C	7 days	500 ml
Residue, Nonfilterable (TSS)	P, G	Cool, 4°C	7 days	500 ml
Residue, Setttable	P, G	Cool, 4°C	48 hours	1000 ml
Residue, volatile	P, G	Cool, 4°C	7 days	500 ml
Specific conductance	P, G	Cool, 4°C	28 days	500 ml
Sulfate	P, G	Cool, 4°C	28 days	500 ml
Sulfide	P, G	Cool, 4°C add zinc acetate plus NaOH to pH > 8	7 days	250 ml
Sulfite	P, G	None Required	Analyze Immediately	250 ml
Surfactants	P, G	Cool, 4°C	48 hours	500 ml
Temperature	P, G	None Required	Analyze Immediately	Not Applicable
Turbidity	P, G	Cool, 4°C	48 hours	200 ml

Parameter Name	Container ¹	Preservation Technique ^{2,3}	Max. Holding Time ⁴	Sample Vol. Recommended
Organic Tests⁵				
Purgeable halocarbons				
Purgeable aromatic hydrocarbons	Q, Teflon-lined septum	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵	14 days	40 mL
Acrolein and acrylonitrile	Q, Teflon-lined septum	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵ , HCl to pH 4	14 days	40 mL
Phenols ¹¹	Q, Teflon-lined septum	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵ , Adjust pH to 4-6	14 days	40 mL
Benzidines ¹¹	Q, Teflon-lined cap	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵	7 days until extraction, 40 days after extraction	2,000 mL
Phthalate esters ¹¹	Q, Teflon-lined cap	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵	7 days until extraction ¹²	2,000 mL
Nitroaromatics ^{11, 14}	Q, Teflon-lined cap	Cool, 4°C	7 days until extraction, 40 days after extraction	2,000 mL
PCBs ¹¹ , acrylonitrile	Q, Teflon-lined cap	Cool, 4°C, store in dark, 0.008% Na ₂ S ₂ O ₃ ⁵	7 days until extraction, 40 days after extraction	2,000 mL
Nitroaromatics and isophorone	Q, Teflon-lined cap	Cool, 4°C	7 days until extraction, 40 days after extraction	2,000 mL
Polynuclear aromatic hydrocarbons	Q, Teflon-lined cap	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵ , store in dark	7 days until extraction, 40 days after extraction	2,000 mL
Halobenzenes ¹¹	Q, Teflon-lined cap	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵ , store in dark	7 days until extraction, 40 days after extraction	2,000 mL
Chlorinated hydrocarbons ¹¹	Q, Teflon-lined cap	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵	7 days until extraction, 40 days after extraction	2,000 mL
TCOD ¹¹	Q, Teflon-lined cap	Cool, 4°C	7 days until extraction, 40 days after extraction	2,000 mL
	Q, Teflon-lined cap	Cool, 4°C, 0.008% Na ₂ S ₂ O ₃ ⁵	7 days until extraction, 40 days after extraction	2,000 mL
Pesticides ¹¹	Q, Teflon-lined cap	Cool, 4°C, pH 5-8 ¹⁵	7 days until extraction, 40 days after extraction	1,000 mL
Radiochemical Tests:				
Alpha, beta and radium	P, Q	HNO ₃ to pH < 2	6 months	3,000 mL

COMMENTS

NOTE: Container, preservation procedure, and maximum holding time are adapted from 40 CFR 136, Table B, Required Containers, Preservation Techniques and Holding Time, dated 1-4-85. Sample Volume Recommended is a consensus of recommendations from analytical laboratories used for analyses.

1. Polyethylene (P) or Glass (Q).
2. Sample preservation should be performed immediately upon sample collection. For composite chemical samples each aliquot should be preserved at the time of collection. When use of an automated sampler makes it impossible to preserve each aliquot, then chemical samples may be preserved by maintaining at 4°C until compositing and sample splitting is completed.
3. When any sample is to be shipped by common carrier or sent through the United States Mail, it must comply with the Department of Transportation Hazardous Materials Regulations (49 CFR Part 172). The person offering such material for transportation is responsible for ensuring such compliance. For the preservation requirements of Table B, the Office of Hazardous Materials, Materials Transportation Bureau, Department of Transportation has determined that the Hazardous Materials Regulations do not apply to the following materials: Hydrochloric acid (HCl) in water solutions at concentrations of 0.04% by weight or less (pH about 1.98 or greater); Nitric acid (HNO₃) in water solutions at concentrations of 0.13% by weight or less (pH about 1.62 or greater); Sulfuric acid (H₂SO₄) in water solutions at concentrations of 0.35% by weight or less (pH about 1.15 or greater); and Sodium hydroxide (NaOH) in water solutions at concentrations of 0.008% by weight or less (pH about 12.30 or less).
4. Samples should be analyzed as soon as possible after collection. The times listed are the maximum times that samples may be held before analysis and still be considered valid. Samples may be held for longer periods only if the permittee, or monitoring laboratory, has data on file to show that the specific types of samples under study are stable for the longer time, and has received a variance from the Regional Administrator under section 136.3(e). Some samples may not be stable for the maximum time period given in the table. A permittee, or monitoring laboratory, is obligated to hold the samples for a shorter time if knowledge exists to show that this is necessary to maintain sample stability. See paragraph 136.3(e) for details.
5. Should only be used in the presence of residual chlorine.
6. Maximum holding time is 24 hours when Sulfide is present. Optionally all samples may be tested with lead acetate paper before pH adjustment in order to determine if Sulfide is present. If Sulfide is present, it can be removed by the addition of cadmium nitrate powder until a negative spot test is obtained. The sample is filtered and then NaOH is added to pH 12.
7. Samples should be filtered immediately on-site before adding preservative for dissolved metals.
8. Guidance applies to samples to be analyzed by GC, LC, or GC/MS for specific compounds.
9. Sample receiving no pH adjustment must be analyzed within seven days of sampling.
10. The pH adjustment is not required if acrolein will not be measured. Samples for acrolein receiving no pH adjustment must be analyzed within three days of sampling.
11. When the extractable analytes of concern fall within a single chemical category, the specified preservative and maximum holding times should be observed for optimum safeguard of sample integrity. When the analytes of concern fall within two or more chemical categories, the sample may be preserved by cooling to 4°C, reducing residual chlorine with 0.008% sodium thiosulfate, storing in the dark, and adjusting the pH to 8-9; samples preserved in this manner may be held for seven days before extraction and for 40 days after extraction. Exceptions to this optional preservation and holding time procedure are noted in footnote 5 (re: the requirement for thiosulfate reduction of residual chlorine), and footnotes 12, 13 (re: the analysis of benzidine).
12. 1,2-diphenylhydrazine is likely to be present, adjust the pH of the sample to 4.0 plus or minus 0.2 to prevent rearrangement to benzidine.
13. Extracts may be stored up to seven days before analysis if storage is conducted under an inert (oxidant-free) atmosphere.
14. For the analysis of diphenylhydrazine, add 0.008% Na₂S₂O₃ and adjust pH to 7-10 with NaOH within 24 hours of sampling.
15. The pH adjustment may be performed upon receipt at the laboratory and may be omitted if the samples are extracted within 72 hours of collection. For the analysis of aldrin, add 0.008% Na₂S₂O₃.

CITY OF BRENTWOOD SEWER PERMIT AND REQUIREMENTS



City of Brentwood

5211 MARYLAND WAY • BRENTWOOD, TENNESSEE 37027 • PHONE (615) 371-0060

MAILING ADDRESS: P.O. BOX 788 • BRENTWOOD, TN 37024-0788

JOHN C. GRISSOM
DIRECTOR, WATER AND SEWER DEPARTMENT

WATER AND SEWER DEPARTMENT
1750 GEN. GEORGE PATTON DRIVE
BRENTWOOD, TN 37027
TELEPHONE (615) 371-0080
FAX (615) 371-2225

May 29, 1992

Mr. Ralph E. Mosely
Environmental Consultant
Mosely and Associates
232 Genesco Park
Nashville, Tennessee 37217

RE: Genesco Inc. - Kennon Site
Wastewater Discharge Permit -
Renewal of Old Permit

Dear Mr. Mosely:


Thank you for the application which was mailed to me on March 1992 for renewal of the Wastewater Discharge Permit for the Kennon site.

Application has been approved for the next two years.

Copies of the permit has been forwarded to others.

Please call me if there are any questions.

Sincerely,


Larry Moore

c: Ms. Brenda Apple, Depart. of Environment and Conser.
Mr. Jim Kirby, Hart-Freeland-Roberts
Mr. Jim Hale, Genesco
Mr. Bob Carnahan, Metro

DEPARTMENT OF WATER AND SEWERAGE SERVICES

5211 Maryland Way
Brentwood, Tennessee 37212

Page 1 of 1

Permit No. S2-001

PERMIT
FOR THE DISCHARGE OF INDUSTRIAL WASTES

In accordance with the provisions of Tennessee Code Annotated Section 69-3-108 and Regulations promulgated pursuant thereto, and the CITY OF BRENTWOOD, Ordinance No. 81-25.

PERMISSION IS HEREBY GRANTED TO

GENESCO, INC.
232 Genesco Park
Nashville, Tennessee 37217

FOR THE DISCHARGE OF

A Groundwater Collector System from the
Kennon Farm disposal site under remediation

In accordance with the application filed on May 28, 1992
in the City Hall of the City of Brentwood, Tennessee, and in conformity with approved plans, specifications and other data submitted to the City in support of the above application, all of which are filed with and considered as a part of this permit, together with the following named conditions and requirements.

GENESCO, INC. shall comply with the rules and regulations of Metro
Ordinance No. 080-343, an Ordinance establishing new criteria for
use of the publicly owned treatment works of Nashville and Davidson
County, Tennessee.

Issued this First day of June 1992

Michael W. Walker
City Manager, City of Brentwood, TN

Expires Thirty-First day of May 1994

John Christensen
Director, Dept. of Water & Sewerage

Hart Freeland Roberts

architects • engineers • planners • interior designers

March 15, 1990

Mr. James W. O'Brien
Vice President
Genesco, Inc.
232 Genesco Park
Nashville, Tennessee 37217

RE: PERMIT NO. 89-001
City of Brentwood, Tennessee

Dear Mr. O'Brien:

The Metro Government has requested the enclosed rules and regulations should be attached to your Discharge Permit No. 89-001 that was issued to Genesco by the City of Brentwood.

Please contact me if you have any questions.

Yours truly,

HART-FREELAND-ROBERTS, INC.


James G. Kirby, P.E.

JGK:jm

pc: Mr. Ralph Mosely w/copy of attached
Mosely & Associates, Inc.
232 Genesco Park
Nashville, TN 37217

Mr. John Grissom

PART I

A. LIMITATIONS ON WASTEWATER STRENGTH AND MONITORING REQUIREMENTS

No permittee shall discharge wastewater in excess of the concentration set forth in the table below unless: (1) an exception has been granted the user under the provisions of Section 40-1-187 Part II of the Metropolitan Code or, (2) the wastewater discharge permit of the user provides as a special permit condition a higher interim concentration level in conjunction with a requirement that the user construct a pretreatment facility or institute changes in operation and maintenance procedures to reduce the concentration of pollutants to levels not exceeding the standards set forth in the table within a fixed period of time.

<u>PARAMETER</u>	<u>MAXIMUM CONCENTRATION mg/L (FLOW PROPORTIONAL COMPOSITE SAMPLE</u>	<u>MAXIMUM INSTANTANEOUS CONCENTRATION mg/L (GRAB SAMPLE)</u>
Ammonia Nitrogen	30.0	60.0
Biochemical Oxygen Demand	300.0	600.0
Chemical Oxygen Demand	500.0	1000.0
Suspended Solids	325.0	650.0
Arsenic (As)	1.0	2.0
Cadmium (Cd)	1.0	2.0
Total Toxic Organics (TTO)	50.0	100.0
Chromium - Total (Cr)	5.0	10.0
Chromium - Hexavalent (Cr6)	0.05	0.1
Copper (Cu)	5.0	10.0
Cyanide (CN-)	2.0	4.0
Lead (Pb)	1.5	3.0
Mercury (Hg)	0.1	0.2
Nickel (Ni)	5.0	10.0
Selenium (Se)	1.0	2.0
Silver (Ag)	5.0	10.0
Zinc (Zn)	5.0	10.0
Oil & Grease (Freon Extractable)	50.0	100.0

1. CRITERIA TO PROTECT THE TREATMENT PLANT INFLUENT

The Director shall monitor the treatment works influent for each parameter in the following table. The Municipal User shall be subject to the reporting and monitoring requirements set forth in this permit as to these parameters. In the event that the influent at the treatment works reaches or exceeds the levels established by said table, the Director shall initiate technical studies to determine the cause of the influent violations, and shall initiate such remedial measures as are necessary, including, but not limited to, the establishment of new or revised pretreatment levels for these parameters. The Director may also change any of these criteria in the event the POTW effluent standards are changed or in the event changes are deemed advisable for effective operation of the POTW.

2. PARAMETER: MAXIMUM CONCENTRATIONS (ppm)/FLOW PROPORTIONAL COMPOSITE SAMPLE

	<u>CWWTP</u>	<u>DCWWTP</u>	<u>WCWWTP</u>
Ammonia	30.0	30.0	10.2
Arsenic	0.1	0.1	0.011
Boron	2.0	2.0	0.3
Cadmium	0.007	0.0016	0.0011
Calcium	2500.0	2500.0	2500.0
Chromium Total	1.5	0.51	0.51
Copper	1.0	0.52	0.52
Iron	0.17	0.07	0.07
Lead	5.0	5.0	1.0
Magnesium	0.23	0.23	0.23
Manganese	50.0	---	6.8
Mercury	11.8	11.8	11.8
Nickel	0.004	0.0009	0.0009
Phenols	0.52	0.32	0.32
Pyrene	0.6	0.03	0.03
Silver	0.0002	0.0002	0.0002
Sodium	6.2	6.2	6.2
Sulfate	---	---	23.8
Sulfide	500.0	---	---
Zinc	---	---	0.34
Butyl Benzylphthalate	2.7	0.43	0.43
Di-N Butyl Phthalate	0.003	0.003	0.003
Di-N Octyl Phthalate	0.03	0.03	0.03
2,4,5 TP Silvex	0.006	0.006	0.006
	0.01	0.01	0.01

3. PREVENTION OF ACCIDENTAL DISCHARGES

All Municipal Users shall provide such facilities and institute such procedures as are reasonably necessary to prevent or minimize the potential for accidental discharge into the POTW of waste regulated by this permit from liquid or raw material storage areas, from truck and rail car loading and unloading areas, from inplant transfer or processing and materials handling areas, from diked areas or holding ponds of any waste regulated by this permit. The permittee shall notify the POTW immediately by telephone of any slug loading, as defined by Metropolitan Code Section 40-1-186.

B. MONITORING PROCEDURES

1. Samples and measurements taken in compliance with the monitoring requirements of this permit shall be representative of the volume and nature of the monitored discharge during a normal production day and shall be taken as follows:
 - a. Be performed on FLOW-PROPORTIONAL SAMPLES REPRESENTATIVE OF THE TOTAL WASTEWATER FLOW discharge to the CITY OF BRENTWOOD Sewerage System with the maximum time interval between samples being no longer than sixty (60) minutes.
 - b. Be conducted in accordance with U. S. Environmental Protection Agency protocol. The results must be reported to the lowest detectable limit of the methodology.
 - c. Provide the flow rate for which the results are indicative to the nearest 100 gallons per day.

2. SAMPLE LOCATION

The samples will be collected at a manhole as shown on the plans prior to connection to the Brentwood Collection System.

3. TEST PROCEDURES

- a. Test procedures for the analysis of pollutants shall conform to regulations published pursuant to Section 304 (h) of the Clean Water Act of 1977, under which such procedures may be required.
- b. Unless otherwise noted in the permit, all pollutants parameters shall be determined according to methods prescribed in Title 40, CFR, Part 136, as amended, promulgated pursuant to Section 304 (h) of the Act.
- c. GENESCO, INC. must sample and analyze SEMI-ANNUALLY for the following parameters:

FLOW, BIOCHEMICAL OXYGEN DEMAND, SUSPENDED SOLIDS, OIL & GREASE, pH, AMMONIA, IRON*, ZINC*, CADMIUM*, AND MAGNESIUM*.

*INDICATES PARAMETERS OF CONCERN AT THE RECEIVING P.O.T.W.

4. MAINTENANCE OF RECORDS

Any Municipal User subject to the reporting requirements established in this section, shall maintain records of all information resulting from any monitoring activities required by this section. Such records shall include for all samples:

- (a) The date, exact place, method, and time of sampling and the names of the persons taking the samples;
- (b) The date analyses were performed.
- (c) Who performed the analyses;
- (d) The analytical techniques/method used; and
- (e) The results of such analyses.

Any Municipal User required by this paragraph to submit a similar report to the State of Tennessee or EPA under the provisions of 40 CFR 403.12, may submit to the Director a copy of said report in lieu of a separate report to the Director provided that all information required by this permit is included in the report to the State of Tennessee or EPA.

5. RECORDS RETENTION

Any Municipal User subject to the reporting requirements established in this permit shall be required to retain for a minimum of four (4) years any records of monitoring activities and results (whether or not such monitoring activities are required by this permit) and shall make such records available for inspection and copying by the Department of Water and Sewerage Services, the Division of Water Quality Control-Tennessee Department of Health and Environment, or the Environmental Protection Agency. This period of retention shall be extended during the course unresolved litigation regarding the permittee or when requested by the Department of Water and Sewerage Services, the Division of Water Quality Control-Tennessee Department of Health and Environment, or the Environmental Protection Agency.

6. DURATION OF THE PERMIT

Wastewater discharge permits shall be issued for a period stated on the permit. Notwithstanding the foregoing, users becoming subject to a National Pretreatment Standard shall apply for new permits on the effective date of such National Pretreatment Standards. A user must apply in writing for a renewal permit within the period of time not more than ninety (90) days and not less than thirty (30) days prior to expiration of the current permit. Provided further, that limitations or conditions of a permit are subject to modification or changes due to changes in applicable water quality standards, changes in Metro's NPDES permit, changes in the limitations of wastewater strength or POTW protection criteria, changes in other applicable law or regulation, or for other just causes.

7. TRANSFER OF A PERMIT

Wastewater discharge permits are issued to a specific user for a specific operation. A wastewater discharge permit shall not be reassigned, transferred or sold to a new owner, new user, or for different premises, unless approved by the Department of Water and Sewerage Services.

C. REPORTING

1. MONITORING RESULTS

Monitoring results shall be submitted SEMI-ANNUALLY using Discharge Monitoring Report Forms supplied by the City. A copy should be retained for the permittee's files. Discharge Monitoring Reports must be signed and certified by a principal municipal executive officer or ranking elected official, or his duly authorized representative. Such authorization must be submitted in writing and must be submitted in writing and must explain the duties and responsibilities of the authorized representative. Discharge Monitoring Reports and any communication regarding compliance with the conditions of this permit must be sent to:

CITY OF BRENTWOOD, TENNESSEE
P. O. Box 788
Brentwood, Tennessee 37024-0788

Attn: Mr. John Grissom

2. REPORTING SCHEDULE

THE FIRST DISCHARGE MONITORING REPORT IS DUE March 1, 1990. ADDITIONAL MONITORING REPORTS MUST BE RECEIVED IN THIS OFFICE ON OR PRIOR TO SEPTEMBER 1, 1990; MARCH 1, 1990; SEPTEMBER 1, 1991; ETC. UNTIL THIS PERMIT EXPIRES.

3. ADDITIONAL MONITORING BY PERMITTEE

If the permittee monitors any pollutant at the location(s) designated herein more frequently than required by this permit, using approved analytical methods as specified above, the results of such monitoring shall be included in the calculation and reporting of the values required in the Discharge Monitoring Report Form. Such increased frequency shall also be indicated.

4. FALSIFYING REPORTS

Knowingly, making any false statement on any report required by this permit may result in the imposition of criminal penalties as provided for in Section 309 of the Federal Water Pollution Control Act, as amended.

PART II

A. NATIONAL PRETREATMENT STANDARDS

Certain Municipal Users are now or hereafter shall become subject to National Pretreatment Standards promulgated by the Environmental Protection Agency specifying quantities or concentrations of pollutants or pollutant properties which may be discharge into the POTW. All Industrial Users subject to a National Pretreatment Standard shall comply with all requirements of such standard, and shall also comply with any additional or more stringent limitations contained in their permit. Compliance with National Pretreatment Standards for existing sources subject to such standards or for existing sources which hereafter become subject to such standards shall be within three (3) years following promulgation of the standards, unless a shorter compliance time is specified in the standard. Compliance with National Pretreatment Standards for new sources shall be required upon promulgation of the standard. Except, where, expressly, authorized by an applicable National Pretreatment Standard, no Industrial User shall increase the use of process water or in any way attempt to dilute a discharge as a partial or complete substitution for adequate treatment to achieve compliance with such standard.

B. PROHIBITIONS ON STORM DRAINAGE AND GROUND WATER

Storm water, ground water, rain water, street drainage, roof top drainage, basement drainage, sub-surface drainage, or yard drainage, if unpolluted shall not be discharged through direct or indirect connections to a community sewer unless a storm sewer or other reasonable alternative for removal of such drainage does not exist, and then only when such discharge is permitted by the user's wastewater discharge permit and the appropriate fee is paid for the volume thereof.

C. LIMITATION ON RADIOACTIVE WASTE

No permittee shall discharge or permit to be discharge any radioactive waste into a community sewer except:

- (1) When the user is authorized to use radioactive material by the Tennessee Department of Public Health or the Nuclear Regulatory Commission;
- (2) When the waste is discharged in strict conformity with applicable laws and regulations of the aforementioned agencies, or any other agency having jurisdiction; and
- (3) When a copy of permits received from said regulatory agencies have been filed with the Department of Water and Sewerage Services.

D. PROHIBITIVE DISCHARGE STANDARDS

- (1) No permittee shall introduce into the publicly owned treatment works any of the following pollutants which acting either alone or in conjunction with other substances present in the POTW interfere with the operation of the POTW as follows:

- a. Pollutants which could create a fire or explosion hazard in the POTW;
- b. Pollutants which cause corrosive structural damage to the POTW, but in no case discharges with a pH lower than 5.0 or higher than 10.0;
- c. Solid or viscous pollutants in amounts which cause obstruction to the flow of the sewers, or other interference with the operation of or which cause injury to the POTW, including waxy or other materials which tend to coat and clog a sewer line or other appurtenances thereto;
- d. Any pollutant, including oxygen demanding pollutants (BOD, etc.) released in a discharge of such volume or strength as to cause interference in the POTW;
- e. Heat in amounts which will inhibit biological activity in the POTW resulting in interference, but in no case heat in such quantities that the temperature at the treatment works influent exceeds 40 degrees Centigrade (104 degrees Fahrenheit). Unless a higher temperature is allowed in the user's wastewater discharge permit, no user shall discharge into any sewer line or other appurtenance of the POTW wastewater with a temperature exceeding 65.5 degrees Centigrade (150 degrees Fahrenheit).

The aforesaid pollutants represent a general description of harmful or dangerous conditions, and are in addition to such specific pollutants as may be identified and added from time to time to the Industrial User's Permit.

- (2) The permittee shall notify the Industrial Compliance Section on any of the following changes in user discharge to the system no later than 180 days prior to change of discharge:
 - a. New introductions into such works of pollutants from any source which would be a new source, if such source were discharging pollutants.
 - b. New introductions of pollutants into such works from a source which would be subject to the Sewer Use Ordinance if it were discharging such pollutants.
 - c. A substantial change in volume or character or pollutants being discharged into such works at the time the permit is issued.
- (3) This notice will include information on the quality and quantity of the wastewater introduced by the new source into the publicly owned treatment works, and on any anticipated impact on the effluent discharged from such works.

PART III

The City of Brentwood shall establish and maintain a Pretreatment Program in accordance with 40 CFR 403 with all changes and corrections. The City of Brentwood, as part of their Program, shall permit and sample or cause to be sampled, in accordance with current protocol; (1) all Industries covered by an enacted or proposed Categorical Pretreatment Standard; (2) all Industries with wastewater flows or strength of compatible pollutants, that would be considered significant contributors to their system. The City of Brentwood shall have legal authority established to enforce their Pretreatment Program. The City of Brentwood shall submit their report to the Metropolitan Department of Water Services, Industrial Compliance Section on the first of September and the first of March, semi-annually, consisting of; (1) the current State of Tennessee format for Pretreatment reporting, (2) results of sampling performed by the City of Brentwood, in accordance with their Trunk and Treatment Agreement with the Metropolitan Government and/or requirements of this permit.

The City of Brentwood's Pretreatment Submittal shall be reviewed by Metro Water Services and transmitted to the State of Tennessee as part of Metro Water Services Pretreatment Submittal.

Metro Water Services shall be the Control Authority for the City of Brentwood relative to all aspects of Pretreatment reporting and enforcement. Metro Water Services shall have the right to audit and/or inspect the City of Brentwood's Pretreatment Program at any time during the effective dates of this permit.

PERMIT SUMMARY

THE CITY OF BRENTWOOD SHALL SAMPLE AND ANALYZE SEMI-ANNUALLY FOR THE FOLLOWING PARAMETERS:

FLOW, BIOCHEMICAL, OXYGEN DEMAND, SUSPENDED SOLIDS, OIL & GREASE, AMMONIA, pH, LEAD, ZINC, CADMIUM, IRON, AND MAGNESIUM

GROUNDWATER SAMPLING SCHEDULE

TABLE 2-3

GROUNDWATER SAMPLING SCHEDULE
Kennon Site - Brentwood, Tennessee

I. KENNON SITE - WELL MONITORING PROGRAM

Quarterly samples of selected monitor wells analyzed for Organic Priority Pollutants - Volatiles, and annual sample for full Priority Pollutants List, less pesticides and PCB's. These samples are required until the site is de-listed by TDEC.

II. CITY OF BRENTWOOD SEWER SAMPLING PROGRAM

Quarterly sample taken at the manhole to City of Brentwood sewer system for Organic Priority Pollutants - Volatiles, with semi-annual Baseline Analysis for the "METRO" list. These are required as long as the site is connected to the City of Brentwood sewer system.

III. SOURCE REMOVAL PHASE - GROUNDWATER DISCHARGE MONITORING PROGRAM

Weekly samples of discharge to sewer for Organic Priority Pollutants - Volatiles, and monthly Baseline Analysis for the "METRO" List required during the excavation of source material in 1990 and 1991.

WATER SAMPLING SCHEDULE FOR THE KENNON SITE

1993 - 1995

SAMPLE COLLECTION PERIOD	SAMPLING LOCATIONS							SEWER	TEST REQUIRED
	Intermediate Monitoring Wells			Downgradient Monitoring Wells					
	UN-1	UN-2	UN-5	UN-3	UN-4	W-10	W-25		
1st Quarter - 1993								X	Priority Pollutants-Volatiles
2nd Quarter - 1993	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 1993								X	Priority Pollutants-Volatiles
4th Quarter - 1993	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"
1st Quarter - 1994								X	Priority Pollutants-Volatiles
2nd Quarter - 1994	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 1994								X	Priority Pollutants-Volatiles
4th Quarter - 1994	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"
1st Quarter - 1995								X	Priority Pollutants-Volatiles
2nd Quarter - 1995	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 1995								X	Priority Pollutants-Volatiles
4th Quarter - 1995	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"

WATER SAMPLING SCHEDULE FOR THE KENNON SITE

1996 - 1998

SAMPLE COLLECTION PERIOD	SAMPLING LOCATIONS							SEWER	TEST REQUIRED
	Intermediate Monitoring Wells			Downgradient Monitoring Wells					
	UN-1	UN-2	UN-5	UN-3	UN-4	W-10	W-25		
1st Quarter - 1996								X	Priority Pollutants-Volatiles
2nd Quarter - 1996	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 1996								X	Priority Pollutants-Volatiles
4th Quarter - 1996	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"
1st Quarter - 1997								X	Priority Pollutants-Volatiles
2nd Quarter - 1997	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 1997								X	Priority Pollutants-Volatiles
4th Quarter - 1997	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"
1st Quarter - 1998								X	Priority Pollutants-Volatiles
2nd Quarter - 1998	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 1998								X	Priority Pollutants-Volatiles
4th Quarter - 1998	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"

WATER SAMPLING SCHEDULE FOR THE KENNON SITE

1999 - 2001

SAMPLE COLLECTION PERIOD	SAMPLING LOCATIONS							SEWER	TEST REQUIRED
	Intermediate Monitoring Wells			Downgradient Monitoring Wells					
	UN-1	UN-2	UN-5	UN-3	UN-4	W-10	W-25		
1st Quarter - 1999								X	Priority Pollutants-Volatiles
2nd Quarter - 1999	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 1999								X	Priority Pollutants-Volatiles
4th Quarter - 1999	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"
1st Quarter - 2000								X	Priority Pollutants-Volatiles
2nd Quarter - 2000	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 2000								X	Priority Pollutants-Volatiles
4th Quarter - 2000	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"
1st Quarter - 2001								X	Priority Pollutants-Volatiles
2nd Quarter - 2001	X			X		X		X	Priority Pollutants-Volatiles; "Metro List" for sewer
3rd Quarter - 2001								X	Priority Pollutants-Volatiles
4th Quarter - 2001	X	X	X	X	X	X	X	X	Full Priority Pollutants List (less pesticides and PCB's) and "Metro List"

NOTE: The above schedule continues until the site is de-listed by the Tennessee Department of Environment and Conservation.

WATER SAMPLING LOG

MOSELY & ASSOCIATES, INC.
Water Sampling Log

Project Name/No:

Site Location:

Sample Well/Point:

Weather:

Time Sampling Began:

Time Sampling Completed:

Date:

EVACUATION DATA - WELL SAMPLING ONLY

Description of Measuring Point:

Listed Elevation of MP (ft msl):

Total Sounded Depth of Well Below MP:

Listed Surface Elevation (ft msl):

Sounded Depth of Water Below MP:

Height of MP Above Land Surface:

Height of Water Column In Well:

Listed Depth of Boring (ft):

Gallons Pumped/Balled Prior to Sampling:

Diameter of Casing:

Gallons per Foot In Casing:

Evacuation Method:

SAMPLING DATA/FIELD PARAMETERS

Color:

Odor:

Appearance:

Temperature:

Other (Specification; OVA; HNU; etc.):

Specific Conductance, umhos/cm:

pH:

Sampling Method and Material:

SAMPLE CONTAINER DESCRIPTION

Laboratory Supplying Containers:

Sample Container/Vial Number

Type Container

Preservation

Remarks:


Sampling Personnel:

Well Casing Volumes								
GAL/FT	1-1/4"	= 0.077	2"	= 0.16	3"	= 0.37	4"	= 0.65
	1-1/2"	= 0.10	2-1/2"	= 0.24	3-1/2"	= 0.50	6"	= 1.46

CHAIN OF CUSTODY RECORD

(Use extra sheets, if necessary)

LOCATION OF MONITORING WELLS IN SAMPLING PROGRAM



MAP DEPICTING LOCATIONS OF WELLS TO BE SAMPLED

LIST OF PRIORITY POLLUTANTS TO BE ANALYZED

"METRO LIST"

Flow
Biochemical Oxygen Demand (BOD₅)
Suspended Solids (SS)
Oil and Grease (O & G)
pH

Ammonia
Iron
Zinc
Cadmium
Magnesium

EPA PRIORITY POLLUTANTS LIST (Less Pesticides and PCB's)

ORGANIC

Volatiles

Benzene
Bromoform
Carbon tetrachloride
Chlorobenzene
Chlorodibromomethane
Chloroethane
2-Chloroethylvinyl ether
Chloroform
Dichlorobromomethane
1,1-Dichloroethane
1,2-Dichloroethane
1,2-Dichloroethylene
1,2-Dichloropropane
1,3-Dichloropropene
Ethylbenzene
Methyl Bromide
Methyl chloride
Methylene chloride
1,1,2,2-Tetrachloroethane
Tetrachloroethylene
Toluene
Trans-1,2-dichloroethylene
1,1,1-Trichloroethane
1,1,2-Trichloroethane
Trichloroethylene
Vinyl chloride

Acid and Base/Neutral Extractables

2-Chlorophenol
2,4-Dichlorophenol
2,4-Dimethylphenol
4,6-Dinitro-o-cresol
2,4-Dinitrophenol
2-Nitrophenol
4-Nitrophenol
p-chloro-m-cresol
Pentachlorophenol
Phenol
2,4,6-Trichlorophenol
Acenaphthene
Acenaphthylene
Anthracene
Benzidine
Benzo(a)anthracene
Benzo(a)pyrene
Benzo(b)fluoranthene
Bis-2-chloroethoxymethane
Bis(2-chloroethyl) ether
Bis(2-chloroisopropyl) ether
Bis(2-ethylhexyl) phthalate
4-Bromophenyl phenyl ether
Butyl benzyl phthalate
2-Chloronaphthalene
4-Chlorophenyl phenyl ether
Chrysene

Acid and Base/Neutral Extractables (Cont.)

Dibenz(a,h)anthracene
1,2-Dichlorobenzene
1,3-Dichlorobenzene
1,4-Dichlorobenzene
3,3-Dichlorobenzidine
Diethyl phthalate
Di-n-butyl phthalate
2,4-Dinitrotoluene
2,6-Dinitrotoluene
Di-n-octyl phthalate
1,2-Diphenyl-hydrazine
Fluoranthene
Fluorene
Hexachlorobenzene
Hexachlorobutadiene
Hexachlorocyclopentadiene
Hexachloroethane
Indeno(1,2,3-cd)pyrene
Isophorone
Naphthalene
Nitrobenzene
N-nitrosodimethylamine
N-nitrosodi-n-propylamine
N-nitrosodiphenylamine
Phenanthrene
Pyrene
1,2,4,-Trichlorobenzene

INORGANIC/OTHER

Antimony
Arsenic
Asbestos
Beryllium
Cadmium

Chromium
Copper
Cyanide
Lead
Mercury

Nickel
Phenols
Selenium
Silver
Thallium
Zinc

**STATUS, CONSTRUCTION DETAILS AND
LOCATION OF WELLS**

STATUS OF WELLS - KENNON SITE

A total of 56 groundwater monitoring wells were drilled on the Kennon property. Many of the wells were designed and used during the initial investigation activities on the property; others were designed for use as groundwater monitoring wells. Several of the wells have been damaged by farm equipment (i.e., W-27, SB-12, W-28, W-17, W-19) and others are screened in extremely low permeability zones and do not produce sufficient water for sampling purposes (e.g., PZ-1, PZ-7A, W-20, W-21, W-22, W-18, W-13, W-14, SB-10, SB-12, SB-13).

The following Status of Wells Report lists all wells and describes those proposed to be retained in the sampling program, as well as those proposed to be closed. The map and construction details charts that follow contain additional information relative to the Kennon site wells.

It is proposed that those wells identified as unsuitable for sampling be closed in 1994 or 1995. The remainder of the wells would either be included in the groundwater sampling program or available for alternates, if needed, for the program, and would be closed as a part of site de-listing procedures when specified by TDEC.

Well closure will follow Tennessee Rule 1200-4-10, Well Construction and Abandonment Standards, with the exception of 1200-4-10-.09(b)3, which specifies well chlorination prior to sealing. Since this would introduce chlorinated hydrocarbons into the shallow aquifer which might interfere with subsequent groundwater analysis, this requirement is not deemed appropriate for this site.

STATUS OF WELLS
Kennon Site - Brentwood, Tennessee

Well Number	Status	Reason
DB1	Will Be Closed	Upgradient, too deep for meaningful sample.
DB2	Will Be Closed	Upgradient, too deep for meaningful sample.
DB3	Will Be Closed	Upgradient, too deep for meaningful sample.
DB4	Will Be Closed	Too deep for meaningful sample.
DB5	Will Be Closed	Too deep for meaningful sample.
DB6	Will Be Closed	Too deep for meaningful sample.
DB7	Will Be Closed	Too deep for meaningful sample.
DB8	Will Be Closed	Too deep for meaningful sample.
PZ1	Will Be Closed	None or limited recovery.
PZ2	Will Be Closed	Upgradient of site.
PZ3	Will Be Closed	Upgradient of site.
PZ4	Remain Open	Alternate for UN5.
PZ5	Will Be Closed	Upgradient of site.
PZ6	Will Be Closed	Upgradient of site.
PZ7	Remain Open	Alternate for UN5.
PZ7A	Will Be Closed	None or limited recovery.
PZ8	Remain Open	Alternate for UN1, UN9
PZ9	Remain Open	Alternate for UN1, UN9
SB1	Will Be Closed	Upgradient of site.
SB2	Will Be Closed	Upgradient of site.
SB3	Will Be Closed	Upgradient of site.
SB4	Remain Open	Alternate for W25.
SB5	Remain Open	Alternate for W25.
SB6	Will Be Closed	Upgradient of site.
SB7	Remain Open	Alternate for UN5.

Well Number	Status	Reason
SB8	Remain Open	Alternate for UN1.
SB9	Remain Open	Alternate for UN2.
SB10	Will Be Closed	None or limited recovery.
SB11	Remain Open	Alternate for UN1, UN5.
SB12	Will Be Closed	Damaged by farm equipment/none or limited recovery.
SB13	Will Be Closed	None or limited recovery.
UN1	Remain Open	Included in groundwater sampling plan.
UN2	Remain Open	Included in groundwater sampling plan.
UN3	Remain Open	Included in groundwater sampling plan.
UN4	Remain Open	Included in groundwater sampling plan.
UN5	Remain Open	Included in groundwater sampling plan.
W10	Remain Open	Included in groundwater sampling plan.
W11	Remain Open	Alternate for W10.
W12	Remain Open	Alternate for W10.
W13	Will Be Closed	None or limited recovery.
W14	Will Be Closed	None or limited recovery.
W15	Remain Open	Alternate for W25.
W16	Remain Open	Alternate for W23.
W17	Will Be Closed	Damaged by farm equipment.
W18	Will Be Closed	None or limited recovery.
W19	Will Be Closed	Damaged by farm equipment.
W20	Will Be Closed	None or limited recovery.
W21	Will Be Closed	None or limited recovery.
W22	Will Be Closed	None or limited recovery.
W23	Remain Open	Alternate for W25.
W24	Remain Open	Alternate for W25.
W25	Remain Open	Included in groundwater sampling plan.

Well Number	Status	Reason
W26	Will Be Closed	Upgradient of site.
W27	Will Be Closed	Upgradient of site/damaged by farm equipment.
W28	Will Be Closed	Upgradient of site/damaged by farm equipment.
W29	Will Be Closed	Upgradient of site.

Table 4. Construction Details of Monitor Wells Installed by Geologic Associates, Inc.

WELL NO.	INSTALLATION DATE	SURFACE ELEV. (ft msl)	MEAS. PT. ELEV. (ft msl)	SCREENED INTERVAL (Depth, ft)	FILTER PACK INTERVAL (Depth, ft)	DENTONITE SEAL INTERVAL (Depth, ft)	GROUT BACKFILL INTERVAL (Depth, ft)	AUGER OR WASH BIT REFUSAL (Depth, ft)
PZ-1	1/15/86	777.1	780.3	20.55 - 30.55	12.0 - 31.3	9.6 - 12.0	0 - 9.6	9.6
PZ-2	1/15/86	778.08	781.2	20.7 - 30.7	6.0 - 30.7	4.5 - 6.0	0 - 4.5	5.4
PZ-3	1/17/86	787.25	790.0	20.7 - 30.5	6.5 - 30.7	5.0 - 6.5	0 - 5.0	5.7
PZ-4	1/17/86	790.40	793.6	20.0 - 30.0	7.0 - 31.2	5.0 - 7.0	0 - 5.0	5.7
PZ-5	1/20/86	797.70	800.6	21.0 - 32.0	6.0 - 32.0	4.0 - 6.0	0 - 4.0	5.0
PZ-6	1/21/86	808.47	810.5	18.5 - 28.5	10.5 - 28.5	8.5 - 10.5	0 - 8.5	9.3
PZ-7	1/23/86	779.08	782.0	5.0 - 8.5	5.0 - 8.3	3.5 - 5.0	0 - 3.5	6.2
PZ-7A	1/24/86	778.77	781.5	11.4 - 21.4	7.5 - 21.4	6.0 - 7.5	0 - 6.0	6.3
PZ-8	1/27/86	777.60	780.7	8.0 - 11.1	8.0 - 11.0	6.0 - 8.0	0 - 6.0	9.9
PZ-9	1/28/86	777.0	779.4	7.5 - 10.4	7.0 - 10.4	5.5 - 7.0	0 - 5.5	7.4
W-10	3/04/86	769.8	772.1	5.4 - 13.2	3.7 - 13.2	1.7 - 3.7	0 - 1.75	7.8
W-11	3/04/86	768.83	771.2	1.8 - 7.2	1.8 - 7.2	0 - 1.8		4.9
W-12	3/04/86	771.19	773.5	4.1 - 9.5	3.1 - 9.5	1.0 - 3.1	0 - 1.0	7.2
W-13	3/04/86	764.07	776.5	1.4 - 7.0	1.3 - 7.0	0 - 1.3		4.6
W-14	3/04/86	767.29	769.7	2.6 - 5.5	2.6 - 5.5	0 - 2.6		3.5
W-15	3/14/86	765.16	767.6	3.6 - 6.5	2.6 - 6.5	0 - 2.6		4.5
W-16	3/04/86	767.5	769.9	6.1 - 11.5	5.1 - 11.5	2.6 - 5.1	0 - 2.6	1.2
W-17	3/14/86	758.3	760.6	2.0 - 7.5	2.1 - 8.0	0 - 2.1		5.7
W-18	3/14/86	759.0	761.4	4.7 - 9.2	3.4 - 9.2	1.2 - 3.4	0 - 1.2	7.0
W-19	3/14/86	759.9	761.3	5.6 - 11.0	4.6 - 11.0	2.6 - 4.6	0 - 2.6	8.9
W-20	3/14/86	751.2	753.6	3.7 - 6.5	2.7 - 6.5	0 - 2.7		4.4
W-21	2/28/86	750.31	752.7	6.0 - 11.5	5.2 - 11.5	3.2 - 5.2	0 - 3.2	8.5
W-22	2/28/86	750.0	752.4	2.2 - 7.8	2.0 - 7.8	0 - 2.0		5.4
W-23	2/28/86	744.63	747.0	6.5 - 14.5	4.5 - 14.5	2.5 - 4.5	0 - 2.5	11.2
W-24	3/03/86	745.0	748.0	8.5 - 13.8	7.0 - 13.8	4.5 - 7.0	0 - 4.5	11.3
W-25	3/14/86	765.10	767.5	1.5 - 6.9	3.0 - 6.9	0 - 3.0		6.9
W-26	3/03/86	792.10	794.5	8.0 - 21.2	6.5 - 21.2	3.0 - 6.5	0 - 3.0	10.9
W-27	3/03/86	794.79	797.3	1.0 - 11.6	1.6 - 11.6	0 - 1.6		7.0
W-28	3/03/86	764.99	767.4	3.0 - 11.0	2.5 - 11.0	0 - 2.5		5.8
W-29	3/04/86	822.0	824.4	16.7 - 44.5	10.2 - 44.5	8.2 - 10.2	0 - 8.2	8.3

NOTES

1. Measuring points are top of PVC casing.
2. Total depth of each well is the bottom of the filter pack.
3. All casing is 2-inch-diameter PVC, flush threaded.
4. All screen is 2-inch-diameter PVC, slotted (0.01 in slot).
5. Wells PZ-1 through PZ-9 wash-bored to bedrock (6-inch-diameter borehole).
6. Wells W-10 through W-29 augered to bedrock (6-inch-diameter borehole).
7. All wells except W-25 cored from top of bedrock to total depth (3-inch-diameter corehole).

Table 7. G&M Monitor-Well Construction Details

Well Number	Surface Elevation (ft msl)	Top of Casing* Elevation (ft msl)	Surface** Casing	Top of** Bentonite Seal	Top of** Filter Pack	Top of** Screen	Total Depth of Boring
DB1	793.3	796.87	35.0	102.2	107.1	108.9	119.4
DB2	787.2	790.22	21.5	91.0	95.5	97.7	108.2
DB3	771.0	773.76	27.0	68.2	72.0	74.5	94.9
DB4	744.8	747.84	20.0	76.8	80.3	82.4	92.9
DB5	760.7	764.09	25.0	93.2	97.4	99.6	110.1
DB6	790.5	793.68	35.0	126.8	129.8	132.9	143.7
DB7	779.2	782.41	22.0	94.3	100.7	103.9	114.3
DB8	777.9	781.06	30.0	86.0	95.7	98.7	109.1
SB1	820.2	823.62	18.0	18.4	25.6	26.7	37.1
SB2	788.2	791.11	7.5	8.5	12.5	14.5	20.0
SB3	771.6	774.34	12.0	19.4	23.2	24.7	30.2
SB4	768.1	771.09	8.5	7.8	10.4	12.8	18.4
SB5	760.5	763.40	8.5	7.6	12.1	13.6	19.2
SB6	790.6	793.96	10.0	23.1	26.6	28.7	34.3
SB7	780.0	783.36	13.5	11.7	14.5	16.6	22.0
SB8	777.9	781.12	12.0	11.3	14.3	16.8	22.2
SB9	770.7	773.79	6.5	8.8	13.3	15.4	20.8
SB10	781.9	784.85	7.5	12.0	16.5	18.6	24.0
SB11	780.4	783.82	9.0	12.8	16.1	18.4	23.8
SB12	783.6	786.68	9.0	12.3	16.8	18.9	24.3
SB13	784.3	787.36	8.0	12.8	16.5	18.9	24.3
UN1	777.4	780.45	N/A	3.4	7.1	7.2	9.4
UN2	770.6	773.70	N/A	0.1	2.1	2.2	4.5

* Top of 2-in-diameter casing (water level measuring point)

** Measured depth in feet below land surface

ADDITIONAL MONITORING WELLS IN 1988

Well Number	Installation Date	Surface Elevation (ft msl)	Measurement Point Elevation (ft msl)	Screened Interval (depth, ft)	Filter Pack Interval (depth, ft)	Bentonite Seal Interval (depth, ft)	Total Depth of Boring (ft)
UN-3	05/11/88	770.50	773.00	3.1 - 5.2	2.5 - 5.2	0.0 - 2.5	5.2
UN-4	05/10/88	772.05	774.33	4.6 - 6.7	3.0 - 6.7	0.0 - 3.0	6.7
UN-5	05/10/88	780.01	782.22	8.2 - 10.3	3.0 - 10.3	0.0 - 3.0	10.3

NOTE: Depth, ft measurements are from land surface.

**GROUNDWATER MONITORING RESULTS
TDEC WELL MONITORING PROGRAM**

QUARTERLY/BI-ANNUAL MONIT VG PROGRAM - KENNON SITE

(

[illegible]

TDEC WELL MONITORING - ANALYSIS OF RESULTS (All results in milligrams/liter)
QUARTERLY/BI-ANNUAL MONITORING PROGRAM - KENNON SITE

VOLATILE ORGANICS

[illegible]

TDEC WELL MONITORING - ANALYSIS OF RESULTS (All results in milligrams/liter)
QUARTERLY/BI-ANNUAL MONITORING PROGRAM - KENNON SITE

VOLATILE ORGANICS

[illegible]

TDEC WELL MONITORING - ANALYSIS OF RESULTS (All results in milligrams/liter)
QUARTERLY/BI-ANNUAL MONITORING PROGRAM - KENNON SITE

VOLATILE ORGANICS

[illegible]

()

1

[illegible]

(

[illegible]

**GROUNDWATER MONITORING RESULTS
CITY OF BRENTWOOD MONITORING PROGRAM**

(

[illegible]

WASTE WATER SAMPLING PROGRAM - CITY OF BRENTWOOD
KENNON SITE - MANHOLE "X"
All Results in Milligrams per Liter

PARAMETER	4TH QTR. 12-29-92	1ST QTR. 4-6-93	2ND QTR. 5-6-93	3RD QTR. 8-4-93	4TH QTR. 10-26-93	1ST QTR.	2ND QTR.	3RD QTR.	4TH QTR.	1ST QTR.	2ND QTR.	3RD QTR.	4TH QTR.
Ammonia Nitrogen Dist.													
BOD													
Hexavalent Chromium													
COD													
T. Cyanide													
Oil & Grease					0.0099								
TSS					0.03								
Cadmium													
Chromium													
Copper													
Lead													
Nickel													
Silver													
Zinc					0.034								
Arsenic													
Selenium													
Mercury													
Priority Poll. VOC													
Dichlorobromomethane													
Chloroethane													
1,1-Dichloroethane													
1,2-Dichloroethane													
Tetrachloroethylene													
1,1,1-Trichloroethane													
Benzene													
Methylene Chloride					0.0014J								
Toluene													
1,2-Dichloroethylene													
Trichloroethylene													
Vinyl Chloride													
1,1-Dichloroethylene													
Ethylbenzene													
Dichlorodifluoromethane													
1,2-Dichloroethene													
1,1-Dichloroethene													
Trichloroethene													
Acetone					0.013J								

**GROUNDWATER MONITORING RESULTS
EVACUATION MONITORING PROGRAM**

WASTE WATER SAMPLING PROGRAM - CITY OF BRENTWOOD
KENNON SITE - EXCAVATION SAMPLES
All Results in Milligrams per Liter

PARAMETER	BASELINE 11-30-90	EXCAV. 10-24-90	EXCAV. 11-20-90	EXCAV. 12-7-90	EXCAV. 12-14-90	EXCAV. 12-19-90	EXCAV. 1-18-91	EXCAV. 1-25-91*	EXCAV. 1-31-91	EXCAV. 4-9-91
Ammonia Nitrogen Dist.	0.14	0.93	3.4							
BOD	<5	40.0	7.0				9.0			
Hexavalent Chromium	<0.01									
COD	18		43.0				43			
T. Cyanide	<0.01									
Oil & Grease	<2		1.4							
TSS	4	9.3	12.0				18.0			
Cadmium	<0.005	0.011								
Chromium	<0.02									
Copper	<0.01									
Lead	<0.1									
Nickel	<0.02									
Silver	<0.01									
Zinc	0.04	0.053	0.076				0.024			
Arsenic	0.004									
Selenium	<0.02									
Mercury	<0.0002		0.48							
Priority Poll. VOC										
Dichlorobromomethane										
Chloroethane	0.013	0.0034	0.049			0.017			0.011	
1,1-Dichloroethane	0.050	0.042	0.12	0.0053	0.0097	0.061	0.0048	0.26	0.072	.016
1,2-Dichloroethane		0.014	0.11		0.013		0.0047	0.19	0.009	
Tetrachloroethylene		0.0033	0.022	0.011	0.0075		0.011		0.0036	
1,1,1-Trichloroethane	0.023	0.0084	0.12	0.039	0.027	0.012	0.03	0.68	0.019	.011
Benzene			0.0031					0.019		
Methylene Chloride			0.069		0.004		0.0021			
Toluene			0.16	0.017		0.0073		.11	0.013	
1,2-Dichloroethylene	0.056		0.19		0.0039	0.09	0.0042		0.039	.014
Trichloroethylene			0.0077					0.17		
Vinyl Chloride			0.024			0.018		0.0091	0.0048	
1,1-Dichloroethylene			0.0038					0.025		
Ethylbenzene								0.026		
Dichlorodifluoromethane										
1,2-Dichloroethene										
1,1-Dichloroethene										
Trichloroethene										

* - construction mishap caused small spill directly into sampling intake

WASTE WATER SAMPLING PROGRAM - CITY OF BRENTWOOD
KENNON SITE - EXCAVATION SAMPLES
All Results in Milligrams per Liter

PARAMETER	EXCAV. 4-19-91	EXCAV. 4-29-91	EXCAV. 5-3-91	EXCAV. 5-9-91	EXCAV. 5-16-91	EXCAV. 8-23-91	EXCAV. 8-21-91	EXCAV. 10-25-91
Ammonia Nitrogen Dist.								
BOD								
Hexavalent Chromium								
COO	49.5							
T. Cyanide								
Oil & Grease								
TSS	58.7							
Cadmium								
Chromium								
Copper								
Lead								
Nickel	0.03							
Silver								
Zinc	0.022							
Arsenic								
Selenium								
Mercury								
Priority Poll. VOC								
Dichlorobromomethane								
Chloroethane								.0038J
1,1-Dichloroethane	.003	.0049	.0043	.0076	.019	.008		
1,2-Dichloroethane							.0025J	.0067J
Tetrachloroethylene								
1,1,1-Trichloroethane	.0038	.0037	.0046	.0036	.010	.0054		
Benzene								
Methylene Chloride								
Toluene						.003		.0013J
1,2-Dichloroethylene	.0022	.0032	.0048	.0066	.017	.0054		
Trichloroethylene								
Vinyl Chloride								
1,1-Dichloroethylene								
Ethylbenzene								
Dichlorodifluoromethane								
1,2-Dichloroethene							.0036J	
1,1-Dichloroethene							.0062J	
Trichloroethene								

SITE SECURITY PROGRAM

SITE SECURITY PROGRAM
Kennon Site - Brentwood, Tennessee

Site security is described in two sections of the following report; Site Security - Source Control/Remediation (during the source control and remediation activities), and; Site Security - Soils Management/Bioremediation Activities (during the long-term soils management and bioremediation process).

Site Security - Source Control/Remediation Activities

The following security devices were utilized in conjunction with site security during the source control/remediation activities:

- An eight (8) foot high chain link fence was installed completely around the site as one of the first security activities. It has remained intact since that time, except for renovation and improvement to facilitate installation of gates, repair, etc.
- High density security lights, mounted on five telephone poles throughout the site, were installed to provide additional lighting for security purposes at night and at times when lighting was less than desired.
- The site access road was moved from exiting from the south end of the Kennon Farm to exit in the middle of the Kennon Farm at the existing railroad crossing. This move was accomplished to comply with a request from the City of Brentwood, but did allow additional site security since the road passed directly in front of the farm manager's home. Additional gate and locks were installed across the roadway directly in front of the farm manager's home.
- A uniformed guard service was employed during all of the source control/remediation activities, with the security guard being stationed at the front gate of the site in front of the farm manager's home. Traffic was limited to those contractors and deliveries necessary to site operations. Access was gained through radio communications with the site operations trailer. At nights and on weekends during the source control/remediation stage, (when activity was conducted on the site), a security guard was stationed in the site operation trailer to provide additional security.
- The electrical systems to the site, the floats that control the pumping mechanism in the lift station, and two underground storage tanks are monitored electronically by an alarm system with an automatic telephone dialer. In this twenty-four hour monitoring system, should the electricity fail or the sensors indicate that the waste water control pumping system is not working accurately, then the automatic telephone dialer calls the offices of Mosely & Associates, Inc. every four minutes until corrective action is taken on the site.

Site Security - Soils Management/Bioremediation Activities:

The following activities will take place throughout the soils management/bioremediation phase of the site remediation program:

- The eight (8) foot high chain link fence with lock-secured gates will remain intact around the site until the site is de-listed by the Tennessee Department of Environment and Conservation.
- The high density security lights, mounted on the five telephone poles throughout the site, will remain active during dark hours until such time as the Tennessee Department of Environment and Conservation agrees that they may be disconnected.

- The site access road will remain in the location utilized during the source control activities, through the middle of the farm. It will continue to exit directly in front of the farm managers home, to provide additional security for the site. Dual locks will remain on the farm gate in front of the farm managers home, to allow entrance to the site access road to the farm manager, Mosely & Associates, Inc. personnel, or the Tennessee Department of Environment and Conservation
- The site electrical/pumping system alarm mechanism will continue to operate until the site is de-listed by the Tennessee Department of Environment and Conservation. Should the electricity be interrupted at the site, or should the sensors located in the lift station, electrical panels or underground storage tanks detect that the water flow control program is not working satisfactorily, the office of Mosely & Associates, Inc. in Nashville, Tennessee will be called by the automatic telephone calling system every four minutes until personnel arrive at the site to correct the situation. It should be emphasized that there is at least four to six weeks of groundwater holding capacity on the site itself, even in times of heavy rain, in the event that the system fails to function properly. Temporary situations such as electrical outages during storms, etc. are usually self-corrected within a matter of minutes.

Emergency Personnel Listing:

The following personnel have been designated and properly trained for emergency purposes to accomplish any emergency actions that may occur on the site itself:

**INITIAL CONTACT FOR ALL EMERGENCIES
AND OVERALL RESPONSIBILITY:**

Ralph Mosely, President
Mosely & Associates, Inc.

**DAY TIME
TELEPHONE**

615-399-1016

**EMERGENCY
TELEPHONE**

615-664-1813

David Johnson, Sr. Consultant
Mosely & Associates, Inc.

615-399-1016

615-664-1813

**ELECTRICAL AND MECHANICAL PROBLEMS
AND PUMPING SYSTEM:**

Roy Gregory/John Ray
Genesco Inc.

615-367-8222

615-367-7701

**TENNESSEE OF DEPARTMENT ENVIRONMENT
AND CONSERVATION - NASHVILLE FIELD OFFICE:**

Brenda Apple

615-741-5940

1-800-251-3479

Reference 5

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION

OFFICE CORRESPONDENCE

DATE: 12-18-92

TO: DSF, NFO Staff

FROM: Brenda Apple ~~EA~~

SUBJECT: Public Drinking Water Systems in Middle Tennessee

[illegible]

Please find attached two lists. One is of community systems and one is of non-community systems. Both lists should be reviewed for PA/SI purposes. The main difference between the two systems is the number of people they serve. The reference for this source of information is "Tennessee Division of Water Supply, Public Water System Directory, December 15, 1992".

You will still need to contact the Ground Water section in the Division of Water Supply for private well information. Following is an explanation of some of the codes:

1. 01, 02...indicates the systems source of water (even if they buy water from someone else.)
2. The latitude, longitude and river mile is listed when appropriate and available.
3. The column with service connections can be treated as number of residences in service area and then is multiplied by county household factors to get population column.
4. Source Codes are: S=surface water
G=ground water (well or spring)
P=purchased surface water
W=purchased ground water

FROM	DATE

10

[illegible]

pkal.doc

BKA/kdr

00429 MANCHESTER WATER DEPARTMENT (615) 728-7171 P 9900 3574
 200 W. Fort Street
 Manchester, TN 37355

RIVER MILE

01 DUCK RIVER UC (PWSID # 0000821)

00879 SHADY GROVE MHP (615) 728-3169 G 110 40
 Route 8, Dixie Highway West
 Manchester, TN 37355

01 WELL

LATITUDE LONGITUDE RIVER MILE
 0352658 0860208

000880 STACEY ANN'S MHP [REDACTED] 1 G 108 42
 [REDACTED] [REDACTED]

01 WELL 1

LATITUDE LONGITUDE RIVER MILE
 0352604 0860551

02 WELL 1

0352606 0860556

000715 TULLAHOMA BOARD OF UTILITIES (615) 455-4515 P 21367 7170
 P.O. BOX 788
 Tullahoma, TN 37388

RIVER MILE

01 DUCK RIVER UC (PWSID # 0000821)

AVIDSON COUNTY	SRCE	SERVICE
PWSID NAME TELEPHONE CODE POPUL. CONN.		

000297 CUMBERLAND UTILITY DISTRICT (615) 883-8505 S 23220 9000		
6020 PANAMA DR		
HERMITAGE, TN 37076		

01 CUMBERLAND R.

LATITUDE LONGITUDE RIVER MILE
 0361228 0863830 207.6

000286 HARPEETH VALLEY U D (615) 352-7076 S 20885 8095		
P.O. BOX 319		
Nashville, TN 37221		

01 CUMBERLAND RIVE

LATITUDE LONGITUDE RIVER MILE
 0360810 0865515 172.6

000528 LAKEWOOD WATER DEPARTMENT (615) 847-3711 P 1935 750		
3401 Hadley Avenue		
Old Hickory, TN 37138		

PIVLR MILE

01 OLD HICKORY U D (PWSID # 0000527)

000424 MADISON SUBURBAN UD (615) 868-3201 S 33700 15000		
P.O. Box 175		
Madison, TN 37116		

01 CUMBERLAND RIVE

LATITUDE LONGITUDE RIVER MILE
 0361427 0864245 200.3

000494 NASHVILLE WATER DEPT (615) 259-6425 S 690000 130526		
1600 Second Avenue, North		
Nashville, TN 37201		

01 CUMBERLAND PL#1

LATITUDE LONGITUDE RIVER MILE
 0360948 0864331 193.8

02 CUMBERLAND PL#2

0361140 0863925 206.3

000527 OLD HICKORY UTILITY DISTRICT (615) 847-2043 S 3422 1450		
1050 Donelson Avenue		
Old Hickory, TN 37138		

00190 DEWHITE UTILITY DISTRICT (615) 836-8101 P 3819 1170
P.O. BOX 328
Sparta, TN 38583

RIVER MILE

01 SPARTA (PWSID # 0000652)

00526 DENBOR UTILITY DISTRICT (615) 738-5610 P 4926 1734
P.O. BOX 36
Sparta, TN 38583

RIVER MILE

01 SPARTA, CITY OF (PWSID # 0000652)

00831 PRIDES SWITCH WATER COMPANY (615) 935-2618 P 186 87
P.O. BOX 144
Sparta, TN 38583

RIVER MILE

01 BCM DE CROFT UD (PWSID # 0000653)

000569 QUEBECK WALLING U D #1 (615) 836-2147 P 2363 850
Sparta Shopping Center Annex
Sparta, TN 38583

RIVER MILE

01 SPARTA WATER (PWSID # 0000652)

000852 QUEBECK WALLING U D #2 (615) 836-2147 P 487 175
Sparta Shopping Center Annex
Sparta, TN 38583

RIVER MILE

01 DEWHITE U.D. (PWSID # 0000190)

00852 SPARTA WATER SYSTEM (615) 738-2281 S 8259 2971
P.O. BOX 468
Sparta, TN 38583

LATITUDE LONGITUDE RIVER MILE
0355555 0852745 016.1

01 CALFKILLER RIVE

WILLIAMSON COUNTY

PWSID	NAME	TELEPHONE	SRCE CODE	POPUL.	SERVICE CONN.
0000069	BRENTWOOD WATER DEPT. P.O. BOX 788 Brentwood, TN 37024	(615) 371-0080	P	14593	4719

RIVER MILE

01 HARFETH VALLEY (PWSID # 0000286)

02 METRO WATER (PWSID # 0000494)

000036 FAIRVIEW WATER SYSTEM (615) 799-2482 S 4326 1502
P.O. Box 69 City Hall
Fairview, TN 37062

LATITUDE LONGITUDE RIVER MILE
0355935 0870805

01 HORN TAVERN SPR

02 HARFETH VALLEY (PWSID # 0000286)

03 MIDDLE SCH WELL 0355400 0870905

000036 FRANKLIN WATER DEPT (615) 794 4572 S 25410 3217
838 Lewisburg Pike
Franklin, TN 37064

LATITUDE LONGITUDE RIVER MILE
0355433 0865115 (49.2)

01 HARFETH RIVER

03 HARFETH VALLEY (PWSID # 0000286)

Reference 6

4/27/93

Federally Listed Species by State

TENNESSEE

(E=Endangered; T=Threatened; CH=Critical Habitat determined)

Mammals

General Distribution

Bat, gray (<u>Myotis grisescens</u>) - E	Entire State
Bat, Indiana (<u>Myotis sodalis</u>) - E, CH	Central, East
Cougar, eastern (<u>Felis concolor couguar</u>) - E	North, East
Panther, Florida (<u>Felis concolor coryi</u>) - E	Southwest
Squirrel, Carolina northern flying (<u>Glaucomys sabrinus coloratus</u>) - E	Eastern mountains (Carter and Sevier Counties)

Birds

Eagle, bald (<u>Haliaeetus leucocephalus</u>) - E	Entire State
Falcon, American peregrine (<u>Falco peregrinus anatum</u>) - E	East, Central, Extreme Northwest
Falcon, Arctic peregrine (<u>Falco peregrinus tundrius</u>) - T	Entire State (mostly West)
Tern, least (<u>Sterna antillarum</u>) interior population - E	Mississippi River West
Warbler, Bachman's (<u>Vermivora bachmanii</u>) - E	West
Warbler, Kirtland's (<u>Dendroica kirtlandii</u>) - E	Extreme Northeast
Woodpecker, ivory-billed (<u>Campephilus principalis</u>) - E	Extreme West
Woodpecker, red-cockaded (<u>Picoides [=Dendrocopos] borealis</u>) - E	East

Fishes

Chub, slender (<u>Hybopsis cahni</u>) - T,CH	Hancock, Claiborne, Grainger Counties
Chub, spotfin (<u>Hybopsis monacha</u>) - T,CH	Hawkins, Sullivan, Morgan, Fentress, and Cumberland Counties
Dace, blackside (<u>Phoxinus cumberlandensis</u>) - T	Upper Cumberland River System (Scott, Campbell, and Claiborne Counties)
Darter, amber (<u>Percina antesella</u>) - E,CH	Conasauga R., Polk County

TENNESSEE (Cont'd)

State Lists 4/27/93

General Distribution

Mussel, Appalachian monkeyface pearly
(Quadrula sparsa) - E

Powell River

Mussel, birdwing pearly
(Conradilla caelata) - E

Powell, Clinch, Elk and
Duck Rivers

Mussel, Cumberland bean pearly
(Villosa trabilis) - E

Big S. Fork of
Cumberland River

Mussel, Cumberland monkeyface pearly
(Quadrula intermedia) - E

Elk, Powell and Duck
Rivers

Mussel, Cumberland pigtoe
(Pleurobema gibberum) - E

Caney Fork River System

Mussel, dromedary pearly
(Dromus dromas) - E

Powell, Clinch,
Cumberland and Tennessee
Rivers

Mussel, fine-rayed pigtoe pearly
(Fusconaia cuneolus) - E

Powell, Clinch, Elk,
Sequatchie, N. Fork Holston
and Little Rivers

Mussel, green-blossom pearly
(Epioblasma [= Dysnomia]
torulosa gubernaculum) - E

Clinch River

Mussel, little-wing pearly
(Pegias fabula) - E

Cave Creek

Mussel, orange-footed pearly
(Plethobasus cooperianus) - E

Tennessee and
Cumberland Rivers

Mussel, pale lilliput pearly
(Toxolasma [= Carunculina] cylindrella) - E

Historic; no recent TN
records

Mussel, pink mucket pearly
(Lampsilis orbiculata) - E

Tennessee, Clinch and
Cumberland Rivers

Mussel, rough pigtoe pearly
(Pleurobema plenum) - E

Clinch, Cumberland and
Tennessee Rivers

Mussel, shiny pigtoe pearly
(Fusconaia edgariana) - E

Powell, Clinch and Elk
Rivers

Mussel, tan riffle shell
(Epioblasma [= Dysnomia] walkeri) - E

Historic; no recent TN
records

TENNESSEE (Cont'd)

State Lists 4/27/93

General Distribution

Isotria medeoloides (small whorled
pogonia) - E

Hamilton County

Phyllitis scolopendrium var. Americana
(American Hart's Tongue Fern) - T

Marion County

Pityopsis ruthii (Ruth's golden aster) - E

Polk County

Scutellaria montana (large-flowered
skullcap) - E

Hamilton and Marion
Counties

Solidago spithamaea (Blue Ridge
goldenrod) - T

Carter County

Spiraea virginiana - T
(Virginia spiraea)

Nolichucky River, Unicoi County; Abrams Creek and Little River, Blount County; Cane Creek, Van Buren County; White Oak Creek, Scott County; Clifty Creek in Roane County; Daddy's Creek in Cumberland County; and Clear Fork in Morgan and Scott Counties

Xyris Tennesseensis (Tennessee yellow-eyed
grass) - E

Lewis County

Reference 7

**HALLIBURTON NUS
ENVIRONMENTAL CORPORATION**

TELECON NOTE

CONTROL NO. MK63AP

DATE: 6/13/94

TIME: 1130

DISTRIBUTION:

The Kennon Site - Brentwood, Williamson County, Tennessee

BETWEEN: James Brian

OF: Tennessee Wildlife Resources
Agency

PHONE: (615) 896-3046

AND: Teresa Sawyer, Halliburton NUS Corporation

DISCUSSION:

I spoke with Mr. Brian concerning the Little Harpeth River. He said that it is not commercially fished, but that it was definitely used for recreational fishing. He also stated that Clovercroft Lake is used for recreation and fishing.

Reference 8

Kennon Site

LATITUDE 35:57:22 LONGITUDE 86:46:27 1983 POPULATION

	0.00-.400	.400-.810	.810-1.60	1.60-3.20	3.20-4.80	4.80-6.40	SECTOR TOTALS
KM							
S 1	0	0	0	0	0	0	0
S 2	0	0	0	434	0	4147	4581
S 3	0	0	0	0	0	0	0
S 4	0	0	0	0	0	0	0
S 5	0	0	0	0	0	349	349
S 6	0	0	0	0	0	0	0
S 7	0	0	0	0	0	0	0
S 8	0	0	0	0	0	2673	2673
RING	0	0	0	434	0	7169	7603
TOTALS							

press RETURN to continue

MENU: Geodata Handling Data List procedures

Enter commands in parentheses

(REENTER)

or a command: HELP, HELP option, BACK, CLEAR, EXIT, TUTOR

GEMS> exit

Type YES to confirm the EXIT command; type NO to restart GEMS

GEMS> yes

\$ logout

HTW logged out at 7-JUN-1994 15:25:00.93

Itemized resource charges, for this session, follow:

NODE: VAXTM1

ACCT: 9040

PROJ: GEMS0001

USER: HTW

UIC: [000710,000012]

BAUD:

START TIME: 7-JUN-1994 15:23:30.51

FINISH TIME: 7-JUN-1994 15:25:00.93

BILLING PERIOD: 940601

WEEKDAY: TUESDAY

TERMINAL PORT: VTA9018

DESCRIPTION OF CHARGE	QUANTITY	EXPENDITURE
ALL CHARGE LEVELS		
300 baud (Seconds)	90	0.0000
CPU TIME (Seconds)	3	0.6983
TOTAL FOR THIS SESSION		\$ 0.6983

** Note: This total reflects the charges for this process only, subprocesses created during this session are accounted for separately

CLR PAD

R)2

NO CARRIER

Reference 9

HALLIBURTON NUS ENVIRONMENTAL CORPORATION

PROJECT NOTES

TO: FILE: THE KENNON SITE

DATE: JUNE 13, 1994

FROM: TERESA SAWYER, SITE PROJECT MANAGER

COPIES:

SUBJECT: POPULATION

I called the Chamber of Commerce, and the population of Brentwood is 19,317 persons.

KENNON SITE GENESCO

TND 981473515

SITE SUMMARY

The Kennon Site (Genesco) is located near the junction of Split Log Road and Wilson Pike east of Brentwood in Williamson County, Tennessee.

The site is on the Kennon farm in an area of old phosphate pits where in 1978 General Adhesives, a subsidiary of Genesco, dumped approximately 300 drums of organic solvents, organic fillers, and adhesives. The pits were then filled. The state was informed of this unregistered landfill by Genesco in 1985. Chemicals detected on site at appreciable levels in 1986 sampling were toluene; tetrachloroethylene; 1,1,1 trichloroethylene; 2 Butanone (Methyl ethyl ketone); xylene; hexane; 1,1,1 trichloroethene; acetone; 1,2 dichloroethane; and benzene.

Several private wells are still in use within three miles of the site and ground water contamination was discovered in early 1986. Residents with wells within a one mile radius (a population of approximately 118) were provided with bottled water at their discretion by Genesco until water lines could be run from Brentwood. Brentwood water is supplied by Metro Nashville and Harpeth Valley Utilities. The total population within three miles on groundwater prior to remedial action of running water lines was 410.

RCRA SUMMARY
KENNON SITE (GENESCO)
TND 981473515

The Kennon Site (Genesco) is a farm with phosphate pits that was used to dump approximately 800 drums of organic solvents, fillers, and adhesives in 1978. The site was never registered as a landfill and did not have a MSD permit.

TAM/ib

Facility name: Kennon Site (Genesco) TND 981473515

Location: Brentwood, Williamson County, Tennessee

EPA Region: IV

Person(s) in charge of the facility: Emmett Kennon

Ralph Mosely, Genesco

Name of Reviewer: Thomas A. Moss

Date: 4/30/87

General description of the facility:

(For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

The Kennon Site (Genesco) is a drum disposal site used by General Adhesives,

a subsidiary of Genesco, in 1978 to dispose of approximately 800 drums of

organic solvents, fillers, water based adhesives by dumping them in phosphate

pits and covering the pits at the site. The aquifer of concern is a car-

bonate, fracture-based, solutionally enlarged aquifer. A population of

approx 410 persons were on private wells within 3 miles of the site prior to

the remedial action of water lines being run.

Scores: $S_M = 25.2$ ($S_{gw} = 43.2$ $S_{sw} = 5.3$ $S_a = NR$)

$S_{FE} =$ Not Rated

$S_{DC} =$ Not Rated

FIGURE 1
HRS COVER SHEET

Ground Water Route Work Sheet							
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Rel. (Section)		
1 Observed Release	0 <u>45</u>	1	45	45	3.1		
If observed release is given a score of 45, proceed to line 14 . If observed release is given a score of 0, proceed to line 2 .							
2 Route Characteristics					3.2		
Depth to Aquifer of Concern	0 1 2 3	2		6			
Net Precipitation	0 1 2 3	1		3			
Permeability of the Unsaturated Zone	0 1 2 3	1		3			
Physical State	0 1 2 3	1		3			
Total Route Characteristics Score				15			
3 Containment	0 1 2 3	1		3	3.3		
4 Waste Characteristics					3.4		
Toxicity/Persistence	0 3 6 9 12 <u>15</u> 18	1	15	18			
Hazardous Waste Quantity	0 1 2 3 <u>4</u> 5 6 7 8	1	4	8			
Total Waste Characteristics Score			19	26			
5 Targets					3.5		
Ground Water Use	0 1 2 <u>3</u>	3	9	9			
Distance to Nearest Well/Population Served	0 4 6 8 10 12 16 18 <u>20</u> 24 30 32 35 40	1	20	40			
Total Targets Score			29	49			
If line 1 is 45, multiply 15 x 15 x 3 If line 1 is 0, multiply 2 x 3 x 15 x 3			24,795	57,000			
Divide line 15 by 57,000 and multiply by 100			Spw = 43.2				

FIGURE 2
GROUND WATER ROUTE WORK SHEET

Surface Water Route Work Sheet							
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)		
1 Observed Release	(0) 45	1	0	45	4.1		
If observed release is given a value of 45, proceed to line 4 . If observed release is given a value of 0, proceed to line 2 .							
2 Route Characteristics					4.2		
Facility Slope and Intervening Terrain	0 (1) 2 3	1	1	3			
1-yr. 24-hr. Rainfall	0 1 (2) 3	1	2	3			
Distance to Nearest Surface Water	0 1 (2) 3	2	4	6			
Physical State	0 1 2 (3)	1	3	3			
Total Route Characteristics Score			10	15			
3 Containment	0 1 2 (3)	1	3	3	4.3		
4 Waste Characteristics					4.4		
Toxicity/Persistence	0 3 6 9 12 (15) 18	1	15	18			
Hazardous Waste Quantity	0 1 2 3 (4) 5 6 7 8	1	4	8			
Total Waste Characteristics Score			19	26			
5 Targets					4.5		
Surface Water Use	0 1 (2) 3	3	6	9			
Distance to a Sensitive Environment	(0) 1 2 3	2	0	6			
Population Served/Distance to Water Intake Downstream	(0) 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40			
Total Targets Score			6	55			
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			3,420	64,350			
7 Divide line 6 by 64,350 and multiply by 100			S _{SW} = 5.3				

FIGURE 7
SURFACE WATER ROUTE WORK SHEET

NOT RATED

Air Route Work Sheet				Kernon Site IND 981473515	
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)
<input type="checkbox"/> Observed Release	0 45	1		45	5.1
Date and Location:					
Sampling Protocol:					
If line <input type="checkbox"/> 1 is 0, the $S_a = 0$. Enter on line <input type="checkbox"/> 5. If line <input type="checkbox"/> 1 is 45, then proceed to line <input type="checkbox"/> 2.					
<input type="checkbox"/> Waste Characteristics					5.2
Reactivity and Incompatibility	0 1 2 3	1		3	
Toxicity	0 1 2 3	3		9	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		3	
Total Waste Characteristics Score				20	
<input type="checkbox"/> Targets					5.3
Population Within 4-Mile Radius	{ 0 9 12 15 18 21 24 27 30	1		30	
Distance to Sensitive Environment	0 1 2 3	2		6	
Land Use	0 1 2 3	1		3	
Total Targets Score				39	
<input type="checkbox"/> 4 Multiply <input type="checkbox"/> 1 x <input type="checkbox"/> 2 x <input type="checkbox"/> 3					35,100
<input type="checkbox"/> 5 Divide line <input type="checkbox"/> 4 by 35,100 and multiply by 100				$S_a =$	

FIGURE 9
AIR ROUTE WORK SHEET

	S	S ²
Groundwater Route Score (S _{gw})	43.2	1866.24
Surface Water Route Score (S _{sw})	5.3	28.09
Air Route Score (S _a)	Not Rated	Not Rated
$S_{gw}^2 + S_{sw}^2 + S_a^2$		1894.33
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		43.5
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M =$		25.2

FIGURE 10
WORKSHEET FOR COMPUTING S_M

NOT RATED

Fire and Explosion Work Sheet		Kennon Site TND 981473515			
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Per. (Section)
1 Containment	1 3	1		3	7.1
2 Waste Characteristics					7.2
Direct Evidence	0 3	1		3	
Ignitability	0 1 2 3	1		3	
Reactivity	0 1 2 3	1		3	
Incompatibility	0 1 2 3	1		3	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8	
Total Waste Characteristics Score				20	
3 Targets					7.3
Distance to Nearest Population	0 1 2 3 4 5	1		5	
Distance to Nearest Building	0 1 2 3	1		3	
Distance to Sensitive Environment	0 1 2 3	1		3	
Land Use	0 1 2 3	1		3	
Population Within 2-Mile Radius	0 1 2 3 4 5	1		5	
Buildings Within 2-Mile Radius	0 1 2 3 4 5	1		5	
Total Targets Score				24	
4 Multiply 1 x 2 x 3				1,440	
5 Divide line 4 by 1,440 and multiply by 100			SFE =		

FIGURE 11
FIRE AND EXPLOSION WORK SHEET

NOT RATED

Direct Contact Work Sheet		Kennon Site TND 981473515			
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)
<input type="checkbox"/> 1 Observed Incident	0 45	1		45	8.1
If line <input type="checkbox"/> 1 is 45, proceed to line <input type="checkbox"/> 3 If line <input type="checkbox"/> 1 is 0, proceed to line <input type="checkbox"/> 2					
<input type="checkbox"/> 2 Accessibility	0 1 2 3	1		3	8.2
<input type="checkbox"/> 3 Containment	0 15	1		15	8.3
<input type="checkbox"/> 4 Waste Characteristics Toxicity	0 1 2 3	5		15	8.4
<input type="checkbox"/> 5 Targets					8.5
Population Within a 1-Mile Radius	0 1 2 3 4 5	4		20	
Distance to a Critical Habitat	0 1 2 3	4		12	
Total Targets Score				32	
<input type="checkbox"/> 6 If line <input type="checkbox"/> 1 is 45, multiply <input type="checkbox"/> 1 x <input type="checkbox"/> 4 x <input type="checkbox"/> 5 If line <input type="checkbox"/> 1 is 0, multiply <input type="checkbox"/> 2 x <input type="checkbox"/> 3 x <input type="checkbox"/> 4 x <input type="checkbox"/> 5				21,600	
<input type="checkbox"/> 7 Divide line <input type="checkbox"/> 6 by 21,600 and multiply by 100			SDC =		

FIGURE 12
DIRECT CONTACT WORK SHEET

**DOCUMENTATION RECORDS
FOR
HAZARD RANKING SYSTEM**

FACILITY NAME: Kennon Site (Genesco) TND 981473515

FACILITY DESCRIPTION: Phosphate pits on farm filled with dumped liquids and drums and covered.

LOCATION: Brentwood, Tennessee

DATE SCORED: April 28, 1987

PERSON SCORING: Thomas A. Moss

PRIMARY SOURCE(S) OF INFORMATION (e.g., EPA region, state, FIT, etc.):

State Superfund Files

FACTORS NOT SCORED DUE TO INSUFFICIENT INFORMATION:

Air, Fire and Explosion, Direct Contact

COMMENTS OR QUALIFICATIONS:

Water lines have been run to houses that were on private wells within a one-mile radius of the site.

GROUND WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected (5 maximum):

Trans-1,2-dichloroethene; toluene; 1,1,-dichloroethane; and 1,1,1-trichloroethane detected in Hackett Spring and on site monitoring wells by State Superfund sampling (Ref. 1, 2) and are known to be toxic (Ref. 3, 4). Background well (Johnson) showed no contamination (Ref. 1, 2).

Rationale for attributing the contaminants to the facility:

Contamination found in monitoring wells on site, no contamination found in background well (Ref. 1).

2 ROUTE CHARACTERISTICS

Depth to Aquifer of Concern

Name/description of aquifer(s) of concern:

The aquifer of concern would be the Ordovician limestone formations (Ref. 5, 6) of the Bigby-Cannon Limestone (70-130 ft. thick), Hermitage Formation (50-150 ft. thick), and Carters Limestone (70 ft. thick). The majority of private wells in the area have depths of 150-350 ft. (Ref. 7) and would be completed in the Hermitage Formation or Carters Limestone (Ref. 5, 6) (50-100 ft. thick). See attachment 2A for further discussion of aquifer of concern.

Depth(s) from the ground surface to the highest seasonal level of the saturated zone (water table(s)) of the aquifer of concern:

N/A

Depth from the ground surface to the lowest point of waste disposal/storage:

N/A

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

N/A

Mean annual lake or seasonal evaporation (list months for seasonal):

N/A

Attachment 2A
Aquifer of Concern

There are no confining layers present within the Bigby-Cannon Limestone, Hermitage Formation, and Carters Limestone. The Bigby-Cannon Limestone contains facies ranging from a microcrystalline limestone facies to medium- and coarse-grained limestone facies (Ref. 5). The Bigby-Cannon has sinkhole development and deep weathering along vertical fractures (Ref. 6). Numerous springs are present in the area (Ref. 2).

The underlying Hermitage Formation consists of a coquina (shell hash) facies with shale partings, a laminated argillaceous limestone facies, and a limestone with shale partings (Ref. 5). The Carters Limestone underlying the Hermitage consists of an upper and lower limestone member of cryptocrystalline to fine-grained limestone with shale partings separated by a thin bentonite clay (Ref. 5). The Carters weathers to a brown plastic clay with some sinkholes (Ref. 6).

Net precipitation (subtract the above figures):

N/A

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

N/A

Permeability associated with soil type:

N/A

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

N/A

* * *

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

N/A

Method with highest score:

N/A

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

1,1-dichloroethene and 1,1-dichloroethane detected in pits A and B and monitoring well #8 on site and not detected in background well (Johnson) by State Superfund sampling (Ref. 1, 2, 8).

Compound with highest score:

1,1-dichloroethene has a toxicity rating of 3 (Ref. 4) and a persistence rating of 2 (Ref. 9).

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

800 drums

Basis of estimating and/or computing waste quantity:

Genesco admission of the dumping of approximately 800 55-gallon barrels of waste material containing organic solvents, organic fillers, and water based adhesives at the site by their subsidiary General Adhesives (Ref. 10).

5 TARGETS

Ground Water Use

Use(s) and aquifer(s) of concern within a 3-mile radius of the facility:

Drinking water with no municipal water presently available (Ref. 11, 12). Genesco paid for lines to be run from Brentwood for the area within a one-mile radius of the site that had no municipal water source.

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

Hackett Spring is used as a drinking water supply by the Hacketts (Ref. 13). Hackett house is on east side of Wilson Pike approximately 1000 ft. north of Split Log Road (Ref. 2, 14, 15).

Distance to above well or building:

Hackett Spring is contaminated (Ref. 1), distance would be considered as zero. Actual distance from the pits is approximately 1500 ft. (Ref. 14, 15).

Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

108 houses not on public water for a population of 410 (Ref. 16).

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

None identified (Ref. 17)

Total population served by ground water within a 3-mile radius:

410

SURFACE WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

None identified

Rationale for attributing the contaminants to the facility:

N/A

* * *

2 ROUTE CHARACTERISTICS

Facility Slope and Intervening Terrain

Average slope of facility in percent:

60 ft. in 1800 ft. for 3.3% slope (Ref. 14, 15).

Name/description of nearest downslope surface water:

Unnamed creek entering the Little Harpeth River north of the junction of Wilson Pike and Split Log Road (Ref. 14, 15).

Average slope of terrain between facility and above-cited surface water body in percent:

80 ft. in 1800 ft. for 4% slope (Ref. 14, 15).

Is the facility located either totally or partially in surface water?

No (Ref. 14, 15)

Is the facility completely surrounded by areas of higher elevation?

No (Ref. 14, 15)

1-Year 24-Hour Rainfall in Inches

3 inches (Ref. 9)

Distance to Nearest Downslope Surface Water

0.4 miles from the site to where surface drainage enters unnamed tributary of Little Harpeth River (Ref. 14, 15).

Physical State of Waste

Liquids dumped at site by admission of company (Ref. 10).

* * *

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

Landfill not adequately covered and no diversion system present--drums and liquid emptied into pits and covered with no documentation indicating adequate cap (Ref. 10).

Method with highest score:

Landfill not covered, no diversion system present.

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

1,1-dichloroethene and 1,1-dichloroethane detected in pits A and B and monitoring #8 on site by State Superfund sampling (Ref. 1, 2).

Compound with highest score:

1,1-dichloroethene has a toxicity rating of 3 (Ref. 4) and a persistence rating of 2 (Ref. 9).

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

800 drums

Basis of estimating and/or computing waste quantity:

Genesco admission of the dumping of approximately 800 55-gallon barrels of waste material containing organic solvents, organic fillers, and water-based adhesives at the site by their subsidiary General Adhesives (Ref. 10).

5 TARGETS

Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:

Recreational use of the Little Harpeth River between Split Log Road and Concord Road (Ref. 17).

Is there tidal influence?

No (Ref. 14, 15)

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

None identified (Ref. 14, 15)

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

None identified (Ref. 14, 15)

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

None identified (Ref. 18)

Population Served by Surface Water

Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:

None identified (Ref. 19)

Computation of land area irrigated by above-cited intake(s) and conversion to population (1.5 people per acre):

None identified (Ref. 17)

Total population served:

N/A

Name/description of nearest of above water bodies:

N/A

Distance to above-cited intakes, measured in stream miles:

N/A

AIR ROUTE
NOT RATED

1 OBSERVED RELEASE

Contaminants detected:

Date and Location of detection of contaminants:

Methods used to detect the contaminants:

Rationale for attributing the contaminants to the site:

* * *

2 WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

Most incompatible pair of compounds:

Toxicity

Most toxic compound:

Hazardous Waste Quantity

Total quantity of hazardous waste:

Basis of estimating and/or computing waste quantity:

* * *

3 TARGETS

Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

0 to 4 mi 0 to 1 mi 0 to 1/2 mi 0 to 1/4 mi

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

Distance to critical habitat of an endangered species, if 1 mile or less:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

**FIRE AND EXPLOSION
NOT RATED**

1 CONTAINMENT

Hazardous substances present:

Type of containment, if applicable:

* * *

2 WASTE CHARACTERISTICS

Direct Evidence

Type of instrument and measurements:

Ignitability

Compound used:

Reactivity

Most reactive compound:

Incompatibility

Most incompatible pair of compounds:

* * *

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility:

Basis of estimating and/or computing waste quantity:

* * *

3 TARGETS

Distance to Nearest Population

Distance to Nearest Building

Distance to Sensitive Environment

Distance to wetlands:

Distance to critical habitat:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

Population Within 2-Mile Radius

Buildings Within 2-Mile Radius

DIRECT CONTACT
NOT RATED

1 OBSERVED INCIDENT

Date, location, and pertinent details of incident:

* * *

2 ACCESSIBILITY

Describe type of barrier(s):

* * *

3 CONTAINMENT

Type of containment, if applicable:

* * *

4 WASTE CHARACTERISTICS

Toxicity

Compounds evaluated:

Compound with highest score:

* * *

5 TARGETS

Population within one-mile radius

Distance to critical habitat (of endangered species)

TAM/ah
Disc--Higgs/GrndW4
SF-12

REFERENCES
KENNON SITE (GENESCO)
TND 981473515

1. Kennon Site Sampling and Event Chronology; State Superfund Sampling Results for Kennon Site (Genesco) with Sample Points for Wells/Springs. See Geraghty and Miller, 1986 for Sampling Locations.
2. Geraghty and Miller (1986): Plan for Investigation of the Kennon Site, Brentwood, Tennessee; prepared for Genesco, Inc., Dec. 1986.
3. G. Hawley, revised (1981): Condensed Chemical Dictionary, Tenth Edition; Van Nostrand Reinhold.
4. N.I. Sax (1984): Dangerous Properties of Industrial Materials, 6th Edition; Van Nostrand Reinhold.
5. (1963) Franklin Quadrangle Geologic Map - GM 63 NE.
6. Beaver Engineering (1977): Bedrock Geology of the Nashville and Middle Tennessee Area.
7. 2/19/87 Letter from Roger W. Lee, U.S. Geological Survey to Todd Hughes, TN Dept. of Health and Environment (Superfund) - Data on Observation Wells.

3. 3/19/86 and 3/24/86 Analytical Reports from Wayne McCoy, Edge to Ronnie Bowers, DSF; Re: Kennon Property Analytical Results. - Background Soil Sample (See Pond Sediment and Hackett Ditch).
9. (1984) Uncontrolled Hazardous Waste Site Ranking System, A Users Manual (HW-10), U.S. E.P.A.
10. 5/21/85 Letter from Ralph Mosely, Genesco to Tom Tiesler, DSWM; RE: Chemical Waste Site Once Used by a Division of Genesco.
11. 2/19/86 Letter from Frank W. Clifton Jr. Brentwood City Manager to Don Shackleford, TN Div. Superfund; Re: Cost Estimates for Water Lines.
12. 7/28/86 Letter from Ralph Mosely, Genesco to Frank W. Clifton, Jr., Brentwood City Manager; Re: Service Connections.
13. 3/16.87 Conversation of Thomas A. Moss, DSF with Ronnie L. Bowers, DSF; Re: Kennon Site (Genesco) Sample Results, Water Use.
14. (1981) Franklin Quadrangle Topographic Map - 63 NE.
15. (1957) Nolensville Quadrangle Topographic Map - 70NW.
16. 4/24/87 TDH&E Memo from Thomas A. Moss, DSF to Kennon Site (Genesco) File; Re: Ground Water Use Survey/House County for 3 Mile Radius.

17. 3/10/87 Telephone Conversation of Thomas A. Moss, DSF with Robin Bowie, Williamson County Soil Conservation Service; Re: Surface and Groundwater Use for Irrigation in the Area of the Genesco Site.
18. 12/19/85 Letter from Robert M. Thatcher, TWRA to Gordon S. Caruthers, DSWM with attachments: Critical Wildlife Habitat of Tennessee.
19. (1978) Water Quality Management Plan for the Lower Cumberland River Basin, TN Division of Water Quality Control.
20. Commissioners Order: Genesco Inc./Emmett & Rose Kennon. Order No. 863013.

TAM/dje SF #5



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION
01 STATE TN 02 SITE NUMBER D 981473515

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) Kennon (Genesco) Site		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Split Log Road			
03 CITY Brentwood	04 STATE TN	05 ZIP CODE 37027	06 COUNTY Williamson *	07 COUNTY CODE 187	08 CONG. DIST. 6
09 COORDINATES LATITUDE 35 57 25 LONGITUDE 86 45 44		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN			

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 1, 14, 86 MONTH DAY YEAR	02 SITE STATUS <input type="checkbox"/> ACTIVE <input checked="" type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1978 1978 BEGINNING YEAR ENDING YEAR
04 AGENCY PERFORMING INSPECTION (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR <input checked="" type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR <input type="checkbox"/> G. OTHER		

05 CHIEF INSPECTOR Charles Powers	06 TITLE Field Coordinator	07 ORGANIZATION Superfund	08 TELEPHONE NO. (615) 741-6287
09 OTHER INSPECTORS Ronnie Bowers	10 TITLE Environmental Specialist	11 ORGANIZATION Superfund	12 TELEPHONE NO. (615) 741-6287
			()
			()
			()
			()
13 SITE REPRESENTATIVES INTERVIEWED Wayne McCoy	14 TITLE Consultant-Edge	15 ADDRESS 4301 Hillsboro Rd.; Nash.	16 TELEPHONE NO. (615) 383-3588
Ralph Mosely	Genesco	Genesco Park; Nashville	(615) 367-7314
			()
			()
			()
			()

17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION	19 WEATHER CONDITIONS
---	-----------------------	-----------------------

IV. INFORMATION AVAILABLE FROM

01 CONTACT Charles Powers	02 OF Agency Organization TDH&E/Superfund	03 TELEPHONE NO. (615) 741-6287		
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Thomas A. Moss	05 AGENCY TDH&E	06 ORGANIZATION Superfund	07 TELEPHONE NO. (615) 741-6287	08 DATE 5, 12, 87 MONTH DAY YEAR



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 2 - WASTE INFORMATION

I. IDENTIFICATION
01 STATE TN 02 SITE NUMBER D 981473515

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES (Check all that apply): <input type="checkbox"/> A SOLID <input type="checkbox"/> B POWDER, FINES <input type="checkbox"/> C SLUDGE <input type="checkbox"/> D OTHER (Specify) _____ <input type="checkbox"/> E SLURRY <input checked="" type="checkbox"/> F LIQUID <input type="checkbox"/> G GAS	02 WASTE QUANTITY AT SITE (Measures of waste quantities must be independent) TONS _____ CUBIC YARDS _____ NO. OF DRUMS 800	03 WASTE CHARACTERISTICS (Check all that apply): <input checked="" type="checkbox"/> A TOXIC <input type="checkbox"/> B CORROSIVE <input type="checkbox"/> C RADIOACTIVE <input checked="" type="checkbox"/> D PERSISTENT <input type="checkbox"/> E SOLUBLE <input type="checkbox"/> F INFECTIOUS <input type="checkbox"/> G FLAMMABLE <input type="checkbox"/> H IGNITABLE <input type="checkbox"/> I HIGHLY VOLATILE <input type="checkbox"/> J EXPLOSIVE <input type="checkbox"/> K REACTIVE <input type="checkbox"/> L INCOMPATIBLE <input type="checkbox"/> M NOT APPLICABLE
--	--	---

III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE			
OLW	OILY WASTE			
SOL	SOLVENTS	Unknown		Organic solvents.
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS	Unknown		Organic fillers, adhesives.
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
SOL	Toluene	108883	dumped in pits	unknown	
SOL	Tetrachloroethylene	127184	dumped in pits	unknown	
SOL	1,1,1 Trichloroethylene	79016	dumped in pits	unknown	
SOL	2 Butanone (MEK)	78933	dumped in pits	unknown	
SOL	Xylene	1330207	dumped in pits	unknown	
SOL	Hexane	110543	dumped in pits	unknown	
SOL	1,1,1 Trichloroethene	79016	dumped in pits	unknown	
SOL	Acetone	67641	dumped in pits	unknown	
SOL	1,2 Dichloroethane	1300216	dumped in pits	unknown	
SOL	Benzene	71432	dumped in pits	unknown	

V. FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

VI. SOURCES OF INFORMATION (See specific references @ p. State files, sample analysis reports)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE TN 02 SITE NUMBER D 981473515

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A GROUNDWATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: 410
02 ☒ OBSERVED (DATE 1/28/86)
04 NARRATIVE DESCRIPTION
Hackett Spring sampling shows contamination. Population in area not on public water approximately 410. Site is in Ordovician carbonates with no confining layer for aquifer of concern.

01 ☒ B. SURFACE WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: 0
02 ☐ OBSERVED (DATE:)
04 NARRATIVE DESCRIPTION
Seep from site may enter tributary of Little Harpeth River.

01 ☐ C. CONTAMINATION OF AIR
03 POPULATION POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE:)
04 NARRATIVE DESCRIPTION

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS
03 POPULATION POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE:)
04 NARRATIVE DESCRIPTION

01 ☐ E. DIRECT CONTACT
03 POPULATION POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE:)
04 NARRATIVE DESCRIPTION

01 ☒ F. CONTAMINATION OF SOIL
03 AREA POTENTIALLY AFFECTED: Unknown (Acres)
02 ☐ OBSERVED (DATE:)
04 NARRATIVE DESCRIPTION
Seep leaving site. Drums and liquids dumped in pits.

01 ☒ G. DRINKING WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: 410
02 ☒ OBSERVED (DATE 1/28/86)
04 NARRATIVE DESCRIPTION
Hackett Spring sampling shows contamination and is used for drinking water supply. Population within three miles of site not on public water approximately 410.

01 ☐ H. WORKER EXPOSURE/INJURY
03 WORKERS POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE:)
04 NARRATIVE DESCRIPTION

01 ☐ I. POPULATION EXPOSURE/INJURY
03 POPULATION POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE:)
04 NARRATIVE DESCRIPTION



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
TN	D 981473515

II. HAZARDOUS CONDITIONS AND INCIDENTS *(Continued)*

01 ☐ J. DAMAGE TO FLORA 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☐ K. DAMAGE TO FAUNA 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION *(Include names of species)*

01 ☐ L. CONTAMINATION OF FOOD CHAIN 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
(Spills, Runoff, Standing liquids, Leaking drums)
03 POPULATION POTENTIALLY AFFECTED: 410 04 NARRATIVE DESCRIPTION
Drums and liquids dumped in pits. By admission of company.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
Drums and liquids dumped in phosphate pits. Site was not a permitted landfill.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: 410

IV. COMMENTS

Residents within a one mile radius of the site have been run municipal water from Brentwood at Genesco's expense.

V. SOURCES OF INFORMATION *(Check all that apply: 1. Direct observation; 2. State files; 3. Other agency reports)*

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION
01 STATE TN 02 SITE NUMBER D 981473515

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A NPDES				
<input type="checkbox"/> B UIC				
<input type="checkbox"/> C AIR				
<input type="checkbox"/> D RCRA				
<input type="checkbox"/> E RCRA INTERIM STATUS				
<input type="checkbox"/> F SPCC PLAN				
<input type="checkbox"/> G STATE (Specify)				
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input checked="" type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE, DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCINERATION	<input type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input checked="" type="checkbox"/> F. LANDFILL	800	drums	<input type="checkbox"/> F. SOLVENT RECOVERY	06 AREA OF SITE
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER (Specify)	(Acres)
<input type="checkbox"/> I. OTHER (Specify)				

07 COMMENTS

Drums and liquids dumped in phosphate pits on site and covered.

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one):
☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☒ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC

Drums dumped in phosphate pits on site.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE ☐ YES ☒ NO
02 COMMENTS

VI. SOURCES OF INFORMATION (Cite specific references, e.g., State files, satellite analysis, records)

State Superfund Files

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
TN	D 981473515

A $\frac{23}{0.25}$ (mi)

08 SOLE SOURCE AQUIFER
☒ YES ☐ NO

11 DISCHARGE AREA	
<input type="checkbox"/> YES	COMMENTS
<input type="checkbox"/> NO	

NAME:	AFFECTED	DISTANCE TO SITE
Tributary of Little Harpeth River	0	0.1 (mi)
Little Harpeth River	00	(mi)
	00	(mi)

(m)

_____ (m)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site e.g. rural village, densely populated urban area)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

(01 STATE) (02 SITE NUMBER)

TN 0 981473515

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A $10^{-6} - 10^{-8}$ cm/sec ☐ B $10^{-4} - 10^{-6}$ cm/sec ☐ C $10^{-4} - 10^{-2}$ cm/sec ☐ D GREATER THAN 10^{-1} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A IMPERMEABLE (Less than 10^{-6} cm/sec) ☐ B RELATIVELY IMPERMEABLE ($10^{-6} - 10^{-5}$ cm/sec) ☒ C RELATIVELY PERMEABLE ($10^{-2} - 10^{-4}$ cm/sec) ☐ D VERY PERMEABLE (Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK

10 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

(ft)

05 SOIL pH

06 NET PRECIPITATION

48 (in)

07 ONE YEAR 24 HOUR RAINFALL

3 (in)

08 SLOPE
SITE SLOPE

4 %

DIRECTION OF SITE SLOPE

SW

TERRAIN AVERAGE SLOPE

4 %

09 FLOOD POTENTIAL

10

SITE IS IN YEAR FLOODPLAIN

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

OTHER

A. (mi)

B. (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

(mi)

ENDANGERED SPECIES:

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL/STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. (mi)

B. (mi)

C. (mi)

D. (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Site is in rural area on the toe of hill with a number of old farmhouses and newer residences in the vicinity.

VII. SOURCES OF INFORMATION (Cite specific references # C. State info. Sample analysis reports)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D 981473515

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL			
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF _____ (Name of organization or individual)
03 MAPS <input type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS _____

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

Numerous wells have been sampled within the vicinity of the site as well as pits on site.

VI. SOURCES OF INFORMATION (Cite specific references, e.g., State files, sample analysis reports)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

II. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D 981473515

II. CURRENT OWNER(S)				PARENT COMPANY (If applicable)			
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
Emmett Kennon							
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
2934 Sidco Drive							
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
Nashville		TN	37204				
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
III. PREVIOUS OWNER(S) (List most recent first)				IV. REALTY OWNER(S) (If applicable, list most recent first)			
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
V. SOURCES OF INFORMATION (Cite specific references, e.g., State files, sample analysis reports.)							
State Superfund Files							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D 981473515

II. CURRENT OPERATOR (Provide if different from owner)				OPERATOR'S PARENT COMPANY (If applicable)			
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					
III. PREVIOUS OPERATOR(S) (List most recent first. Provide only if different from owner)				PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)			
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
IV. SOURCES OF INFORMATION (Cite specific references e.g., state regs., sample analysis reports)							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
TN D 981473515

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
General Adhesives					
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
6100 Centennial Blvd.					
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
Nashville	TN	37202			
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
Genesco					
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
Genesco Park					
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
Nashville	TN	37202			

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., State files, sample analysis reports.)

State Superfund Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D 981473515

II. PAST RESPONSE ACTIVITIES

01 <input type="checkbox"/> A. WATER SUPPLY CLOSED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> B. TEMPORARY WATER SUPPLY PROVIDED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> C. PERMANENT WATER SUPPLY PROVIDED 04 DESCRIPTION Brentwood water lines run to residents within one mile of site. Paid for by Genesco.	02 DATE <u>11/86</u>	03 AGENCY <u>Superfund</u>
01 <input type="checkbox"/> D. SPILLED MATERIAL REMOVED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> E. CONTAMINATED SOIL REMOVED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> F. WASTE REPACKAGED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> G. WASTE DISPOSED ELSEWHERE 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> H. ON SITE BURIAL 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> I. IN SITU CHEMICAL TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> J. IN SITU BIOLOGICAL TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> K. IN SITU PHYSICAL TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> L. ENCAPSULATION 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> M. EMERGENCY WASTE TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> N. CUTOFF WALLS 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> O. EMERGENCY DIKING/SURFACE WATER DIVERSION 04 DESCRIPTION Genesco had silt fence constructed to limit off site contamination.	02 DATE <u>1/86</u>	03 AGENCY <u>Superfund</u>
01 <input type="checkbox"/> P. CUTOFF TRENCHES/SUMP 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Q. SUBSURFACE CUTOFF WALL 04 DESCRIPTION	02 DATE _____	03 AGENCY _____



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
TN D 981473515

II. PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ S. CAPPING/COVERING
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ T. BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ U. GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ V. BOTTOM SEALED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ W. GAS CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ X. FIRE CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ Y. LEACHATE TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ Z. AREA EVACUATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ 1. ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ 2. POPULATION RELOCATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ 3. OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

III. SOURCES OF INFORMATION (Cite specific references, e.g., State files, sample analysis reports)

State Superfund Files; Geraghty and Miller 1986 Report



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
TN	D 981473515

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☐ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

III. SOURCES OF INFORMATION (Give specific references, e.g., state files, sample analysis reports)

KENNON SITE

Site No. TND 981473575

Reference No. 1

94-508

KENNON SITE (GENESCO)

<u>Date</u>	<u>EVENT</u>
1/15/86	Monitoring well installation begins.
1/22/86	Areas of suspected pits excavated. Samples of water, waste, and soil obtained.
1/24/86	Further excavation of suspected pits to determine extent of dumping. Monitoring well installation continues. Local person informs state personnel of nearby wells and springs being used for drinking water.
1/28/86	Sampling of offsite Hacket Spring and Fletcher Well. Seep below site is also sampled. Full priority pollutants analysis is requested.
1/29/86	Resampled Fletcher Well (previously sampled 1/28/86) due to concern of owner over taking sample from his holding tank.
2/7/86	Resample Hacket Spring after heavy rain.
2/11/86	Sample Hacket Spring for verification of analysis by State Laboratory. Sample Myatt well also.
2/12/86	Sample offsite drinking water sources - Steve Smith Spring, Pewitt Well, Fischer Well, Johnson Well, Stubblefield Spring.
2/13/86	Sample offsite drinking water sources - Glass Well, Levine Well, Sharp Spring, Reece Smith Spring.
2/14/86	Sample offsite drinking water sources - Foster Well, Harpeth River at Moores Lane Bridge.
2/17/86	Sample offsite drinking water sources - Hacket Spring at Indian Tap, Allen Well, Primm Spring, Sullivan Well, Legieza Well.
2/18/86	Meeting with Genesco Consultants to discuss sampling plans for Shallow Monitoring Wells onsite. Determined areas of soil borings and offsite shallow monitoring wells. Charcoal filter was installed at Hacket's home by Genesco.
2/21/86	Sample Hacket water supply at Tap after installation of the charcoal filter. Split one sample of Monitoring well #8 onsite with Genesco Consultant. Sample spring below Edgar Johnson's home.
2/24/86	Resample Legiaza well to verify results with State Laboratory.

<u>Date</u>	<u>Event</u>
2/25/86	Sample offsite drinking water sources - Denny Well, Waggoner Well, Lowe Well, Hackett Creek (above spring), Hackett Creek (below Spring), Little Harpeth (below Hackett Creek), Dickie Well, Beyer Well, Clark Well, Dalton Well. Sampled offsite drinking water sources - Scott Well, Myatt Well, Mallory Well, Howe Well, Carson Spring.
2/26/86	All individuals whose Analysis had been returned were called and informed of these results. Sampled offsite drinking water sources - Turner Well, Clark Well, Burris Well.
2/27/86	Sample offsite drinking water sources - Atkinson Well, Denny Well (resampled), Shaw Well.
2/28/86	Drilling of shallow monitoring wells continue. Genesco consultants are running an Electro Magnetic survey of the site to determine areas of dumping.
3/4/86	Genesco Consultants are running a ground penetrating radar survey. Drill crew is still working. Delivered sample results to residences.
3/5/86	Sample Holt Well.
3/6/86	Talked to several citizens about there wells. (Outside 3 mile radius).
3/7/86	Sample offsite drinking water sources - Mallory Well, Myatt Well, Pewitt Well, Anderson Well.
3/11/86	Sample offsite drinking water sources - Dennison Well, Harmon Well.

RB/lag Customs House #8

KENNON SITE/GENESCO SAMPLING

FAMILY NAME	SPRING/WELL	SAMPLE DATE	RESULTS	REPORT ON FILE
Hackett	Spring	1-28-86	Detected	Yes
		2-7-86	Detected	Yes
		2-11-86	Detected	Yes
		2-17-86	Detected	Yes
		2-21-86	No results yet	
Fletcher	Well	1-29-86	Non-detected	Yes
Myatt	Well	2-11-86	Non-detected	Yes
Smith (Steve)	Spring	2-12-86	Non-detected	Yes
Pewitt	Well	2-12-86	Non-detected	Yes
Fisher	Well	2-16-86	Non-detected	Yes
Johnson	Well	2-16-86	Non-detected	Yes
Stubblefield (Younger & Stubblefield)	Spring	2-12-86	Non-detected	Yes
Glass	Well	2-13-86	Non-detected	Yes
Foster	Well	2-14-86	Non-detected	Yes
Levine	Well	2-13-86	Non-detected	Yes
Sharp/Farrar	Spring	2-13-86	Non-detected	Yes
Smith (Reece)	Spring	2-13-86	Non-detected	Yes
Allen	Well	2-17-86	Non-detected	Yes
Primm	Spring	2-17-86	Non-detected	Yes
Sullivan	Well	2-17-86	Non-detected	Yes
Legieza	Well	2-17-86	Detected	Yes
Little Harpeth	River	2-14-86	Non-detected	Yes

CHRONOLOGY - KENNON (GENESCO SITE)

- May 21, 1985 By a letter dated 5/21/85 signed by Ralph Mosley, Genesco Inc., Genesco Park, Nashville, Tennessee 37202 notified the Division of Solid Waste Management of a chemical waste site once used by a division of Genesco, Inc. (General Adhesives). The site is on a farm owned by Emmett N. Kennon. Genesco, Inc. solicited the assistance and approval of TDHE with respects to certain actions. Genesco indicated that some of the waste was buried in barrels (50 - 80 barrels) and the remainder (44,000 gallons) was poured into a phosphate pit or pits. Genesco, Inc. stated that they believed the waste contained water based adhesives and may have contained acetone, ethyl acetate, hexane, methylene chloride, methylethyl ketone, rubber solvent, toluene, 111-trichlorolthane, trichloroethylene, and organic fillers. Genesco, Inc. expressed the intent to excavate, exhume, analyze and dispose of contaminated materials.
- May 31, 1985 Don Shackelford, Head of Superfund Section, Barry Atnip, Field Coordinator, Superfund, Ralph Mosley, Genesco, and Wayne McCoy, Resource Consultant met to discuss the site. Genesco indicated that they were not sure if they really had a problem or if there was a problem they believed that it possibly was not very extensive. They agreed to submit an investigation plan by August 15, 1985.
- July 2, 1985 Barry Atnip, Coordinator Superfund, Ralph Mosley, Genesco, Ed Wilson and Mark Levy of Geologic Associates, Edgar Johnson (Kennon Foreman) and Emmett Kennon made a vist to the site. This was a preliminary site investigation to visually assess the site. The trip report stated in part that there were no houses near, utility water available to homes in the area and pits were covered and sown in grass.
- August 13, 1985 A proposed plan of investigation dated August 9, 1985 was received.
- August 22, 1985 Barry Atnip, Coordinator, Superfund, Todd Hughes, Geologist, Superfund and Charles Powers, Coordinator, Superfund met to review the proposed plan of investigation. Several revisions were agreed on as being needed.
- August 28, 1985 A letter to Ralph Mosley, Genesco, dated August 28, 1985 signed by Charles H. Powers stating the required revisions of the proposed plan of investigation was mailed.
- September 13, 1985 As requested by Ralph Mosely, Genesco. Todd Hughes, Geologist, Wayne McCoy of Resource Consultants and Charles Powers, Coordinator, Superfund met to discuss the required revisions to the site investigation plan.

September 25, 1985	A revised proposed plan of investigation dated September 20, 1985 was received from Genesco with cover letter from Ralph Mosely to Charles Powers. The plan included all the required revisions.
October 2, 1985	By letter dated October 2, 1984 from Charles Powers, Superfund to Ralph Mosely, Genesco, the revised plan of investigation dated September 20, 1985 was approved.
October 9, 1985	Charles Powers, was notified by phone by Ralph Mosely that Task A and B had been started.
December 12, 1985	Charles Powers, Coordinator, Todd Hughes, Geologist, Ralph Mosely, Genesco, Wayne McCoy Rsource Consultants, and Mark Levy of Geologic Associates met for an update on the work. Wayne McCoy stated that Task A and B was completed. They presented a map indicating locations of trenches and proposed locations of wells for installation of piezometers. The start of the well drilling and pit excavation for exact location and testing would start immediately after January 1, 1986.
December 23, 1985	Received from Ralph Mosely, Genesco to Charles Powers, Superfund a ground water monitoring configuration which Todd Hughes had requested.
January 6, 1986	Todd Hughes and Charles Powers sent letter dated January 6, 1986 to Ralph Mosely stating our concerns relative to the kind of pipe proposed to be used and that if the wells were to be used for long term sampling then a diferent kind of pipe must be used.
January 14, 1986	Charles Powers, Coordinator and Ronnie Bowers, Superfund made a site visit and joined Wayne McCoy of Edge and Ralph Mosely, Genesco. Geologic Associates started drilling the wells.
January 17, 1986	Ronnie Bowers, Superfund and Charles Powers, Superfund made a site visit. We saw Mr. Hobbs of Geologic Associates. Two wells had been completed and a third well started.
January 22, 1986	Excavation of the pits for sampling started. Ronnie Bowers and Todd Hughes collected samples for Superfund. Geologic Associates did sampling for Genesco.
January 27, 1986	Meeting with Genesco, Inc. Don Shackelford, Todd Hughes, Ralph Mosely, Wayne McCoy, Ronnie Bowers, Mark Levy and Charles Powers attended. This was a session of updating. It appeared that the problem was much larger than expected. Sampling was discussed. We became aware that there were wells and springs in the area used for drinking water. An

immediate sampling plan and information to homeowners was initiated. This included immediate samples of Mr. Hackett's and Dr. Fletcher's drinking water.

Ralph Mosely stated that the transport of waste was by Mr. Kennon driver and truck and possibly a vehicle owned or operated by Genesco.

January 28, 1986

Sampling was started on Mr. Hackett's spring. A complete list of water supply sampling and dates are attached. This list is complete up to 2-14-86. Sampling of water supply is continuing as of February 25, 1986.

February 11, 1986

Laboratory report received relative to Hackett's spring. Genesco, Inc. made plan and commitment to furnish bottled water to all households in the area if they wanted the service.

February 13, 1986

State Laboratory verified sample results of Hacketts Spring. Dr. Michael T. Bruner, Assistant Commissioner, Department of Health and Environment issued a press release.

February 18, 1986

A charcoal filter system installed in Hacketts Water supply.

February 19, 1986

An update meeting with the following present: Levy, Seaborg, Kennon, Mosely, McCoy, Shackleford, Roland, Hughes, Powers, Bowers and Ault. Mr. Shackleford stated that we would prepare an order and would attempt to get it through the system in one (1) month. Mr. Kennon, in response to a question, stated that to the best of his knowledge no one else used the site for a dump.

A letter signed by James Ault, Director of Superfund dated February 19, 1986 to Mr. Kennon and Ralph Mosely requesting them to respond to us relative to all known responsible parties.

February 24, 1986

Dr. Michael T. Bruner, Assistant Commissioner attended the Brentwood City Commission meeting and presented the state's position.

DS/sdm/CH-8

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 6, 1986
PROJECT CODE: ITEK 21683
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site Pit A, 1-22-86, 1:30


VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS


<u>Compound</u>	<u>Concentration (ppb)</u>	<u>Compound</u>	<u>Concentration (ppb)</u>
acrolein	ND	1,1-dichloroethene	290.
acrylonitrile	ND	trans-1,2-dichloroethene	3,000.
benzene	200.	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	300.
carbon tetrachloride	ND	methylene chloride	340.
chlorobenzene	14.	1,1,2,2-tetrachloroethane	ND
chloroethane	750.	tetrachloroethene	110.
2-chloroethylvinyl ether	ND	toluene	120,000.
chloroform	ND	1,1,1-trichloroethane	2,000.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	75.
1,1-dichloroethane	4,300.	vinyl chloride	<10.
1,2-dichloroethane	1,200.		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Sworn to and subscribed before me this 6th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Manager
Title





INTERNATIONAL
TECHNOLOGY
CORPORATION

ANALYTICAL SERVICES

5815 Middlebrook Pike • Knoxville, Tennessee 37921 • 615-588-6401

CERTIFICATE OF ANALYSIS

TO IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED February 6, 1986
PROJECT CODE ITEK 21683
ORDER NUMBER TN Contract FA-1353

Sample Description: Kennon Site Pit B, Grab Waste, 1-22-86, 11:30


VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS


<u>Compound</u>	<u>Concentration</u> <u>(ppm)</u>	<u>Compound</u>	<u>Concentration</u> <u>(ppm)</u>
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	ND
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	<20,000.
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	ND	tetrachloroethene	<20,000.
2-chloroethylvinyl ether	ND	toluene	570,000.
chloroform	ND	1,1,1-trichloroethane	<20,000.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	<20,000.
1,1-dichloroethane	ND	vinyl chloride	ND
1,2-dichloroethane	ND		

Remarks: ND = Not detected.

<20,000. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Sworn to and subscribed before me this 6th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Manager
Title



Accredited by the American Association for Laboratory Accreditation in the chemical field of testing, as listed in the current AAALAC Directory of Accredited Laboratories



INTERNATIONAL
TECHNOLOGY
CORPORATION

ANALYTICAL SERVICES

5815 Middlebrook Pike • Knoxville, Tennessee 37921 • 615-588-6401



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 6, 1986
PROJECT CODE: ITEK 21683
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site Pit B, Grab Soil, 1-22-86, 11:30

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

<u>Compound</u>	<u>Concentration (ppb)</u>	<u>Compound</u>	<u>Concentration (ppb)</u>
acrolein	ND	1,1-dichloroethene	3,300.
acrylonitrile	ND	trans-1,2-dichloroethene	1,300.
benzene	1,000.	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	19,000.
carbon tetrachloride	ND	methylene chloride	3,300.
chlorobenzene	530.	1,1,2,2-tetrachloroethane	ND
chloroethane	ND	tetrachloroethene	220,000.
2-chloroethylvinyl ether	ND	toluene	6,200,000.
chloroform	<250.	1,1,1-trichloroethane	160,000.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	6,900.
1,1-dichloroethane	950.	vinyl chloride	ND
1,2-dichloroethane	11,000.		

Remarks: ND = Not detected.

<250. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Sworn to and subscribed before me this 6th
day of February, 1986
My commission expires January 16, 1988

Notary Public

Approved

Laboratory Manager

Title



Accredited by the American Association for Laboratory Accreditation in the chemical field of testing, as listed in the current AALA Directory of Accredited Laboratories

93-9-8'

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED February 10, 1986
PROJECT CODE WPK 21702
ORDER NUMBER TN Contract FA-1313

Sample Description: Two (2) water samples and one (1) soil sample received
January 29, 1986

Concentration units are mg/liter (ppm) unless otherwise stated


PRIORITY POLLUTANT METALS


	Kennon Site, 1-28-86		
	Field #1 Hackett Spring 9:15	Field #3, Seep (water) 10:30	Field #3, Seep (soil) 10:30 (per gram, ppm)
Antimony	<0.001	<0.002*	<0.05
Arsenic	<0.001	0.217	18.
Beryllium	<0.002	0.010	0.69
Cadmium	<0.001	<0.001	<0.03
Chromium	<0.01	0.15	9.3
Copper	<0.002	0.088	6.5
Lead	<0.01	0.12	7.6
Mercury	<0.001	<0.001	0.048
Nickel	<0.01	<0.01	8.3
Selenium	<0.001	<0.03*	<0.3*
Silver	<0.002	<0.002	<0.1
Thallium	<0.02	<0.02	<0.6
Zinc	<0.001	0.519	30.
Cyanide	<0.01	0.01	0.20

* Detection limits higher than normal due to sample matrix interferences.

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-8403

Sworn to and subscribed before me this 10th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Director
Title



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED February 10, 1986
PROJECT CODE: ITEX 21702
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site, Field #1, Hackett Spring, 1-28-86, 9:15

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (ppb)	Compound	Concentration (ppb)
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	10.
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	ND
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	ND	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	ND
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	ND
1,1-dichloroethane	<10.	vinyl chloride	ND
1,2-dichloroethane	ND		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 10th
day of February, 1986
My commission expires January 16, 1988

[Signature]
Notary Public

[Signature]
Approved by
Laboratory Director
Title





CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 11, 1986
PROJECT CODE: ITEK 21765
ORDER NUMBER: TN Contract FA-1363
Job #41504

Sample Description: Kennon Site, Hackett Loring, Field #1, 2-7-86, 9:00

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (ppb)	Compound	Concentration (ppb)
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	70.
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	ND
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	<10.	tetrachloroethene	ND
1-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	13.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	<10.
1,1-dichloroethane	26.	vinyl chloride	ND
1,2-dichloroethane	<10.		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-6403

Sworn to and subscribed before me this 11th day of February, 1986
My commission expires January 15, 1988

[Signature]
Notary Public

[Signature]
Approved by
Laboratory Manager
Title



ANALYTICAL SERVICE

1011 Middlebrook Pike • Knoxville, Tennessee 37921 • 615-566-6401



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 26, 1986
PROJECT CODE: ITEK 21854
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kannon Site, Field #17, Well #8, 2-21-86, 10:30

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS


Compound	Concentration (ppb)	Compound	Concentration (ppb)
acrolein	ND	1,1-dichloroethene	13. ✓
acrylonitrile	ND	trans-1,2-dichloroethene	350. ✓
benzene	<10.	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	<10.
carbon tetrachloride	ND	methylene chloride	<10. ✓
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	370. ~ 400	tetrachloroethene	<10.
2-chloroethylvinyl ether	ND	toluene	1,600. ✓
chloroform	<10.	1,1,1-trichloroethane	57. ✓
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	ND
1,1-dichloroethane	200. ✓	vinyl chloride	ND
1,2-dichloroethane	22. ✓		


Remarks: ND = Not detected.


<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 26th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by _____
Laboratory Manager
Title _____



Accredited by the American Association for Laboratory Accreditation in the chemical field of testing, as listed in the current AALA Directory of Accredited Laboratories



INTERNATIONAL
TECHNOLOGY
CORPORATION

ANALYTICAL SERVICES

5815 Middlebrook Pike • Knoxville, Tennessee 37921 • 615 588 6401



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 21, 1986
PROJECT CODE ITEK 21797
ORDER NUMBER: TN Contract FA-1353

Sample Description: Field #4, Kennon Site, Johnson Well, 2-16-86, 4:00

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS


<u>Compound</u>	<u>Concentration (ppb)</u>	<u>Compound</u>	<u>Concentration (ppb)</u>
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	ND
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	ND
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	ND	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	ND
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	ND
1,1-dichloroethane	ND	vinyl chloride	ND
1,2-dichloroethane	ND		


Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 21st
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Manager
Title




A member of the American Association for Laboratory Accreditation in the chemical
and environmental fields in the current AAIA Directory of Accredited Laboratories



INTERNATIONAL
TECHNOLOGY
CORPORATION

ANALYTICAL SERVICES

5815 Middlebrook Pike • Knoxville, Tennessee 37921 • 615-588-6401



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 6, 1986
PROJECT CODE: ITEK 21683
ORDER NUMBER: TN Contract FA-1353


Sample Description: Kennon Site Pit B, Grab Soil, 1-22-86, 11:30


PESTICIDES AND PCB's - PRIORITY POLLUTANT ANALYSIS

<u>Compound</u>	<u>Concentration (ppm)</u>	<u>Compound</u>	<u>Concentration (ppm)</u>
aldrin	ND	endrin aldehyde	ND
α-BHC	ND	heptachlor	ND
β-BHC	ND	heptachlor epoxide	ND
γ-BHC (lindane)	ND	PCB-(Aroclor)-1242	ND
δ-BHC	ND	PCB-(Aroclor)-1254	ND
chlordane	ND	PCB-(Aroclor)-1221	ND
4,4'-DDT	ND	PCB-(Aroclor)-1232	ND
4,4'-DDE	ND	PCB-(Aroclor)-1248	ND
4,4'-DDD	ND	PCB-(Aroclor)-1260	ND
dieldrin	ND	PCB-(Aroclor)-1016	ND
α-endosulfan	ND	toxaphene	ND
β-endosulfan	ND	methoxychlor	ND
endosulfan sulfate	ND		
endrin	ND		

Remarks: ND = Not detected at a level of 1.0 ppm (parts per million).

Sworn to and subscribed before me this 6th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by _____
Laboratory Manager
Title _____



Accredited by the American Association for Laboratory Accreditation in the chemical
field of testing, as listed in the current AALA Directory of Accredited Laboratories

ANALYTICAL SERVICES

1000 Abbott Pike • Knoxville, Tennessee 37921 • 615 588-6401

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37913

DATE REPORTED: March 25, 1986
PROJECT CODE: ITEK 22002
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site, Hackett Spring, 3-18-86, 2:00

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS


<u>Compound</u>	<u>Concentration (ppb)</u>	<u>Compound</u>	<u>Concentration (ppb)</u>
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	66.
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	ND
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	<10.	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	22.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	<10.
1,1-dichloroethane	26.	vinyl chloride	ND
1,2-dichloroethane	<10.		


Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-8403

Sworn to and subscribed before me this 25th
day of March, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Manager
Title



Accredited by the American Association of Laboratory Accreditation in the chemical field of testing, as listed in the current AALA Directory of Accredited Laboratories

ANALYSIS

SERVICES

ROZ

16413 Madisonville, Tenn. • Knoxville, Tenn. 37601 • 615-518-6401

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED April 1, 1986
PROJECT CODE ITEX 22038
ORDER NUMBER TN Contract 14-1353
Job #409374.11.71.89

Sample Description: Field #61, Kennon Site, Hackett Sp., 3-15-86, 2:15

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (pph)	Compound	Concentration (ppt)
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	41.
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	<10.
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	<10.	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	11.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	<10.
1,1-dichloroethane	24.	vinyl chloride	ND
1,2-dichloroethane	ND		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 1st day of April, 1986

My commission expires January 16, 1986

[Signature]
Notary Public

[Signature]
Approved Laboratory Manager

Title



Accredited by the American Association of Laboratories Accredited in the chemical field of testing, as listed in the current AALA Directory of Accredited Laboratories.

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: June 10, 1986
PROJECT CODE: ITEX 22457
ORDER NUMBER: TN Contract FA-1353
PAGE 5 OF 5
Job #409374.01.71.89

Sample Description: Kennon Site, Field #99, Genesco Well #9, 5-31-86, 9:40

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (ppb)	Compound	Concentration (ppb)
benzene	ND	1,1-dichloroethene	ND
bromodichloromethane	ND	trans-1,2-dichloroethene	2,000.
bromoform	ND	1,2-dichloropropane	ND
bromomethane	ND	cis-1,3-dichloropropene	ND
carbon tetrachloride	ND	trans-1,3-dichloropropene	ND
chlorobenzene	ND	ethyl benzene	ND
chloroethane	1,200.	methylene chloride	ND
2-chloroethylvinyl ether	ND	1,1,2,2-tetrachloroethane	ND
chloroform	ND	tetrachloroethene	ND
chloromethane	ND	toluene	39,000.
dibromochloromethane	ND	1,1,1-trichloroethane	<1,000.
1,1-dichloroethane	1,600.	1,1,2-trichloroethane	ND
1,2-dichloroethane	<1,000.	trichloroethene	ND
		vinyl chloride	ND

Remarks: ND = Not detected.

<1,000. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 10th
day of June, 1986
My commission expires January 16, 1988

Notary Public

Approved by *Alexander P. Moore*
Laboratory Manager

Title





INTERNATIONAL
TECHNOLOGY
CORPORATION

ANALYTICAL SERVICES

5815 Middlebrook Pike • Knoxville, Tennessee 37921 • 615-588-6421

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED February 10, 1986
PROJECT CODE ITEK 21702
ORDER NUMBER TN Contract FA-1353

Sample Description: Two (2) water samples and one (1) soil sample received
January 29, 1986

Concentration units are mg/liter (ppm) unless otherwise stated

PRIORITY POLLUTANT METALS


Kennon Site, 1-28-86


	Field #1 Hackett Spring 9:15	Field #3, Seep (water) 10:30	Field #3, Seep (soil) 10:30 (ug/gram, ppm)
Antimony	<0.001	<0.002*	<0.05
Arsenic	<0.001	0.217	18.
Beryllium	<0.002	0.010	0.69
Cadmium	<0.001	<0.001	<0.03
Chromium	<0.01	0.15	9.3
Copper	<0.002	0.088	6.5
Lead	<0.01	0.12	7.6
Mercury	<0.001	<0.001	0.048
Nickel	<0.01	<0.01	8.3
Selenium	<0.001	<0.03*	<0.3*
Silver	<0.002	<0.002	<0.1
Thallium	<0.02	<0.02	<0.6
Zinc	<0.001	0.519	30.
Cyanide	<0.01	0.01	0.20

* Detection limits higher than normal due to sample matrix interferences.

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 10th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Director
Title



Accredited by the American Association for Laboratory Accreditation in the chemical
field of testing, as listed in the current AALA Directory of Accredited Laboratories

CERTIFICATE OF ANALYSIS

TO IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED February 6, 1986
PROJECT CODE ITEK 21683
ORDER NUMBER TN Contract FA-1353


Sample Description: Two (2) soil samples and one (1) waste sample received
January 24, 1986


Concentration units are $\mu\text{g}/\text{gram}$ (ppm)

PRIORITY POLLUTANT METALS

	Grab Waste Pit B 1-22-86, 11:30	Pit A 1-22-86, 1:30	Pit B 1-22-86, 11:30
Antimony	0.10	<0.1	<0.1
Arsenic	<0.1	9.0	9.0
Beryllium	<0.1	1.2	1.1
Cadmium	0.25	<0.1	<0.1
Chromium	14.	14.	14.
Copper	0.80	7.5	4.4
Lead	1.2	8.0	8.2
Mercury	<0.1	<0.1	0.12
Nickel	<0.7	11.	7.3
Selenium	<0.8	<1.	<1.
Silver	<0.1	<0.2	<0.2
Thallium	<1.	<2.	<2.
Zinc	560.	33.	37.
Total Cyanide	0.07	0.10	0.26


Sworn to and subscribed before me this 6th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved _____
Laboratory Manager
Title _____



SAMPLE POINTS



KENNON SITE

Site No. TND 981473575

Reference No. 2

GERAGHTY & MILLER, INC.

Plan for Investigation of the Kennon Site,
Brentwood, Tennessee

Prepared for

GENESCO, INC.
Nashville, Tennessee

December 1986

PROJECT # 01088BR1

GERAGHTY & MILLER, INC.
Ground-Water Consultants
140 East Division Road, Building A, Suite 2
Oak Ridge, Tennessee 37830

TABLE OF CONTENTS

	<u>Page</u>
INTRODUCTION.....	1
BACKGROUND.....	3
General Setting and Site History.....	3
Farming & Residential Development.....	3
Industrial Facilities.....	6
Phosphate Mining.....	9
Waste Disposal at the Kennon Site.....	11
Previous and Ongoing Work.....	14
Initial Fact Finding by Genesco.....	14
Inspection Pit Sampling.....	14
Off-Site Sampling.....	16
On-Site Monitor Well Installation and Sampling.....	20
Geophysical Surveys.....	25
Soil Sampling.....	25
USGS Study.....	25
Remedial Actions.....	27
Hydrogeologic Setting.....	31
Climate.....	31
Drainage.....	31
Geology.....	32
Surficial Material.....	35
Bigby-Cannon Formation.....	35
Hermitage Formation.....	36
Carters Limestone.....	37
Lebanon Limestone.....	38
Structure.....	38
Joints.....	39
Ground-Water Flow.....	40
Extent of Contamination.....	42
Disposal Area.....	42
Delineation of Disposal Pits.....	42
Chemical Characterization.....	44
Contaminant Plume.....	46
On-Site.....	46
Off-Site.....	50
Source of Constituents.....	51
WORK PLAN.....	53
Program Concept.....	53
Objectives.....	53

TABLE OF CONTENTS
(continued)

	<u>Page</u>
Delineation of Source Areas.....	53
Characterization of Hydrogeologic System.....	54
Delineation and Characterization of Possible Contaminant Plume.....	55
Gathering of Additional Background Information.....	55
Monitor Well Installation.....	57
Well Locations and Depths.....	57
Well Construction.....	61
Unconsolidated Zone Monitor Wells....	61
Shallow Bedrock Monitor Wells.....	63
Deep Bedrock Monitor Wells.....	65
Well Completion and Development.....	67
Water Level Monitoring and Hydraulic Testing.....	68
Static Head Monitoring.....	68
Hydraulic Testing.....	69
Soil Sampling and Testing of Source Area..	70
Ground-Water Sampling.....	73
 SCHEDULE AND BUDGET.....	 74
REFERENCES.....	76
 APPENDIX A: Results of Sample Analyses of Inspection Pits and On-Site Seep, January 1986.....	 A-1
APPENDIX B: Results of Sample Analyses of Off-Site Water Supplies, January through June, 1986.....	B-1
APPENDIX C: Results of Sample Analyses of Surface Runoff and the Little Harpeth River.....	C-1
APPENDIX D: Lithologic Logs of Monitor Wells Boreholes.....	D-1
APPENDIX E: Sample Analyses of On-Site Monitor Wells, Pond, and Ditch, February through May, 1986.....	E-1
APPENDIX F: Lithologic Logs of Auger Borings.....	F-1
APPENDIX G: Results of Soil Sample Analyses, June and August, 1986.....	G-1

INTRODUCTION

In June of 1986, Geraghty & Miller, Inc. (G&M) was retained by Genesco, Inc. (Genesco) to conduct a ground-water investigation of the Kennon site in Brentwood, Tennessee, where approximately 800 barrels of industrial waste materials were disposed. Preliminary investigations have been made by Genesco and their consultants, Geologic Associates (GA), and the State Superfund Division of the Tennessee Department of Health and Environment (TDHE). In addition, the U. S. Geological Survey (USGS) is presently conducting a regional study of the area.

From this work, areas of waste disposal have been approximately delineated, a network of shallow monitor wells has been installed and sampled to determine the possible distribution of disposed substances in the surficial soil and shallow bedrock aquifer. Area domestic wells and springs have also been sampled to determine possible off-site migration of contaminants. However, additional data are needed to further delineate the disposal pit areas and shallow plume, and to characterize the deeper hydrogeologic system and determine whether any contamination of the deeper bedrock aquifer has occurred.

This plan sets forth a program of additional remote sensing, test boring, monitor well installation, and soil and water sampling, which, when implemented, will provide better understanding of the shallow and deeper ground-water flow

GERAGHTY & MILLER, INC.

system and the extent of possible contamination, and will provide the basis for a hazard evaluation and the design of remedial measures. TDHE will be notified in advance of any additions, deletions or changes to the proposed work plan. Seven days advance notice will be given to TDHE of the initiation of work at the site.

BACKGROUND

General Setting and Site History

Farming and Residential Development

The Kennon property is located in a rural part of Williamson County in which livestock is the most important farming commodity. Cash crops include tobacco, hay, corn, and small grains (U.S. Soil Conservation Service, 1961). The fenced tract containing the disposal area is currently used as a pasture for cattle. It is not known whether the tract has ever been cultivated or whether fertilizers or pesticides have ever been applied to this or adjoining tracts.

A number of old farmhouses are located in the Wilson Pike/Split Log Road area. In addition, several new residences have been constructed over the past five years. Most of the new homes are situated on four to ten acre tracts.

Residential water needs have historically been supplied by individual wells, springs, and cisterns. Domestic wells in the area are generally cased 20 to 25 feet (ft) into the bedrock with an unscreened open hole extending to depths of a few hundred feet to more than 2000 ft. Construction data for individual domestic wells are summarized in Table 1. Locations of area domestic water supply wells and springs are shown in Figure 1. State records have been searched for

TABLE 1

CONSTRUCTION & STATUS OF DOMESTIC WELLS

WELL OWNER	DATE COMPLETED	CASING DIAM. (IN)	DEPTH OF CASING (FT)	TOTAL DEPTH (FT)	OPEN INTERVAL FORMATION	PRINCIPLE WATER BEARING ZONE (DEPTH FT)	STATUS	DRILLER
Allen	04/05/69	7	20	68-80	B, H, C	195	Residential	Henry Drilling Co.
Beyer	08/14/85	6.25	20	200	H, L, R, P, M, K	1020	Residential	Henry Drilling Co.
Boswell	10/18/84	6.25	21	1050	H, C, L	277	Residential	Henry Drilling Co.
Denny	06/27/84	6.25	21	350	H, C, L	70, 110	Residential	Henry Drilling Co.
Fletcher (1)				240	H, C, L	115-117	Residential	Henry Drilling Co.
Fletcher (2)				200	H, C, L	23, 115-116	Residential	Henry Drilling Co.
Foster (1)	08/08/85	6.25	20	198	H, C, L	146	Heat Pump	Henry Drilling Co.
Foster (2)	05/22/84	6.25	21	260	H, C, L, R	230	Residential	Henry Drilling Co.
Gore	06/04/70	6	20	450	H	65	Residential	Henry Drilling Co.
Holt		6	25	75	B	36	Residential	Henry Drilling Co.
Hall	03/03/86	6.25	24	36	H, C, L	80	Residential	Henry Drilling Co.
Howe				400	H, C, L	130	Residential	Henry Drilling Co.
Johnson	12/30/72	6	20	220	H, C	184	Residential	
Levine (1)	08/17/74	6	22	198	H, C, L, R, P, M, K	1170	Residential	
Levine (2)				1235	H, C, L, R, P, M, K		Residential	
Myatt				2200	H		Residential	
Legieza				73		18	Residential	
Mallory						28	Residential	
Pawitt	09/16/81	6.25	21	350	H, C, L, R	112	Non-Potable	Herman Clark Water Walls
Sullivan				105	H, C	105	Residential	
Wilson	02/28/84	6.25	21	260	B, H, C	28	Residential	Henry Drilling Co.

B = Bigby-Cannon Formation
 H = Hermitage Formation
 C = Carters Formation
 L = Lebanon Formation
 R = Ridley Formation
 P = Pierce Formation
 M = Murfreesboro Formation
 K = Knox Group

Information Provided by TUE, Division of Ground Water Protection.

Geraghty & Miller, Inc.




FIGURE 1. DOMESTIC WELLS AND SPRINGS IN THE VICINITY OF THE KENNON SITE

GERAGHTY & MILLER, INC.

additional wells in the vicinity that may be abandoned and none have been found. Aerial photographs from 1946, 1967, 1969 , 1976, and 1980 do not show any old farm houses which may have had wells other than those listed in Table 1. A water main from the City of Brentwood is being constructed to serve the residents along part of Wilson Pike and Split Log Road.

Septic tanks and leach fields are used for disposal of domestic waste-water in the area. State regulations require that leach fields be located a minimum of 50 ft from wells and springs which serve as domestic water supplies; septic tanks may be located closer than 50 ft to domestic wells and springs.

Industrial Facilities

An electrical power substation is located on Wilson Pike just south of Moore's Lane (Figure 2). It was constructed around 1981 by TVA and is operated by Middle Tennessee Electric Co-op, which provides electric service to the area. One transformer is currently in operation to convert 161 kilovolt power from the TVA Power line to 14 kilovolt power which is distributed to local users.

Seaboard Systems Railroad owns and operates a line that follows the western boundary of the Kennon property (Figure 2). This track was formerly operated by the Louisville and Nashville Railroad, Lewisburg Division, and has been in

Geraghty & Miller, Inc.




FIGURE 2 INDUSTRIAL FACILITIES IN THE VICINITY OF THE KENNON SITE

GERAGHTY & MILLER, INC.

service since approximately 1914. The Moran Rail Siding, consisting of a passing track and a public team track, is located near the Johnson residence. Rail sidings such as this are commonly used for loading, for car and equipment repairs, and as laydown areas for materials. No records of spills or derailments are available from either the Nashville office of Seaboard Systems or from the Federal Railroad Administration. Records at those offices are reportedly kept on file for one year and then destroyed.

Three natural gas pipelines pass to the south and east of Brentwood and cross Split Log Road about 4,500 ft southeast of the Kennon Site (Figure 2). One 36-inch (in)-diameter and two 30-in-diameter lines, operated by Columbia Gulf Transmission Company, transport Southern Louisiana and Louisiana offshore natural gas northward for distribution by Columbia Gas Companies. A valve station, for isolating sections of pipeline, is located just south of Split Log Road.

For four years the Williamson County Landfill Division has operated a garbage collection site south of Moore's Lane, between the railroad and Wilson Pike (Figure 2). The site contains two to five dumpsters, where local residents may dispose of garbage. The facility is intended for domestic garbage only; however, it is not manned and there is no way to insure that small amounts of industrial waste or hazardous household and farm wastes are not disposed.

Phosphate Mining

The phosphate mined in Williamson County is of the brown type, which is the most economically important type of phosphate ore in Tennessee. It occurs in the western part of the Central Basin physiographic region and is associated with certain phosphate-rich Ordovician Period limestones. (Smith and Whitlatch, 1940).

The brown phosphate deposits in the Franklin area occur as rim deposits around hillsides, formed as weathering residuum of Ordovician Bigby-Cannon and Hermitage Formation limestones. Low-grade phosphate ore was strip-mined by drag lines or bulldozers in this area. The ore was washed and processed off-site to obtain high-grade elemental phosphorus.

Phosphate mining in Tennessee is regulated by the Department of Conservation. The permitting process, in operation since 1972, includes submission of a reclamation plan and a bond which is released after reclamation is approved, as well as documentation of land ownership and other details such as location, acreage and surface drainage.

Phosphate was mined from the Kennon Property between November 1972 and April 1974, by Monsanto Industrial Chemicals Company. A total of 20 acres were permitted to be mined and an additional two acres were permitted as an access road. According to TDHE records, a total of eight acres were actually disturbed (Figure 3). Low-grade phosphate deposits

Geraghty & Miller, Inc.




FIGURE 3. AREAS MINED FOR PHOSPHATE BY MONSANTO FROM 1972-1974

as much as 15 ft thick, occurring as weathering residuum of the Bigby-Cannon limestone, were mined from the property. Reclamation consisted of grading and sowing the area in fescue and rye. The bond for mining of the Kennon property was released in April 1974, when reclamation was considered complete; however, a small mine pit was left unfilled and was later used for disposal of industrial wastes.

It is not clear why the mine pit used for waste disposal at the Kennon Site was left unreclaimed. Correspondence between Monsanto and the State of Tennessee suggest that the mining of that pit was followed by an unusually rainy period which inhibited reclamation. Reclamation of the site was approved after a site inspection by TDHE in September 1973.

Waste Disposal at the Kennon Site

For a short period during the late summer and fall of 1978, industrial waste from General Adhesives, a division of Genesco, was disposed of in pits on the Kennon site. Approximately 800 barrels of waste, primarily from the cleaning of kettles used in the production of adhesives and caulking compounds, was disposed of at the Kennon site. Approximately 50 to 80 barrels containing waste were buried in the disposal pits.

Initially wastes were poured into the abandoned phosphate mine pit, (Pit D) shown on Figure 4. When this pit was filled, four additional disposal trenches (Pits A, B, C,

Geraghty & Miller, Inc.




FIGURE 4. DISPOSAL PITS

GERAGHTY & MILLER, INC.

and E) were excavated to a depth of about 6 ft with a bulldozer at the approximate locations shown in Figure 4. The disposal pits were left open for a short period to allow for evaporation and then were covered with soil and graded.

Previous and Ongoing Work

Initial Fact-Finding by Genesco

During May 1985, the present management of Genesco learned of the 1978 waste disposal at the Kennon site. Genesco promptly notified TDHE and began an investigation to determine the extent of contamination. The areas of the disposal pits shown in Figure 4 were delineated from the recollections of the landowner's bulldozer operator who was responsible for excavation of the trenches. It was determined that the major components of the waste were water-soluble adhesives, acetone, ethyl acetate, hexane, methylene chloride, methyl ethyl ketone, rubber solvent, toluene, 1,1,1 trichloroethane, trichloroethylene, and organic fillers.

Inspection Pit Sampling

During January 1986, 101 inspection pits were excavated with a backhoe in and around the disposal area to verify and more precisely delineate the areas of the disposal pits (Figure 5). Samples of water, soil, and sludge were collected from 36 of the pits by personnel from TDHE and GA. Samples were taken from only those pits where sludge, metal drums or ground-water seepage were found. Samples collected by TDHE were analyzed for full priority pollutants and those collected by GA were analyzed for priority pollutant volatile organic compounds (VOCs). TDHE also sampled water and soil

Geraghty & Miller, Inc.




FIGURE 5. INSPECTION PITS

GERAGHTY & MILLER, INC.

from an on-site seep, the location of which is shown in Figure 6. A total of 31 organic chemical compounds were detected on-site. Results of chemical analyses from this phase of work are presented in Appendix A.

Off-Site Sampling

Off-site domestic wells and springs in the area have been sampled by TDHE and analyzed for priority pollutants, the results of which are included in Appendix B. Traces of organic compounds were detected in seven wells and one spring. In four of the wells only chloroform, bromodichloromethane and dibromochloromethane (Trihalomethanes) were found, and only in trace amounts. Trihalomethanes are commonly present in chlorinated water supplies. Small concentrations of organic compounds other than trihalomethanes were found in three wells (Mallory, Legieza, and Fletcher) and one spring (Hackett). The Fletcher well was found to contain a trace of bis(2-ethylhexyl)phthalate in only one of four samples. This substance is commonly found in association with plastics such as PVC. Substances found were within limitations allowed by the Safe Drinking Water Act. Occurrences of unexplained organics are shown in Figure 7. Samples of surface runoff from the Kennon site were collected by TDHE on March 13, 1986, and from the Little Harpeth River on February 14 and 25, 1986, at locations shown in Figure 8. No hazardous substances were found in these samples. Analytical results of this sampling are included in Appendix C.




FIGURE 6. ON-SITE SEEP SAMPLED BY TDHE

Geraghty & Miller, Inc.




FIGURE 7. OCCURRENCES OF UNEXPLAINED ORGANIC COMPOUNDS

Geraghty & Miller, Inc.




FIGURE 8. SAMPLING POINTS FOR SURFACE RUNOFF AND LITTLE HARPETH RIVER

GERAGHTY & MILLER, INC.

On-Site Monitor Well Installation and Sampling

Thirty shallow 2-in-diameter PVC monitor wells were constructed on-site by GA between January and March 1986. The first ten wells, designated PZ-1 through PZ-9 and PZ-7A were installed as piezometers to monitor ground-water levels. Wells W-10 through W-29 were installed to monitor groundwater quality in the vicinity of the disposal site. Subsequently the PZ wells have been included in the water quality sampling network. As shown in Figure 9, most of the wells are located in a drainage swale leading from the disposal area.

Construction details are summarized in Table 2 and illustrated in Figure 10. Lithologic logs for these wells are included in Appendix D. The wells designated with "PZ" have essentially the same construction as those designated with "W" except that the holes for the PZ wells were wash-bored to bedrock, whereas those for the W wells were augered and the drilling equipment was cleaned before drilling each W well. The bedrock was cored using an NQ core barrel, which has a nominal outside diameter (O.D.) of three inches. The screen was set in the 3-in hole and a filter pack was added around the screen. A bentonite seal was placed above the filter pack and the remainder of the annulus was filled with cement grout. A 1.7-in O.D. Brainard-Kilman hand pump was used to develop the wells.

The wells are relatively shallow and most are screened over an interval which spans the unconsolidated zone/bedrock

Thirty shallow 2-in-diameter PVC monitor wells were constructed on-site by GA between January and March 1986. The first ten wells, designated PZ-1 through PZ-9 and PZ-7A were installed as piezometers to monitor ground-water levels. Wells W-10 through W-29 were installed to monitor groundwater quality in the vicinity of the disposal site. Subsequently the PZ wells have been included in the water quality sampling network. As shown in Figure 9, most of the wells are located in a drainage swale leading from the disposal area.

Construction details are summarized in Table 2 and illustrated in Figure 10. Lithologic logs for these wells are included in Appendix D. The wells designated with "PZ" have essentially the same construction as those designated with "W" except that the holes for the PZ wells were wash-bored to bedrock, whereas those for the W wells were augered and the drilling equipment was cleaned before drilling each W well. The bedrock was cored using an NQ core barrel, which has a nominal outside diameter (O.D.) of three inches. The screen was set in the 3-in hole and a filter pack was added around the screen. A bentonite seal was placed above the filter pack and the remainder of the annulus was filled with cement grout. A 1.7-in O.D. Brainard-Kilman hand pump was used to develop the wells.

The wells are relatively shallow and most are screened over an interval which spans the unconsolidated zone/bedrock




FIGURE 9. MONITOR WELLS AND DISPOSAL PITS

Geraghty & Miller, Inc.

GERAGHTY & MILLER, INC.

TABLE 2
CONSTRUCTION DETAILS OF ON-SITE MONITOR WELLS

WELL NO.	INSTALLATION DATE	SURFACE ELEV. (ft. msl)	MEAS. PT. ELEV. (ft. msl)	SCREENED INTERVAL (Depth, ft)	FILTER PACK INTERVAL (Depth, ft)	BENTONITE SEAL INTERVAL (Depth, ft)	GROUT BACKFILL INTERVAL (Depth, ft)	AUGER OR WASH BIT REFUSAL (Depth, ft)
P2-1	1/15/86	777.1	780.30	20.55 - 30.55	12.0 - 31.3	9.6 - 12.0	0 - 9.6	9.6
P2-2	1/15/86	778.08	781.20	20.7 - 30.7	6.0 - 30.7	4.5 - 6.0	0 - 4.5	5.4
P2-3	1/17/86	787.25	790.00	20.7 - 30.5	6.5 - 30.7	5.0 - 6.5	0 - 5.0	5.7
P2-4	1/17/86	790.40	793.60	20.0 - 30.0	7.0 - 31.2	5.0 - 7.0	0 - 5.0	5.7
P2-5	1/20/86	797.70	800.60	21.0 - 32.0	6.0 - 32.0	4.0 - 6.0	0 - 4.0	5.0
P2-6	1/21/86	808.47	810.50	18.5 - 28.5	10.5 - 28.5	8.5 - 10.5	0 - 8.5	9.3
P2-7	1/23/86	779.08	782.00	5.0 - 8.5	5.0 - 8.3	3.5 - 5.0	0 - 3.5	6.2
P2-7A	1/24/86	778.77	781.50	11.4 - 21.4	7.5 - 21.4	6.0 - 7.5	0 - 6.0	6.3
P2-8	1/27/86	777.60	780.70	8.0 - 11.1	8.0 - 11.0	6.0 - 8.0	0 - 6.0	9.9
P2-9	1/28/86	777.0	779.40	7.5 - 10.4	7.0 - 10.4	5.5 - 7.0	0 - 5.5	7.4
W-10	3/04/86	769.8	772.10	5.4 - 13.2	3.7 - 13.2	1.7 - 3.7	0 - 1.75	7.8
W-11	3/04/86	768.83	771.20	1.8 - 7.2	1.8 - 7.2	0 - 1.8	0 - 1.0	4.9
W-12	3/04/86	771.19	773.50	4.1 - 9.5	3.1 - 9.5	1.0 - 3.1	0 - 1.0	7.2
W-13	3/04/86	764.07	776.50	1.4 - 7.0	1.3 - 7.0	0 - 1.3	0 - 1.3	4.6
W-14	3/04/86	767.29	769.70	2.6 - 5.5	2.6 - 5.5	0 - 2.6	0 - 2.6	3.5
W-15	3/14/86	765.16	767.60	3.6 - 6.5	2.6 - 6.5	0 - 2.6	0 - 2.6	4.5
W-16	3/04/86	767.5	769.90	6.1 - 11.5	5.1 - 11.5	2.6 - 5.1	0 - 2.6	1.2
W-17	3/14/86	758.3	760.60	2.0 - 7.5	2.1 - 8.0	0 - 2.1	0 - 2.1	5.7
W-18	3/14/86	759.0	761.40	4.7 - 9.2	3.4 - 9.2	1.2 - 3.4	0 - 1.2	7.0
W-19	3/14/86	759.9	761.30	5.6 - 11.0	4.6 - 11.0	2.6 - 4.6	0 - 2.6	8.9
W-20	3/14/86	751.2	753.60	3.7 - 6.5	2.7 - 6.5	0 - 2.7	0 - 2.7	4.4
W-21	2/28/86	750.31	752.70	6.0 - 11.5	5.2 - 11.5	3.2 - 5.2	0 - 3.2	8.5
W-22	2/28/86	750.0	752.40	2.2 - 7.8	2.0 - 7.8	0 - 2.0	0 - 2.0	5.4
W-23	2/28/86	744.63	747.00	6.5 - 14.5	4.5 - 14.5	2.5 - 4.5	0 - 2.5	11.2
W-24	3/03/86	745.0	748.00	8.5 - 13.8	7.0 - 13.8	4.5 - 7.0	0 - 4.5	11.3
W-25	3/14/86	765.10	767.50	1.5 - 6.9	3.0 - 6.9	0 - 3.0	0 - 3.0	6.9
W-26	3/03/86	792.10	794.50	8.0 - 21.2	6.5 - 21.2	3.0 - 6.5	0 - 3.0	10.9
W-27	3/03/86	794.79	797.30	1.0 - 11.6	1.6 - 11.6	0 - 1.6	0 - 1.6	7.0
W-28	3/03/86	764.99	767.40	3.0 - 11.0	2.5 - 11.0	0 - 2.5	0 - 2.5	5.8
W-29	3/04/86	822.0	824.40	16.7 - 44.5	10.2 - 44.5	8.2 - 10.2	0 - 8.2	8.3

NOTES

1. All wells installed by GA.
2. Elevations determined by GA.
3. Measuring points are top of PVC casing.
4. Total depth of each well is the bottom of the filter pack.
5. All casing is 2-inch-diameter PVC, flush threaded.
6. All screen is 2-inch-diameter PVC, slotted (0.01 in slot).
7. Wells P2-1 through P2-9 wash-bored to bedrock (6-inch-diameter borehole).
8. Wells W-10 through W-29 augered to bedrock (6-inch-diameter borehole).
9. All wells except W-25 cored from top of bedrock to total depth (3-inch-diameter corehole).

GERAGHTY & MILLER, INC.

water flow system, to determine directions and rates of ground-water flow, and to determine ground-water discharge points. The USGS plans to install monitor well clusters on the Kennon property and in the surrounding area. Each cluster will consist of a shallow well open to the Bigby Cannon or Upper Hermitage Formations and a deep well open to the Carters and Lower Hermitage Formations.

Remedial Actions

Measures have been taken to minimize potential threats to human health and the environment. A continuous silt screen was constructed during January 1986 along the fence directly down slope from the source area (Figure 12). This is designed to prevent the transport of contaminated sediment off-site onto adjoining property and eventually into the Little Harpeth River. Samples of surface runoff from the Kennon site and from the Little Harpeth River collected by TDHE show none of the contaminants detected in the source area.

When it was learned that water for residences around the site was supplied by individual wells, Genesco began providing bottled water to the residents in the area. In addition, carbon adsorption filtration units were installed in the water supply systems of the Hackett and Legieza households to remove organics that might be present in the water.

Geraghty & Miller, Inc.




FIGURE 12. SILT FENCE

GERAGHTY & MILLER, INC.

Genesco and the City of Brentwood are cooperating to extend a water main along Wilson Pike and Split Log Road in order to supply Brentwood City water to 28 residences and three unoccupied properties in the area (Figure 13). This project is expected to be completed in the fall of 1986.

Geraghty & Miller, Inc.




FIGURE 13. CITY OF BRENTWOOD WATER MAIN

GERAGHTY & MILLER, INC.

drains similar terrain near Franklin, may be applicable to the Little Harpeth River Basin as well. Ground-water discharge provides the base flow of streams, and the USGS study of the Franklin area (Zurawski and Burchett, 1980) indicates an average base flow of 8 inches or 18 percent of the year's rainfall. The actual proportion of annual rainfall that recharges the ground-water system in the study area may vary somewhat from this.

Geology

The Kennon property is underlain by a sequence of relatively flat-lying rocks, principally limestones with interbedded layers of shale and shaley or sandy limestone that is phosphatic in places (Figure 14). A generalized stratigraphic column is presented in Figure 15.

The site lies on the Nashville Dome, along the axis of the Cincinnati Arch, a broad northeast-trending structural high, where erosion along the breached crest has exposed older, underlying rock in an extensive lowland called the Central Basin. The Central Basin is bounded on all sides by escarpments of the younger overlying rocks. The rolling topography within the Central Basin results from weathering of the limestones and erosion of the residual clay and sand into valleys and hills or knobs.




FIGURE 14. GEOLOGIC SECTION THROUGH THE KENNON SITE




FIGURE 15. GENERALIZED STRATIGRAPHIC COLUMN AT THE KENNON SITE

GERAGHTY & MILLER, INC.

Surficial Material

Unconsolidated weathering residuum overlying bedrock averages 7-ft thick at the site, and ranges from 3 to 12 ft in the 30 monitor wells drilled by GA. Moderately deep sandy, silty, clayey residuum, which is fairly permeable, typically overlies the Hermitage formation, usually in the lower elevations and along Little Harpeth River. In the upland areas, more commonly underlain by Bigby-Cannon limestones, a relatively thin, clayey residuum develops. Permeability is diminished by the clay content and proportionately less water is able to infiltrate the clayey soils. Steeper slopes, common to areas of clayey soils, are naturally more conducive to surface runoff than infiltration.

Bigby-Cannon Formation

Cores recovered from test drilling of the monitor wells into the Bigby-Cannon Formation show a relatively thin-bedded calcarenite, composed of sand-size grains of carbonate rock cemented to form a consolidated limestone. Cross-bedding of the particles is evident, and color varies from light to dark gray through a vertical distance of a few inches or less, due principally to varying content of clay. This appears to be the basal member of the Bigby limestone. Thickness of this unit ranges from 1.9 to 13.5 ft and averages 8 ft in the 7 test holes that penetrated to the Hermitage Formation.

The texture of the rock is relatively open, suggesting

moderate primary permeability. Solution features are common throughout the core samples, particularly in the lighter-colored, less clayey sections and along bedding planes. Secondary permeability through these solution conduits would appear to be very good, particularly horizontal permeability. Cross beds are not extensive, so vertical permeability may be greater than suggested by observation of any one core. Vertical fractures, not seen in the cores, may be present and would also increase the vertical permeability.

Hermitage Formation

The Hermitage Formation underlies the Bigby limestone beneath much of the site, particularly the uplands. In the southern edge of the Kennon property, and along the bed and floodplain of Little Harpeth River, the Bigby has been eroded away and the Hermitage is the uppermost rock unit. The Hermitage, in this area, may be as much as 50 ft thick. The upper Hermitage is a coquina facies, a poorly consolidated deposit of shells that is quite permeable. This facies apparently does not occur at the Kennon site because the ten test holes that penetrated the Hermitage Formation revealed alternate shale and limestone typical of the middle Hermitage "laminated argillaceous limestone facies". This facies, which is reportedly 40 to 75 ft thick is described as silty to sandy limestone with thin shale partings. Core recovered at the site show the Hermitage to be about 50 percent shale, with some shale beds exceeding 1 ft in thickness. This

GERAGHTY & MILLER, INC.

accords with drillers' descriptions of the Hermitage as a confining formation. The basal 5 ft of the Hermitage, the Curdsville limestone member, is a thin-bedded limestone with thin shale partings.

The top of the Hermitage Formation may be an important control of ground-water flow because of the low permeability of the Hermitage shales. Additional data collected during the proposed drilling program will be sufficient to delineate this surface. Although the Hermitage is tentatively considered a confining unit that may well limit the contaminants to the uppermost aquifer, it will be necessary to verify that this is indeed the case.

Carters Limestone

The upper 5 to 10 ft of Carters is thin-bedded, fine-grained to cryptocrystalline limestone with thin shale partings. Immediately below is a dense sticky bentonite clay, the T-3 bed, which is 6 to 12 inches thick. Beneath the T-3 bed, the lower member of the Carters is a very fine-grained to cryptocrystalline thick-bedded limestone with minor mottlings of dolomite and thin bands and lenses of chert locally. Thickness of the lower unit is about 70 ft. The lower unit includes two additional bentonite layers, the T-1 and T-2 beds, that are apparently less distinct than T-3.

The Carters limestone was exposed to erosion prior to deposition of the Hermitage formation and is reported to be

riddled with solution features that provide conduits for ground-water flow. The Carters has yielded 400 gallons per minute (gpm) to wells near Franklin, apparently from solution conduits in the lower unit. (Zurawski and Burchett, 1980). The Carters crops out about 2 miles south of the site in the valley of Mayes Creek and is extensively exposed from there southward.

Lebanon Limestone

The Lebanon limestone is a cryptocrystalline to, occasionally, coarse grained, thin bedded limestone with thin shale partings. The Lebanon is reported to be about 100 ft thick in the study area. The shale beds apparently comprise a confining layer and the Lebanon is considered here to be the base of local ground-water flow.

Structure

Although the rock units in the area are generally flat-lying, local flexures are not uncommon. The valley of the Little Harpeth may be simply erosional; it may have developed along a downward flexure in the underlying rocks; or it may have developed in an area of subsidence or collapse into solution features in the underlying limestone. Examples of all three cases exist within the area.

If the valley is simply erosional, shallow ground water is, most likely, discharging to the banks and bottom of Little Harpeth River from either side. This would be even

more likely if a structural downwarp had initiated erosion of the valley.

Subsidence of the Hermitage into solution cavities in the underlying Carters limestone would likely have resulted in breaching of the confining shale layers and development of vertical flow paths through the Hermitage Formation. Topography of the Little Harpeth Valley suggests that this was probably not the case. There are no closed depressions or steep scarps indicative of collapse.

Joints


Joints are vertical or near-vertical fractures that, in limestone, are commonly enlarged by dissolution of the carbonate rock by downward-percolating water. The enlarged joints become increasingly active conduits for horizontal ground-water flow as well as vertical flow between aquifers. Regional studies in the Nashville area have demonstrated a prominent joint set oriented northwest and another set oriented northeast (Barr, 1961).

A study of air photos of the site reveals linear depressions that may be due to solution enlarged joints in the underlying bedrock. One lineation is the axis of the northeast trending swale in which the disposal pits are located. Another trends northwest, approximately in line with monitor wells W-28 and W-19. The relatively high yields of water from wells W-25 and W-19 may be explained by underlying joints at these locations.

Ground-Water Flow

Ground water moving beneath the Kennon site is recharged from precipitation on the site. Contours of the water table (Figure 16) show that ground-water flow in the uppermost aquifer, the surficial material and Bigby-Cannon limestones, generally follows the topography of the land surface and, most likely, discharges to Little Harpeth River and to springs and seeps in topographically low areas.

The Hermitage Formation is assumed to be a confining bed that isolates shallow ground water at the site from the deeper aquifers, although some vertical leakage may take place. Solutionally-enlarged joints in the Hermitage may provide conduits for vertical movement of water between the Bigby limestone and the Carters. Proposed deep wells are designed to verify whether this is the case, as well as to determine the presence of contaminants, if any, and the rate and direction of flow in the deeper aquifers.



KENNON SITE

Site No. TND 981473575

Reference No. 3

The
Condensed Chemical
Dictionary

TENTH EDITION (1981)

Revised by

GESSNER G. HAWLEY



VAN NOSTRAND REINHOLD COMPANY
NEW YORK CINCINNATI TORONTO LONDON MELBOURNE

cars.
to skin and eyes; causes blis-
ard.

Exists only at low tempera-
f.p. -114°C ; b.p. -20°C ;
tion at normal pressure to
hexachlorobenzene.
carbon tetrachloride vapor
and 10^{-3} mm Hg.
on with carbon; forms phos-
oxygen.

cene (ferrocenyl dichlo-
ne solid; m.p. $93-95^{\circ}\text{C}$.

phenyl)-1,3,5-triazin-2-
 $\text{N}(\text{Cl})_2$.
line solid; m.p. $159-160^{\circ}\text{C}$;

vic. See aniline.

rsine. See chlorovinylidi-

odiphenylmethane. See
oroaniline).

benzoquinone (DDQ)
 $\text{N}(\text{C}(\text{CN}))_2$.

ow-orange solid; m.p. $213-$

oxidizing agent for organic

r. See dichloroethyl ether.

See dichloroethyl formal.

(mustard gas; dichloroethyl
d; b.p. 228°C ; f.p. 14°C ; sp.
 10°F (104°C).

ethylene through sulfur chlo-
tycol and hydrogen chloride.
containing excess sulfur as a

Vesicant war gas; causes
ndness! Can be decontami-
or bleaching powder. Vapor
and can be absorbed through

poison gas; medicine.
Rail) Poison gas label. Not
(Air) Not acceptable.

$(\text{ClCH}_2\text{CH}_2)_2\text{SO}_2$.
ystal $179-181^{\circ}\text{C}$ ($14-15$
cohol, chloroform,
in water.
irritant to eyes and skin.

2,2-dichloro-1,1-difluoroethyl methyl ether (meth-
oxylurane) $\text{HCCl}_2\text{CF}_2\text{OCH}_3$.
Properties: Clear, colorless liquid; fruity odor; b.p.
 104.65°C ; f.p. -35°C ; sp. gr. 1.4223 (25°C); com-
pletely stable in the presence of alkali, air, light, or
moisture. Slightly soluble in water. Combustible.
Grade: N.D.
Use: Anesthetic.

dichlorodifluoromethane (difluorodichlorometh-
ane; fluorocarbon-12). CCl_2F_2 .
Properties: Colorless, odorless, noncorrosive gas.
B.p. -29.8°C ; f.p. -158°C ; critical pressure 43.2
atm. Insoluble in water; soluble in most organic
solvents. Nonflammable.
Derivation: (a) Reaction of carbon tetrachloride and
anhydrous hydrogen fluoride, in the presence of an
antimony halide catalyst; (b) high temperature chlo-
rination of vinylidene fluoride (vinylidene fluorides
made by addition of hydrogen fluoride to acetylene).
Grade: 99.9% min. purity.
Containers: Cylinders.
Hazard: Narcotic in high concentrations. Tolerance,
1000 ppm in air.

Uses: Refrigerant and air conditioner; plastics; blow-
ing agent; low-temperature solvent; leak-detecting
agent; freezing of foods by direct contact; chilling
cocktail glasses.
Shipping regulations: (Rail, Air) Nonflammable Gas
label.
See also chlorofluorocarbon.

1,3-dichloro-5,5-dimethylhydantoin (DDH)
 $\text{CINCONClO}(\text{CH}_3)_2$.

Properties: White powder with mild chlorine odor.
M.p. approximately 130°C ; sublimes about 100°C
without decomposition. Contains approximately
36% active chlorine. Slightly soluble in water with
gradual liberation of hypochlorous acid; soluble in
benzene, chloroform, ethylene dichloride, alcohol.
Combustible, with evolution of chlorine at 210°C .
Derivation: Chlorination of dimethylhydantoin.
Grades: Technical.
Hazard: Toxic by inhalation. Tolerance, 0.2 mg per
cubic meter of air. Skin irritant.
Uses: Household laundry bleach; water treatment;
mild chlorinating agent; pharmaceutical interme-
diate; catalyst.

dichlorodimethylsilane. See dimethyldichlorosilane.

dichlorodiphenyldichloroethane. See TDE.

dichlorodiphenyldichloroethylene. See DDE.

dichlorodiphenyltrichloroethane. See DDT.

1,1-dichloroethane. See ethylidene chloride.

1,2-dichloroethane. See ethylene dichloride.

dichloroether. See dichloroethyl ether.

dichloroethoxymethane. See dichloroethylformal.

1,2-dichloroethyl acetate $\text{CH}_3\text{COOCHClCH}_2\text{Cl}$.
Properties: Water-white liquid. Sp. gr. 1.296 (20°C);
boiling range: $58-65^{\circ}\text{C}$ (13 mm); f.p. $< -32^{\circ}\text{C}$;
refractive index 1.444 (20°C); b.p., dec. Flash point
 307°F (152°C). Combustible. Miscible with alcohol
and ethyl ether. Immiscible with water.
Hazard: Toxic by inhalation.
Use: Organic synthesis.

para-di(2-chloroethyl)aminophenylamine.
See mephalan.

dichloroethylarsine. See ethyldichloroarsine.

dichloroethyl carbonate $(\text{ClH}_2\text{CCH}_2\text{O})_2\text{CO}$.
Properties: Colorless liquid. Slowly hydrolyzed by
alkalies. Volatile in steam. Sp. gr. 1.3506 (20°C);
b.p. 240°C (partial decomposition). Insoluble in
water.
Derivation: By heating ethylene chlorohydrin and
trichloromethylchloroformate together (under re-
flux).

sym-dichloroethylene (1,2-dichloroethylene; acety-
lene dichloride). $\text{ClHC}=\text{CHCl}$. Exists as cis and
trans isomers.

Properties: Colorless, low-boiling liquid. Pleasant
odor. It decomposes slowly on exposure to air, light
and moisture. Soluble in most organic solvents;
slightly soluble in water. Trans-isomer; sp. gr. 1.257;
b.p. $47-49^{\circ}\text{C}$. Cis-isomer; sp. gr. 1.282; b.p. $58-$
 60°C . Flash point 39°F (3.9°C); f.p. -80°C .
Derivation: Two stereoisomeric compounds made by
the partial chlorination of acetylene.
Grades: Technical; as cis, trans, and mixture of both.
Containers: 300-, 550-lb drums.

Hazard: Moderately toxic by ingestion, inhalation
and skin contact; irritant and narcotic in high con-
centrations. Tolerance, 200 ppm in air. Flammable,
dangerous fire hazard.

Uses: General solvent for organic materials; dye
extraction; perfumes; lacquers; thermoplastics;
organic synthesis.

Shipping regulations: (Rail, Air) Flammable Liquid
label.

sym-dichloroethyl ether (dichloroether; dichloro-
ethyl oxide; 2,2'-dichlorodiethyl ether, bis(2-chloro-
ethyl) ether) $\text{ClCH}_2\text{CH}_2\text{OCH}_2\text{CH}_2\text{Cl}$.

Properties: Colorless liquid. Odor like that of ethyl-
ene dichloride. B.p. 178.5°C ; sp. gr. 1.2220 (20 /
 20°C); wt/gal 10.2 lb (20°C); refractive index 1.457
(20°C); flash point (closed cup) 131°F (55°C); f.p.
 -51.8°C . Autoignition temp. 696°F (368°C). Mis-
cible with most organic solvents; insoluble in water.
Combustible.

Derivation: Chlorination of ethyl ether.

Grades: Technical.

Containers: Glass bottles; iron drums; tank cars.

Hazard: Toxic by inhalation and ingestion; absorbed
by skin; strong irritant. Tolerance, 5 ppm in air.
Moderate fire hazard.

Uses: General solvent; selective solvent for produc-
tion of high-grade lubricating oils; textile scouring

KENNON SITE

Site No. TND 981473575

Reference No. 4 SAX

KENNON SITE

Site No. TND 981473575

Reference No. 5

Leipers and Catheys Formations

Limestone, argillaceous, nodular and shaly, medium dark gray to brownish-gray, fine-grained, thin-bedded, fossiliferous, limestone, dark gray weathers to pale yellowish-brown, fine-grained, thin- to medium-bedded, calcarenite, medium light-gray to brownish-gray, coarse-grained, medium-bedded, crossbedded, phosphatic, weathers to brown phosphatic residuum and thin zones of limestone, clayey, medium-gray weathers to light-gray surface, crypto-crystalline, medium-bedded, breaks with conchoidal fracture, present only in the north. At base of formation is shaly limestone or calcareous shale, olive-gray to yellowish-brown, fine-grained, which typically contains large numbers of bryozoans (*Con-sistaria* zone). Thickness 120 to 200 feet.

Obc

Bigby-Cannon Limestone

The Bigby-Cannon Limestone in the Franklin quadrangle consists of three facies—the Cannon limestone, Dove-colored limestone, and Bigby limestone—which replace each other laterally and vertically. The Bigby comprises the upper and lower parts of the formation, whereas the middle part includes all three facies. The formation ranges in thickness from 70 to 130 feet.

Cannon limestone facies is medium dark-gray to brownish-black, microcrystalline to medium-grained, thin- to medium-bedded, evenly bedded. Composite thickness 10 to 40 feet.

Dove-colored limestone facies is medium light-gray to medium-gray (weathers to a characteristic light-gray surface), cryptocrystalline, medium and evenly bedded, brittle, breaks with pronounced conchoidal fracture, contains specks and stringers of clear calcite. Composite thickness 5 to 30 feet.

Bigby limestone facies is calcarenite, medium light-gray to brownish-gray, coarse-grained, medium-bedded, crossbedded, contains brown phosphate pellets, weathers to brown phosphatic residuum. Composite thickness 60 to 100 feet.

Oh

Hermitage Formation

Coquina facies at top is limestone with disseminated silt and shale partings, medium-gray to brownish-gray, medium-bedded, characterized by numerous shells of the brachiopod *Resserella fertilis* (formerly *Dalmanella fertilis*). Thickness 10 to 20 feet.

Laminated argillaceous limestone facies is silty to sandy, medium-gray to dark-gray (weathers to pale to dark yellowish-brown), very fine- to medium-grained, laminated to thin-bedded with thin shale partings. Thickness about 40 to 75 feet.

Curdsville Limestone Member at base is medium- to dark-gray, fine- to medium-grained, thin-bedded with thin shale partings, fossiliferous. Thickness 0 to 5 feet.

Thickness of formation 50 to 100 feet.

Oc

Carters Limestone

Upper member is limestone, medium light-gray to brownish-gray and yellowish-brown, very fine-grained to cryptocrystalline, thin-bedded with thin shale partings. Thickness 5 to 10 feet.

Bentonite (T-3 bed), green when fresh but weathers to white and greenish-yellow sticky clay, 6 to 12 inches thick; occurs between upper and lower members, but rarely seen in natural outcrops. (This is the "Pencil Cave" of drillers' terminology in Central Tennessee.)

Lower member is limestone, medium light-gray to brownish-gray and yellowish-brown, cryptocrystalline to very fine-grained with some beds ranging up to coarse-grained, medium- to thick-bedded, with minor amounts of saccharoidal magnesian limestone as small irregular mottlings, and thin bands and lenses of chert locally. Thickness about 60 to 70 feet.

Olb

Lebanon Limestone


Limestone, medium- to medium dark-gray and brownish-gray to yellowish-brown, cryptocrystalline to very fine-grained with some beds ranging up to coarse-grained, thin-bedded with thin calcareous shale partings, fossiliferous. Maximum exposed thickness about 30 feet.

GEOLOGIC MAP

FRANKLIN QUADRANGLE

TENNESSEE

GM 63-NE



KENNON SITE

Site No. TND 981473575

Reference No. 6

BEDROCK GEOLOGY OF THE NASHVILLE AND MIDDLE TENNESSEE AREA

Copyright 1977
BEAVER ENGINEERING, INC.
Hendersonville, Tennessee

SYSTEM	GROUP	FORMATION	ROCK STRATA	AVERAGE THICKNESS ft.	RANGE OF THICKNESS ft.	GENERALIZED DESCRIPTION OF ROCKS OUTCROPPING IN NASHVILLE AND MIDDLE TENNESSEE.
MISSISSIPPIAN		STE. GENEVIEVE (MONTEAGLE)		250	180-350	STE. GENEVIEVE LIMESTONE: Gray to white limestone, variable bedding thickness, oolitic layers, gray chert near base. Weathers to present ground water table, very cavernous, develops karst topography, weathers to reddish brown clay 20-40 feet thick. Outcrops on Northern Highland Rim.
		ST. LOUIS		180	100-280	ST. LOUIS FORMATION: Brownish gray cherty limestone, thick bedded to massive, numerous gray to black chert beds and nodules. Weathers deep to present ground water table, develops karst topography, weathers to reddish brown clay about 20 feet thick. Outcrops on Highland Rim.
		WARSAW		100	40-150	WARSAW LIMESTONE: Gray, cross bedded limestone, massive, fine grained, some chert. Weathers deep but sinkhole development not as intense as St. Louis Formation. Sandy and shaley facies near base. Weathers to reddish brown clay about 20 feet deep. Outcrops on Highland Rim.
		FT. PAYNE		250	200-400	FORT PAYNE FORMATION: Dark gray siltstone, shale, and cherty limestone. Thin beds of crinoidal limestone, green shale at base (Maury Shale), contains phosphate nodules. Weathers to residual cherty clay about 15 feet deep. Outcrops along Highland Rim and higher hills within Central Basin. Excellent road metal.
		CHATTANOOGA		20	10-70	CHATTANOOGA SHALE: Dark grayish black fissile, carbonaceous shale, thin sandstone at base. Weathers to light buff clay. Outcrops on Highland Rim and on higher hills within Central Basin. Widely used by geologists as a mapping unit, both in surface and subsurface.
DEVONIAN		PEGRAM		17	0-30	PEGRAM FORMATION: Light gray limestone, massive. Minor amounts of light gray shale and sandstone in lower portion. Outcrops mainly in the Kingston Springs area.
		CAMDEN		95	0-220	CAMDEN FORMATION: Thin to medium bedded blue gray, shaley limestone containing nodules and bands of chert. Chert beds average 6 to 12 inches thick and are separated by white clay partings. Weathers to thin residual soil less than three feet thick then a thicker weathered layer of angular blocks and sharp fragments of chert rubble. Very difficult to drill or excavate with conventional excavation equipment. Outcrops mainly in Benton, Decatur, and Perry counties. Chert beds are used locally as road metal and ballast.
		FLAT GAP		20	0-55	FLAT GAP LIMESTONE: Light gray and pink limestone, occasionally glauconitic in upper part. Outcrops in extreme western counties of Highland Rim. Very good concrete aggregate.
		ROSS		45	0-110	ROSS FORMATION: Alternating facies of thin limestone and thick shales. Shales are blue or greenish gray. Limestones weather to glades and shales generally do not have slope stability on steep road cuts.
		SEQUATCHIE		55	0-275	SILURIAN SYSTEM: Extremely variable in outcrop and thickness. Major unconformity extends from base of Mississippian System through Devonian and Silurian Systems. Silurian is predominantly limestone and shaley limestone. See Tennessee Division Geology Bulletin 56 for complete description.
SILURIAN		DECATUR		VARIABLE	0-250	SEQUATCHIE FORMATION: Greenish gray, massive mudstone with some sand, shale, and limestone. Contains Mannie Shale facies which is a green calcareous shale that weathers into laminated cobbles of green silt. Outcrops mostly in Lincoln, Franklin, and Marion Counties. Contains Fernvale Limestone facies, which is an irregular bedded massive limestone containing enough limonite to be a low grade iron ore.
		BROWNSPORT				LEIPERS FORMATION: Dark blue gray, earthy, nodular limestone. Thin beds of limestone separated by shale mudstone and siltstone beds from a few inches to 10 feet thick. Weathers to light brown silty clay soil 3 to 5 feet thick. Weathering along fractures and faults can penetrate 20 feet into rock mass. Outcrops mostly along edge of Central Basin.
	WAYNE					INMAN FORMATION: Greenish gray calcareous shale interbedded with thin beds of dense limestone. Weathers to thin clay soil. Outcrops in southeastern part of Middle Tennessee is a very restricted outcrop belt.
		BRASSFIELD				CATHEYS FORMATION: A complex mixture of shaley limestone units. Typically it is thin bedded, blue gray nodular limestone interbedded with thin partings of shale and siltstone. Weathers to thin silty clay soil usually 3 to 4 feet thick. Outcrops extensively in Central Basin.
		SEQUATCHIE				BIGBY CANNON LIMESTONE: Composed of 3 facies: (1) the Bigby facies is blue gray, massive, granular, cross bedded, and phosphatic; (2) Dove facies is a light gray (Dove colored) dense fine grained limestone; (3) Cannon facies is blue gray limestone, massive but non-phosphatic. All facies weather to reddish-brown clay usually less than 10 feet thick. Some sinkhole development and considerable deep weathering along vertical fractures. Outcrops in Central Basin. Mined for phosphate in several counties of Central Basin.
ORDOVICIAN		SEQUATCHIE		70	0-160	HERMITAGE FORMATION: Variable rock units consisting of thin-bedded, dark blue-gray shaley limestone and sandy limestone in northwest part of Central Basin. Persistent layer of shale and phosphatic shale in central part of Central Basin. Silty shale and nodular limestone in south part of Central Basin. Weathers to a silty and sandy clay up to 20 feet thick. Outcrops extensively in Central Basin.
		MAYSVILLE		50	0-70	CARTERS LIMESTONE: Contains upper and lower member separated by T ¹ bentonite clay. Upper member is thin bedded, light gray shaley limestone about 10 feet thick. Lower member is massive, light gray, fine grained limestone about 50 feet thick and contains T ¹ and T ² bentonite clays. Weathers to brown plastic clay about 4 feet thick with some sink holes. Outcrops extensively in Central Basin.
		EDEN		130	10-250	LEBANON LIMESTONE: Blue-gray, dense, fine-grained, thin-bedded limestone. Bedding planes contain thin shale layers, weathers to loose slabs of limestone with very little residual soil. Forms cedar glades and has worm-eaten appearance. Outcrops in central part of Central Basin.
	NASHVILLE	CATHEYS		80	50-100	
		BIGBY CANNON		120	70-180	
ORDOVICIAN		HERMITAGE		60	37-93	
		CARTERS				

KENNON SITE

Site No. TND 981473575

Reference No. 7



United States Department of the Interior

GEOLOGICAL SURVEY
Water Resources Division
Tennessee District

A-413 Federal Bldg.
U.S. Courthouse
Nashville, TN 37203
February 19, 1987

Mr. Todd Hughes
Tennessee Department of Health
and Environment
Customs House - 4th Floor
701 Broadway
Nashville, TN 37219-5403

94-508(1)

Dear Todd:

We have completed observation well installations and logging for the Genesco Hazardous Waste Site Investigation. Enclosed please find tables of data on the new wells and a sample resistivity log. We are completing a first draft of a basic data report on the site study, but we thought that both you and Geraghty and Miller would like to have preliminary copies of this data. If you approve, let me know and I'll route copies to Don Brice of Geraghty and Miller.

Sincerely yours,

FOR THE DISTRICT CHIEF

Roger W. Lee

Enclosure

LOCAL WELL NUMBER	LATITUDE (DEGREES)	LONGITUDE (DEGREES)	ALTITUDE OF LAND SURFACE (FEET)	DATE WELL CONSTRUCTED	DEPTH OF WELL, (FEET)
WM:N-020	355809	0864626	740	10-18-84	350
WM:N-022	355805	0864627	710	05-01-81	158
WM:N-023	355756	0864625	720	08-14-85	1050
WM:N-024	355724	0864617	750	06-27-84	240
WM:N-033	355707	0864509	830	08-17-74	150
WM:N-038	355706	0864431	890	--	175
WM:N-039	355712	0864539	766.9	11-03-78	220
WM:N-040	355723	0864614	760	--	350
WM:N-041	355700	0864544	780.1	06-23-86	45.0
WM:N-041A	355700	0864544	780	09-23-86	225
WM:N-042	355701	0864557	754.0	06-23-86	35.0
WM:N-042A	355701	0864557	753.8	09-22-86	193
WM:N-043	355720	0864606	737.6	06-24-86	28.0
WM:N-043A	355720	0864606	738.4	10-07-86	102
WM:N-044	353718	0864610	744.1	06-25-86	34.1
WM:N-044A	353718	0864610	738.8	10-07-86	102
WM:N-045	355723	0864533	812.6	06-26-86	49.0
WM:N-045A	355723	0864532	812.6	10-10-86	167
WM:N-046	355732	0864602	758.0	06-30-86	30.0
WM:N-046A	355732	0864602	758.7	10-09-86	135
WM:N-047	355738	0864551	762.4	07-01-86	20.0
WM:N-047A	355738	0864551	759.9	10-09-86	162
WM:N-048	355733	0864540	806.4	07-01-86	45.0
WM:N-048A	355733	0864540	808.8	10-10-86	152
WM:N-050	355748	0864551	785.9	07-04-86	45.0
WM:N-050A	355748	0864551	786.8	10-08-86	162
WM:N-051	355745	0864601	754.1	07-05-86	25.0
WM:N-051A	355745	0864601	754.8	10-08-86	137
WM:N-052	355715	0864621	791.8	07-07-86	35.0
WM:N-052A	355715	0864621	792.9	10-06-86	132
WM:N-053	355654	0864550	795.8	07-08-86	55.0
WM:N-053A	355654	0864550	798.4	09-24-86	203
WM:N-054	355710	0864541	759.8	07-10-86	30.0
WM:N-054A	355710	0864541	760.3	10-13-86	139
WM:N-055	355714	0864545	757.8	07-11-86	30.0
WM:N-055A	355714	0864545	758.6	10-13-86	177
WM:N-056	355729	0864618	775	01-09-87	45.0
WM:N-056A	355729	0864618	775	01-12-87	175
WM:N-057	355713	0864552	795	01-07-87	57.0
WM:N-057A	355713	0864552	795	01-08-87	204
WM:N-058	355711	0864631	760	01-08-87	35.0
WM:N-058A	355711	0864631	760	01-09-87	165

LOCAL WELL NUMBER	DEPTH OF WELL (FEET)	BOTTOM OF CASING (FEET)	WATER- LEVEL DATE	WATER LEVEL (FEET)
WM:N-020	350	21.0	--	--
WM:N-022	158	20.0	--	--
WM:N-023	1050	20.0	--	--
WM:N-024	240	21.0	--	--
WM:N-033	150	--	--	--
WM:N-038	175	--	--	--
WM:N-039	220	20.0	--	--
WM:N-040	350	--	--	--
WM:N-041	45.0	10.0	02-05-87	10.05
WM:N-041A	225	62.0	02-05-87	39.13
WM:N-042	35.0	10.7	02-05-87	16.06
WM:N-042A	193	34.0	02-05-87	15.76
WM:N-043	28.0	5.00	02-05-87	25.53
WM:N-043A	102	15.0	02-05-87	9.27
WM:N-044	34.1	5.00	02-05-87	10.06
WM:N-044A	102	20.0	02-05-87	9.57
WM:N-045	49.0	--	02-05-87	30.94
WM:N-045A	167	59.0	02-05-87	71.46
WM:N-046	30.0	4.50	02-05-87	4.98
WM:N-046A	135	15.0	02-05-87	29.57
WM:N-047	20.0	3.10	02-05-87	5.92
WM:N-047A	162	17.0	02-05-87	35.83
WM:N-048	45.0	6.00	--	--
WM:N-048A	152	41.0	02-05-87	71.81
WM:N-050	45.0	10.0	02-05-87	11.70
WM:N-050A	162	55.0	02-05-87	80.82
WM:N-051	25.0	8.70	02-05-87	11.63
WM:N-051A	137	34.0	02-05-87	36.46
WM:N-052	35.0	19.5	02-05-87	19.50
WM:N-052A	132	33.0	02-05-87	57.94
WM:N-053	55.0	10.0	02-05-87	35.09
WM:N-053A	203	41.0	02-05-87	63.79
WM:N-054	30.0	4.50	02-05-87	2.69
WM:N-054A	139	32.0	02-05-87	17.85
WM:N-055	30.0	5.80	02-05-87	14.32
WM:N-055A	177	26.0	02-05-87	18.03
WM:N-056	775	20.0	02-05-87	22.54
WM:N-056A	775	67.0	02-05-87	113.29
WM:N-057	795	9.0	02-05-87	--
WM:N-057A	795	57.0	02-05-87	50.74
WM:N-058	760	12.5	02-05-87	16.51
WM:N-058A	760	35.0	02-05-87	16.97

WM:N-020

↓

040

are domestic wells.

No W/L Data

obtained

W/L referenced to
depth below land
surface.

WM:N-057 is a
flowing well w/
head > 10' above
land surface.

TABLE 1
CONSTRUCTION & STATUS OF DOMESTIC WELLS

WELL OWNER	DATE COMPLETED	CASING DIAM. (IN)	DEPTH OF CASING (FT)	TOTAL DEPTH (FT)	OPEN INTERVAL FORMATION	PRINCIPLE WATER BEARING ZONE (DEPTH FT)	STATUS	DRILLER
Allen				68-80			Residential	
Beyer	04/05/69	7	20	200	B,H,C	195	Residential	Henry Drilling Co.
Boswell	08/14/85	6.25	20	1050	H,,L,R,P,M,K	1020	Residential	Henry Drilling Co.
Genny	10/18/84	6.25	21	350	H,C,L	277	Residential	Henry Drilling Co.
Fischer	06/27/84	6.25	21	240	H,C,L	70, 110	Residential	Henry Drilling Co.
Fletcher (1)				200	H,C,L	115-117	Residential	Henry Drilling Co.
Fletcher (2)				198	H,C,L	23, 115-116	Residential	Henry Drilling Co.
Foster (1)	08/08/85	6.25	20	260	H,C,L	146	Heat Pump	Henry Drilling Co.
Foster (2)	05/22/84	6.25	21	450	H,C,L,R	230	Residential	Henry Drilling Co.
Gore	06/04/70	6	20	75	H	65	Residential	
Holt		6	25	36	B	36	Residential	Henry Drilling Co.
Hall	03/03/86	6.25	24	400	H,C,L	80	Residential	
Howe				220	H,C,L	130	Residential	
Johnson	12/30/72	6	20	198	H,C	184	Residential	
Levine (1)	08/17/74	6	22	1235	H,C,L,R,P,M,K	1170	Residential	
Levine (2)				2200	H,C,L,R,P,M,K		Residential	
Myatt				73	H	18	Residential	
Legieza						28	Residential	
Mallory				350	H,C,L,R	112	Non-Potable	Berman Clark Water Wells
Pawitt	09/16/81	6.25	21	105	H,C	105	Residential	
Sullivan						28	Residential	
Wilson	02/28/84	6.25	21	260	B,H,C	160	Residential	Henry Drilling Co.

B = Bigby-Cannon Formation R = Ridley Formation
 H = Hermitage Formation P = Pierce Formation
 C = Carters Formation M = Murfreesboro Formation
 L = Lebanon Formation K = Knox Group

Information Provided by TUE, Division of Ground Water Protection.

KENNON SITE

Site No. TND 981473575

Reference No. 8

1304 H. Stone Road, Suite 333
Nashville, TN 37215
615 383-3588

Engineering, Design & Construction Group, Inc.

442068

EDGE

March 19, 1986

Mr. Ronnie Bowers
Environmental Specialist/Chemist
Tennessee Division of Superfund
Customs House, Fourth Floor
701 Broadway
Nashville, TN 37219-5403

Re: Kennon Property
Analytical Results
Revised Well Sampling Plan

Dear Mr. Bowers:

Pursuant to our telephone conversation of March 18, 1986, I have enclosed a copy of our revised (3/14/86) Well Sampling Plan.

I have also enclosed copies of the analytical results obtained from the samples collected on February 21, 1986. To aid in identification of the samples, a copy of the obverse of the custody tag is attached to the respective analytical report.

As we discussed, the samples from wells 4, 5 and 6 had acetone present at low concentrations with no detectable concentrations of any of the other suspected solvents. These three wells are upgradient of the disposal site. The test pit data showed the presence of acetone in the disposal site but acetone was not the dominant solvent. Thus, the presence of acetone in wells 4, 5 and 6 is currently an unresolved issue but our investigation is continuing. I am convinced that acetone is not selectively migrating upgradient from the site to wells 4, 5 and 6. These comments are offered to reinforce my verbal comments and to caution against undue concern.

During our telephone conversation you requested additional information/data which will be provided in the very near future. Also, I would appreciate your sending to me all analytical data the

Subsidiaries:
Geologic Associates
MCI Consulting Engineers

Engineering, Design & Geosciences Group, Inc.


Mr. Ronnie Bowers
March 19, 1986
Page 2

State has obtained in its sampling efforts. Such data could be of great value in our assessment activities.

Your continued cooperation in this very complex issue is greatly appreciated.

Very truly yours,

ENGINEERING, DESIGN &
GEOSCIENCES GROUP, INC.


V. Wayne McCoy

VWM/11s
Enclosures: 2
cc: Ralph Mosely (with enclosures)




FIGURE 9. MONITOR WELLS AND DISPOSAL PITS

Engineering Division Geosciences Group, Inc.

EDGE

WELL SAMPLING PLAN
Kennon Property, Williamson County

- Starting with the upgradient wells, the wells should all be purged as follows:
 - Determine water elevation and record time and date of elevation determination.
 - Determine volume of water in well and purge by pump or bailer three volumes if possible. Record the date of purging and the starting and ending time of purging. Also, measure and record the total volume of water purged.
- Starting with the upgradient wells, the wells should be sampled by the following guidelines:
 - Attempt to sample within 24 hours of purging.
 - Sample, starting with upgradient wells, the deep wells before sampling any of the shallow wells.
 - Record water elevation prior to sampling.
 - A teflon bailer should be used to collect samples. Before each well sampling the bailer should be equipped with a clean, unused rope.
- Initially and before each well sampling, the bailer should be cleaned as follows:
 - Scrub using detergent.
 - Thoroughly rinse with deionized or distilled water until all soap and other residue is removed.
 - Rinse with reagent grade isopropyl alcohol, taking care to avoid allowing isopropyl alcohol to contact the bailer rope.
 - Following the isopropyl alcohol rinse, triple rinse the bailer with deionized or distilled water to remove the isopropyl alcohol.
- Sampling personnel use new disposable gloves prior to each well sampling.
- Since contaminants of concern may be heavier than water and are only slightly soluble in water, lower teflon bailer to bottom of well to collect sample.
- Collect and discard two (2) bailers of well water; the third bailer of well water should be used for the actual sample.
- Transfer sample from bailer to volatile organics vial with minimum of agitation and such that there are no entrained air bubbles.
- Collect duplicate samples from one well of each ten (10) wells sampled.
- Complete chain of custody card and attach to sample container, also label sample container.
- Keep samples chilled until delivery to laboratory.

206594

4000 E. BROADWAY
NASHVILLE, TENN. 37203

Plant No.

SAMPLE IDENTIFICATION AND CUSTODY TAG

1. Source of Sample and COMPLETE Sample Identification ELABORATE

Well # Pond

2. County Williamson Nearest Town or City Brentwood

3. Type of Sample WATER

4. Date Collected 2/21/86 Time Collected 10:00 AM

5. Name of Sampler (Please Print) Mark Hobbs

6. Names of Others Present at Time Sample Collected


7. Field No. # 3 Approximate Vol. of Sample 40 ml

8. Describe field collection procedure and special handling or preservation of this sample

WATER - AS PER PROJECT PROTOCOL

9. Describe how sample conveyed or transported to the laboratory PERSONAL TRUCK

10. Requested Analyses



WATER POND FILL# 3

0296594

296594

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

RECEIVED

02/21/86

10:00

02/21/86

CLIENT LAB NO.

REPORTED

GENESCO, INC., EMP. & ENV. SAFET

00000

03/04/86

TEST

RESULT

REFERENCE LIMITS


UNITS

VOLATILE ORGANICS

ACROLEIN	<0.10	PPM
ACRYLONITRILE	<0.10	PPM
BENZENE	<0.010	PPM
BIS(CHLORMETHYL)ETH	<0.010	PPM
BROMOFORM	<0.010	PPM
CARBON TETRACHLORIDE	<0.010	PPM
CHLOROBENZENE	<0.010	PPM
CHLORODIBROMETHANE	<0.010	PPM
CHLOROETHANE	<0.010	PPM
2-CLETHYVINYL ETHER	<0.010	PPM
CHLOROFORM	<0.010	PPM
DI-CL-BR-METHANE	<0.010	PPM
DI-CL-DI-F-METHANE	<0.010	PPM
1,1-DICHLOROETHANE	<0.010	PPM
1,2-DICHLOROETHANE	<0.010	PPM
1,1-DI-CL-ETHYLENE	<0.010	PPM
1,2-DICHLOROPROPANE	<0.010	PPM
1,2-DI-CL-PROPYLENE	<0.010	PPM
ETHYLBENZENE	<0.010	PPM
METHYL BROMIDE	<0.010	PPM
METHYL CHLORIDE	<0.010	PPM
METHYLENE CHLORIDE	<0.010	PPM
1,1,2,2 TET CL ETHAN	<0.010	PPM
TETRACHLOROETHYLENE	<0.010	PPM
TOLUENE	<0.010	PPM
1,2-DICHLOROETHYLENE	<0.010	PPM
1,1,1-TRI-CL-ETHANE	<0.010	PPM
1,1,2-TRI-CL-ETHANE	<0.010	PPM
TRICHLOROETHYLENE	<0.010	PPM
TRI-CL-F-METHANE	<0.010	PPM
VINYL CHLORIDE	<0.010	PPM
2-BUTANONE	<0.10	PPM
HEXANE	<0.10	PPM
ACETONE	<0.10	PPM
ETHYL ACETATE	<0.10	PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So - Nashville, TN 37203
Phone 1-615-255-5786

SAMPLE IDENTIFICATION AND CUSTODY TAG

1. Source of Sample and COMPLETE Sample Identification GENESCO
Well # Pond sediment
2. County Williamson Nearest Town or City BRENTWOOD
3. Type of Sample WATER
4. Date Collected 2/21/86 Time Collected 9:53
5. Name of Sampler (Please Print) MARK HOBBS
6. Names of Others Present at Time Sample Collected
7. Field No # 2 Approximate Vol. of Sample 200 ml
8. Describe field collection procedure and special handling or preservation of this sample
WATER - AS PER PROJECT PROTOCOL
9. Describe how sample conveyed or transported to the laboratory PERSONAL TRUCK
10. Requested Analyses

POND SEDIMENT FIELD #2

0296599

296599

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

RECEIVED

02/21/86

09: 58

02/21/86

CLIENT LAB NO.

REPORTED

GENESCO, INC., EMP. & ENV. SAFET

00000

03/04/86

TEST

RESULT

REFERENCE LIMITS


UNITS

VOLATILE ORGANICS

ACROLEIN	<0.100	PPM
ACRYLONITRILE	<0.100	PPM
BENZENE	<0.050	PPM
BIS(CHLOROMETHYL)ETH	<0.050	PPM
BROMOFORM	<0.050	PPM
CARBON TETRACHLORIDE	<0.050	PPM
CHLOROBENZENE	<0.050	PPM
CHLORODIBROMETHANE	<0.050	PPM
CHLOROETHANE	<0.050	PPM
2-CLETHYVINYL ETHER	<0.050	PPM
CHLOROFORM	<0.050	PPM
DI-CL-BR-METHANE	<0.050	PPM
DI-CL-DI-F-METHANE	<0.050	PPM
1,1-DICHLOROETHANE	<0.050	PPM
1,2-DICHLOROETHANE	<0.050	PPM
1,1-DI-CL-ETHYLENE	<0.050	PPM
1,2-DICHLOROPROPANE	<0.050	PPM
1,2-DI-CL-PROPYLENE	<0.050	PPM
ETHYLBENZENE	<0.050	PPM
METHYL BROMIDE	<0.050	PPM
METHYL CHLORIDE	<0.050	PPM
METHYLENE CHLORIDE	<0.050	PPM
1,1,2,2 TET CL ETHAN	<0.050	PPM
TETRACHLOROETHYLENE	<0.050	PPM
TOLUENE	<0.050	PPM
1,2-DICHLOROETHYLENE	<0.050	PPM
1,1,1-TRI-CL-ETHANE	<0.050	PPM
1,1,2-TRI-CL-ETHANE	<0.050	PPM
TRICHLOROETHYLENE	<0.050	PPM
TRI-CL-F-METHANE	<0.050	PPM
VINYL CHLORIDE	<0.050	PPM
2-BUTANONE	<0.10	PPM
HEXANE	<0.10	PPM
ACETONE	<0.10	PPM
ETHYL ACETATE	<0.10	PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

ENGINEERING, DESIGN & GEOSCIENCES GROUP, INC.

4001 HILLSBORO ROAD, SUITE 1135

NASHVILLE, TENNESSEE 37215

(Lab No

SAMPLE IDENTIFICATION AND CUSTODY TAG

- 96598
1. Source of Sample and COMPLETE Sample Identification GENESCO
6001 # 100's adjacent to Hackett property, located approx. 50 yards
upstream from Wilson Pike
 2. County Williamson Nearest Town or City Brentwood
 3. Type of Sample WATER
 4. Date Collected 2/21/96 Time Collected 10:46
 5. Name of Sampler (Please Print) MARK HOBBS
 6. Names of Others Present at Time Sample Collected W. McCoy, State Representative
 7. Field No. # 6 Approximate Vol. of Sample 200 ml
 8. Describe field collection procedure and special handling or preservation of this sample
WATER - AS PER PROJECT PROTOCOL
 9. Describe how sample conveyed or transported to the laboratory PERSONAL TRUCK
 10. Requested Analyses

DITCH-HACKETT PROPERTY FIELDS

029659B

29659B

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

RECEIVED

02/21/86

10:46

02/21/86

CLIENT LAB NO.

REPORTED

GENESCO, INC., EMP. & ENV. SAFET

00000

03/04/86

TEST

RESULT

REFERENCE LIMITS

UNITS

VOLATILE ORGANICS

ACROLEIN	<0.100	PPM
ACRYLONITRILE	<0.100	PPM
BENZENE	<0.050	PPM
BIS(CHLOROMETHYL)ETH	<0.050	PPM
BROMOFORM	<0.050	PPM
CARBON TETRACHLORIDE	<0.050	PPM
CHLOROBENZENE	<0.050	PPM
CHLORODIBROMETHANE	<0.050	PPM
CHLOROETHANE	<0.050	PPM
2-CLETHYVINYL ETHER	<0.050	PPM
CHLOROFORM	<0.050	PPM
DI-CL-BR-METHANE	<0.050	PPM
DI-CL-DI-F-METHANE	<0.050	PPM
1,1-DICHLOROETHANE	<0.050	PPM
1,2-DICHLOROETHANE	<0.050	PPM
1,1-DI-CL-ETHYLENE	<0.050	PPM
1,2-DICHLOROPROPANE	<0.050	PPM
1,2-DI-CL-PROPYLENE	<0.050	PPM
ETHYLBENZENE	<0.050	PPM
METHYL BROMIDE	<0.050	PPM
METHYL CHLORIDE	<0.050	PPM
METHYLENE CHLORIDE	<0.050	PPM
1,1,2,2 TET CL ETHAN	<0.050	PPM
TETRACHLOROETHYLENE	<0.050	PPM
TOLUENE	<0.050	PPM
1,2-DICHLOROETHYLENE	<0.050	PPM
1,1,1-TRI-CL-ETHANE	<0.050	PPM
1,1,2-TRI-CL-ETHANE	<0.050	PPM
TRICHLOROETHYLENE	<0.050	PPM
TRI-CL-F-METHANE	<0.050	PPM
VINYL CHLORIDE	<0.050	PPM
2-BUTANDNE	<0.10	PPM
HEXANE	<0.10	PPM
ACETONE	<0.10	PPM
ETHYL ACETATE	<0.10	PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So - Nashville, TN 37203
Phone 1-615-255-5786

ENGINEERING, DESIGN & GEOSCIENCES GROUP, INC.

4800 HILLSBORO ROAD, SUITE 333

NASHVILLE, TENNESSEE 37215

(Lab No. _____)

296590
SAMPLE IDENTIFICATION AND CUSTODY TAG

1. Source of Sample and COMPLETE Sample Identification GENESCO
Well #3
2. County Williamson Nearest Town or City BRENTWOOD
3. Type of Sample WATER
4. Date Collected 2/21/86 Time Collected 11:56 AM
5. Name of Sampler (Please Print) MARK HOBBS
6. Names of Others Present at Time Sample Collected _____
7. Field No. #56 Approximate Vol. of Sample 40 ml
8. Describe field collection procedure and special handling or preservation of this sample
WATER - AS PER PROJECT PROTOCOL
9. Describe how sample conveyed or transported to the laboratory PERSONAL TRUCK
10. Requested Analyses _____

WATER WELL #3 FIELD #8

0296590

296590

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

RECEIVED

02/21/86

11:56

02/21/86

CLIENT LAB NO.

REPORTED

GENESCO, INC., EMP. & ENV. SAFET

00000

03/04/86

TEST

RESULT

REFERENCE LIMITS


UNITS

VOLATILE ORGANICS

ACROLEIN	<0.10	PPM
ACRYLONITRILE	<0.10	PPM
BENZENE	<0.010	PPM
BIS(CHLOROMETHYL)ETH	<0.010	PPM
BROMOFORM	<0.010	PPM
CARBON TETRACHLORIDE	<0.010	PPM
CHLOROBENZENE	<0.010	PPM
CHLORODIBROMETHANE	<0.010	PPM
CHLOROETHANE	<0.010	PPM
2-CHLOROVINYL ETHER	<0.010	PPM
CHLOROFORM	<0.010	PPM
DI-CL-BR-METHANE	<0.010	PPM
DI-CL-DI-F-METHANE	<0.010	PPM
1,1-DICHLOROETHANE	<0.010	PPM
1,2-DICHLOROETHANE	<0.010	PPM
1,1-DI-CL-ETHYLENE	<0.010	PPM
1,2-DICHLOROPROPANE	<0.010	PPM
1,2-DI-CL-PROPYLENE	<0.010	PPM
ETHYLBENZENE	<0.010	PPM
METHYL BROMIDE	<0.010	PPM
METHYL CHLORIDE	<0.010	PPM
METHYLENE CHLORIDE	<0.010	PPM
1,1,2,2 TET CL ETHAN	<0.010	PPM
TETRACHLOROETHYLENE	<0.010	PPM
TOLUENE	<0.010	PPM
1,2-DICHLOROETHYLENE	<0.010	PPM
1,1,1-TRI-CL-ETHANE	<0.010	PPM
1,1,2-TRI-CL-ETHANE	<0.010	PPM
TRICHLOROETHYLENE	<0.010	PPM
TRI-CL-F-METHANE	<0.010	PPM
VINYL CHLORIDE	<0.010	PPM
2-BUTANONE	<0.10	PPM
HEXANE	<0.10	PPM
ACETONE	<0.10	PPM
ETHYL ACETATE	<0.10	PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. Nashville, TN 37203
Phone 1-615-255-5786

ENGINEERING, DESIGN & GEOSCIENCES GROUP, INC.

4201 HILLSBORO ROAD, SUITE 333

NASHVILLE, TENNESSEE 37215

(Lab No

593

SAMPLE IDENTIFICATION AND CUSTODY TAG

1. Source of Sample and COMPLETE Sample Identification GENCO
Well # 7 SHALLOW
2. County WILLIAMSON Nearest Town or City BRENTWOOD
3. Type of Sample WATER
4. Date Collected 2/21/96 Time Collected 1:01 PM
5. Name of Sampler (Please Print) MARK HOBBS
6. Names of Others Present at Time Sample Collected
7. Field No. # 14 Approximate Vol. of Sample 40ml
8. Describe field collection procedure and special handling or preservation of this sample
WATER - AS PER PROJECT PROTOCOL
9. Describe how sample conveyed or transported to the laboratory PERSONAL TRUCK
10. Requested Analyses

REFERRING CLIENT

DATE COLLECTED

02/21/86

TIME COLLECTED

13:07

RECEIVED

02/21/86

GENESCO, INC., EMP. & ENV. SAFET

CLIENT LAB NO.

00000


REPORTED

03/05/86

TEST	RESULT	REFERENCE LIMITS	UNITS
XYLENE	2.00		PPM
VOLATILE ORGANICS			
ACROLEIN	<0.100		PPM
ACRYLONITRILE	<0.100		PPM
BENZENE	<0.010		PPM
BIS(CHLOROMETHYL)ETH	<0.010		PPM
BROMOFORM	<0.010		PPM
CARBON TETRACHLORIDE	<0.010		PPM
CHLOROBENZENE	<0.010		PPM
CHLORODIBROMETHANE	<0.010		PPM
CHLOROETHANE	<0.010		PPM
2-CLETHYVINYL ETHER	<0.010		PPM
CHLOROFORM	<0.010		PPM
DI-CL-BR-METHANE	<0.010		PPM
DI-CL-DI-F-METHANE	<0.010		PPM
1-1-DICHLOROETHANE	<0.010		PPM
1,2-DICHLOROETHANE	5.700		PPM
1,1-DI-CL-ETHYLENE	<0.010		PPM
1,2-DICHLOROPROPANE	<0.010		PPM
1,2-DI-CL-PROPYLENE	<0.010		PPM
ETHYLBENZENE	<0.010		PPM
METHYL BROMIDE	<0.010		PPM
METHYL CHLORIDE	<0.010		PPM
METHYLENE CHLORIDE	12.5		PPM
1,1,2,2 TET CL ETHAN	<0.010		PPM
TETRACHLOROETHYLENE	6.5		PPM
TOLUENE	359.7		PPM
1,2-DICHLOROETHYLENE	0.622		PPM
1,1,1-TRI-CL-ETHANE	15.1		PPM
1,1,2-TRI-CL-ETHANE	<0.010		PPM
TRICHLOROETHYLENE	1.00		PPM
TRI-CL-F-METHANE	<0.010		PPM
VINYL CHLORIDE	<0.010		PPM
2-BUTANONE	6.91		PPM
HEXANE	<0.10		PPM
ACETONE	2.97		PPM
ETHYL ACETATE	<0.10		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

290585

ENGINEERING, DESIGN & GEOSCIENCES GROUP, INC.

4301 HILLSBORO ROAD, SUITE 333

NASHVILLE, TENNESSEE 37215

(Lab No.)

SAMPLE IDENTIFICATION AND CUSTODY TAG

1. Source of Sample and COMPLETE Sample Identification GENESCO
WELL # 7 3M9400
2. County Williamson Nearest Town or City Brentwood
3. Type of Sample WATER
4. Date Collected 2/21/96 Time Collected 1:07 PM
5. Name of Sampler (Please Print) MARK HOBBS
6. Names of Others Present at Time Sample Collected
7. Field No. # 13 Approximate Vol. of Sample 40 ml
8. Describe field collection procedure and special handling or preservation of this sample
WATER - AS PER PROJECT PROTOCOL
9. Describe how sample conveyed or transported to the laboratory PERSONAL TRUCK
10. Requested Analyses

WATER WELL #7 SHALLOW FIELD NO. 13

DOCUMENT NUMBER
0296585

296585

REFERRING CLIENT

DATE COLLECTED
02/21/86TIME COLLECTED
13:07RECEIVED
02/21/86


GENESCO, INC., EMP. & ENV. SAFET

CLIENT LAB NO.
00000REPORTED
03/05/86

TEST	RESULT	REFERENCE LIMITS	UNITS
XYLENE	1.8		PPM
VOLATILE ORGANICS			
ACROLEIN	<0.100		PPM
ACRYLONITRILE	<0.100		PPM
BENZENE	<0.010		PPM
BIS(CHLOROMETHYL)ETH	<0.010		PPM
BROMOFORM	<0.010		PPM
CARBON TETRACHLORIDE	<0.010		PPM
CHLOROBENZENE	<0.010		PPM
CHLORODIBROMETHANE	<0.010		PPM
CHLOROETHANE	<0.010		PPM
2-CLETHYVINYL ETHER	<0.010		PPM
CHLOROFORM	<0.010		PPM
DI-CL-BR-METHANE	<0.010		PPM
DI-CL-DI-F-METHANE	<0.010		PPM
1-1-DICHLOROETHANE	<0.010		PPM
1,2-DICHLOROETHANE	5.300		PPM
1,1-DI-CL-ETHYLENE	<0.010		PPM
1,2-DICHLOROPROPANE	<0.010		PPM
1,2-DI-CL-PROPYLENE	<0.010		PPM
ETHYLBENZENE	<0.010		PPM
METHYL BROMIDE	<0.010		PPM
METHYL CHLORIDE	<0.010		PPM
METHYLENE CHLORIDE	10.800		PPM
1,1,2,2 TET CL ETHAN	<0.010		PPM
TETRACHLOROETHYLENE	6.000		PPM
TOLUENE	361.2		PPM
1,2-DICHLOROETHYLENE	0.700		PPM
1,1,1-TRI-CL-ETHANE	14.300		PPM
1,1,2-TRI-CL-ETHANE	<0.010		PPM
TRICHLOROETHYLENE	0.900		PPM
TRI-CL-F-METHANE	<0.010		PPM
VINYL CHLORIDE	<0.010		PPM
2-BUTANONE	6.58		PPM
HEXANE	<0.10		PPM
ACETONE	2.96		PPM
ETHYL ACETATE	<0.10		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

SAMPLE IDENTIFICATION AND CUSTODY TAG

- 196591
1. Source of Sample and COMPLETE Sample Identification GENESCO
WELL # 7 DEEP
 2. County Williamson Nearest Town or City BRENTWOOD
 3. Type of Sample WATER
 4. Date Collected 2/20/96 Time Collected 12:52
 5. Name of Sampler (Please Print) Mark Hobbs
 6. Names of Others Present at Time Sample Collected
 7. Field No. #12 Approximate Vol. of Sample 40ml
 8. Describe field collection procedure and special handling or preservation of this sample
WATER - AS PER PROJECT PROTOCOL
 9. Describe how sample conveyed or transported to the laboratory personal truck
 10. Requested Analyses

REFERRING CLIENT

DATE COLLECTED

02/20/86

TIME COLLECTED

12:52

RECEIVED

02/21/86

CLIENT LAB NO.

00000

REPORTED


03/05/86

GENESCO, INC., EMP. & ENV. SAFET

TEST	RESULT	REFERENCE LIMITS	UNITS
XYLENE	0.308		PPM
VOLATILE ORGANICS			
ACROLEIN	<0.10		PPM
ACRYLONITRILE	<0.10		PPM
BENZENE	0.162		PPM
BIS(CHLOROMETHYL)ETH	<0.010		PPM
BROMOFORM	<0.010		PPM
CARBON TETRACHLORIDE	<0.010		PPM
CHLOROBENZENE	<0.010		PPM
CHLORODIBROMETHANE	<0.010		PPM
CHLOROETHANE	<0.010		PPM
2-CLETHYVINYL ETHER	<0.010		PPM
CHLOROFORM	<0.010		PPM
DI-CL-BR-METHANE	<0.010		PPM
DI-CL-DI-F-METHANE	<0.010		PPM
1,1-DICHLOROETHANE	0.801		PPM
1,2-DICHLOROETHANE	1.200		PPM
1,1-DI-CL-ETHYLENE	0.035		PPM
1,2-DICHLOROPROPANE	<0.010		PPM
1,2-DI-CL-PROPYLENE	<0.010		PPM
ETHYLBENZENE	<0.010		PPM
METHYL BROMIDE	<0.010		PPM
METHYL CHLORIDE	<0.010		PPM
METHYLENE CHLORIDE	2.200		PPM
1,1,2,2 TET CL ETHAN	<0.010		PPM
TETRACHLOROETHYLENE	0.688		PPM
TOLUENE	81.80		PPM
1,2-DICHLOROETHYLENE	1.100		PPM
1,1,1-TRI-CL-ETHANE	6.100		PPM
1,1,2-TRI-CL-ETHANE	<0.010		PPM
TRICHLOROETHYLENE	0.343		PPM
TRI-CL-F-METHANE	<0.010		PPM
VINYL CHLORIDE	<0.010		PPM
2-BUTANONE	3.15		PPM
HEXANE	0.10		PPM
ACETONE	2.02		PPM
ETHYL ACETATE	<0.10		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



SAMPLE IDENTIFICATION AND CUSTODY TAG

- 16597
1. Source of Sample and COMPLETE Sample Identification GENSCO
Well # 3
 2. County Williamson Nearest Town or City Brentwood
 3. Type of Sample WATER
 4. Date Collected 2/2/96 Time Collected 12:42 PM
 5. Name of Sampler (Please Print) Mark Holbo
 6. Names of Others Present at Time Sample Collected
 7. Field No. # 11 Approximate Vol. of Sample 40ml
 8. Describe field collection procedure and special handling or preservation of this sample
WATER - AS PER PROJECT PROTOCOL
 9. Describe how sample conveyed or transported to the laboratory PERSONAL TRUCK
 10. Requested Analyses

WATER WELL #9 FIELD #11

SPECIMEN NUMBER

0296597

ACCESSION NO.

0296597

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

RECEIVED

02/21/86

12:42

02/21/86

CLIENT LAB NO.

REPORTED

GENESCO, INC., EMP. & ENV. SAFET

00000

03/04/86

TEST

RESULT

REFERENCE LIMITS


UNITS

VOLATILE ORGANICS

ACROLEIN	<0.10	PPM
ACRYLONITRILE	<0.10	PPM
BENZENE	<0.010	PPM
BIS(CHLOROMETHYL)ETH	<0.010	PPM
BROMOFORM	<0.010	PPM
CARBON TETRACHLORIDE	<0.010	PPM
CHLOROBENZENE	<0.010	PPM
CHLORODIBROMETHANE	<0.010	PPM
CHLOROETHANE	<0.010	PPM
2-CHLOROVINYL ETHER	<0.010	PPM
CHLOROFORM	<0.010	PPM
DI-CL-BR-METHANE	<0.010	PPM
DI-CL-DI-F-METHANE	<0.010	PPM
1,1-DICHLOROETHANE	0.258	PPM
1,2-DICHLOROETHANE	0.063	PPM
1,1-DI-CL-ETHYLENE	<0.010	PPM
1,2-DICHLOROPROPANE	<0.010	PPM
1,2-DI-CL-PROPYLENE	<0.010	PPM
ETHYLBENZENE	<0.010	PPM
METHYL BROMIDE	<0.010	PPM
METHYL CHLORIDE	<0.010	PPM
METHYLENE CHLORIDE	0.025	PPM
1,1,2,2 TET CL ETHAN	<0.010	PPM
TETRACHLOROETHYLENE	<0.010	PPM
TOLUENE	<0.010	PPM
1,2-DICHLOROETHYLENE	0.184	PPM
1,1,1-TRI-CL-ETHANE	0.095	PPM
1,1,2-TRI-CL-ETHANE	<0.010	PPM
TRICHLOROETHYLENE	<0.010	PPM
TRI-CL-F-METHANE	<0.010	PPM
VINYL CHLORIDE	<0.010	PPM
2-BUTANONE	<0.10	PPM
HEXANE	<0.10	PPM
ACETONE	0.59	PPM
ETHYL ACETATE	<0.10	PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

ENGINEERING, DESIGN & GEOSCIENCES GROUP, INC.

4301 HILLSBORO ROAD, SUITE 333

NASHVILLE, TENNESSEE 37215

(Lab No. _____)

SAMPLE IDENTIFICATION AND CUSTODY TAG

1. Source of Sample and COMPLETE Sample Identification
- GENESCO

WE44 #1

2. County
- WILLIAMSON

Nearest Town or City BRENTWOOD

3. Type of Sample
- WATER

4. Date Collected
- 2/21/86

Time Collected 12:27am

5. Name of Sampler (Please Print)
- MARK HOBBS

6. Names of Others Present at Time Sample Collected _____

7. Field No.
- #10

Approximate Vol. of Sample 4ml

8. Describe field collection procedure and special handling or preservation of this sample _____

WATER - AS PER PROJECT PROTOCOL

9. Describe how sample conveyed or transported to the laboratory
- PERSONAL TRUCK

10. Requested Analyses _____

WATER WELL #1 FIELD #10

0196092

296592

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

RECEIVED

02/21/86

CLIENT LAB NO

12:27

02/21/86

REPORTED

GENESCO, INC., EMP. & ENV. SAFET

00000

03/04/86

TEST

RESULT

REFERENCE LIMITS


UNITS

VOLATILE ORGANICS

ACROLEIN	<0.10	PPM
ACRYLONITRILE	<0.10	PPM
BENZENE	<0.010	PPM
BIS(CHLORD METHYL)ETH	<0.010	PPM
BROMOFORM	<0.010	PPM
CARBON TETRACHLORIDE	<0.010	PPM
CHLOROBENZENE	<0.010	PPM
CHLORODIBROMETHANE	<0.010	PPM
CHLOROETHANE	<0.010	PPM
2-CLETHYVINYL ETHER	<0.010	PPM
CHLOROFORM	<0.010	PPM
DI-CL-BR-METHANE	<0.010	PPM
DI-CL-DI-F-METHANE	<0.010	PPM
1-1-DICHLOROETHANE	0.116	PPM
1,2-DICHLOROETHANE	0.030	PPM
1,1-DI-CL-ETHYLENE	0.011	PPM
1,2-DICHLOROPROPANE	<0.010	PPM
1,2-DI-CL-PROPYLENE	<0.010	PPM
ETHYLBENZENE	<0.010	PPM
METHYL BROMIDE	<0.010	PPM
METHYL CHLORIDE	<0.010	PPM
METHYLENE CHLORIDE	0.050	PPM
1,1,2,2 TET CL ETHAN	<0.010	PPM
TETRACHLOROETHYLENE	<0.010	PPM
TOLUENE	1.156	PPM
1,2-DICHLOROETHYLENE	0.446	PPM
1,1,1-TRI-CL-ETHANE	<0.010	PPM
1,1,2-TRI-CL-ETHANE	<0.010	PPM
TRICHLOROETHYLENE	<0.010	PPM
TRI-CL-F-METHANE	<0.010	PPM
VINYL CHLORIDE	<0.010	PPM
2-BUTANONE	0.53	PPM
HEXANE	<0.10	PPM
ACETONE	0.47	PPM
ETHYL ACETATE	<0.10	PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

ENGINEERING, DESIGN & GEOSCIENCES GROUP, INC.

4301 HILLSBORO ROAD, SUITE 333

NASHVILLE, TENNESSEE 37215

(Lab No. _____)

SAMPLE IDENTIFICATION AND CUSTODY TAG

1. Source of Sample and COMPLETE Sample Identification GENESCO
WELL #2
2. County Williamson Nearest Town or City BRENTWOOD
3. Type of Sample WATER
4. Date Collected 2/21/86 Time Collected 12:10
5. Name of Sampler (Please Print) MARK HOBBS
6. Names of Others Present at Time Sample Collected _____
7. Field No. #9 Approximate Vol. of Sample 40ml
8. Describe field collection procedure and special handling or preservation of this sample
WATER - AS PER PROJECT PROTOCOL
9. Describe how sample conveyed or transported to the laboratory PERSONAL TRUCK
10. Requested Analyses _____
296587

WATER WELL#2 FIELD #9

0296587

296587

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

RECEIVED

02/21/86

12:10

02/21/86

CLIENT LAB NO.

REPORTED

GENESCO, INC., EMP. & ENV. SAFET

00000

03/04/86

TEST

RESULT

REFERENCE LIMITS


UNITS

VOLATILE ORGANICS

ACROLEIN	<0.10	PPM
ACRYLONITRILE	<0.10	PPM
BENZENE	<0.010	PPM
BIS(CHLOROMETHYL)ETH	<0.010	PPM
BROMOFORM	<0.010	PPM
CARBON TETRACHLORIDE	<0.010	PPM
CHLOROBENZENE	<0.010	PPM
CHLORODIBROMETHANE	<0.010	PPM
CHLOROETHANE	<0.010	PPM
2-CLETHYVINYL ETHER	<0.010	PPM
CHLOROFORM	<0.010	PPM
DI-CL-BR-METHANE	<0.010	PPM
DI-CL-DI-F-METHANE	<0.010	PPM
1,1-DICHLOROETHANE	<0.010	PPM
1,2-DICHLOROETHANE	<0.010	PPM
1,1-DI-CL-ETHYLENE	<0.010	PPM
1,2-DICHLOROPROPANE	<0.010	PPM
1,2-DI-CL-PROPYLENE	<0.010	PPM
ETHYLBENZENE	<0.010	PPM
METHYL BROMIDE	<0.010	PPM
METHYL CHLORIDE	<0.010	PPM
METHYLENE CHLORIDE	<0.010	PPM
1,1,2,2 TET CL ETHAN	<0.010	PPM
TETRACHLOROETHYLENE	<0.010	PPM
TOLUENE	<0.010	PPM
1,2-DICHLOROETHYLENE	<0.010	PPM
1,1,1-TRI-CL-ETHANE	<0.010	PPM
1,1,2-TRI-CL-ETHANE	<0.010	PPM
TRICHLOROETHYLENE	<0.010	PPM
TRI-CL-F-METHANE	<0.010	PPM
VINYL CHLORIDE	<0.010	PPM
2-BUTANONE	<0.10	PPM
HEXANE	<0.10	PPM
ACETONE	0.82	PPM
ETHYL ACETATE	<0.10	PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

404 Hixson Street, Suite 300
Nashville, TN 37217
GL 333-3588

Engineering, Design & Geosciences Group, Inc.

EDGE

March 24, 1986

Mr. Ronnie Bowers
Environmental Specialist/Chemist
Tennessee Division of Superfund
Customs House, Fourth Floor
701 Broadway
Nashville, TN 37219-5403

Re: Kennon Property
Analytical Results


Dear Mr. Bowers:

The enclosed analytical reports present the arsenic, chromium and lead results obtained from the samples we collected on February 21, 1986. Under my cover letter dated March 19, 1986, I submitted the results of the volatile organics analytical effort associated with these same samples.

If you have any questions, please advise.

Very truly yours,

ENGINEERING, DESIGN &
GEOSCIENCES GROUP, INC.



V. Wayne McCoy
Project Manager

VWM/lls
Enclosure

Subsidiaries:
Geologic Associates
MCI Consulting Engineers

SPECIMEN

SPECIMEN NUMBER

ACCESSION

WATER WELL #6 FIELD #1 296555

0310505

310505

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

00000

RECEIVED

03/20/86

REPORTED


03/20/86

GENESCO, INC., EMP. & ENV. SAFET

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

SPECIMEN 270511

SPECIMEN ID NUMBER

ACCESSION NO

POND SEDIMENT FIELD #2

031051B

31051B

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

00000

296399

RECEIVED

03/20/86

REPORTED


03/20/86

GENESCO, INC., EMP. & ENV. SAFETY

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	3.8		PPM
LEAD	11.5		PPM
CHROMIUM, TOTAL	15.3		PPM
COMMENT	VALUES, WET WEIGHT		

GENESCO, INC., EMP. & ENV. SAFETY
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4036

**SPECIALIZED
ASSAYS**

206 12th Ave., So. Nashville, TN 37203
Phone 1-615-255-5786

SPECIMEN NO. 310513
WATER POND FIELD #3

SPECIMEN ID. NUMBER

0310513

ACCESSION NO.

310513

REFERRING CLIENT

DATE COLLECTED

02/21/86

TIME COLLECTED

00:00

CLIENT LAB NO.

00000 296594

RECEIVED

03/20/86

REPORTED

03/20/86

GENESCO, INC., EMP. & ENV. SAFET

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



SPECIALIZED
ASSAYS

206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #8 FIELD #4 296584

SPECIMEN NUMBER

0310503

ACCESSION IN.

310503

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

CLIENT LAB NO.

00:00

GENESCO, INC., EMP. & ENV. SAFET

00000

RECEIVED

03/20/86

REPORTED

03/20/86

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	0.002		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

310515

03/20/84

256596

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

WATER WELL #8 FIELD #5

0310515

310515

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

0000

296596

RECEIVED

03/20/86

REPORTED


03/20/86

GENESCO, INC., EMP. & ENV. SAFETY

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFETY
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

DITCH HACKETT - PROPERTY FIELD

SPECIMEN ID NUMBER

0310517

310517

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

00000

296598

RECEIVED

03/20/86

REPORTED

03/20/86

GENESCO, INC., EMP. & ENV. SAFET

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	4.6		PPM
LEAD	14.9		PPM
CHROMIUM, TOTAL	22.3		PPM
COMMENT	VALUES, WET WEIGHT		

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE

TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #5 FIELD #7 296509

SPECIMEN ID NUMBER

0310508

ACCESSION NO.

310508

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

CLIENT LAB NO.

00:00

GENESCO, INC., EMP. & ENV. SAFETY

00000

RECEIVED

03/20/86

REPORTED

03/20/86

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFETY
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #4 FIELD #8 296588

SPECIMEN ID NUMBER

0210307

ACCESSION NO.

310507

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

00000

RECEIVED

03/20/86

REPORTED

03/20/86

GENESCO, INC., EMP. & ENV. SAFETY

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFETY
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #3 FIELD #296550

0310507

0310507

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

00000

RECEIVED

03/20/86

REPORTED

03/20/86

GENESCO, INC., EMP. & ENV. SAFET

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. ROSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #2 FIELD #7 293567

0310506

310506

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

00000

RECEIVED

03/20/86

REPORTED

03/20/86

GENESCO, INC., EMP. & ENV. SAFET

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	0.003		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #1 FIELD #10

0210511

ACCESSION NO

310511

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

00000 296592

RECEIVED

03/20/86

REPORTED

03/20/86

GENESCO, INC., EMP. & ENV. SAFET

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #9 FIELD #11

0310516

310516

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

00:00

CLIENT LAB NO.

00000 296597

RECEIVED

03/20/86

REPORTED

03/20/86

GENESCO, INC., EMP. & ENV. SAFET

TEST

RESULT

REFERENCE LIMITS

UNITS

ARSENIC

<0.001

PPM

LEAD

<0.001

PPM


CHROMIUM, TOTAL

<0.005

PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #7 DEEP FIELD #12

SPECIMEN ID NUMBER

0310510

ACCESSION NUMBER

310510

REFERRING CLIENT

GENESCO, INC., EMP. & ENV. SAFET

DATE COLLECTED

02/21/86

TIME COLLECTED

00:00

CLIENT LAB NO.

00000

2561 71

RECEIVED

03/20/86

REPORTED

03/20/86

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.075		PPM

GENESCO, INC., EMP. & ENV. SAFET
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #7 SHALLOW (296585)

0310504

310504

FIELD #13

REFERRING CLIENT

DATE COLLECTED

TIME COLLECTED

02/21/86

CLIENT LAB NO.

00:00

RECEIVED

03/20/86

REPORTED

03/20/86

GENESCO, INC., EMP. & ENV. SAFETY

00000

TEST	RESULT	REFERENCE LIMITS	UNITS
ARSENIC	<0.001		PPM
LEAD	<0.001		PPM
CHROMIUM, TOTAL	<0.005		PPM

GENESCO, INC., EMP. & ENV. SAFETY
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



206 12th Ave., So. - Nashville, TN 37203
Phone 1-615-255-5786

WATER WELL #7 SHALLOW FIELD #14

0310512

310912

REFERRING CLIENT

GENESCO, INC., EMP. & ENV. SAFETY

DATE COLLECTED

02/21/56

TIME COLLECTED

00:00

CLIENT LAB NO.

00000

RECEIVED

03/20/56

REPORTED

03/20/56

TEST

ARSENIC
LEAD

CHROMIUM, TOTAL

RESULT

<0.001
<0.001
<0.005

REFERENCE LIMITS

UNITS

PPM
PPM
PPM

GENESCO, INC., EMP. & ENV. SAFETY
RALPH E. MOSELY, DIRECTOR
430 GENESCO PARK
NASHVILLE TN 37202

4056



SPECIALIZED
ASSAYS

206 12th Ave., So. Nashville, TN 37203
Phone 1-615-255-5786

KENNON SITE

Site No. TND 981473575

Reference No. 9 HRS Manual

KENNON SITE

Site No. TND 981473575

Reference No. 10

May 21, 1985

Mr. Tom Tiesler
Director
Division of Solid Waste Management
Department of Health and Environment
4th Floor, Custom House
701 Broadway
Nashville, Tennessee 37219-5403

Dear Tom:

The purpose of this letter is to advise you of a chemical waste site once used by a division of Genesco Inc. (the "Company" or "Genesco") and to solicit the assistance and approval of the Tennessee Department of Health and Environment (the "Department") with respect to certain actions the Company proposes to take.

The Company is a Tennessee corporation with its executive offices located at Genesco Park, Nashville, Tennessee. Genesco operates in two major industry segments - footwear and men's apparel - and employs approximately 3,900 persons in the State of Tennessee. General Adhesives, formerly known as General Adhesives and Chemical Company, is a division of Genesco's footwear segment which operates a manufacturing plant at 6100 Centennial Boulevard in Nashville, Tennessee. General Adhesives manufactures and sells specialty industrial and consumer products, which include adhesives, sealants and coatings utilizing solvent based, thermoplastic and water based technologies. It is a generator (EPA I.D. Number TND 001981240) and transporter (EPA I.D. Number TND 001367549) of hazardous waste currently disposed of at either the Stauffer Chemical Company, Mt. Pleasant, Tennessee or Chemical Waste Management Company, Emelle, Alabama.

It has recently been brought to the attention of Genesco's corporate management that for a limited period of time during the summer and/or fall of 1978, approximately eight hundred 55-gallon barrels of waste material from General Adhesives were disposed of in a rural area in Williamson County, Tennessee. Preliminary indications are that some of the waste

Mr. Tom Tiesler
May 21, 1985
Page 2

(approximately 50-80 barrels) was buried in the barrels and the remainder was poured from barrels into phosphate pits or earthen trenches. The disposal site is an approximately two acre section of a 146 acre farm owned by Emmett N. Kennon located in the fifteenth civil district of Williamson County, Tennessee on the east side of Wilson Pike between Moores Lane and Split Log Road (the "Kennon Property"). Enclosed is a copy of a map showing the location of the Kennon Property and the approximate location of the disposal site.

The exact amount and contents of the waste material are unknown; however, it is believed that it contained water based adhesives and may have contained acetone; ethyl acetate; hexane; methylene chloride; methyl ethyl ketone; rubber solvent; toluene; 1,1,1-trichloroethane; trichloroethylene and organic fillers. A large portion of the organic solvents that was poured into the phosphate pits and earthen trenches may have evaporated, but it is believed that approximately 50-80 barrels were buried on the Kennon Property and may still contain waste material.

Having been informed of the reported waste disposal, corporate management immediately instructed its counsel to undertake an investigation of this matter. Based on the preliminary findings of that investigation, the Company developed the general plan of action outlined herein and arranged for a meeting with you. The plan has been developed in consultation with Mr. V. Wayne McCoy of Resource Consultants Inc. of Brentwood, Tennessee. Implementation of the plan calls for the employment of hydrogeologists, soil geologists and other experts, possibly including a waste disposal firm.

The details of the plan and the retention of experts and others to carry out the plan are subject to the Department's approval, and representatives of the Department are invited to observe or participate in all aspects of its implementation.

The first phase of the plan, as proposed by Genesco, is designed, through hydrogeological study, to:

1. Identify more specifically the area and volume of the land area on the Kennon Property that has been used for disposal of waste generated by General Adhesives;
2. Determine the extent to which chemical waste generated by General Adhesives is still present in the soil in and around the disposal site;

Mr. Tom Tiesler
May 21, 1985
Page 3

3. Determine the existence and direction of possible surface water flows and subsurface aquifers in and around the disposal site;
4. Determine if any of the chemicals generated by General Adhesives is present in any surface water or groundwater in and around the disposal site; and
5. Develop a report regarding the environmental impact and preliminary recommendations for any corrective action indicated.

Subject to Department approval, Genesco proposes to retain the services of Resource Consultants and Geologic Associates Inc. of Franklin, Tennessee, as soon as possible to perform the initial surveys, tests and analyses to define the nature and extent of any environmental problem that may exist on the Kennon Property and surrounding area.

Genesco will meet with appropriate Department representatives to review the results of the surveys, tests and analyses and to more fully develop any preliminary plan for any remedial action.

If waste removal and site cleanup is required, the Company will retain the services of a Department-approved firm to excavate, exhume, analyze, transport and dispose of contaminated material. Any cleanup and removal required will be subject to necessary pre-closure site tests and analyses conducted by Geologic Associates Inc. or other approved firms.

Sincerely,



Ralph Mosely
Director

37.04
53 AC.

37
165.5 AC
165.5 AC

37.01
3527 AC.

REVISED 8-1-85

38
112.5 AC.

"KENNON PROPERTY"

APPROXIMATE LOCATIONS
OF DISPOSAL SITES

39.04
501 AC.

39.05
502 AC.

42
34.3 AC


42.0
12 AC

42.06
1026 AC

42.02
15 AC

42.07
2034 AC

CT-22-36



KENNON SITE

Site No. TND 981473575

Reference No. 11



FEB 21 1986

City of Brentwood

P.O. BOX 788, 116 WILSON PIKE

BRENTWOOD, TENNESSEE 37027

TELEPHONE (615) 371-0011 371-0060

T. MACK BLACKBURN
MAYOR
PHILLIP HARDEMAN
VICE MAYOR
FRANK W. CLIFTON, JR.
CITY MANAGER

COMMISSIONERS
T. MACK BLACKBURN
PHILLIP HARDEMAN
HAROLD J. McMURTRY
BRIAN J. SWEENEY
RICHARD L. VAUGHN

February 19, 1986

Mr. Donald Shackelford
Tennessee Department of Health and Environment
701 Broadway, 4th floor Customs House
Nashville, TN 37219-5403

Dear Mr. Shackelford:

Based on our previous conversations and our meeting with Dr. Bruner and Mayor Blackburn, the following cost estimates are provided:

Alternative 1

6" Ductile Iron Pipe from Alamo Drive to the intersection of Split Log Road and Wilson Pike and east on Split Log Road to the existing city limits and south on Wilson Pike to the existing city limits.

17,000 L.F. of 6" DI Pipe at \$14/LF	\$ 238,000
37 6" Gate Valves at \$400 each	14,800
24 Fire Hydrants at \$1,100 each	26,400
Railroad Crossing (Tunnelled)	20,000
Pavement Repairs 300 LF at \$12/LF	3,600
Crushed Stone 8,000 LF at \$1/LF	8,000
Meters/Boxes 25 at \$200 each	5,000
Service Lines 625 LF at \$4/LF	2,500
Engineering (6%)	19,100
Inspection (4%)	12,700
Contingency (10%)	31,400
	<hr/>

Total Estimated Cost \$ 382,000

Mr. Donald Shackelford
February 19, 1986
Page two

Alternative 2

Instead of 6" Ductile Iron Pipe use Class 200 PVC Pipe at an estimated cost of \$7/LF instead of \$14/LF for Ductile Iron. All other factors remain the same, a savings of \$119,000 is realized. Total revised project cost will be \$263,000.

Alternative 3

Replacing the proposed minimum 6" Ductile Iron Pipe with a 12" Ductile Iron Pipe to provide adequate water supply for future growth. A revised cost estimate is as follows:

16,000 L.F. of 12" Ductile Iron Pipe at \$28/LF	\$ 448,000
500 L.F. of 6" Ductile Iron Pipe at \$14/LF	7,000
12" Gate Valves--13 at \$900 each	11,700
6" Gate Valves--24 at \$400 each	9,600
Fire Hydrants--24 at \$1,100 each	26,400
Railroad Crossing (Tunnelled)	20,000
Pavement Repairs--300 L.F. at \$12/LF	3,600
Crushed Stone--8,000 L.F. at \$1/LF	8,000
Meters/Boxes--25 at \$200 each	5,000
Service Lines 625 L.F. at \$4/LF	2,500
Engineering (6%)	33,400
Inspection (4%)	22,300
Contingency (10%)	<u>55,700</u>

Total Estimated Cost \$ 668,000

Alternative 4

Instead of 12" Ductile Iron Pipe Use Class 200 PVC Pipe at an estimated cost of \$14/LF instead of \$28/LF for Ductile Iron. All other factors remain consistent, a savings of \$227,500 is realized. Total revised project cost will be \$440,500.

In addition to one of the above options the City will be required to bring a second feeder line into the new proposed line. This second feeder will come down Wilson Pike from Concord Road to the new connection off of Alamo Drive. The approximate length of this additional line is estimated to be 4,500 L.F. This second feeder line will cost additionally above alternatives 1-4 (depending on the option selected) as follows:

Mr. Donald Shackleford
February 19, 1986
Page three

- 6" Ductile Iron Pipe	\$ 97,000
- 6" Class 200 PVC	64,800
- 12" Ductile Iron Pipe	180,000
- 12" Class 200 PVC	115,600

Summarizing

To effectively get a reliable source of public water to area in question would cost a minimum of \$327,800 and under the most desirable conditions, using 12" PVC Class 200 Pipe, \$556,500. These estimates would be subject to actual bids.

If Class 200 PVC Pipe is allowable under these conditions, I feel the City would want to install the 12" line as a minimum, understanding that the City would have to pick up the cost difference between the 12" and 6" pipe and the second feeder to the area in question.

Based on the above calculations, I feel a reasonable estimate of cost sharing on this project would be:

Local Sources	\$ 293,100
State and/or Pollution Offenders	<u>263,000</u>
Total Estimated Cost	\$ 556,100

Please recognize that these figures include no cost for right-of-way acquisition or condemnation expenses.


This information is being provided the Brentwood City Commission for their review and knowledge. We will await further contact from your office with regards to proceeding with any additional action.

Respectfully,


Frank W. Clifton, Jr.
City Manager

cc: Mayor and City Commission
City Attorney Robert H. Jennings, Jr.

FWC:NS



KENNON SITE

Site No. TND 981473575

Reference No. 12

10/27/11
ORJ 8/4
AUG 01 1986
CHP-8/1
File

Employee and Environmental Safety

Mr. Frank W. Clifton, Jr.
City Manager
City of Brentwood
P.O. Box 788
Brentwood, TN 37027

RE: SERVICE CONNECTIONS

July 28, 1986

Dear Frank:

As we discussed with you and with John Grissom, an estimate of the cost of each service connection prior to installation would probably be the best method of insuring we are in agreement of the costs involved.

To facilitate the cost estimates, we asked Bill Griggs of Barge, Waggoner, Sumner and Cannon, to meet with John Grissom, Manager of Water Service of the City of Brentwood, to estimate distances and size of service line needed, etc. Attached is his report.

Bill's basic assumption on sizes, etc. was to assume that your storage tank would be 50% full, a residual pressure of 20 psi would be maintained, and that 10 GPM would be adequate for each residence.

There are questions we have involving three service connections that we would like to ask either John Grissom or the contractor to clarify:

It would appear to be much more cost effective to combine the service lines to the three residences on the Sharp property, and to extend the service connection to Mr. Reese Smith's house back down the hill to connect to Woodrow Shaw's residence (Mr. Smith's tenant). If a common service line is not applicable, we would still prefer a common trench.


If you could have someone clarify this before we proceed further, it would expedite the cost estimating process.

As quickly as the cost estimates are submitted, we will have a prompt review, so we could proceed without undue delay.

Mr. Frank W. Clifton
July 28, 1986
Page two

Thank you for your assistance.

Sincerely,

A handwritten signature in cursive script, appearing to read "R. Mosely", written in dark ink.

Ralph E. Mosely
Director
Employee and Environmental Safety

RM/bb

cc: Mr. John Grissom - City of Brentwood
Mr. Bill Griggs - Barge, Waggoner, Sumner & Cannon
Mr. Don Shackelford - Tennessee Dept. of Health & Environment

RECOMMENDED SERVICE LINE SIZES
BRENTWOOD WATER LINE
FILE 9835

Jan 4/13/00
1 MILE RADIUS
- Charles Powers, Superintendent
Rel. Grid

Address	Parcel	Elev.	Estimated Dist. from Road, Ft.	Service Line Size, In.	Available GPM	Remarks
[REDACTED]	54-39.15	730	200	3/4	13	
[REDACTED]	54-39.14	720	400	3/4	10	
[REDACTED]	54-39.13	720	200	3/4	14	
1) [REDACTED]	54-39.11	725	175	3/4	14	
[REDACTED]	54-39.10	725	175	3/4	14	
[REDACTED]		730	150	3/4	15	
am [REDACTED]		730	300	3/4	10	
[REDACTED]		750	600	1	14	1
[REDACTED]		750	600	1	14	
[REDACTED]	54-39.04	760	600	1	13	
[REDACTED]	54-39.05	770	600	1	12	
[REDACTED]	54-42.01	760	200	3/4	11	
[REDACTED]	54-42.02	760	500	1	15	
[REDACTED]	54-40	760	600	1	14	
[REDACTED]	54-40	820	2,000	2	25	
[REDACTED]	54-40	780	1,800	1-1/2	18	
[REDACTED]	61-5	830	1,500	2	25	

¹John Grisson was unsure of exact location.

³Includes head loss through meter, minimal loss through 12" main, tank 50% full, and 20 psi residual pressure.

<u>Name</u>	<u>Address</u>	<u>Parcel</u>	<u>Elev.</u>	<u>Estimated Dist. from Road, Ft.</u>	<u>Service Line Size, In.</u>	<u>Available GPM³</u>	<u>Remarks</u>
[REDACTED]	[REDACTED]	61-5	830	1,700	2	23	
[REDACTED]	[REDACTED]	61-5	810	1,200	1-1/2	17	2
[REDACTED]	[REDACTED]		770	250	1	20	
[REDACTED]	[REDACTED]		780	250	1	19	
[REDACTED]	[REDACTED]		765	600	1	13	
[REDACTED]	[REDACTED]		760	200	3/4	11	
[REDACTED]	[REDACTED]		790	400	1	13	
[REDACTED]	[REDACTED]		785	400	1	14	
[REDACTED]	[REDACTED]		790	700	1	10	
[REDACTED]	[REDACTED]		800	150	3/4	10	
[REDACTED]	[REDACTED]		825	600	1-1/2	20	
[REDACTED]	[REDACTED]		765	500 ⁴	1	14	
[REDACTED]	[REDACTED]		790	400	1	13	
[REDACTED]	[REDACTED]		720	600	1	16	

Summary - 3/4" - 2,150 LF
 - 1" - 7,600 LF
 - 1-1/2" - 3,600 LF
 - 2" - 5,200 LF

²Served from Split Log Road.

³Includes head loss through meter, minimal loss through 12" main, tank 50% full, and 20 psi residual pressure.

⁴No existing house, assumed distance.

KENNON SITE

Site No. TND 981473575

Reference No. 13

OFFICE CORRESPONDENCE

SUBJECT: Details of Conversation - pertinent site information.

FROM	TO	DATE

Hackett Spring is the nearest drinking water source to the site. The Little Hackett is very shallow except for small pools. Mr. Bowers has seen fish in the pools, but has never seen anyone fishing in the 1 1/2 years he has been involved with the site. Glass Creek is intermittent.

[illegible]

KENNON SITE

Site No. TND 981473575

Reference No. 14¹ 15

OVERSIZED

DOCUMENT

KENNON SITE

Site No. TND 981473575

Reference No. 1E

OFFICE CORRESPONDENCE

SUBJECT: Ground Water Use Survey/House Count For 3 Mile Radius

FROM	TO	DATE

TAM/ib

Thomas A. Moss

[illegible]

KENNON SITE

Site No. TND 981473575

Reference No. 17

KENNON SITE

Site No. TND 981473575

Reference No. 18



TENNESSEE WILDLIFE RESOURCES AGENCY

ELLINGTON AGRICULTURAL CENTER
P. O. BOX 40747
NASHVILLE, TENNESSEE 37204

December 19, 1985

Mr. Gordon Caruthers
Solid Waste Management Division
Department of Health & Environment
701 Broadway
Nashville, TN 37219

Dear Gordon:

In response to your call of December 19, I am happy to enclose descriptions of critical wildlife habitat of Tennessee, as designated by the U.S. Fish and Wildlife Service.

Please advise if I can be of further assistance.

Sincerely,

TENNESSEE WILDLIFE RESOURCES AGENCY

A handwritten signature in dark ink, appearing to read "R. Hatcher".

Robert M. Hatcher, Coordinator
Nongame/Endangered Species


RMH/ch
enc.

8/85

Proposed Rules (Region 4)

(E = Endangered; T = Threatened; CH = Critical Habitat; S/A = Classified under similarity of appearance provision)

<u>SPECIES</u>	<u>LOCATION</u>	<u>DETERMINATION</u>	<u>FEDERAL REGISTER</u>
Trispot Darter (<u>Etheostoma trisella</u>)	Conasauga River, Coahulla Creek, TN, GA	E, CH	07/13/84
Prickly-ash (<u>Zanthoxylum thomsonianum</u>)	PR, VI	E	02/11/85
Dismal Swamp Southeastern Shrew (<u>Sorex longirostris</u> <u>fisheri</u>)	VA and NC	T	07/16/85
Short's Goldenrod (<u>Solidago shortii</u>)	Robertson, Nicholas, Fleming Co., KY	E	10/11/84
Key Largo Cotton Mouse and Woodrat	N. Key Largo, FL	CH	02/09/84, 08/31/84, 11/21/84
Prickly Apple Cactus (<u>Cereus eriophorus</u> var. <u>fragrans</u>)	St. Lucie Co., FL	E	03/06/85
Longspurred Balm (<u>Dicerandra cornutissima</u>)	Marion Co., FL	E	
Scrub Balm (<u>Dicerandra frutescens</u>)	Highlands Co., FL	E	03/28/85
Canby's Dropwort (<u>Oxypolis canbyi</u>)	Burke, Lee, Sumter Co., GA; Scotland Co., NC; Bamberg, Colleton Co., SC; MD	E	03/28/85
Florida Golden Aster (<u>Oenysopsis floridana</u>)	Hillsborough and Pinellas Counties, FL	E	08/05/85
Pondberry (<u>Lindera melissifolia</u>)	AR: Clay Co. MS: Sharkey Co. MO: Ripley Co. NC: Bladen Co. SC: Berkeley Co. GA: Wheeler Co.	E	08/13/85



ENDANGERED AND THREATENED WILDLIFE AND PLANTS

JULY 20, 1984

50 CFR 17.11 and 17.12

Department of the Interior
U.S. Fish and Wildlife Service

DEPARTMENT OF THE INTERIOR

Fish and Wildlife Service

50 CFR Part 17

Republication of the Lists of Endangered and Threatened Species

AGENCY: Fish and Wildlife Service, Interior.

ACTION: Final rule.

SUMMARY: The Service republishes the U.S. Lists of Endangered and Threatened Wildlife and Plants. The last complete republication was May 20, 1980 (45 FR 33768-33781). Minor changes, principally in names of the species, are incorporated in this republication.

DATES: This rule is effective on July 27, 1983.

ADDRESSES: Comments concerning this republication should be sent to the Associate Director—Federal Assistance, Fish and Wildlife Service, U.S. Department of the Interior, Washington, D.C. 20240.

FOR FURTHER INFORMATION CONTACT: Mr. John L. Spinks, Jr., Chief, Office of Endangered Species, U.S. Fish and Wildlife Service, Washington, D.C. 20240 (703/235-2771).

SUPPLEMENTARY INFORMATION:**Background**

These lists contain the names of species officially listed as Endangered or Threatened under the Endangered Species Act of 1973, as amended (16 U.S.C. 1531, *et seq.*) through the date of this republication. The listing regulations promulgated under that Act are found at 50 CFR Part 424 and are under revision to conform to the Endangered Species Act Amendments of 1982 (Pub. L. 97-304, 96 Stat. 1411). The previous compilation of these lists appears in the 1982 edition of the Code of Federal Regulations for Title 50, which was actually issued in early 1983. That compilation was effective through October 1, 1982. This republication of §§ 17.11 and 17.12 incorporates all subsequent changes (i.e., additions, reclassifications, and deletions) published as Final Rules in the Federal Register.

In addition to those changes, the Service has made extensive revisions on some of the entries. Most of these changes reflect current nomenclature. The entries for the common and scientific names of many plants and animals are amended by adding synonyms, indicated by the use of (=). Synonyms aid law enforcement officials, importers, exporters, and many others

who routinely use these names by identifying alternative names that may appear in documents and other references.

The species named in these lists were placed there either by the U.S. Fish and Wildlife Service, Department of the Interior, or jointly by that Service and the National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce. References to "Services" in the text of §§ 17.11 and 17.12 refer to those two agencies. The Fish and Wildlife Service maintains the lists through republications and other administrative practices.

No entry to these lists has been added, deleted, or significantly altered by this republication. Such actions must be published as separate documents in the Federal Register.

Minor changes are made in §§ 17.11(d) and 17.12(d) to clarify that some of the data in these lists are provided for the information of the reader and may now be changed without public notice when the annual (October 1) compilation of Title 50 is being done. This procedure will annually save the government several thousand dollars in publication costs in the daily Federal Register by permitting such changes of a nonregulatory nature.

The Service finds for good cause that this document shall be effective upon publication and that notice and public comment are unnecessary. This action is merely a republication of existing, and previously published, requirements. By bringing earlier lists up to date, it will provide more timely guidance to the public. Readers are requested to advise the Service of any errors or omissions, particularly with regard to historic ranges and alternative names in these lists.

Authors

This document was compiled by the staff of the Office of Endangered Species, U.S. Fish and Wildlife Service, Washington, D.C. 20240 (703/235-1975).

List of Subjects in 50 CFR Part 17

Endangered and threatened species.

Dated: July 21, 1983.

J. Craig Potter,

Acting Assistant Secretary for Fish and Wildlife and Parks.

Regulations Promulgation**PART 17—[AMENDED]**

Accordingly, the Service amends Part 17 of Title 50 of the Code of Federal Regulations as follows:

1. The authority citation for Part 17 reads as follows:

Authority: Pub. L. 93-205, 87 Stat. 884; Pub. L. 95-632, 92 Stat. 3751; Pub. L. 96-159, 93 Stat. 1241; and Pub. L. 97-304, 96 Stat. 1411 (16 U.S.C. 1531, *et seq.*).

2. Revise Subpart B of 50 CFR Part 17 to read as follows:

Subpart B—Lists**§ 17.11 Endangered and threatened wildlife.**

(a) The list in this section contains the names of all species of wildlife which have been determined by the Services to be Endangered or Threatened. It also contains the names of species of wildlife treated as Endangered or Threatened because they are sufficiently similar in appearance to Endangered or Threatened species (see § 17.50 *et seq.*).

(b) The columns entitled "Common Name," "Scientific Name," and "Vertebrate Population Where Endangered or Threatened" define the species of wildlife within the meaning of the Act. Thus, differently classified geographic populations of the same vertebrate subspecies or species shall be identified by their differing geographic boundaries, even though the other two columns are identical. The term "Entire" means that all populations throughout the present range of a vertebrate species are listed. Although common names are included, they cannot be relied upon for identification of any specimen, since they may vary greatly in local usage. The Services shall use the most recently accepted scientific name. In cases in which confusion might arise, a synonym(s) will be provided in parentheses. The Services shall rely to the extent practicable on the *International Code of Zoological Nomenclature*.

(c) In the "Status" column the following symbols are used: "E" for Endangered, "T" for Threatened, and "E [or T] (S/A)" for similarity of appearance species.

(d) The other data in the list are nonregulatory in nature and are provided for the information of the reader. In the annual revision and compilation of this Title, the following information may be amended without public notice: the spelling of species' names, historical range, footnotes, references to certain other applicable portions of this Title, synonyms, and more current names. In any of these revised entries, neither the species, as defined in paragraph (b) of this section, nor its status may be changed without following the procedures of Part 424 of this Title.

(e) The "Historic Range" indicates the known general distribution of the

species or subspecies as reported in the current scientific literature. The present distribution may be greatly reduced from this historic range. This column does not imply any limitation on the application of the prohibitions in the Act or implementing rules. Such prohibitions apply to all individuals of the species, wherever found.

(f)(1) A footnote to the Federal Register publication(s) listing or reclassifying a species is indicated under the column "When Listed." Footnote numbers to §§ 17.11 and 17.12 are in the same numerical sequence, since plants and animals may be listed in the same Federal Register document. That document, at least since 1973, includes a statement indicating the basis

for the listing, as well as the effective date(s) of said listing.

(2) The "Special Rules" and "Critical Habitat" columns provide a cross reference to other sections in Parts 17, 222, 226, or 227. The term "NA" (not applicable) appearing in either of these two columns indicates that there are no special rules and/or Critical Habitat for that particular species. However, all other appropriate rules in Parts 17, 217-227, and 402 still apply to that species. In addition, there may be other rules in this Title that relate to such wildlife, e.g., port-of-entry requirements. It is not intended that the references in the "Special Rules" column list all the regulations of the two Services which might apply to the species or to the

regulations of other Federal agencies or State or local governments.

(g) The listing of a particular taxon includes all lower taxonomic units. For example, the genus *Hylobates* (gibbons) is listed as Endangered throughout its entire range (China, India, and SE Asia); consequently, all species, subspecies, and populations of that genus are considered listed as Endangered for the purposes of the Act. In 1978 (43 FR 6230-6233) the species *Haliaeetus leucocephalus* (bald eagle) was listed as Threatened in "USA (WA, OR, MN, WI, WI, MI)" rather than its entire population; thus, all individuals of the bald eagle found in those five States are considered listed as Threatened for the purposes of the Act.

(h) The "List of Endangered and Threatened Wildlife" is provided below:

KENNON SITE

Site No. TND 981473575

Reference No. 19

WATER QUALITY MANAGEMENT PLAN
FOR THE
LOWER CUMBERLAND RIVER BASIN

November, 1978

PRODUCED BY
TENNESSEE DEPARTMENT OF PUBLIC HEALTH
DIVISION OF WATER QUALITY CONTROL
309 CAPITOL TOWERS
NASHVILLE, TENNESSEE 37219

Authorization No. 0871 ; 150 copies printed. This document was printed at a cost of 5599.50 , or 22.66 each, to fulfill a requirement of EPA Grant No. P004193010 to the State of Tennessee and Section 208 of the Federal Water Pollution Control Act Amendments of 1972.

Printed by Enviro-Printers, Franklin, Tennessee

Adams-Cedar Hill	Red River	34.1	36°05'20"	87°35'55"	0.0960
Greenbrier	Impounded Reservoir	-	-	-	0.2810
Springfield	Sulphur Fork Creek	-	36°31'36"	86°52'54"	-
White House Utility District	Cumberland River- Old Hickory Lake	216.5	36°17'50"	86°38'00"	2.0200
Murfreesboro	East Fork Stones River (Spring)	12.3	-	-	5.3050
Smyrna	Stones River (Percy Priest Reservoir)	-	35°59'55"	86°28'45"	1.7230
Carthage	Cumberland River	309.0	36°14'36"	85°56'45"	0.3710
Dover	Cumberland River	88.8	36°29'27"	37°50'22"	0.1360
Gallatin	Cumberland River	239.1	36°20'25"	86°26'25"	2.3900
Hendersonville Utility District	Drakes Creek Cumberland River	3.7 222.1	36°17'45"	86°37'50"	2.1510
Portland	Impounded Reservoir	-	-	-	0.4330
Westmoreland	Impoundment		36°36'23"	86°29'23"	0.1640
Hartsville	Cumberland River	278.6	36°22'25"	86°10'44"	0.2810
Franklin	Harpeth River	81.5	35°54'30"	86°51'30"	1.9630
Lebanon	Cumberland River	263.0	36°17'57"	86°15'47"	2.718
West Wilson Utility District	Cumberland River	225.6	36°16'32"	86°33'35"	0.8000

TABLE III - 2
Domestic Surface Water Supplies In The Lower Cumberland River Basin

<u>Municipality or Water Company</u>	<u>Water Source</u>	<u>River Mile</u>	<u>Intake Location</u>		<u>Avera Dai Use (c</u>
			<u>Latitude</u>	<u>Longitude</u>	
Woodbury	East Fork Stones River	44.3	35 ⁰ 49'36"	86 ⁰ 04'28"	0.3
Ashland City	Big Marrowbone Creek.	1.1			
	Cumberland River	160.0	36 ⁰ 15'41"	87 ⁰ 03'33"	0.4
Pleasant View Utility District	Sycamore Creek	-	36 ⁰ 19'36"	87 ⁰ 03'30"	0.3
River Road Utility District	Brush Creek	1.1			
	Cumberland River	160.7	36 ⁰ 16'14"	87 ⁰ 03'07"	0.6
South Cheatham Utility District	Harpeth River	36.1	36 ⁰ 06'38"	86 ⁰ 06'48"	0.
Cumberland Utility District	Cumberland River	207.6	36 ⁰ 12'30"	86 ⁰ 38'30"	
Harpeth Valley Utility District	Cumberland River- Cheatham Lake	172.5	36 ⁰ 08'10"	86 ⁰ 55'15"	2.7230
Madison Suburban Utility District	Cumberland River	200.3	36 ⁰ 14'22"	86 ⁰ 12'52"	7.1290
Nashville-Plant No. 1	Cumberland River	193.8	-	-	63.502
Nashville-Plant No. 2	Cumberland River	206.3	-	-	35.000
Old Hickory Utility District	Cumberland River	218.8	36 ⁰ 15'40"	86 ⁰ 38'30"	0.5790
Dickson	Impounded Reservoir	-	36 ⁰ 04'48"	87 ⁰ 24'14"	0.6500
Turnbull Utility District	Turnbull Creek	11.1	36 ⁰ 03'30"	87 ⁰ 12'15"	1.2000
Erin	Cumberland River	108.3	36 ⁰ 25'25"	87 ⁰ 34'33"	0.4110
Clarksville	Cumberland River	132.8			
	Big West Fork Creek	5.5	-	-	9.7710

KENNON SITE

Site No. TND 981473575

Reference No. 20

STATE OF TENNESSEE
DEPARTMENT OF HEALTH AND ENVIRONMENT

IN THE MATTER OF:)	
)	
GENESCO INC.)	DIVISION OF SUPERFUND
EMMETT N. KENNON)	
AND)	
ROSE S. KENNON)	NO. 86-2013
)	
RESPONDENTS)	

COMMISSIONER'S ORDER

Comes now, James E. Word, Commissioner of the Tennessee Department of Health and Environment, and states that:

PARTIES

I.

James E. Word is the duly appointed Commissioner of the Tennessee Department of Health and Environment (the "Department").

II.

Respondent, Genesco Inc., is a domestic corporation qualified to do business in Tennessee. Its agent for service of process is W. C. O'Connor whose mailing address is Genesco Park, Nashville, TN 37202.

III.

Respondents, Emmett N. Kennon, and wife, Rose S. Kennon are husband and wife and both are residents of the state of Tennessee. Their mailing address is 2934 Sidco Drive, Nashville, TN 37204.

JURISDICTION

IV.

Pursuant to T.C.A. Section 68-46-206, the Commissioner is authorized to issue an order to any liable party requiring such party to investigate, identify, contain, and clean-up, including monitoring and maintenance, inactive hazardous substance sites which pose or may pose a danger to public health, safety or the environment because of the release or threatened release of hazardous substances. Pursuant to T.C.A. Section 68-46-215 the Commissioner may issue an Order for correction to the appropriate person, who will then comply with the Order within the time limit specified in the Order.

V.

Respondents are "persons" within the meaning of T.C.A. Section 68-46-104 and each is also a "liable party" within the meaning of T.C.A. Section 68-46-202.

FACTS

VI.

Respondent, Genesco Inc. (hereinafter "Genesco"), is a Tennessee corporation with its executive offices located at Genesco Park, Nashville, TN. Genesco operates in two major industry segments which are footwear and men's apparel. It employs approximately 3,900 persons in Tennessee.

VII.

General Adhesives, formerly known as General Adhesives and Chemical Company, is a division of Genesco Inc. which operates a manufacturing plant at 6100 Centennial Boulevard in Nashville, TN. It manufactures and sells specialty industrial and consumer products which includes adhesives, sealants, and coatings utilizing solvent-based thermoplastic and water-based technologies. It is a hazardous waste generator utilizing the EPA installation identification number TND 001981240. It is a permitted hazardous waste transporter utilizing the EPA installation identification number TND 001367549.

VIII.

Emmett N. Kennon and Rose S. Kennon are owners of certain property described herein. They have owned the property since at least 1976. A portion of said property was used for a period of time in approximately 1978 for the disposal of certain hazardous substances. To the knowledge of the Department it has not been operated as a disposal site since that time and, therefore, said property is an inactive hazardous substance disposal site, (hereinafter, the "site").

IX.

The site is within a 146.8 acre tract located along Wilson Pike in Williamson County, Tennessee, and all of said tract is located within the city limits of Brentwood, Tennessee. The site is approximately two (2) acres.

X.

The site was operated by Respondents, Kennons, as a disposal site for construction waste and for certain other waste described herein which were hazardous substances. At least one or more of the trenches used in the disposal operation were already in existence from the excavation for phosphate mining.

XI.

Genesco notified the Department on or about August 19, 1981 that it was a generator of hazardous waste. It reported that it generated hazardous waste which were described as being "waste, cement and solvents, N.O.S.". The waste was further described as being ignitable (as described in Division rule 1200-1-11-.02 promulgated under the Hazardous Waste Management Act). The waste was reported to be generated at an average rate of 7,400 kilograms per month. The major compounds of the waste were described as being acetone, hexane, toluene, methyl ethyl ketone, and 1, 1, 1 trichloroethylene.

XII.

On or about May 21, 1985 Genesco reported in a letter to the Department, that during the summer and/or fall of 1978, General Adhesives had disposed of approximately eight hundred (800) 55 gallon barrels of waste material in a rural area of Williamson County, Tennessee". The rural disposal area is now known to be the property of Respondents Emmett N. Kennon and Rose S. Kennon. To the knowledge and belief of the Department, the waste was transported to the site by Respondent Genesco and/or by Respondents Kennon.

XIII.

In the same letter referenced above, it was stated that approximately 50 to 80 barrels were buried and the remainder of the waste was poured from the barrels into earthen trenches at the site.

XIV.

It was further stated in the same letter, that the exact amount and contents of the waste material were unknown; however, Genesco believed that the waste contained water-based adhesives and may have contained acetone, ethyl acetone, hexane, methylene chloride, methyl ethyl ketone, rubber solvent, toluene, 1, 1, 1 - trichloroethane, trichloroethylene, and 1, 1, 1 - trichloroethane.

XV.

On or about August 9, 1985 Genesco submitted a plan of investigation of the site to the Department. The plan was revised according to Department comments and resubmitted on September 25, 1985. The plan was approved by the Department on or about October 2, 1985. Genesco then began to investigate the extent of any environmental impact including the sampling of waste, soil, and water in and around the site. Water samples included samples of leachate at the site, springs, a seep, and water wells in the vicinity.

XVI.

Laboratory analysis of certain samples reveal the presence of hazardous substances including, but not limited to: arsenic, lead, chromium, trans-1, 2-dichloroethene, 1,1,1 trichloroethane, 1, 1-dichloroethane, 1, 2-dichloroethane, toluene, bis (2-ethyl hexyl) phthalate, naphthalene, ethylbenzene and trichloroethane. The location of a spring and a seep and the laboratory analysis of the same indicate that the contaminants are migrating from the site. The exact analysis results and sampling locations are listed in Tables A, B, C and D of this Order.

TABLE A

Samples Collected January 28, 1986 by Department Staff
at an On-Site Seep Approximately 500 feet Southeast
of the Site

<u>Hazardous Substance</u>	<u>Level of Contamination</u>	<u>Type of Sample</u>
Arsenic	.217 ppm	water
Arsenic	18.0 ppm	soil
Lead	.12 ppm	water
Lead	7.6 ppm	soil
Chromium	.15 ppm	water
Chromium	9.3 ppm	soil

TABLE B

Samples Collected February 7, 1986 by Department Staff
at an Off-Site Spring (Hackett Spring)
Approximately 1200 Feet Southeast
of the Site

<u>Hazardous Substances</u>	<u>Level of Contamination</u>	<u>Type of Sample</u>
Trans -1, 2-dichloroethene	.07 ppm	water
1, 1, 1 trichloroethane	.013 ppm	water
1, 1-dichloroethane	.026 ppm	water

TABLE C

Sample Collected January 22, 1986 by Department

Staff at Pit A from the Disposal Site

<u>Hazardous Substance</u>	<u>Level of Contamination</u>	<u>Type of Sample</u>
Arsenic	9 ppm	soil
Chromium	14 ppm	soil
Lead	8 ppm	soil
1, 1-dichloroethane	4.3 ppm	soil
1, 2-dichloroethane	1.2 ppm	soil
Trans -1, 2-dichloroethane	3.3 ppm	soil
Toluene	120 ppm	soil
1, 1, 1-trichloroethane	2.2 ppm	soil

TABLE D

Samples Collected January 22, 1986 by Department

Staff from PIT B from the Disposal Site

<u>Hazardous Substance</u>	<u>Level of Contamination</u>	<u>Type of Sample</u>
Chromium	14 ppm	waste
Bis (2-ethyl hexyl) phthalate	940 ppm	waste
Naphthalene	110 ppm	waste
Chromium	14 ppm	soil
1, 2-dichlorethane	11.11 ppm	soil
Ethyl benzene	19.19 ppm	soil
Tetrachloroethene	220 ppm	soil
Toluene	6,200 ppm	soil
1, 1, 1-trichloroethane	160 ppm	soil
Trichloroethane	6.9 ppm	soil

XVII.

Based on the laboratory analysis and the location of these samples, it is the opinion of the Department that hazardous substances have been disposed of at the site, migrated from the site, and that the substances have contaminated ground water. Immediate remedial measures are necessary and appropriate because of potential harm to the public health and environment.

CLAIMS FOR RELIEF

XVIII.

By owning and operating a hazardous substance disposal site and by being the generator of the hazardous substances who at the time of disposal caused such substance to be disposed at the site, each of the Respondents is a "liable party" as defined at T.C.A. Section 68-46-202 which is defined as:

- "(a) The owner or operator of an inactive hazardous substance site;
- (b) Any person who at the time of disposal was the owner or operator of an inactive hazardous substance site;
- (c) Any generator of hazardous substance who at the time of disposal caused such substance to be disposed of at an inactive hazardous substance site; or
- (d) Any transporter of hazardous substances which is disposed of at an inactive hazardous substance site who, at the time of disposal, selected the site of disposal of such substances."

This site is an inactive hazardous substance site within the meaning of T.C.A. Section 68-46-202 which is defined as "any site or area where hazardous substance disposal has occurred."

XIX.

PREMISES CONSIDERED, I, James E. Word, hereby ORDER the Respondents to comply with the following:

1. The Respondents must submit a plan to the Department within fifteen (15) days of the receipt of this Order describing how the Respondents will provide a permanent adequate, and potable water source for human consumption and household use to the residents potentially impacted by the site. Until such time as a permanent water supply is provided, the Respondents shall supply adequate drinking water to those persons in the vicinity of the site that they are presently supplying and others deemed appropriate by the Department.
2. The Respondents will define the potentially impacted area within the above referenced plan and said plan will include a proposed chronology of activities and a schedule for the completion of activities. The plan will describe how the Respondents will provide and install said water source including any agreements with public utility districts. The plan will further include a well water monitoring program for sampling and testing specified existing wells outside the perimeter of the "potentially impacted area."
3. The Respondents will submit a separate plan to the Department within thirty (30) days of the receipt of this Order which will describe how the Respondents will control the source of release of the contaminants to prevent migration of the same. Said plan will define the scope of the source and provide a proposal of activities for immediate remedial measures and a schedule for completion of said activities. The Respondent will implement the plan upon the approval and notice to proceed of the Department.
4. The Department will review said plans and may require revisions as deemed necessary. Respondents shall implement all immediate remedial action plans as they are approved by the Department.

B. INITIAL ASSESSMENT

1. Within sixty (60) days of receipt of this Order, the Respondents shall submit to the Department any existing data available to the

Respondents which is pertinent to the assessment of the hazard that the specified site may pose to public health and the environment. This information shall include available data listed in paragraph XIX C2 of this Order and shall be submitted in duplicate.

2. Following receipt of this information, the Department will schedule an initial assessment conference which the Respondents shall attend in the Nashville Office of the Department, Division of Superfund. The Respondents shall be given seven (7) days notice prior to this meeting. The purpose of this conference will be to discuss existing data and determine the need for further investigation, remedial action and/or long term monitoring and maintenance. A schedule for future activities, deemed necessary by the Department, shall be established at this conference. Depending on existing data, the Department may determine that no further action is necessary. In all other cases, the schedule established in this conference will provide the dates by which the activities enumerated herein must be completed.

C. INVESTIGATION PROGRAM

1. According to the schedule established in the initial assessment conference, the Respondents shall submit to the Department a proposed Investigation Plan.
2. In order to provide an accurate assessment of the hazard posed by the site to public health and the environment and to develop design data for remedial action, the Investigation Plan shall include, but not be limited to, assessment of the following factors:
 - a. Types and quantities of hazardous substances disposed at the site.
 - b. Physical state, analytical summary, toxicological characteristics and other pertinent data defining hazardous substances present at the site.

- c. Methods and extent of the disposal operation including containment methods used, plans and/or photographs of site operation, perimeter and depth of disposal area; duration of disposal operation conducted (open burning, trench, surface impoundment, etc.).
- d. Observed release of contaminants to ground water, surface water or air, including sampling, to determine contaminant concentrations and extent of contaminant migration.
- e. Hydrogeologic factors to determine depth to groundwater, permeability of the unsaturated zone, distance to nearest surface water and slope of the disposal area and intervening terrain.
- f. Population and environment potentially affected:
 - (1.) Ground water use and population served by ground water sources within a three (3) mile radius of the perimeter of contaminant migration.
 - (2.) Surface water use and population served within a three (3) mile reach downstream of the perimeter of contaminant migration.
 - (3.) Population potentially affected by contaminant releases to the air within a four (4) mile radius of the perimeter of contaminant migration.
 - (4.) Distance from the site to sensitive environments such as a natural wetland, critical habitat for an endangered species or a National Wildlife Refuge.
- g. Fire and explosion hazard assessment of the site.
- h. Direct contact hazard assessment of the site.

3. The Investigation Plan must include cost estimates and a proposed schedule for completion of activities involved in the investigation. Following a review of the Plan, the Department may schedule a meeting which Respondents shall attend to discuss any revisions required by the Department. The Respondents will be given seven (7) days notice prior to the meeting. On or before a deadline date established in this review meeting, a revised Investigation Plan shall be submitted by the Respondents to the Department. Upon approval by the Department of the revised Investigation Plan, the Respondents shall begin required activities according to the revised Investigation Plan.

D. REMEDIAL ACTION SELECTION AND IMPLEMENTATION

1. Following completion of the investigation activities, a report providing an assessment of the hazard posed by the site to public health and the environment and proposing remedial action alternatives shall be submitted by the Respondents to the Department according to the Investigation Plan schedule. One of the alternatives that shall be addressed in the report shall be the removal of the source of contamination. This report will be referred to as a Hazard Evaluation/Remedial Action report (herein after referred to as "HE/RA"). Remedial action alternatives must include cost estimates and proposed schedules for completion of activities involved in remedial action implementation.
2. Assessment of each remedial action alternative must include consideration of the following factors:
 - a. The technological feasibility of each alternative;
 - b. The cost-effectiveness of each alternative;
 - c. The nature of the danger to the public health, safety, and the environment posed by the hazardous substances at the site; and


- d. The extent to which each alternative would achieve the goal of T.C.A. Section 68-46-206(d) which states, in part, "... The goal of any such action shall be cleanup and containment of the site through the elimination of the threat to public health, safety and the environment posed by the hazardous substance."
3. Following the Department's review of the HE/RA Report, the Department may schedule a meeting which the Respondents shall attend, to discuss any revisions required by the Department. The Respondents will be given seven (7) days notice prior to the meeting. On or before a deadline date established in this review meeting, a final HE/RA Report shall be submitted to the Department. Upon receipt of approval by the Department of the final HE/RA Report, the Respondents shall begin activities required by the final HE/RA Report, unless the Department determines no further action is necessary.
4. The HE/RA activities shall not be considered complete until the Department has reviewed these activities and issued a letter of acceptance to the Respondents.

E. SITE MONITORING AND MAINTENANCE

1. Where the Department determines a need for site monitoring and maintenance, the Respondents shall provide a Site Monitoring and Maintenance Plan (herein after referred to as "M/M Plan") which shall include a proposed schedule for completion of required activities and cost estimates within ninety (90) days of receipt of a request for said Plan by the Department.
2. Within forty-five (45) days of receipt of this M/M Plan by the Department, the Respondents shall attend a meeting with the Department to discuss any required revisions. On or before a deadline established in this review meeting, a revised M/M Plan shall be submitted by the Respondents to the Department. Upon receipt of approval by the Department, the revised M/M Plan will go into

- F. To the extent practicable, any investigation, identification, containment and clean-up, including monitoring and maintenance, shall be consistent with the national contingency plan promulgated pursuant to Section 105 of Public Law 96-510.
- G. Certain activities may be deemed critical by the Department and shall require observation by the Department. The Respondents shall provide sufficient notice to the Department to allow scheduling of personnel for these activities. The Department also reserves the right to observe any other activities required pursuant to this Order.
- H. Any failure to comply with approved schedules of activities required under this Order shall be a failure to comply with this Order.
- I. In this Order, any reference to the singular includes the plural.
- J. Further, I, James E. Word, do not waive any rights or authority available to me to assess the Respondents for liability for costs, expenditures, civil penalties or damages incurred by the State pursuant to this Order. I also reserve the right to order such further remedial action to be completed by the Respondents where it is determined that further remedial action is needed.

Issued in this office of the Commissioner of the Tennessee Department of Health and Environment this 15th day of March, 1986.



JAMES E. WORD, Commissioner
Tennessee Department of Health
and Environment

NOTICE OF RIGHTS

Respondents are hereby advised that in accordance with T.C.A. Section 68-46-215 they may secure a review of the necessity for or reasonableness of this Order by filing with the Commissioner, a written petition setting forth the grounds and reasons for objection and asking for a hearing in the matter involved before the Solid Waste Disposal Control Board. The Order shall become final and not subject to review unless the person or persons named herein shall file such petition for a

hearing no later than thirty (30) days after the date such Order is secured. Hearings will be conducted in accordance with the Tennessee Uniform Administrative Procedures Act.

Correspondence regarding this Order should be addressed to Mary E. Johnston, TERRA Bldg. 6th Floor, Assistant General Counsel, 150 Ninth Avenue, North, Nashville, Tennessee 37203 or telephone (615)741-0657.


Mary E. Johnston
Assistant General Counsel

MEJ/djv
SWM Order - Genesco

SITE SUMMARY
KENNON SITE (GENESCO)
TND 981473515

The Kennon Site (Genesco) is located near the junction of Split Log Road and Wilson Pike east of Brentwood in Williamson County, Tennessee.

The site is on the Kennon farm in an area of old phosphate pits where in 1978 General Adhesives, a subsidiary of Genesco, dumped approximately 800 drums of organic solvents, organic fillers, and adhesives. The pits were then filled. The state was informed of this unregistered landfill by Genesco in 1985.

Several private wells are still in use within three miles of the site and ground water contamination was discovered in early 1986. Residents with wells within a one mile radius (a population of approximately 118) were provided with bottled water at their discretion by Genesco until water lines could be run from Brentwood. Brentwood water is^{now} supplied by Metro Nashville.

TAM/ib

DRAFT

2

DRAFT

**RCRA SUMMARY
KENNON SITE (GENESCO)
TND 981473515**

The Kennon Site (Genesco) is a farm with phosphate pits that was used to dump approximately 800 drums of organic solvents, fillers, and adhesives in 1978. The site was never registered as a landfill and did not have a TSD permit.

TAM/ib

Facility name: KENNON SITE (GENESCO) TND 981473515

Location: Brentwood, Williamson County, Tennessee

EPA Region: IV

Person(s) in charge of the facility: _____

Name of Reviewer: Thomas A. Moss Date: 3/5/87

General description of the facility:
 (For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

The Kennon Site (Genesco) is a drum disposal site used by General Adhesives, a subsidiary of Genesco, in 1978 to dispose of approximately 800 drums of organic solvents, fillers, water-based adhesives by dumping them in phosphate pits and covering the pits at the site. The aquifer of concern is a carbonate, fracture-based, solutionally enlarged aquifer. A population of over 100 persons were on private wells within 3 miles of the site prior to the remedial action of water lines being run.

Scores: $S_M = 25$ ($S_{gw} = 43.2$ $S_{sw} = 5.3$ $S_a = N.R.$)

$S_{FE} = \text{NOT RATED}$

$S_{DC} = \text{NOT RATED}$

FIGURE 1
HRS COVER SHEET

Ground Water Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Rel. (Section)	
[1] Observed Release	0 45	1	45	45	3.1	
If observed release is given a score of 45, proceed to line [4] . If observed release is given a score of 0, proceed to line [2] .						
[2] Route Characteristics					3.2	
Depth to Aquifer of Concern	0 1 2 3	2		6		
Net Precipitation	0 1 2 3	1		3		
Permeability of the Unsaturated Zone	0 1 2 3	1		3		
Physical State	0 1 2 3	1		3		
Total Route Characteristics Score				15		
[3] Containment	0 1 2 3	1		3	3.3	
[4] Waste Characteristics					3.4	
Toxicity/Persistence	0 3 6 9 12 15 18	1	18	18		
Hazardous Waste Quantity	0 1 2 3 <u>4</u> 5 6 7 8	1	4	8		
Total Waste Characteristics Score			22	26		
[5] Targets					3.5	
Ground Water Use	0 1 2 <u>3</u>	3	9	9		
Distance to Nearest Well/Population Served	0 4 6 8 10 12 16 18 <u>20</u> 24 30 32 35 40	1	20	40		
Total Targets Score			29	48		
If line [1] is 45, multiply [2] x [3] x [5] If line [1] is 0, multiply [2] x [3] x [4] x [5]			24795	57,330		
Divide line [6] by 57,330 and multiply by 100			S _{pw} = 43.2 50.08			

FIGURE 2
GROUND WATER ROUTE WORK SHEET

Surface Water Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
1 Observed Release	0 45	1	0	45	4.1	
If observed release is given a value of 45, proceed to line 4 . If observed release is given a value of 0, proceed to line 2 .						
2 Route Characteristics					4.2	
Facility Slope and Intervening Terrain	0 1 2 3	1	1	3		
1-yr. 24-hr. Rainfall	0 1 2 3	1	2	3		
Distance to Nearest Surface Water	0 1 2 3	2	4	6		
Physical State	0 1 2 3	1	3	3		
Total Route Characteristics Score			10	15		
3 Containment	0 1 2 3	1	3	3	4.3	
4 Waste Characteristics					4.4	
Toxicity/Persistence	0 3 6 9 12 15 18	1	18	18		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1	4	8		
Total Waste Characteristics Score			22	26		
5 Targets					4.5	
Surface Water Use	0 1 2 3	3	6	9		
Distance to a Sensitive Environment	0 1 2 3	2	0	6		
Population Served/Distance to Water Intake Downstream	<div style="display: flex; align-items: center;"> <div style="margin-right: 10px;"> 0 4 6 8 10 12 16 18 20 24 30 32 35 40 </div> <div> } </div> </div>	1	0	40		
Total Targets Score			6	55		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			3860 3420	64,350		
7 Divide line 6 by 64,350 and multiply by 100			$S_{sw} = 5.3 \quad 6.15$			

FIGURE 7
SURFACE WATER ROUTE WORK SHEET

NOT RATED

L

Air Route Work Sheet											
Rating Factor	Assigned Value (Circle One)		Multi- plier	Score	Max. Score	Ref. (Section)					
1 Observed Release	0	45	1		45	5.1					
Date and Location:											
Sampling Protocol:											
If line 1 is 0, the $S_a = 0$. Enter on line 5 . If line 1 is 45, then proceed to line 2 .											
2 Waste Characteristics						5.2					
Reactivity and Incompatibility	0	1	2	3	1	3					
Toxicity	0	1	2	3	3	9					
Hazardous Waste Quantity	0	1	2	3	4	5	6	7	8	1	8
Total Waste Characteristics Score						20					
3 Targets						5.3					
Population Within 4-Mile Radius	0 9 12 15 18 21 24 27 30		1		30						
Distance to Sensitive Environment	0	1	2	3	2	6					
Land Use	0	1	2	3	1	3					
Total Targets Score						39					
4 Multiply 1 x 2 x 3						35,100					
5 Divide line 4 by 35,100 and multiply by 100 $S_a =$											

FIGURE 9
AIR ROUTE WORK SHEET

	S	S ²
Groundwater Route Score (S _{gw})	43.2 ^{50.08}	1866.24 ^{2508.01}
Surface Water Route Score (S _{sw})	5.3 ^{6.15}	28.09 ^{37.82}
Air Route Score (S _a)	NOT RATED	NOT RATED
$S_{gw}^2 + S_{sw}^2 + S_a^2$		1894.33 ^{2545.83}
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		43.5 ^{50.5}
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M =$		25.2 ^{29.19}

FIGURE 10
WORKSHEET FOR COMPUTING S_M

NOT RATED

8

Fire and Explosion Work Sheet												
Rating Factor	Assigned Value (Circle One)								Multi- plier	Score	Max. Score	Ref. (Section)
1 Containment	1	3							1		3	7.1
2 Waste Characteristics												7.2
Direct Evidence	0	3							1		3	
Ignitability	0	1	2	3					1		3	
Reactivity	0	1	2	3					1		3	
Incompatibility	0	1	2	3					1		3	
Hazardous Waste Quantity	0	1	2	3	4	5	6	7	8	1	8	
Total Waste Characteristics Score											20	
3 Targets												7.3
Distance to Nearest Population	0	1	2	3	4	5			1		5	
Distance to Nearest Building	0	1	2	3					1		3	
Distance to Sensitive Environment	0	1	2	3					1		3	
Land Use	0	1	2	3					1		3	
Population Within 2-Mile Radius	0	1	2	3	4	5			1		5	
Buildings Within 2-Mile Radius	0	1	2	3	4	5			1		5	
Total Targets Score											24	
4 Multiply 1 x 2 x 3											1,440	
5 Divide line 4 by 1,440 and multiply by 100											SFE =	

FIGURE 11
FIRE AND EXPLOSION WORK SHEET

NOT RATED

Direct Contact Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
<input type="checkbox"/> 1 Observed Incident	0 45	1		45	8.1	
If line <input type="checkbox"/> 1 is 45, proceed to line <input type="checkbox"/> 4 If line <input type="checkbox"/> 1 is 0, proceed to line <input type="checkbox"/> 2						
<input type="checkbox"/> 2 Accessibility	0 1 2 3	1		3	8.2	
<input type="checkbox"/> 3 Containment	0 15	1		15	8.3	
<input type="checkbox"/> 4 Waste Characteristics Toxicity	0 1 2 3	5		15	8.4	
<input type="checkbox"/> 5 Targets					8.5	
Population Within a 1-Mile Radius	0 1 2 3 4 5	4		20		
Distance to a Critical Habitat	0 1 2 3	4		12		
Total Targets Score				32		
<input type="checkbox"/> 6 If line <input type="checkbox"/> 1 is 45, multiply <input type="checkbox"/> 1 x <input type="checkbox"/> 4 x <input type="checkbox"/> 5 If line <input type="checkbox"/> 1 is 0, multiply <input type="checkbox"/> 2 x <input type="checkbox"/> 3 x <input type="checkbox"/> 4 x <input type="checkbox"/> 5				21,600		
<input type="checkbox"/> 7 Divide line <input type="checkbox"/> 6 by 21,600 and multiply by 100			SDC =			

FIGURE 12
DIRECT CONTACT WORK SHEET

DOCUMENTATION RECORDS
FOR
HAZARD RANKING SYSTEM

FACILITY NAME: KENNON SITE (GENESCO)
TND 981473515

FACILITY DESCRIPTION: COVERED PITS WITH DRUMS AND DUMPED LIQUIDS
IN FIELD

LOCATION: BRENTWOOD, TENNESSEE

DATE SCORED: March 5, 1987

PERSON SCORING: THOMAS A. MOSS

PRIMARY SOURCE(S) OF INFORMATION (e.g., EPA region, state, FIT, etc.):
State Superfund Files

FACTORS NOT SCORED DUE TO INSUFFICIENT INFORMATION:
Air, Fire and Explosion, Direct Contact

COMMENTS OR QUALIFICATIONS:

Water lines have been run to houses that were on private
wells in the area.

GROUND WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected (5 maximum):

Trans -1,2-dichloroethene; toluene; 1,1 dichloroethane and 1,1,1 trichloroethane detected in Hackett Spring and on site monitoring wells by State Superfund sampling (Ref. 1) and are known to be toxic (Ref. 2,3).

Rationale for attributing the contaminants to the facility:

Genesco has admitted dumping, drums which they say probably contained organic solvents (including 1,1,1 trichloroethane and toluene), rubber solvent, water based adhesives, and organic fillers (Ref. 4). 1,1,1 trichloroethane, toluene, trans-1,2-dichloroethane detected in on site monitoring wells (Ref. 1-Genesco Wells 8 and 9).

2 ROUTE CHARACTERISTICS

Depth to Aquifer of Concern

Name/description of aquifer(s) of concern:

The aquifer of concern ¹⁵ would be the Bigby Cannon Limestone (70-130 ft. thick) as well as the underlying Hermitage Formation (50-100 ft. thick), with no confining layer present. Sinkholes and vertical fractures are present, this carbonate aquifer ¹³ would be a fracture based, solutionally enlarged system. The Bigby-Cannon contains facies ranging from a microcrystalline limestone facies to medium and coarse grained limestone facies. The Hermitage Formation consists of thin bedded shaley limestone and sandy limestone. Underlying the Hermitage is more of the thick sequence of Middle and Lower Ordovician carbonates including the Carters Limestone, a dominantly cryptocrystalline limestone ranging to coarse grained, sometimes dolomitic. The Carters is approx. 70 ft. thick. The underlying Lebanon Limestone has similar lithology and is 30+ ft. thick (Ref. 5,6). The majority of the private wells have depths of 150-350 ft. (Ref. 7) and would be completed in the Hermitage Formation or Carters Limestone (Ref. 5,6).

Depth(s) from the ground surface to the highest seasonal level of the saturated zone (water table(s)) of the aquifer of concern:

Water depth in U.S.G.S. wells averaged 30 feet below land surface, average altitude 772 ft. with site at approx. 780 ft. (Ref. 7).

Depth from the ground surface to the lowest point of waste disposal/storage:

The phosphate pits and trenches in which the material were dumped are of unknown depth (Ref. 4). Assume default value of 6 ft.

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

48 inches (Ref. 8).

Mean annual lake or seasonal evaporation (list months for seasonal):

38 inches (Ref. 8).

Net precipitation (subtract the above figures):

10 inches

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

Soil in area is a salt loam, but is generally ^{only} 2 1/2 to 5 ft thick (REF. 7). Waste dumped in phosphate pits (REF. 4) probably at or near bedrock. The Bigby-Cannon Limestone has sinkhole development (REF. 5) and would be considered a Karst limestone.

Permeability associated with soil type:

> 10⁻³ cm/sec for Karst limestone (REF. 8).

with the soil layer absent or nearly so

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

Liquids dumped in pits at site by admission of company (REF. 4).

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

Landfill with no liner - drums and liquid dumped in unlined pits and trenches (REF. 4).

Method with highest score:

Landfill with no liner present.

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

1,1 dichloroethene and 1,1 dichloroethane detected in pits A and B and monitoring well # 8 on site by State Superfund Sampling (REF. 1).

Compound with highest score:

1,1 dichloroethene has a toxicity rating of 3 (REF. 3) and a persistence rating of 2 (REF. 8).

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

800 drums

Basis of estimating and/or computing waste quantity:

Genesco admission of ~~the~~ dumping approximately 800 55-gallon barrels of waste material containing organic solvents, organic fillers, and water-based adhesives at the site by their subsidiary General Adhesives (REF. 4).

5 TARGETS

Ground Water Use

Use(s) and aquifer(s) of concern within a 3-mile radius of the facility:

Drinking water with no municipal water presently available (REF. 10, 11).

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

Hackett Spring is used as a drinking water supply by the Hackett ^(REF. 12) house is on east side of Wilson Pike approx. 1000 ft north of Split Log Road (REF. 1 - sample points, REF. 13, 14).

Distance to above well or building:

Hackett Spring is contaminated (REF. 1), distance will be considered to be zero. Actual distance from pits is approx. 1500 ft (REF. 13, 14).

Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

31 houses identified not on municipal water ^{within a one mile radius} which required water lines run and service connections (REF. 4 sample points map, REF. 10, 11). Using 3.8 people/house, this would give a population of 118 ^{within a one mile radius} and additional population ^{within a three mile radius}.

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

None identified (REF. 15)

Total population served by ground water within a 3-mile radius:

118 +

600

SURFACE WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

None identified

Rationale for attributing the contaminants to the facility:

N/A

* * *

2 ROUTE CHARACTERISTICS

Facility Slope and Intervening Terrain

Average slope of facility in percent:

60 ft in 1800 ft for 3.3% slope (REF. 13, 14).

Name/description of nearest downslope surface water:

Unnamed creek entering the Little Hurpeth River north of the junction of Wilson Pike and Split Log Road (REF. 13, 14).

Average slope of terrain between facility and above-cited surface water body in percent:

80 ft in 1800 ft for 4% slope (REF. 13, 14).

Is the facility located either totally or partially in surface water?

No (REF. 13, 14).

Is the facility completely surrounded by areas of higher elevation?

No (REF. 13, 14).

1-Year 24-Hour Rainfall in Inches

3 inches (REF. 8).

Distance to Nearest Downslope Surface Water

0.4 miles from site to where surface drainage enters unnamed tributary of Little Harpeth River (REF.13,14).

Physical State of Waste

Liquids dumped in pits at site by admission of company (REF.4).

* * *

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

Landfill not adequately covered and no diversion system present — drums and liquid emptied into pits and covered with no documentation indicating adequate cap (REF.4).

Method with highest score:

Landfill not covered, no diversion system present

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

1,1 dichloroethene and 1,1 dichloroethane detected in pits A and B and monitoring well #8 on site by State Superfund Sampling (REF.1).

Compound with highest score:

1,1 dichloroethene has a toxicity rating of 3 (REF.3) and a persistence rating of 2 (REF.8).

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

800 drums

Basis of estimating and/or computing waste quantity:

Genesco admission of the dumping of approximately 800 55-gallon barrels of waste material containing organic solvents, organic fillers, and water-based adhesives at the site by their subsidiary 6 General Adhesives (REF.4).

5 TARGETS

Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:
Recreational use of the Little Harpeth River between Split Log Road and Concord Road (REF. 15).

Is there tidal influence?

No (REF. 13, 14).

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

None identified (REF. 13, 14).

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

None identified (REF. 13, 14).

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

None identified (REF. ~~15~~). 16

Population Served by Surface Water

Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:

None identified (REF. 17)

Computation of land area irrigated by above-cited intake(s) and conversion to population (1.5 people per acre):

None identified (REF. 15).

Total population served:

N/A

Name/description of nearest of above water bodies:

N/A

Distance to above-cited intakes, measured in stream miles:

N/A

NOT RATED

AIR ROUTE

1 OBSERVED RELEASE

Contaminants detected:

Date and Location of detection of contaminants:

Methods used to detect the contaminants:

Rationale for attributing the contaminants to the site:

* * *

2 WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

Most incompatible pair of compounds:

Toxicity

Most toxic compound:

Hazardous Waste Quantity

Total quantity of hazardous waste:

Basis of estimating and/or computing waste quantity:

* * *

3 TARGETS

Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

0 to 4 mi 0 to 1 mi 0 to 1/2 mi 0 to 1/4 mi

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

Distance to critical habitat of an endangered species, if 1 mile or less:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

NOT RATED
FIRE AND EXPLOSION

1 CONTAINMENT

Hazardous substances present:

Type of containment, if applicable:

* * *

2 WASTE CHARACTERISTICS

Direct Evidence

Type of instrument and measurements:

Ignitability

Compound used:

Reactivity

Most reactive compound:

Incompatibility

Most incompatible pair of compounds:

* * *

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility:

Basis of estimating and/or computing waste quantity:

* * *

3 TARGETS

Distance to Nearest Population

Distance to Nearest Building

Distance to Sensitive Environment

Distance to wetlands:

Distance to critical habitat:

Land Use

Distance to commercial/industrial area, if 1 mile or less:

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

Distance to residential area, if 2 miles or less:

Distance to agricultural land in production within past 5 years, if 1 mile or less:

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

Population Within 2-Mile Radius

Buildings Within 2-Mile Radius

NOT RATED

DIRECT CONTACT

1 OBSERVED INCIDENT

Date, location, and pertinent details of incident:

* * *

2 ACCESSIBILITY

Describe type of barrier(s):

* * *

3 CONTAINMENT

Type of containment, if applicable:

* * *

4 WASTE CHARACTERISTICS

Toxicity

Compounds evaluated:

Compound with highest score:

* * *

5 TARGETS

Population within one-mile radius

Distance to critical habitat (of endangered species)

Disc--Higgs/GrndW2

REFERENCES

1. State Superfund Sampling Results for Kennon Site (Genesco) with Sample Points Map for Wells/Springs

1A. Geology Associates sample results from Kennon site (see attached page 4)

2. G. Hawley, revised (1981): Condensed Chemical Dictionary, Tenth Edition; Van Nostrand Reinhold Company.

3. N.I. Sax (1984): Dangerous Properties of Industrial Materials, 6th Edition; Van Nostrand Reinhold Company.

6/21/85

4. Letter from Ralph Masely, Genesco to Tom Tiesler, ~~Genesco~~ DSWM; Re: Chemical Waste Site once used by a Division of Genesco.

5. (1963) Franklin Quadrangle Geologic Map - GM 63-NE

~~8. (1977) Beaver Engineering~~

6. Beaver Engineering (1977): Bedrock Geology of the Nashville and Middle Tennessee Area.

7. 2/19/87 Letter from Roger W. Lee, U.S. Geological Survey to Todd Hughes, Jr., Dept. Health and Environment (Superfund) - Data on Observation Wells.

Domestic well data, Geology & Miller Plan for Investigation of the Kennon Site, Dec 1972

8. (1984) Uncontrolled Hazardous Waste Site Ranking System, A Users Manual (HW-10); U.S.E.P.A.
9. (1964) Soil Survey of Williamson County, Tennessee; Series 1961, no. 5; U.S. Dept. of Agriculture Soil Conservation Service.
10. 2/19/86 Letter from Frank W. Clifton, Jr. to Brentwood City Manager to Don ~~Shack~~ Shackles Tn. Div. Superfund; Re: Cost Estimates for Water Lines
11. 7/28/86 Letter from Ralph Masely, Genesco to Frank W. Clifton, Jr., Brentwood City Manager Re: Service Connections.
12. 3/6/87 Conversation of Thomas A. Moss DSF with Ronnie L. Bowers, DSF; Re: ~~Sample~~ Kennon Site (Genesco) Sample Results, Water
13. (1981) Franklin Quadrangle Topographic Map 63 NE
14. (1957) Nolensville Quadrangle Topographic Map 70 NW

15. 3/10/87 Telephone Conversation of Thomas A. Moss, DSF with Robin Bowie, Williamson County Soil Conservation Service; Re: Surface and Groundwater Use for Irrigation in the Area of the Genesco Site.

16. 12/19/85 Letter from Robert M. Hatcher, TWRA to Gordon S. Caruthers, DSWM with attachments: Critical Wildlife Habitat of Tennessee, U.S. Fish and Wildlife Service.

17. (1978) Water Quality Management Plan for the Lower Cumberland River Basin, Tn. Division of Water Quality Control.

18. Commissioners Order (Genesco Inc./Emmett & Rose Kennon. Order No 66 30 13

POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT				I. IDENTIFICATION	
PART 1 - SITE LOCATION AND INSPECTION INFORMATION				01 STATE TN	02 SITE NUMBER 981473515
II. SITE NAME AND LOCATION					
01 SITE NAME (Legal, common, or descriptive name of site) WILSON PINE 1.2 MILES S.W. OF TOWN OF TAYLOR, RAILROAD		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER - THAT I-65 FROM NASHVILLE, EXIT NUMBER 5 LANE TO WILSON PIKE, SOUTH BY WILSON PIKE 1.2 MILES, SITE IS 0.5 MILES S.W. OF TOWN OF TAYLOR, RAILROAD			
03 CITY BENTON		04 STATE TN	05 ZIP CODE	06 COUNTY WILLIAMSON	07 COUNTY CODE
09 COORDINATES LATITUDE _____ LONGITUDE _____		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER _____ <input type="checkbox"/> G. UNKNOWN			
III. INSPECTION INFORMATION					
01 DATE OF INSPECTION 1 12 1986 MONTH DAY YEAR		02 SITE STATUS <input type="checkbox"/> ACTIVE <input checked="" type="checkbox"/> INACTIVE		03 YEARS OF OPERATION 1978 1 1979 BEGINNING YEAR ENDING YEAR	
04 AGENCY PERFORMING INSPECTION (Check all that apply)					
<input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR _____ (Name of firm) <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR _____ (Name of firm) <input checked="" type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR _____ (Name of firm) <input checked="" type="checkbox"/> G. OTHER GEOLAB, ASSOCIATES (FOR GENESCO) (Specify)					
05 CHIEF INSPECTOR RONNIE BOWERS		06 TITLE ENVIRONMENTAL SPEC		07 ORGANIZATION SUPERFUND	
09 OTHER INSPECTORS TODD HUGHES		10 TITLE GEOLOGIST		11 ORGANIZATION SUPERFUND	
WAYNE MCCOY		PROJECT MANAGER		EDGE	
MARK LLOYD				GEOLAB ASSOCIATES	
13 SITE REPRESENTATIVES INTERVIEWED ROBERT MURPHY		14 TITLE SAFETY DIRECTOR		15 ADDRESS GENESCO INC, GENESCO PARK NASHVILLE TN 37202	
EMMETT KENLON		SITE OWNER		2934 SIDCO DRIVE, NASHVILLE	
17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT		18 TIME OF INSPECTION		19 WEATHER CONDITIONS	
IV. INFORMATION AVAILABLE FROM					
01 CONTACT CHARLES POWERS		02 OF (Agency/Organization) TDHE - SUPERFUND		03 TELEPHONE NO. (615) 741 6288	
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM WILLIAM FORBES		05 AGENCY SUPERFUND	06 ORGANIZATION TDHE	07 TELEPHONE NO. 741 6288	08 DATE 3 8 87 MONTH DAY YEAR



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 2 - WASTE INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 981473515

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES (Check all that apply) <input type="checkbox"/> A SOLID <input type="checkbox"/> B POWDER, FINES <input type="checkbox"/> C SLUDGE <input type="checkbox"/> D OTHER (Specify) _____ <input type="checkbox"/> E SLURRY <input checked="" type="checkbox"/> F LIQUID <input type="checkbox"/> G GAS	02 WASTE QUANTITY AT SITE (Measures of waste quantities must be independent) TONS _____ CUBIC YARDS _____ NO. OF DRUMS <u>± - 800</u>	03 WASTE CHARACTERISTICS (Check all that apply) <input checked="" type="checkbox"/> A TOXIC <input type="checkbox"/> B CORROSIVE <input type="checkbox"/> C RADIOACTIVE <input checked="" type="checkbox"/> D PERSISTENT <input type="checkbox"/> E SOLUBLE <input type="checkbox"/> F INFECTIOUS <input type="checkbox"/> G FLAMMABLE <input type="checkbox"/> H IGNITABLE <input type="checkbox"/> I HIGHLY VOLATILE <input type="checkbox"/> J EXPLOSIVE <input type="checkbox"/> K REACTIVE <input type="checkbox"/> L INCOMPATIBLE <input type="checkbox"/> M NOT APPLICABLE
---	---	--

III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE			
OLW	OILY WASTE			
SOL	SOLVENTS			
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
	ARSENIC	7440382			0.217 PPM
	LEAD				8 PPM
	CHROMIUM	7440473			14 PPM
	TRANS 1,2 DICHLOROETHANE				
✓	1,1,1 TRICHLOROETHANE	25223891			6950 PPM
	1,1 DICHLOROETHANE				280 PPM
	1,2 DICHLOROETHANE				59 PPM
	TOLUENE	108983			29434 PPM
	BIS(2ETHYLBENXYL)PHTHAATE				940 PPM
	NAPHTHALENE	91203			110 PPM
	ETHYLBENZENE	100414			
	TRICHLOROETHYLENE	79016			44 PPM
	ACETONE				4980 PPM
	BENZENE				6522 PPM
	METHYL ETHYL KETONE				9285 PPM
	TETRACHLOROETHYLENE				14911 PPM

V. FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS	ARSENIC	7440382	FDS		
FDS	CHROMIUM	7440473	FDS		
FDS	NAPHTHALENE	91203	FDS		
FDS	TOLUENE	570000	FDS		

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Gov. fund file 94507 analytical Results from IT, specialized
Ref # 1



POTENTIAL HAZARDOUS WASTE SITE.
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 981473515

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: 1/28/86) ☐ POTENTIAL ☒ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION
Genesco admitted dumping 800 +/- gallons of wastes containing organic solvents, organic fillers, rubber solvents and water based adhesives. Analytical data from 20 monitoring wells, Hachett Spring and off site wells verify the release (Ref # 1, 2, 3, 4)

01 ☐ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION
The Kannon site drain in a southeasterly direction toward the Little Harpeth River. Surface drainage enters an area tributary to the Little Harpeth. 4 mile from the site Hachett Spring flows southeasterly into the Little Harpeth River, and is down gradient to the site. Ref 13, 14

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: 1/28/86) ☐ POTENTIAL ☒ ALLEGED

03 AREA POTENTIALLY AFFECTED: 200 +/- (Acres) 04 NARRATIVE DESCRIPTION
Soil samples taken on site by State Superintending Engineer 22/23, 24, 1976 confirm soil contamination. (Ref #1) It was reported that only 2 acres of a 146 acre tract were used as a disposal site.

01 ☐ G. DRINKING WATER CONTAMINATION 02 ☒ OBSERVED (DATE: 1/28/86) ☐ POTENTIAL ☒ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 118 04 NARRATIVE DESCRIPTION
31 residents are identified as recipients of city water as a result of contamination of ground water. Calculating 3.8 persons per acre and X 31 acres = 118 persons affected (Ref #1 sample points map, REF 10, 11)

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION



**POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS**

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 9814 73515

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☐ K. DAMAGE TO FAUNA 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION (include name(s) of species)

01 ☐ L. CONTAMINATION OF FOOD CHAIN 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

This particular fenced in tract of land encompassing the disposal area is used as a pasture for cattle.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES 02 ☐ OBSERVED (DATE: 1/22/86) ☐ POTENTIAL ☒ ALLEGED
(Spills/Runoff/Standing liquids, Leaking drums)

03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION
Approximately 4800 Barrels of contaminated wastes were disposed of at the Kennon site. 50 to 80 barrels were buried and the remaining 420 to 750 barrels were poured into 6' deep trenches and then covered with soil. No liners in pits or trenches.

01 ☒ N. DAMAGE TO OFFSITE PROPERTY 02 ☐ OBSERVED (DATE: 1/28/86) ☐ POTENTIAL ☒ ALLEGED
04 NARRATIVE DESCRIPTION

Several private drinking water wells and springs have been contaminated with the same hazardous substances found on the Kennon site. (Ref # 1, 13, 14)

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING 02 ☐ OBSERVED (DATE: 5/21/85) ☐ POTENTIAL ☒ ALLEGED
04 NARRATIVE DESCRIPTION

Division of Solid Waste management received a letter dated 5/21/85 from Ralph Wmsley, Director of Safety, Genesco Inc., reporting that Genesco had dumped approximately 800 drums of contamin. wastes on the Emmett Kennon site in Bartwood, TN. (Ref # 1)

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: 118 +

IV. COMMENTS

Population count has not been conducted, however it is known that 31 residences are being connected to municipal water supply therefore using the 3.8 person per household, 118 persons are affected

V. SOURCES OF INFORMATION (Cite specific references e.g., state files, sample analysis reports)

Superfund central file # 94506



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 981473515

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE (Specify)				
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input checked="" type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCENERATION	<input type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	NO
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL	800	BARRELS	<input type="checkbox"/> F. SOLVENT RECOVERY	06 AREA OF SITE
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	2+ - (Acres)
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER (Specify)	
<input type="checkbox"/> I. OTHER (Specify)				

07 COMMENTS

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)

☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☒ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

During 1978 approximately 50 drums of contaminated wastes were buried on the Kennon site. Another 750 drums of the same wastes were poured into an old phosphate pit and several other 6' deep trenches. The pit and trenches both unlined were then covered with soil.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☐ YES ☐ NO

02 COMMENTS

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis reports)

Superfund file # 94508 — letter from Ralph Mastey, Genesco to Tom Tiesler Re: Off Site Disposal



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE TN 02 SITE NUMBER 981473515

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY (Check as applicable)	02 STATUS	03 DISTANCE TO SITE															
<table border="0"><tr><td>SURFACE</td><td>WELL</td></tr><tr><td>COMMUNITY</td><td>A. <input type="checkbox"/> B. <input checked="" type="checkbox"/></td></tr><tr><td>NON-COMMUNITY <input checked="" type="checkbox"/></td><td>C. <input type="checkbox"/> D. <input type="checkbox"/></td></tr></table>	SURFACE	WELL	COMMUNITY	A. <input type="checkbox"/> B. <input checked="" type="checkbox"/>	NON-COMMUNITY <input checked="" type="checkbox"/>	C. <input type="checkbox"/> D. <input type="checkbox"/>	<table border="0"><tr><td>ENDANGERED</td><td>AFFECTED</td><td>MONITORED</td></tr><tr><td>A. <input checked="" type="checkbox"/></td><td>B. <input type="checkbox"/></td><td>C. <input type="checkbox"/></td></tr><tr><td>D. <input type="checkbox"/></td><td>E. <input type="checkbox"/></td><td>F. <input type="checkbox"/></td></tr></table>	ENDANGERED	AFFECTED	MONITORED	A. <input checked="" type="checkbox"/>	B. <input type="checkbox"/>	C. <input type="checkbox"/>	D. <input type="checkbox"/>	E. <input type="checkbox"/>	F. <input type="checkbox"/>	A. <u>0.1500</u> (mi) B. _____ (mi)
SURFACE	WELL																
COMMUNITY	A. <input type="checkbox"/> B. <input checked="" type="checkbox"/>																
NON-COMMUNITY <input checked="" type="checkbox"/>	C. <input type="checkbox"/> D. <input type="checkbox"/>																
ENDANGERED	AFFECTED	MONITORED															
A. <input checked="" type="checkbox"/>	B. <input type="checkbox"/>	C. <input type="checkbox"/>															
D. <input type="checkbox"/>	E. <input type="checkbox"/>	F. <input type="checkbox"/>															

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)					
<input checked="" type="checkbox"/> A. ONLY SOURCE FOR DRINKING (Other sources available) COMMERCIAL, INDUSTRIAL, IRRIGATION (No other water sources available)					
<input type="checkbox"/> B. DRINKING (Other sources available) COMMERCIAL, INDUSTRIAL, IRRIGATION (No other water sources available)					
<input type="checkbox"/> C. COMMERCIAL, INDUSTRIAL, IRRIGATION (Limited other sources available)					
<input type="checkbox"/> D. NOT USED, UNUSEABLE					
02 POPULATION SERVED BY GROUND WATER <u>118</u>			03 DISTANCE TO NEAREST DRINKING WATER WELL <u>0</u> (1500 ft) (mi)		
04 DEPTH TO GROUNDWATER <u>30</u> (ft)	05 DIRECTION OF GROUNDWATER FLOW <u>Southwesterly</u>		06 DEPTH TO AQUIFER OF CONCERN <u>30</u> (ft)	07 POTENTIAL YIELD OF AQUIFER _____ (gpd)	08 SOLE SOURCE AQUIFER <input type="checkbox"/> YES <input type="checkbox"/> NO

09 DESCRIPTION OF WELLS (Including usage, depth, and location relative to population and buildings)

Domestic wells in the area are generally cased 20-25 (ft) into the bedrock with unsecured open hole extending to depths of a few hundred ft to more than 2000 ft.

10 RECHARGE AREA		11 DISCHARGE AREA	
<input type="checkbox"/> YES	COMMENTS	<input type="checkbox"/> YES	COMMENTS
<input type="checkbox"/> NO		<input type="checkbox"/> NO	

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)			
<input type="checkbox"/> A. RESERVOIR, RECREATION DRINKING WATER SOURCE			
<input type="checkbox"/> B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCES			
<input type="checkbox"/> C. COMMERCIAL, INDUSTRIAL			
<input type="checkbox"/> D. NOT CURRENTLY USED			
02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER			
NAME: <u>Little Harpeth River</u>		AFFECTED <input type="checkbox"/>	DISTANCE TO SITE <u>✓</u> (mi)
		<input type="checkbox"/>	_____ (mi)
		<input type="checkbox"/>	_____ (mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

NO Demographics

01 TOTAL POPULATION WITHIN			02 DISTANCE TO NEAREST POPULATION
ONE (1) MILE OF SITE	TWO (2) MILES OF SITE	THREE (3) MILES OF SITE	_____ (mi)
A. _____ NO. OF PERSONS	B. _____ NO. OF PERSONS	C. _____ NO. OF PERSONS	
03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE _____			
04 DISTANCE TO NEAREST OFF-SITE BUILDING _____ (mi)			
05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)			



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

TN 981473515

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A. 10^{-6} - 10^{-8} cm/sec ☐ B. 10^{-4} - 10^{-6} cm/sec ☐ C. 10^{-4} - 10^{-3} cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE (Less than 10^{-10} cm/sec) ☒ B. RELATIVELY IMPERMEABLE (10^{-10} - 10^{-6} cm/sec) ☐ C. RELATIVELY PERMEABLE (10^{-6} - 10^{-4} cm/sec) ☐ D. VERY PERMEABLE (Greater than 10^{-4} cm/sec)

$> 10^{-3}$ cm/sec for Karst limestone

03 DEPTH TO BEDROCK

15 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

(ft)

05 SOIL pH

06 NET PRECIPITATION

10 (in)

07 ONE YEAR 24 HOUR RAINFALL

3 (in)

08 SLOPE
SITE SLOPE

3.3 %

DIRECTION OF SITE SLOPE

SOUTH WEST

TERRAIN AVERAGE SLOPE

4 %

09 FLOOD POTENTIAL

SITE IS IN YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

✓

ESTUARINE

NON IDENTIFIED

OTHER

A. (mi)

B. (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

NONE IDENTIFIED (mi)

ENDANGERED SPECIES:

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL/STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. (mi)

B. (mi)

C. (mi)

D. (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

The Kennon site is a 2+-acre parcel within the 146 acre property located in Rural Williamson county and owned by Emmitt and Rose Kennon. This area is an important farming commodity is livestock. The fenced tract containing the disposal area is currently used as a pasture for cattle. The area (primarily along the Wilson Pike/Split Log Road) contains several old farm houses as well as several new residences. The residences are situated on four to ten acre tracts.

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Superfund file #94508



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 9814 73515

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	9	IT Corporation 5815 Middlebrook Knoxville TN	REF INCLUDED (1)
SURFACE WATER			
WASTE	13	Specialized Assays, 206 12th Ave S Nashville TN	Ref 1
AIR			
RUNOFF			
SPILL			
SOIL	4	IT Corporation, 5815 Middlebrook Pktn Knoxville Tenn	REF #1
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

NO PHOTOGRAPHS

01 TYPE <input type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF _____ (Name of organization or individual)
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS Reference 13-14

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

✓

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Superfund Central File # 94508



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 981473515

II. CURRENT OWNER(S)

01 NAME Emmette Rose Kennon			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 2934 Sideco Drive			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY Nashville			06 STATE TN			07 ZIP CODE 37204			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		

III. PREVIOUS OWNER(S) (List most recent first)

01 NAME			02 D+B NUMBER			01 NAME			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		
01 NAME			02 D+B NUMBER			01 NAME			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		
01 NAME			02 D+B NUMBER			01 NAME			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		

V. SOURCES OF INFORMATION (One specific reference e.g., state files, sample analysis, reports)

State superfund file (contaminated area) deed of record
FILE NO. 94-508



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 981473515

II. CURRENT OPERATOR (Provide if different from owner)				OPERATOR'S PARENT COMPANY (If applicable)			
01 NAME SAME AS OWNER		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					
III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)				PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)			
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)			



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 981473515

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
GENESCO	TND001981240				
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
GENESCO PARK					
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
NASHVILLE	TN	37202			
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
GENESCO	TND001367549				
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
GENESCO PARK					
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
NASHVILLE	TN	37202			
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

GENESCO FILE #94508 CENTRAL SUPERFUND FILES, NASHVILLE CENTRAL OFFICE



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 981473515

II PAST RESPONSE ACTIVITIES (Continued)

01 ☒ R. BARRIER WALLS CONSTRUCTED

02 DATE JANUARY 1986

03 AGENCY OWNER (GERAGHTY MILLER)

04 DESCRIPTION A continuous silt screen was constructed during 1/1986 along a fence directly down slope from the source area. Screen was designed to prevent transport of contaminated sediment off site. REF #

01 ☐ S. CAPPING/COVERING

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ T. BULK TANKAGE REPAIRED

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ U. GROUT CURTAIN CONSTRUCTED

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ V. BOTTOM SEALED

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ W. GAS CONTROL

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ X. FIRE CONTROL

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ Y. LEACHATE TREATMENT

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ Z. AREA EVACUATED

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ 1. ACCESS TO SITE RESTRICTED

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☐ 2. POPULATION RELOCATED

02 DATE

03 AGENCY

04 DESCRIPTION

01 ☒ 3. OTHER REMEDIAL ACTIVITIES

02 DATE

03 AGENCY

04 DESCRIPTION

Geraghty & Miller was retained by Genesco in June 1986 to conduct a ground water investigation of the Kennon site. Preliminary investigations have been made by Geological Associates and the State Superfund Program. The USGS is presently conducting a Regional Study of the area. REF #

Municipal water lines are being constructed in the community to all houses identified in the area as using groundwater. REF #

III. SOURCES OF INFORMATION (Cite specific references: e.g., state files, sample analysis reports)

Superfund Control File 94-508



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 981473515

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☒ YES ☐ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

State of Tennessee issued Commission's order to Emmett
& Rose Kennon 2934 Sides Drive Nashville TN, 37204

To Genesco Inc, (agent for service of process, W.C. O'Connor
Genesco Park, Nashville Tenn. 37202. The order stipulates
that the Respondents address the following:

- A. Immediate Remedial measures.
- B. Initial assessment
- C. Investigation program
- D. Remedial action selection and Implementation
- E. Site monitoring & maintenance.

Ref # 15

III. SOURCES OF INFORMATION (Check specific references, e.g., State files, sample analysis, reports)

State super fund file 94580 Commission's order

REF. 1

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 6, 1986
PROJECT CODE: ITEK 21683
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site Pit A, 1-22-86, 1:30

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

<u>Compound</u>	<u>Concentration</u> (ppb)	<u>Compound</u>	<u>Concentration</u> (ppb)
acrolein	ND	1,1-dichloroethene	290.
acrylonitrile	ND	trans-1,2-dichloroethene	3,000.
benzene	200.	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	300.
carbon tetrachloride	ND	methylene chloride	340.
chlorobenzene	14.	1,1,2,2-tetrachloroethane	ND
chloroethane	750.	tetrachloroethene	110.
2-chloroethylvinyl ether	ND	toluene	120,000.
chloroform	ND	1,1,1-trichloroethane	2,000.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	75.
1,1-dichloroethane	4,300.	vinyl chloride	<10.
1,2-dichloroethane	1,200.		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Sworn to and subscribed before me this 6th
day of February, 1986
My commission expires January 16, 1988

Notary Public

Approved by

Laboratory Manager

Title





CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 6, 1986
PROJECT CODE: ITEK 21683
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site Pit B, Grab Soil, 1-22-86, 11:30


VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS



<u>Compound</u>	<u>Concentration (ppb)</u>	<u>Compound</u>	<u>Concentration (ppb)</u>
acrolein	ND	1,1-dichloroethene	3,300.
acrylonitrile	ND	trans-1,2-dichloroethene	1,300.
benzene	1,000.	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	19,000.
carbon tetrachloride	ND	methylene chloride	3,300.
chlorobenzene	530.	1,1,2,2-tetrachloroethane	ND
chloroethane	ND	tetrachloroethene	220,000.
2-chloroethylvinyl ether	ND	toluene	6,200,000.
chloroform	<250.	1,1,1-trichloroethane	160,000.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	6,900.
1,1-dichloroethane	950.	vinyl chloride	ND
1,2-dichloroethane	11,000.		

Remarks: ND = Not detected.

<250. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Sworn to and subscribed before me this 6th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved 
Laboratory Manager
Title



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 10, 1986
PROJECT CODE: TEK 21702
ORDER NUMBER: TN Contract FA-1313

Sample Description: Two (2) water samples and one (1) soil sample received
January 29, 1986

Concentration units are mg/liter (ppm) unless otherwise stated


PRIORITY POLLUTANT METALS


	Kennon Site, 7-28-86		
	Field #1 Hackett Spring 9:15	Field #3, Seep (water) 10:30	Field #3, Seep (soil) 10:30 (microgram, ppm)
Antimony	<0.001	<0.002*	<0.05
Arsenic	<0.001	0.217	18.
Beryllium	<0.002	0.010	0.69
Cadmium	<0.001	<0.001	<0.03
Chromium	<0.01	0.15	9.3
Copper	<0.002	0.088	6.5
Lead	<0.01	0.12	7.6
Mercury	<0.001	<0.001	0.048
Nickel	<0.01	<0.01	8.3
Selenium	<0.001	<0.03*	<0.3*
Silver	<0.002	<0.002	<0.1
Thallium	<0.02	<0.02	<0.6
Zinc	<0.001	0.519	30.
Cyanide	<0.01	0.01	0.20

* Detection limits higher than normal due to sample matrix interferences.

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 10th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Director
Title

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 10, 1986
PROJECT CODE: ITEK 21702
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site, Field #1, Hackett Spring, 1-28-86, 9:15

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS


<u>Compound</u>	<u>Concentration (ppb)</u>	<u>Compound</u>	<u>Concentration (ppb)</u>
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	10.
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	ND
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	ND	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	ND
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	ND
1,1-dichloroethane	<10.	vinyl chloride	ND
1,2-dichloroethane	ND		


Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)


Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 10th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Director
Title





5815 Middlebrook Pike • Knoxville, Tennessee 37921 • 615-588-6401

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 11, 1986
PROJECT CODE: ITEK 21765
ORDER NUMBER: TN Contract FA-1363
Job #41504

Sample Description: Kennon Site, Hackett Spring, Field #1, 2-7-86, 9:00

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (ppb)	Compound	Concentration (ppb)
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	70.
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	ND
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	<10.	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	13.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	<10.
1,1-dichloroethane	26.	vinyl chloride	ND
1,2-dichloroethane	<10.		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-6403

Sworn to and subscribed before me this 11th
day of February, 1986
My commission expires January 15, 1988

[Signature]
Notary Public

[Signature]
Approved by
Laboratory Manager
Title



ANALYTICAL SERVICE

5615 Middlebrook Pike • Knoxville, Tennessee 37921 • 615-588-6401



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 26, 1986
PROJECT CODE: ITEK 21854
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site, Field #17, Well #8, 2-21-86, 10:30

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (ppb)	Compound	Concentration (ppb)
acrolein	ND	1,1-dichloroethene	13. ✓
acrylonitrile	ND	trans-1,2-dichloroethene	350. ✓
benzene	<10.	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	<10.
carbon tetrachloride	ND	methylene chloride	<10. ✓
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	370. ~ 400	tetrachloroethene	<10.
2-chloroethylvinyl ether	ND	toluene	1,600. test failed
chloroform	<10.	1,1,1-trichloroethane	57. ✓
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	ND
1,1-dichloroethane	200. ✓	vinyl chloride	ND
1,2-dichloroethane	22. ✓		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 26th
day of February, 1986
My commission expires January 16, 1988

Notary Public

Approved by

Laboratory Manager

Title



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: March 18, 1986
PROJECT CODE: ITEK 21983
ORDER NUMBER: TN Contract FA-1353

Sample Description: Field #50, Kennon Site, Myatt Well, 3-13-86, 9:20

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (ppb)	Compound	Concentration (ppb)
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	ND
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	ND
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	ND	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	ND
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	ND
1,1-dichloroethane	ND	vinyl chloride	ND
1,2-dichloroethane	ND		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-3403

Sworn to and subscribed before me this 18th
day of March, 1986
My commission expires January 16, 1988

[Signature]
Notary Public

[Signature]
Approved by
Laboratory Manager

Title



ANALYTICAL SERVICES

5415 Middlebrook Pike • Knoxville, Tennessee 37921 • 615-588-6401



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: March 25, 1986
PROJECT CODE: ITEK 22002
ORDER NUMBER: TN Contract FA-1353

Sample Description: Kennon Site, Hackett Spring, 3-13-86, 2:00

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (ppb)	Compound	Concentration (ppb)
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	66.
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	ND
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	<10.	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	22.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	<10.
1,1-dichloroethane	26.	vinyl chloride	ND
1,2-dichloroethane	<10.		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 25th
day of March, 1986
My commission expires January 16, 1988

Notary Public

Approved by

Laboratory Manager

Title



Accredited by the American Association for Laboratory Accreditation in the chemical field of testing, as listed in the current AALA Directory of Accredited Laboratories

CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: April 1, 1986
PROJECT CODE: ITEK 22038
ORDER NUMBER: TN Contract FA-1353
Job #409374.01.71.89

Sample Description: Field #61, Kennon Site, Hackett Sp., 3-15-86, 2:15

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS

Compound	Concentration (ppb)	Compound	Concentration (ppb)
acrolein	ND	1,1-dichloroethene	ND
acrylonitrile	ND	trans-1,2-dichloroethene	41.
benzene	ND	1,2-dichloropropane	ND
bromodichloromethane	ND	cis-1,3-dichloropropene	ND
bromoform	ND	trans-1,3-dichloropropene	ND
bromomethane	ND	ethyl benzene	ND
carbon tetrachloride	ND	methylene chloride	<10.
chlorobenzene	ND	1,1,2,2-tetrachloroethane	ND
chloroethane	<10.	tetrachloroethene	ND
2-chloroethylvinyl ether	ND	toluene	ND
chloroform	ND	1,1,1-trichloroethane	17.
chloromethane	ND	1,1,2-trichloroethane	ND
dibromochloromethane	ND	trichloroethene	<10.
1,1-dichloroethane	24.	vinyl chloride	ND
1,2-dichloroethane	ND		

Remarks: ND = Not detected.

<10. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 1st
day of April, 1986

My commission expires January 16, 1988

Notary Public

Approved by

Laboratory Manager

True



ORGANIC LABORATORY ANALYSIS REPORT

Field Log No. _____ Sampling Agency SWM

Laboratory
Sample No. 1787 H Date Collected 3-19-86 Date Received: 3-20-86

Sampled Collected By: RLB Date Completed 3-21-86

Sample Source & Identification: Kanawha Site, Hackett Spring Field # 61
Grab Water Williamson Co.
State Superfund


UNSUBSTITUTED VOLATILE ORGANIC ANALYSIS

5.0 ML. SAMPLE FROM A SPECIALLY PREPARED VOA BOTTLE IS PURGED ONTO A TENAX TRAP USING ULTRA HIGH PURITY HELIUM. THE TRAP IS THEN DESORBED TO A TRACOR 260 GC AND ANALYZED USING A HALL 700A ELECTROCONDUCTIVITY DETECTOR IN THE CHLORIDE MODE.

COLUMN: 1% SP-1000/CARBOPACK B
STARTING TEMP: 50°C
INITIAL HOLD: 4 MIN.
PROGRAM RATE: 5° PER MIN.
FINAL TEMP: 200°C
FINAL HOLD: 10 MIN.

COMPOUND	RESULTS (ppb)	COMPOUND	RESULTS (ppb)
Chloromethane	ND	Dibromochloromethane	ND
Bromomethane	ND	1,1,2-Trichloroethane	ND
Vinyl Chloride	ND	Bromoform	ND
Chloroethane	ND	1,1,2,2-Tetrachloroethylene	ND
Methylene Chloride	0.8	1,1,2,2-Tetrachloroethane	ND
1,1-Dichloroethylene	0.6	Chlorobenzene	ND
Bromochloromethane	ND		
1,1-Dichloroethane	24.3		
Trans-1,2-Dichloroethylene	43.8		
Chloroform	ND		
1,2-Dichloroethane	1.8		
1,1,1-Trichloroethane	18.6		
Carbon Tetrachloride	ND		
Bromodichloromethane	ND		
Trichloroethylene	4.6		

Remarks: ND = none detected; NA = not analyzed, instrument unable to detect



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: June 10, 1986
PROJECT CODE: ITEK 22457
ORDER NUMBER: TN Contract FA-1353
PAGE 5 OF 5
Job #409374.01.71.89

Sample Description: Kennon Site, Field #99, Genesco Well #9, 5-31-86, 9:40

VOLATILE ORGANIC PRIORITY POLLUTANT ANALYSIS


<u>Compound</u>	<u>Concentration (ppb)</u>	<u>Compound</u>	<u>Concentration (ppb)</u>
benzene	ND	1,1-dichloroethene	ND
bromodichloromethane	ND	trans-1,2-dichloroethene	2,000.
bromoform	ND	1,2-dichloropropane	ND
bromomethane	ND	cis-1,3-dichloropropene	ND
carbon tetrachloride	ND	trans-1,3-dichloropropene	ND
chlorobenzene	ND	ethyl benzene	ND
chloroethane	1,200.	methylene chloride	ND
2-chloroethylvinyl ether	ND	1,1,2,2-tetrachloroethane	ND
chloroform	ND	tetrachloroethene	ND
chloromethane	ND	toluene	39,000.
dibromochloromethane	ND	1,1,1-trichloroethane	<1,000.
1,1-dichloroethane	1,600.	1,1,2-trichloroethane	ND
1,2-dichloroethane	<1,000.	trichloroethene	ND
		vinyl chloride	ND


Remarks: ND = Not detected.

<1,000. = Detected but at a level less than the quantitation limit. (Numerical value is the quantitation limit.)

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 10th
day of June, 1986
My commission expires January 16, 1988


Notary Public


Approved by
Laboratory Manager
Title





INTERNATIONAL
TECHNOLOGY
CORPORATION

ANALYTICAL SERVICES

5815 Middlebrook Pike • Knoxville Tennessee 37921 • 615 588 6401



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 10, 1986
PROJECT CODE: ITEK 21702
ORDER NUMBER: TN Contract FA-1353

Sample Description: Two (2) water samples and one (1) soil sample received
January 29, 1986

Concentration units are mg/liter (ppm) unless otherwise stated

PRIORITY POLLUTANT METALS

	Kennon Site, 1-28-86		
	Field #1 Hackett Spring 9:15	Field #3, Seep (water) 10:30	Field #3, Seep (soil) 10:30 (ug/gram, ppm)
Antimony	<0.001	<0.002*	<0.05
Arsenic	<0.001	0.217	18.
Beryllium	<0.002	0.010	0.69
Cadmium	<0.001	<0.001	<0.03
Chromium	<0.01	0.15	9.3
Copper	<0.002	0.088	6.5
Lead	<0.01	0.12	7.6
Mercury	<0.001	<0.001	0.048
Nickel	<0.01	<0.01	8.3
Selenium	<0.001	<0.03*	<0.3*
Silver	<0.002	<0.002	<0.1
Thallium	<0.02	<0.02	<0.6
Zinc	<0.001	0.519	30.
Cyanide	<0.01	0.01	0.20

* Detection limits higher than normal due to sample matrix interferences.

Copy to: Ronnie Bowers
Tennessee Department of Health & Environment
Division of Solid Waste Management
701 Broadway Street, 4th Floor Customs House
Nashville, TN 37219-5403

Sworn to and subscribed before me this 10th
day of February, 1986
My commission expires January 16, 1988

Notary Public

Approved by

Laboratory Director

Title



Accredited by the American Association for Laboratory Accreditation in the chemical
field of testing, as listed in the current AALA Directory of Accredited Laboratories

93-9-85



INTERNATIONAL
TECHNOLOGY
CORPORATION

ANALYTICAL SERVICES

5815 Middlebrook Pike • Knoxville, Tennessee 37921 • 615 588 6401



CERTIFICATE OF ANALYSIS

TO: IT Corporation
ATTN: Cliff Vaughan
312 Directors Drive
Knoxville, TN 37923

DATE REPORTED: February 6, 1986
PROJECT CODE: ITEK 21683
ORDER NUMBER: TN Contract FA-1353


Sample Description: Two (2) soil samples and one (1) waste sample received
January 24, 1986


Concentration units are $\mu\text{g}/\text{gram}$ (ppm)

PRIORITY POLLUTANT METALS

	Grab Waste Pit B 1-22-86, 11:30	Pit A 1-22-86, 1:30	Pit B 1-22-86, 11:30
Antimony	0.10	<0.1	<0.1
Arsenic	<0.1	9.0	9.0
Beryllium	<0.1	1.2	1.1
Cadmium	0.25	<0.1	<0.1
Chromium	14.	14.	14.
Copper	0.80	7.5	4.4
Lead	1.2	8.0	8.2
Mercury	<0.1	<0.1	0.12
Nickel	<0.7	11.	7.3
Selenium	<0.8	<1.	<1.
Silver	<0.1	<0.2	<0.2
Thallium	<1.	<2.	<2.
Zinc	560.	33.	37.
Total Cyanide	0.07	0.10	0.26

Sworn to and subscribed before me this 6th
day of February, 1986
My commission expires January 16, 1988


Notary Public


Approved by _____
Laboratory Manager
Title _____



Accredited by the American Association for Laboratory Accreditation in the chemical
field of testing as listed in the current AALA Directory of Accredited Laboratories

A detailed topographic map of the Brentwood area in Tennessee. The map features contour lines indicating elevation, with major peaks reaching over 1000 feet. Key landmarks include the Brentwood area, the Harpeth River, and the Crockett Springs National Golf & Country Club. Numerous sample points are marked with circles and labeled with names such as Owen, Green Hill, and Liberty. The map also shows various roads, including US Highway 41, and several cemeteries. A grid system is overlaid on the map, with letters A through J along the top and numbers 1 through 10 along the left side. The title 'SAMPLE POINTS' is prominently displayed at the top center.

APPENDIX A

RESULTS OF SAMPLE ANALYSES OF INSPECTION
PITS AND ON-SITE SEEP, JANUARY 1986

*Includes samples taken by company associates
and those taken by TDHE on Jan 21, 22, 23.*




FIGURE 5. INSPECTION PITS

Geraghty & Miller, Inc.

SOIL, SLUDGE AND SEMI SOLID WASTE

SAMPLING POINT	PIT B	PIT B	PIT B	PIT B	PIT D	PIT A	PIT A	KNN	SEEP
SAMPLE TYPE	SOIL	SOIL	WASTE	WASTE	SOIL	SOIL	SOIL	SOIL	
LABORATORY	IT	IT	IT	IT	IT	IT	IT	IT	
SAMPLED BY	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	
DATE SAMPLED	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	29-Jan-86	

ACID EXTRACTABLE ORGANICS (PPM)

2-CHLOROPHENOL	ND		ND		ND	ND	ND	ND
2,4-DICHLOROPHENOL	ND		ND		ND	ND	ND	ND
2,4-DIMETHYLPHENOL	ND		ND		ND	ND	ND	ND
4,6-DINITRO-3-CRESOL	ND		ND		ND	ND	ND	ND
2,4-DINITROPHENOL	ND		ND		ND	ND	ND	ND
2-NITROPHENOL	ND		ND		ND	ND	ND	ND
4-NITROPHENOL	ND		ND		ND	ND	ND	ND
P-CHLORO-M-CRESOL	ND		ND		ND	ND	ND	ND
PENTACHLOROPHENOL	ND		ND		ND	ND	ND	ND
PHENOL	ND		ND		ND	ND	ND	ND
2,4,6-TRICHLOROPHENOL	ND		ND		ND	ND	ND	ND

Geraghty & Miller, Inc.

SOIL, SLUDGE AND SEMI SOLID WASTE

SAMPLING POINT	PIT B	PIT B	PIT B	PIT B	PIT D	PIT A	PIT A	KNN	SEEP
SAMPLE TYPE	SOIL	SOIL	WASTE	WASTE	SOIL	SOIL	SOIL	SOIL	
LABORATORY	IT	IT	IT	IT	IT	IT	IT	IT	
SAMPLED BY	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	
DATE SAMPLED	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	28-Jan-86	

BASE NEUTRAL EXTRACTABLES (CONT.)

ENDRIN ALDEHYDE	ND		ND		ND	ND	ND	ND
FLUORANTHENE	ND		ND		ND	ND	ND	ND
FLUORENE	ND		ND		ND	ND	ND	ND
HEPTACHLOR	ND		ND		ND	ND	ND	ND
HEPTACHLOR EPOXIDE	ND		ND		ND	ND	ND	ND
HEXACHLOROBENZENE	ND		ND		ND	ND	ND	ND
HEXACHLOROCYCLOPENTADIENE	ND		ND		ND	ND	ND	ND
HEXACHLOROBUTADIENE	ND		ND		ND	ND	ND	ND
HEXACHLOROETHANE	ND		ND		ND	ND	ND	ND
INDENO(1,2,3-cd)PYRENE	ND		ND		ND	ND	ND	ND
ISOPHORONE	ND		ND		ND	ND	ND	ND
NAPHTHALENE	<1.00		110.000		ND	ND	ND	ND
NITROBENZENE	ND		ND		ND	ND	ND	ND
N-NITROSODIMETHYLAMINE	ND		ND		ND	ND	ND	ND
N-NITROSODIPHENYLAMINE	ND		(100.0		ND	ND	ND	ND
N-NITROSODI-N-PROPYLAMINE	ND		ND		ND	ND	ND	ND
PCB-1016	ND		ND		ND	ND	ND	ND
PCB-1221	ND		<4.00		ND	ND	ND	ND
PCB-1232	ND		ND		ND	ND	ND	ND
PCB-1242	ND		ND		ND	ND	ND	ND
PCB-1248	ND		ND		ND	ND	ND	ND
PCB-1254	ND		ND		ND	ND	ND	ND
PCB-1260	ND		ND		ND	ND	ND	ND
PHENANTHRENE	ND		ND		ND	ND	ND	ND
PYRENE	ND		ND		ND	ND	ND	ND
TOXAPHENE	ND		ND		ND	ND	ND	ND
1,2,4,-TRICHLOROBENZENE	ND		ND		ND	ND	ND	ND
METHOXYCHLOR	ND		ND		ND	ND	ND	ND

Geraghty & Miller, Inc.

SOIL, SLUDGE AND SEMI SOLID WASTE

SAMPLING POINT	PIT 3	PIT B	PIT 3	PIT B	PIT D	PIT A	PIT A	KNW	SEEP
SAMPLE TYPE	SOIL	SOIL	WASTE	WASTE	SOIL	SOIL	SOIL	SOIL	
LABORATORY	IT	IT	IT	IT	IT	IT	IT	IT	
SAMPLED BY	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	
DATE SAMPLED	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	23-Jan-86

BASE/NEUTRAL EXTRACTABLES (PPM)

ACENAPHTHENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
ACENAPHTYLENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
ANTHRACENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
ALDRIN	ND	ND	ND	ND	ND	ND	ND	ND	ND
BENZO(a)ANTHRACENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
BENZO(b)FLUORANTHENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
BENZO(k)FLUORANTHENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
BENZO(a)PYRENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
BENZO(ghi)PERYLENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
ALPHA-BHC	ND	ND	ND	ND	ND	ND	ND	ND	ND
BETA-BHC	ND	ND	ND	ND	ND	ND	ND	ND	ND
GAHHA-BHC	ND	ND	ND	ND	ND	ND	ND	ND	ND
DELTA-BHC	ND	ND	ND	ND	ND	ND	ND	ND	ND
BIS(2-CHLOROETHYL)ETHER	ND	ND	ND	ND	ND	ND	ND	ND	ND
BIS(2-CHLOROBUTOXY)METHANE	ND	ND	ND	ND	ND	ND	ND	ND	ND
BIS(2-ETHYLHEXYL)PHTHALATE	4,500		210,000		ND	ND	ND	ND	11.00
BIS(CHLOROMETHYL)ETHER	ND	ND	ND	ND	ND	ND	ND	ND	ND
BIS(2-CHLOROISOPROPYL)ETHER	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-BROMOPHENYL PHENYL ETHER	ND	ND	ND	ND	ND	ND	ND	ND	ND
BUTYL BENZYL PHTHALATE	ND	ND	ND	ND	ND	ND	ND	ND	ND
CHLORODANE	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-CHLORONAPHTHALENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-CHLOROPHENYL PHENYL ETHER	ND	ND	ND	ND	ND	ND	ND	ND	ND
CHRYSENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
4,4'-BDD	ND	ND	ND	ND	ND	ND	ND	ND	ND
4,4'-DDE	ND	ND	ND	ND	ND	ND	ND	ND	ND
4,4'-DDT	ND	ND	ND	ND	ND	ND	ND	ND	ND
DIBENZO(a,h)ANTHRACENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
DI-N-BUTYL PHTHALATE	1,000		<100.0		ND	ND	ND	ND	11.00
1,2-DICHLOROBENZENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-DICHLOROBENZENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-DICHLOROBENZENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
3,3'-DICHLOROBENZIDINE	ND	ND	ND	ND	ND	ND	ND	ND	ND
DIELDRIN	ND	ND	ND	ND	ND	ND	ND	ND	ND
DIETHYL PHTHALATE	<1.00		<100.0		ND	ND	ND	ND	ND
DIMETHYL PHTHALATE	ND	ND	ND	ND	ND	ND	ND	ND	ND
2,4-DINITROTOLUENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
2,6-DINITROTOLUENE	ND	ND	ND	ND	ND	ND	ND	ND	ND
DI-N-OCTYL PHTHALATE	ND	ND	ND	ND	ND	ND	ND	ND	ND
ALPHA-ENDOSULFAM	ND	ND	ND	ND	ND	ND	ND	ND	ND
BETA-ENDOSULFAM	ND	ND	ND	ND	ND	ND	ND	ND	ND
ENDOSULFAM SULFATE	ND	ND	ND	ND	ND	ND	ND	ND	ND
ENDRIN	ND	ND	<3.00		ND	ND	ND	ND	ND

Geraghty & Miller, Inc.

SOIL, SLUDGE AND SEMI SOLID WASTE

SAMPLING POINT	PIT B	PIT B	PIT B	PIT B	PIT D	PIT A	PIT A	KNN	SEEP
SAMPLE TYPE	SOIL	SOIL	WASTE	WASTE	SOIL	SOIL	SOIL	SOIL	
LABORATORY	IT	IT	IT	IT	IT	IT	IT	IT	
SAMPLED BY	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	
DATE SAMPLED	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	28-Jan-86	

METALS (PPM)

ANTIMONY		<0.10		0.100			<0.10	<0.050
ARSENIC	<0.001	9.000	<0.001	<0.10		0.002	9.000	18.000
BARIUM	0.120		0.080			0.140		
BERYLLIUM		1.100		<0.10			1.200	0.690
CADMIUM	<0.001	<0.10	0.006	0.250		0.003	<0.10	<0.030
CHROMIUM	<0.010	14.000	<0.010	14.000		<0.010	14.000	9.300
COPPER		4.400		0.900			7.500	6.500
LEAD	0.120	8.200	<0.010	1.200		<0.010	8.000	7.600
MERCURY	0.001	0.120	0.001	<0.10		0.002	<0.10	0.048
NICKEL		7.300		<0.70			11.000	8.300
SELENIUM	<0.001	<1.00	<0.001	<0.80		<0.001	<1.00	<0.30
SILVER	<0.002	<0.20	<0.002	<0.10		<0.002	<0.20	<0.10
THALLIUM		<2.00		<1.00			<2.00	<0.60
ZINC		37.000		550.000			33.000	30.000
CYANIDE		0.250		0.070			0.250	0.200

Geraghty & Miller, Inc.

SOIL, SLUDGE AND SEMI SOLID WASTE

SAMPLING POINT	PIT B	PIT B	PIT B	PIT D	PIT A	PIT A	KNN	SEEP
SAMPLE TYPE	SOIL	WASTE	WASTE	SOIL	SOIL	SOIL	SOIL	
LABORATORY	IT	IT	IT	IT	IT	IT	IT	
SAMPLED BY	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	TDHE	
DATE SAMPLED	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	28-Jan-86	

VOLATILE ORGANICS, PARTS PER MILLION (PPM)

1,1,1-TRICHLOROETHANE	<20000.0	0.430	ND	ND
1,1,2,2-TETRACHLOROETHANE	ND	ND	ND	ND
1,1,2-TRICHLOROETHANE	ND	ND	ND	ND
1,1-DICHLOROETHANE	ND	0.350	0.024	ND
1,1-DICHLOROETHYLENE	ND	0.026	ND	<0.010
1,2-DICHLOROETHYLENE				
1,2-DICHLOROETHANE	ND	ND	ND	ND
1,2-DICHLOROPROPANE	ND	ND	ND	ND
2-CHLOROETHYL VINYLETHER	ND	ND	ND	ND
ACETONE	ND	ND	ND	ND
ACROLEIN	ND	ND	ND	ND
ACRYLONITRILE	ND	ND	ND	ND
BENZENE	ND	<0.010	ND	ND
BROMODICHLOROMETHANE	ND	ND	ND	ND
BROMOFORM	ND	ND	ND	ND
BROMOMETHANE	ND	ND	ND	ND
CARBON TETRACHLORIDE	ND	ND	ND	ND
CHLOROBENZENE	ND	ND	ND	ND
CHLOROETHANE	ND	0.085	<0.010	ND
CHLOROFORM	ND	ND	ND	ND
CHLOROMETHANE	ND	ND	ND	ND
DICHLORODIFLUOROMETHANE				
DIBROMOCHLOROMETHANE	ND	ND	ND	ND
ETHYL ACETATE				
ETHYL BENZENE	ND	ND	ND	ND
HEXANE				
METHYLENE CHLORIDE	<20000.0	ND	0.090	0.027
METHYL ETHYL KETONE				
METHYL BROMIDE				
METHYL CHLORIDE				
TETRACHLOROETHYLENE	<20000.0	<0.010	<0.010	ND
TOLUENE	570000.000	<0.010	0.260	ND
TRANS-1,2-DICHLOROETHYLENE	ND	0.730	ND	<0.010
TRANS-1,2-DICHLOROMETHYLENE				
TRANS-1,3-DICHLOROPROPENE	ND	ND	ND	ND
TRICHLOROETHYLENE	<20000.0	0.100	0.010	ND
VINYL CHLORIDE	ND	ND	ND	ND
cis-1,3-DICHLOROPROPENE	ND	ND	ND	ND
XYLENE				

Geraghty & Miller, Inc.

SOIL, SLUDGE AND SEMI SOLID WASTE

SAMPLING POINT	PIT A3	B-3A	B-3B	B-3B	B-6	BC-4	C-3	C-5	PIT B
SAMPLE TYPE	SOIL	WASTE	SOIL	SLUDGE	WASTE	SLUDGE	WASTE	SLUDGE	SOIL
LABORATORY	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	IT
SAMPLED BY	GA	GA	GA	GA	GA	GA	GA	GA	TDHE
DATE SAMPLED	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	23-Jan-86	23-Jan-86	23-Jan-86	22-Jan-86

VOLATILE ORGANICS, PARTS PER MILLION (PPM)

[illegible]

Geraghty & Miller, Inc.

WATER AND LIQUID WASTE

SAMPLING POINT	PIT A	KNN SEEP
SAMPLE TYPE	WATER	WATER
LABORATORY	IT	IT
SAMPLED BY	TDHE	TDHE
DATE SAMPLED	22-Jan-86	29-Jan-86

ACID EXTRACTABLE ORGANICS (PPM)

4-CHLORO-3-METHYLPHENOL		
2-CHLOROPHENOL	ND	ND
2,4-DICHLOROPHENOL	ND	ND
2,4-DIMETHYLPHENOL	ND	ND
2-METHYL-4,6-DINITROPHENOL		
4,6-DINITRO-2-CRESOL	ND	ND
2,4-DINITROPHENOL	ND	ND
2-NITROPHENOL	ND	ND
4-NITROPHENOL	ND	ND
P-CHLORO-M-CRESOL	ND	ND
PENTACHLOROPHENOL	ND	ND
PHENOL	ND	ND
2,4,6-TRICHLOROPHENOL	ND	ND

Geraghty & Miller, Inc.

WATER AND LIQUID WASTE

SAMPLING POINT	PIT A	KNM SEEP
SAMPLE TYPE	WATER	WATER
LABORATORY	IT	IT
SAMPLED BY	TDHE	TDHE
DATE SAMPLED	22-Jan-86	28-Jan-86

BASE/NEUTRAL EXTRACTABLES (CONT.)

BETA-ENDOSULFAM		ND
ENDOSULFAM SULFATE		ND
ENDRIN ALDEHYDE		ND
FLUORANTHENE	ND	ND
FLUORENE	ND	ND
HEPTACHLOR		ND
HEPTACHLOR EPOXIDE	ND	ND
HEXACHLOROBENZENE	ND	ND
HEXACHLOROBUTADIENE	ND	ND
HEXACHLOROCYCLOPENTADIENE	ND	ND
HEXACHLOROETHANE	ND	ND
INDENO(1,2,3-cd)PYRENE	ND	ND
ISOPHORONE	ND	ND
NAPHTHALENE	<0.01	ND
NITROBENZENE	ND	ND
N-NITROSODIMETHYLAMINE	ND	ND
N-NITROSODIPHENYLAMINE	ND	ND
N-NITROSODI-N-PROPYLAMINE	ND	ND
PCB-1016		ND
PCB-1221		ND
PCB-1232		ND
PCB-1242		ND
PCB-1248		ND
PCB-1254		ND
PCB-1260		ND
PHENANTHRENE	ND	ND
PYRENE	ND	ND
TOXAPHENE		ND
1,2,4,-TRICHLOROBENZENE	ND	ND
METHOXYCHLOR		ND

Geraghty & Miller, Inc.

WATER AND LIQUID WASTE

SAMPLING POINT	TP-30	PIT A	KNM SEEP
SAMPLE TYPE	WATER	WATER	WATER
LABORATORY	GP ASSAYS	IT	IT
SAMPLED BY	SA	TDHE	TDHE
DATE SAMPLED	22-Jan-86	22-Jan-86	28-Jan-86

VOLATILE ORGANICS, PARTS PER MILLION (PPM) MILLION (PPM)

1,1,1-TRICHLOROETHANE	1.124	2.000	ND
1,1,2,2-TETRACHLOROETHANE	<0.010	ND	ND
1,1,2-TRICHLOROETHANE	<0.010	ND	ND
1,1-DICHLOROETHANE	0.985	4.300	ND
1,1-DICHLOROETHYLENE	0.033	0.290	ND
1,2-DICHLOROETHYLENE	1.950	ND	ND
1,2-DICHLOROETHANE	<0.010	1.200	<0.01
1,2-DICHLOROPROPANE		ND	ND
2-CHLOROETHYL VINYLETHER	<0.010	ND	ND
ACETONE	<0.1		
ACROLEIN	<0.1	ND	ND
ACRYLONITRILE	<0.1	ND	ND
BENZENE	<0.010	0.200	ND
BROMODICHLOROMETHANE	<0.010	ND	ND
BROMOFORM	<0.010	ND	ND
BROMOMETHANE		ND	ND
CARBON TETRACHLORIDE	<0.010	ND	ND
CHLOROBENZENE	<0.010	0.014	ND
CHLOROETHANE	<0.010	0.750	0.011
CHLOROFORM	<0.010	ND	ND
CHLOROMETHANE		ND	ND
DIBROMOCHLOROMETHANE	<0.010	ND	ND
DICHLORODIFLUOROMETHANE	<0.010		
ETHYL ACETATE	<0.1		
ETHYL BENZENE	<0.010	0.300	ND
HEXANE	<0.1		
METHYLENE CHLORIDE	<0.010	0.340	ND
METHYL ETHYL KETONE	<0.1		
METHYL BROMIDE	<0.010		
METHYL CHLORIDE	<0.010		
TETRACHLOROETHYLENE	<0.010	0.110	ND
TOLUENE	0.124	120.000	ND
TRANS-1,2-DICHLOROETHYLENE		2.000	0.011
TRANS-1,2-DICHLOROMETHYLENE			
TRANS-1,3-DICHLOROPROPENE		ND	ND
TRICHLOROETHYLENE	0.080	0.075	ND
VINYL CHLORIDE	<0.010	<0.010	ND
cis-1,3-DICHLOROPROPENE		ND	ND
TRANS 1,3-DICHLOROPROPENE		ND	ND
XYLENE			

Geraghty & Miller, Inc.

WATER AND LIQUID WASTE

SAMPLING POINT	PIT A	KNM SEEP
SAMPLE TYPE	WATER	WATER
LABORATORY	IT	IT
SAMPLED BY	TDHE	TDHE
DATE SAMPLED	22-Jan-86	28-Jan-86

METALS (PPM)

ANTIMONY	0.001	<2
ARSENIC	0.012	217.000- <i>217.000-217</i>
BERYLLIUM	<0.002	0.010
CADMIUM	<0.001	<0.001
CHROMIUM	<0.01	0.150
COPPER	0.011	0.088
LEAD	<0.01	0.120
MERCURY	<0.001	<0.001
NICKEL	<0.01	<0.01
SELENIUM	<0.004	<0.03
SILVER	<0.002	<0.002
THALLIUM	<0.02	<0.02
ZINC	0.012	0.519
CYANIDE	0.001	0.010

Geraghty & Miller, Inc.

WATER AND LIQUID WASTE

SAMPLING POINT	PIT A	KNN SEEP
SAMPLE TYPE	WATER	WATER
LABORATORY	IT	IT
SAMPLED BY	TDHE	TDHE
DATE SAMPLED	22-Jan-86	28-Jan-86

BASE/NEUTRAL EXTRACTABLES (PPM)

ACENAPHTHENE	ND	ND
ACENAPHTHYLENE	ND	ND
ANTHRACENE	ND	ND
ALDRIN		ND
BENZIDINE		
BENZO(a)ANTHRACENE	ND	ND
BENZO(b)FLUORANTHENE		ND
BENZO(k)FLUORANTHENE	ND	ND
BENZO(a)PYRENE		ND
BENZO(ghi)PERYLENE	ND	ND
BENZYL BUTYL PHTHALATE	ND	ND
ALPHA-BHC		ND
BETA-BHC		ND
GAMMA-BHC		ND
DELTA-BHC		ND
BIS(2-CHLOROETHYL)ETHER	ND	ND
BIS(2-CHLOROETHOXY)METHANE	ND	ND
BIS(2-ETHYLHEXYL)PHTHALATE	ND	ND
BIS(2-CHLOROISOPROPYL)ETHER	ND	ND
BIS(CHLOROMETHYL) ETHER		
4-BROMOPHENYL PHENYL ETHER	ND	ND
BUTYL BENZYL PHTHALATE		ND
CHLORODANE		ND
2-CHLORONAPHTHALENE	ND	ND
4-CHLOROPHENYL PHENYL ETHER	ND	ND
CHRYSENE	ND	ND
4,4'-DDD		ND
4,4'-DDE		ND
4,4'-DDT		ND
DIBENZO(a,h)ANTHRACENE	ND	ND
DI-N-BUTYL PHTHALATE	ND	ND
1,2-DICHLOROBENZENE	0.010	ND
1,3-DICHLOROBENZENE	ND	ND
1,4-DICHLOROBENZENE	ND	ND
3,3'-DICHLOROBENZIDINE	ND	ND
DIELDRIN		ND
DIETHYL PHTHALATE	<0.01	ND
DIMETHYL PHTHALATE	ND	ND
2,4-DINITROTOLUENE	ND	ND
2,6-DINITROTOLUENE	ND	ND
DI-N-OCTYL PHTHALATE	ND	ND
ALPHA-ENDOSULFAN		

Geraghty & Miller, Inc.

WATER AND LIQUID WASTE

JANUARY 1986

SAMPLING POINT	E-3	E-4	E-5	E-11	E-12	E-14	P-3	TP-23	TP-29
SAMPLE TYPE	WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER
LABORATORY	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS
SAMPLED BY	GA	GA	GA	GA	GA	GA	GA	GA	GA
DATE SAMPLED	24-Jan-86	24-Jan-86	24-Jan-86	24-Jan-86	24-Jan-86	24-Jan-86	24-Jan-86	22-Jan-86	22-Jan-86

VOLATILE ORGANICS, PARTS PER MILLION (PPM)

1,1,1-TRICHLOROETHANE	0.180	0.339	0.010	0.313	3.100	0.044	<0.010	<0.010	0.371
1,1,1,2,2-TETRACHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
1,1,2-TRICHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
1,1-DICHLOROETHANE	0.240	0.275	<0.010	0.087	1.117	<0.010	<0.010	0.052	0.311
1,1-DICHLOROETHYLENE	0.050	<0.010	<0.010	<0.010	0.149	<0.010	<0.010	<0.010	<0.010
1,2-DICHLOROETHYLENE	0.470	0.075	<0.010	0.028	0.541	<0.010	<0.010	<0.010	0.846
1,2-DICHLOROETHANE	<0.010	<0.010	<0.010	<0.010	0.373	<0.010	<0.010	<0.010	<0.010
1,2-DICHLOROPROPANE									
2-CHLOROETHYL VINYLETHYL ETHER	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
ACETONE	0.010	0.110	<0.1	<0.1	10.000	<0.1	<0.1	<0.1	14.700
ACROLEIN	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
ACRYLONITRILE	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BENZENE	<0.010	0.013	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
BROMODICHLOROMETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
BROMOFORM	<0.010	<0.010	0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
BROMOMETHANE									
CARBON TETRACHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROBENZENE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROFORM	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROMETHANE									
DIBROMOCHLOROMETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
DICHLORODIFLUOROMETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
ETHYL ACETATE	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	20.000
ETHYL BENZENE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
HEXANE	<0.1	<0.1	<0.1	<0.1	3.250	<0.1	<0.1	<0.1	<0.1
METHYLENE CHLORIDE	0.170	<0.010	<0.010	0.117	0.370	<0.010	0.029	<0.010	5.520
METHYL ETHYL KETONE	1.350	0.126	<0.1	<0.1	18.700	<0.1	<0.1	<0.1	7.740
METHYL BROMIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
METHYL CHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
TETRACHLOROETHYLENE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
TOLUENE	12.890	0.145	<0.010	<0.010	21.500	0.019	<0.010	<0.010	2.611
TRANS-1,2-DICHLOROETHYLENE									
TRANS-1,2-DICHLOROMETHYLENE									
TRANS-1,3-DICHLOROPROPENE									
TRICHLOROETHYLENE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
VINYL CHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
cis-1,3-DICHLOROPROPENE									
TRANS 1,3-DICHLOROPROPENE									
XYLENE					0.308				

JANUARY 1955

E-2
 WATER
 S. 45
 54
 24-34

1.6	<0
<0	<0
<0	<0
1.5	<0
0	<0
17	<0
1	<0
51	<0
<0	<0
<0	<0
<0	<0
<0	<0
<0	<0
<0	<0
<0	<0
0	<0
147	<0
1	<0
<0	<0

Geraghty & Miller, Inc.

WATER AND LIQUID WASTE

JANUARY 1986

SAMPLING POINT	BC-10	BC-12	BC-13	D-1	D-2	C-4	C-5	C-7	D-1
SAMPLE TYPE	WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER
LABORATORY	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS
SAMPLED BY	SA	SA	SA	SA	SA	SA	SA	SA	SA
DATE SAMPLED	23-Jan-86	23-Jan-86	23-Jan-86	23-Jan-86	23-Jan-86	23-Jan-86	23-Jan-86	23-Jan-86	23-Jan-86

VOLATILE ORGANICS, PARTS PER MILLION (PPM)

1,1,1-TRICHLOROETHANE	0.550	1.400	8.200	72.300	103.100	25.990	59.590	130.300	0.422
1,1,2,2-TETRACHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
1,1,2-TRICHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
1,1-DICHLOROETHANE	0.180	0.520	0.700	33.400	10.200	9.500	4.990	4.200	0.168
1,1-DICHLOROETHYLENE	0.010	<0.010	0.100	0.150	1.300	2.000	1.300	1.300	<0.010
1,2-DICHLOROETHYLENE	0.990	3.100	1.300	0.530	20.900	<0.010	4.800	2.300	0.450
1,2-DICHLOROETHANE	<0.010	<0.010	0.163	<0.010	2.195	<0.010	24.800	22.100	<0.010
1,2-DICHLOROPROPANE									
2-CHLOROETHYL VINYLETHER	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
ACETONE	<0.1	4.900	1.990	2.000	13.400	48.400	65.400	730.000	<0.1
ACROLEIN	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
ACRYLONITRILE	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BENZENE	<0.010	<0.010	0.095	<0.010	0.900	<0.010	2.300	3.400	<0.010
BROMODICHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
BROMOFORM	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
BROMOMETHANE									
CARBON TETRACHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROBENZENE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROFORM	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROMETHANE									
DIBROMOCHLOROMETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
DICHLORODIFLUOROMETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
ETHYL ACETATE	<0.1	5.900	1.300	22.100	4.500	17.700	21.300	52.300	<0.1
ETHYL BENZENE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
HEXANE	2.710	<0.1	1.800	17.200	12.900	18.000	2.300	4.100	<0.1
METHYLENE CHLORIDE	<0.010	1.000	0.110	5.200	9.500	2.400	63.500	43.800	0.032
METHYL ETHYL KETONE	<0.1	1.000	3.400	21.600	55.200	78.700	281.700	2056.000	<0.1
METHYL BROMIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
METHYL CHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
TETRACHLOROETHYLENE	0.440	<0.010	1.600	11.500	12.300	5.700	5.200	4.500	<0.010
TOLUENE	4.200	13.900	24.200	268.600	462.800	97.000	360.000	534.000	0.079
TRANS-1,2-DICHLOROETHYLENE									
TRANS-1,2-DICHLOROMETHYLENE									
TRANS-1,3-DICHLOROPROPENE									
TRICHLOROETHYLENE	0.060	<0.010	0.230	44.200	7.400	2.200	4.200	<0.010	0.302
VINYL CHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
cis-1,3-DICHLOROPROPENE									
TRANS 1,3-DICHLOROPROPENE									
XYLENE	0.810		2.400	6.000	9.000	5.200	3.620	3.220	

Geraghty & Miller, Inc.

WATER AND LIQUID WASTE

JANUARY 1986

SAMPLING POINT	PIT A3	A8-1	B-3	B-3A	B-3B *	B-4	BC-4	BC-10	BC-10
SAMPLE TYPE	WATER	WATER	LIQ WASTE	LIQ WASTE	LIQ WASTE	WATER	WATER	WATER	WATER
LABORATORY	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS	SP ASSAYS
SAMPLED BY	SA	SA	SA	SA	SA	SA	SA	SA	SA
DATE SAMPLED	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	22-Jan-86	23-Jan-86	23-Jan-86	23-Jan-86

VOLATILE ORGANICS, PARTS PER MILLION (PPM)

1,1,1-TRICHLOROETHANE	5.100	26.400	<0.010	315.400	59.500	14.500	129.000	1.650	0.550
1,1,1,2-TETRACHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
1,1,2-TRICHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
1,1-DICHLOROETHANE	7.100	5.300	<0.010	<0.010	4.200	3.300	280.000	1.400	0.130
1,1-DICHLOROETHYLENE	0.300	0.422	<0.010	<0.010	0.550	0.400	1.000	0.045	0.013
1,2-DICHLOROETHYLENE	5.400	9.300	<0.010	<0.010	10.100	31.500	1.300	1.200	0.990
1,2-DICHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	59.100	0.349	<0.010
1,2-DICHLOROPROPANE									
2-CHLOROETHYL VINYLETHER	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
ACETONE	29.400	85.500	<0.1	4980.000	317.900	91.200	49.600	345.000	<0.1
ACROLEIN	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
ACRYLONITRILE	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
BENZENE	0.800	0.535	<0.010	<0.010	1.100	<0.010	0.240	0.051	<0.010
BROMODICHLOROMETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
BROMOFORM	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
BROMOMETHANE									
CARBON TETRACHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROBENZENE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROFORM	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
CHLOROMETHANE									
DIBROMOCHLOROMETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
DICHLORODIFLUOROMETHANE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
ETHYL ACETATE	7.000	23.500	<0.1	<0.1	<0.1	5.900	9.600	25.300	<0.1
ETHYL BENZENE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
HEXANE	0.800	2.010	<0.1	<0.1	<0.1	<0.1	2.200	4.500	2.710
METHYLENE CHLORIDE	1.200	9.600	<0.010	894.000	13.900	12.600	35.800	0.547	<0.010
METHYL ETHYL KETONE	24.900	73.900	<0.1	9285.000	<0.1	79.900	135.000	340.000	<0.1
METHYL BROMIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
METHYL CHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
TETRACHLOROETHYLENE	<0.010	3.900	<0.010	14911.000	4.000	0.012	3.300	0.946	0.440
TOLUENE	108.200	491.400	183.000	29434.000	657.100	221.200	277.600	319.000	4.200
TRANS-1,2-DICHLOROETHYLENE									
TRANS-1,2-DICHLOROMETHYLENE									
TRANS-1,3-DICHLOROPROPENE									
TRICHLOROETHYLENE	<0.010	1.100	<0.010	<0.010	1.700	1.000	2.500	0.104	0.060
VINYL CHLORIDE	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
cis-1,3-DICHLOROPROPENE									
TRANS 1,3-DICHLOROPROPENE									
XYLENE	3.200	3.380		2.776	3.600	4.000	4.800	2.040	0.810

LIQ = LIQUID

SP ASSAY = SPECIALIZED ASSAYS, INC., NASHVILLE, TN

IT = IT ANALYTICAL SERVICES, KNOXVILLE, TN

<X DENOTES NOT DETECTED IN THE SPECIALIZED ASSAYS ANALYSES,
WHERE X IS THE LEVEL OF DETECTION

ND DENOTES NOT DETECTED IN THE IT ANALYSES. <X DENOTES THAT THE
CONSTITUENT WAS DETECTED BUT AT A LEVEL LESS THAN THE LEVEL OF
QUANTIFICATION, WHERE X IS THE LEVEL OF QUANTIFICATION

SUMMARY OF WASTE, SOIL AND WATER ANALYTICAL RESULTS FOR SAMPLES
OBTAINED DIRECTLY FROM INSPECTION PITS WITHIN DISPOSAL AREA

KENNON PROPERTY

February 22, 23 and 24, 1986

Brentwood, Williamson County, Tennessee

FIELD NO.	DATE COLLECTED	TIME COLLECTED	PIT LOCATION	LAB I.D. NO.	TYPE OF SAMPLE	TOTAL CONC. OF VOL. CONSTITUENTS ppm	NO. OF VOLATILE CONSTITUENTS DETECTED	ARSENIC ppm	CHROMIUM ppm	LEAD ppm
1	1/22/86	1015	A-3	281651	Soil	16.0	2	5.3	27.0	16.9
2	1/22/86	1015	A-3	281643	Water	194.4	12	(0.001	(0.005	(0.001
3	1/22/86	1025	B-3	281644	Liquid Waste	183	1	(0.001	0.03	0.01
4	1/22/86	1042	B-3A	281645	Liquid Waste	65,464	7	(0.001	11.2	0.50
5	1/22/86	1040	B-3A	281652	Semi-Solid Waste	6,632	5	6.2	30.5	20.6
6	1/22/86	1043	B-3B	281995	Soil	3,825	4	4.0	22.8	11.7
7	1/22/86	1053	B-3B	281996	Soil/Sludge	861	4	7.8	22.5	12.2
8	1/22/86	1054	B-3B	281646	Liquid Waste	1,074.55	11	0.003	(0.005	(0.001
9	1/22/86	1325	B-4	281647	Water	471.412	13	0.002	(0.005	0.002
10	1/22/86	1347	B-6	281997	Semi-Solid Material	23,134	4	0.90	17.2	11.9
11	1/22/86	1455	AB-1	281648	Water	737.847	14	(0.001	(0.005	(0.001
12	1/22/86	1504	TP-29	281649	Water	52.199	8	(0.001	(0.005	(0.001
13	1/22/86	1512	TP-30	281650	Water	4.006	6	(0.001	(0.005	(0.001
14	1/22/86	1514	TP-28	281951	Water	0.052	1	(0.001	(0.005	(0.001
16	1/23/86	0835	BC-4	281952	Water	993.7	15	0.003	0.005	0.002
17	1/23/86	0837	BC-4	281998	Soil/Sludge	129.5	4	8.2	26.5	16.7
18	1/23/86	0850	C-1	281953	Water	511.2	13	(0.001	(0.005	(0.001
19	1/23/86	0905	C-2	281954	Water	728.595	15	(0.001	(0.005	(0.001
20	1/23/86	0925	C-3	281999	Semi-Solid Waste	11,936	2	0.05	(0.02	1.0
21	1/23/86	0935	C-4	281955	Water	371.7	12	(0.001	(0.005	(0.001
22	1/23/86	0947	C-5	282000	Sludge	220,380	4	0.03	0.15	0.07
23	1/23/86	1005	C-6	281956	Water	925.32	15	0.002	(0.005	0.002
24	1/23/86	1030	C-7	281957	Water	3,591.32	14	0.002	(0.005	(0.001
25	1/23/86	1145	BC-10	281958	Water	1,042.132	15	0.004	(0.005	0.004
26	1/23/86	1425	BC-13	281959	Water	48.088	15	(0.001	(0.005	(0.001
27	1/23/86	1428	BC-12	281960	Water	31.62	8	(0.001	(0.005	(0.001
28	1/23/86	1432	BC-10	281961	Water	9.943	9	(0.001	(0.005	(0.001
29	1/23/86	1436	D-16	281962	Water	1.154	5	(0.001	(0.005	(0.001
30	1/23/86	1439	D-13	281963	Water	1.269	4	(0.001	(0.005	(0.001
31	1/23/86	1447	D-17	281964	Water	3.07	9	(0.001	(0.005	(0.001
32	1/23/86	1449	D-18	281965	Water	0.701	6	(0.001	(0.005	(0.001
33	1/23/86	1451	D-7	281966	Water	2,875.4	8	(0.001	(0.005	(0.001
34	1/23/86	1454	D-1	281967	Water	1.453	6	(0.001	(0.005	(0.001
35	1/23/86	1455	D-1	281968	Water	1.675	6	(0.001	(0.005	(0.001
36	1/23/86	1456	D-2	281969	Water	17.924	12	(0.001	(0.005	(0.001
37	1/23/86	1500	D-8	281970	Water	0.019	1	(0.001	(0.005	(0.001
38	1/24/86	1005	E-11	281971	Water	0.545	4	(0.001	(0.005	(0.001
39	1/24/86	1007	E-5	281972	Water	0.010	1	(0.001	(0.005	(0.001
40	1/24/86	1009	E-4	281973	Water	1.084	7	(0.001	(0.005	(0.001
41	1/24/86	1011	E-3	281974	Water	17.82	8	(0.001	(0.005	(0.001
42	1/24/86	1015	E-12	281975	Water	60.108	11	(0.001	(0.005	(0.001
43	1/24/86	1018	E-2	281976	Water	323.93	14	(0.001	(0.005	(0.001
44	1/24/86	1021	P-3	281977	Water	0.029	1	(0.001	(0.005	0.002
45	1/24/86	1024	E-14	281978	Water	0.063	2	(0.001	(0.005	(0.001

NOTE: (1) < designates 'less than'.

ENGINEERING, DESIGN & GEOSCIENCES GROUP, INC.

(2) There was no Field No. 15 collected.

4/2/86ls

REF. 2

The
Condensed Chemical
Dictionary

TENTH EDITION (1981)

Revised by

GESSNER G. HAWLEY



VAN NOSTRAND REINHOLD COMPANY
NEW YORK CINCINNATI TORONTO LONDON MELBOURNE

cars.
to skin and eyes; causes blistering.

Exists only at low temperature. F.p. -114°C ; b.p. -20°C ; solid at normal pressure to hexachlorobenzene. Carbon tetrachloride vapor and 10^{-3} mm Hg. Reaction with carbon; forms phosphorus.

rocene (ferrocenyl dichloride).
Solid; m.p. $93-95^{\circ}\text{C}$.

(phenyl)-1,3,5-triazin-2-yl chloride.
Solid; m.p. $159-160^{\circ}\text{C}$.

See aniline.

See chlorovinylidene.

diphenylmethane. See diphenylmethane.

benzoquinone (DDQ)
(N):C(CN).

Orange solid; m.p. $213-215^{\circ}\text{C}$.

Oxidizing agent for organic materials.

See dichloroethyl ether.

See dichloroethyl formal.

Mustard gas; dichloroethyl

b.p. 228°C ; f.p. 14°C ; sp. gr. 1.48 (104°C).

Hydrolyzed through sulfur chlorides and hydrogen chloride. Contains excess sulfur as a

Vesicant war gas; causes blindness! Can be decontaminated by bleaching powder. Vapor can be absorbed through

Poison gas; medicine.
(Rail) Poison gas label. Not acceptable.

(ClCH_2CH_2); SO_2 .
Solid; m.p. $179-181^{\circ}\text{C}$ ($14-15^{\circ}\text{C}$).
Soluble in alcohol, chloroform, carbon tetrachloride.
Irritant to eyes and skin.

2,2-dichloro-1,1-difluoroethyl methyl ether (methoxyfluorane) $\text{HCCl}_2\text{CF}_2\text{OCH}_3$.
Properties: Clear, colorless liquid; fruity odor; b.p. 104.65°C ; f.p. -35°C ; sp. gr. 1.4223 (25°C); completely stable in the presence of alkali, air, light, or moisture. Slightly soluble in water. Combustible.
Grade: N.D.
Use: Anesthetic.

dichlorodifluoromethane (difluorodichloromethane; fluorocarbon-12). CCl_2F_2 .
Properties: Colorless, odorless, noncorrosive gas. B.p. -29.8°C ; f.p. -158°C ; critical pressure 43.2 atm. Insoluble in water; soluble in most organic solvents. Nonflammable.

Derivation: (a) Reaction of carbon tetrachloride and anhydrous hydrogen fluoride, in the presence of an antimony halide catalyst; (b) high temperature chlorination of vinylidene fluoride (vinylidene fluorides made by addition of hydrogen fluoride to acetylene).
Grade: 99.9% min. purity.

Containers: Cylinders.
Hazard: Narcotic in high concentrations. Tolerance, 1000 ppm in air.

Uses: Refrigerant and air conditioner; plastics; blowing agent; low-temperature solvent; leak-detecting agent; freezing of foods by direct contact; chilling cocktail glasses.

Shipping regulations: (Rail, Air) Nonflammable Gas label.

See also chlorofluorocarbon.

1,3-dichloro-5,5-dimethylhydantoin (DDH)
 $\text{CINCONCIOC}(\text{CH}_3)_2$.

Properties: White powder with mild chlorine odor. M.p. approximately 130°C ; sublimes about 100°C without decomposition. Contains approximately 36% active chlorine. Slightly soluble in water with gradual liberation of hypochlorous acid; soluble in benzene, chloroform, ethylene dichloride, alcohol. Combustible, with evolution of chlorine at 210°C .
Derivation: Chlorination of dimethylhydantoin.
Grades: Technical.

Hazard: Toxic by inhalation. Tolerance, 0.2 mg per cubic meter of air. Skin irritant.

Uses: Household laundry bleach; water treatment; mild chlorinating agent; pharmaceutical intermediate; catalyst.

dichlorodimethylsilane. See dimethyldichlorosilane.

dichlorodiphenyldichloroethane. See TDE.

dichlorodiphenyldichloroethylene. See DDE.

dichlorodiphenyltrichloroethane. See DDT.

1,1-dichloroethane. See ethylidene chloride.

1,2-dichloroethane. See ethylene dichloride.

dichloroether. See dichloroethyl ether.

dichloroethoxymethane. See dichloroethyl formal.

1,2-dichloroethyl acetate $\text{CH}_3\text{COOCHClCH}_2\text{Cl}$.

Properties: Water-white liquid. Sp. gr. 1.296 (20°C); boiling range: $58-65^{\circ}\text{C}$ (13 mm); f.p. $< -32^{\circ}\text{C}$; refractive index 1.444 (20°C); b.p., dec. Flash point 307°F (152°C). Combustible. Miscible with alcohol and ethyl ether. Immiscible with water.

Hazard: Toxic by inhalation.

Use: Organic synthesis.

para-di(2-chloroethyl)aminophenylamine.

See melphalan.

dichloroethylarsine. See ethyldichloroarsine.

dichloroethyl carbonate $(\text{ClH}_2\text{CCH}_2\text{O})_2\text{CO}$.

Properties: Colorless liquid. Slowly hydrolyzed by alkalis. Volatile in steam. Sp. gr. 1.3506 (20°C); b.p. 240°C (partial decomposition). Insoluble in water.

Derivation: By heating ethylene chlorohydrin and trichloromethylchloroformate together (under reflux).

sym-dichloroethylene (1,2-dichloroethylene; acetylene dichloride). $\text{ClHC}=\text{CHCl}$. Exists as *cis* and *trans* isomers.

Properties: Colorless, low-boiling liquid. Pleasant odor. It decomposes slowly on exposure to air, light and moisture. Soluble in most organic solvents; slightly soluble in water. *Trans*-isomer: sp. gr. 1.257 ; b.p. $47-49^{\circ}\text{C}$. *Cis*-isomer: sp. gr. 1.282 ; b.p. $58-60^{\circ}\text{C}$. Flash point 39°F (3.9°C); f.p. -80°C .

Derivation: Two stereoisomeric compounds made by the partial chlorination of acetylene.

Grades: Technical; as *cis*, *trans*, and mixture of both. Containers: 300-, 550-lb drums.

Hazard: Moderately toxic by ingestion, inhalation and skin contact; irritant and narcotic in high concentrations. Tolerance, 200 ppm in air. Flammable, dangerous fire hazard.

Uses: General solvent for organic materials; dye extraction; perfumes; lacquers; thermoplastics; organic synthesis.

Shipping regulations: (Rail, Air) Flammable Liquid label.

sym-dichloroethyl ether (dichloroether; dichloroethyl oxide; 2,2'-dichlorodiethyl ether, bis(2-chloroethyl) ether) $\text{ClCH}_2\text{CH}_2\text{OCH}_2\text{CH}_2\text{Cl}$.

Properties: Colorless liquid. Odor like that of ethylene dichloride. B.p. 178.5°C ; sp. gr. 1.2220 (20°C); wt/gal 10.2 lb (20°C); refractive index 1.457 (20°C); flash point (closed cup) 131°F (55°C); f.p. -51.8°C . Autoignition temp. 696°F (368°C). Miscible with most organic solvents; insoluble in water. Combustible.

Derivation: Chlorination of ethyl ether.

Grades: Technical.

Containers: Glass bottles; iron drums; tank cars.

Hazard: Toxic by inhalation and ingestion; absorbed by skin; strong irritant. Tolerance, 5 ppm in air. Moderate fire hazard.

Uses: General solvent; selective solvent for production of high-grade lubricating oils; textile scouring

REF. 3

Dangerous Properties of Industrial Materials

Sixth Edition

N. IRVING SAX

Assisted by:

Benjamin Feiner/Joseph J. Fitzgerald/Thomas J. Haley/Elizabeth K. Weisburger



VAN NOSTRAND REINHOLD
New York

SYNS:

ACETYLENE
ETHINE

ETHYNE

TOXICITY DATA:

ihl-mam LCLo: 500000 ppm/5M

CODEN:

AEPPAE 138,65,28

OSHA Standard: Air: CL 2500 ppm FEREAC 39, 22001,74. DOT: Flammable Gas, Label: Flammable Gas FEREAC 41,57018,76. Occupational Exposure to Acetylene recm std: Air: CL 2500 ppm NTIS**. Reported in EPA TSCA Inventory, 1980.

THR: When mixed with O₂ in proportions of 40% or more, acetylene acts as a narcotic and has been used in anesthesia. Acetylene acts as a simple asphyxiant by diluting the O₂ in the air to a level which will not support life. However, the presence of impurities in commercial acetylene may result in the production of symptoms before an asphyxiant contribution is reached. Thus: 10% in air → slight intoxic; 20% → staggering gait; 30% → general incoordination; 33% → unconsciousness in 7 min; up to 80% → complete anesthesia, increased blood pressure, narcosis and stimulated respiration.

Dizziness, headache, mild gastric symptoms, and (in high conc) semi-asphyxia and brief loss of consciousness have all been reported. In general industrial practice, however, acetylene does not constitute a serious hazard. See argon for discussion of simple asphyxiants.

Fire Hazard: Very dangerous, when exposed to heat, flame or oxidizers.

Spontaneous Heating: No.

Explosion Hazard: Mod when exposed to heat or flame or by spont chemical reaction. At high pressures and even moderate temperatures, and in the absence of air acetylene has been known to decomp explosively. Incompatible with copper, brass, copper salts, copper carbide, pyrophoric Co, Hg, Hg salts, K, Ag and Ag salts, RbH, CsH, halogens, HNO₃, NaH, and halogens. Acetylene + halide + UV can explode. Molten K ignites in C₂H₂ and then explodes. C₂H₂ reacts vigorously with trifluoromethyl hypofluorite. With O₂, C₂H₂ can detonate very powerfully. See acetylides.

Disaster Hazard: Dangerous; when ignited it burns with an intensely hot flame; can react vigorously with oxidizing materials.

To Fight Fire: CO₂, water spray, or dry chemical. Stop flow of gas.

For further information see Vol. 1, No. 2 of *DPIM Report*.

ACETYLENE CHLORIDE

mf: CHCl₂; mw: 60.5

A gas. bp: -31°, vap. d: 2.0. mp: -126°.

SYN: CHLOROETHYNE

THR: Unk. Probably has anesthetic properties if inhaled. See also chlorinated HC, aliphatic.

Fire Hazard: Dangerous, by spont chemical reaction.

Spontaneous Heat: Spontaneously flammable in air.

Disaster Hazard: Dangerous; shock will explode it, when

heated to decomp it emits highly tox fumes of phosgene, can react vigorously with oxidizing materials.

ACETYLENEDICARBOXAMIDE

CAS RN: 543215

NIOSH #: AO 9900000

mf: C₄H₄N₂O₂; mw: 112.10

Produced by Str. Reticuli var. Aquamyceticus and is identical to Cellocidin

SYNS:

ACETYLENEDICARBOXYLIC ACID
DIAMIDE
AQUAMYCIN2-BUTYNYEDIAMIDE
CELLOCIDIN
LENAMYCIN

TOXICITY DATA:

ipr-mus LD50: 15 mg/kg
ivn-mus LD50: 11 mg/kg

CODEN:

ARZNAD 17,693,67
12VXA5 9,12,76

Reported in EPA TSCA Inventory, 1980.

THR: HIGH ivn, ipr.

Disaster Hazard: When heated to decomp it emits tox fumes of NO_x.

ACETYLENEDICARBOXYLIC ACID MONOPOTASSIUM SALT

CAS RN: 928041

NIOSH #: AP 0700000

mf: C₄H₃O₄·K; mw: 152.15

SYN: MONOPOTASSIUM SALT OF ACETYLENEDICARBOXYLIC ACID

TOXICITY DATA:

ori-mus LD50: 63 mg/kg
ipr-mus LD50: 32 mg/kg
ivn-mus LD50: 89 mg/kg

CODEN:

TXAPA9 17,733,70
TXAPA9 17,733,70
TXAPA9 17,733,70

Reported in EPA TSCA Inventory, 1980. EPA TSCA SE No. 12780263—File closed as of April, 1979.

THR: HIGH ori, ipr, ivn.

Disaster Hazard: When heated to decomp it emits acrid smoke and fumes, KO₂.

ACETYLENE DICHLORIDE

CAS RN: 540590

NIOSH #: KV 9360000

mf: C₂H₂Cl₂; mw: 96.94

SYNS:

1,2-DICHLOR-AETHEN (GERMAN)
DICHLORO-1,2-ETHYLENE
(FRENCH)SYM-DICHLOROETHYLENE
1,2-DICHLOROETHYLENE
NCI-C56031

TOXICITY DATA:

ori-rat LD50: 770 mg/kg
ipr-mus LD50: 2000 mg/kg

CODEN:

ARSIM* 20,10,66
JETOAS 7(4),247,74

Aquatic Toxicity Rating: TLM96:1000-100 ppm WQCHM* 3,-,74.

TLV: Air: 200 ppm DTLVS* 4,130,80. *Toxicology Review:* 27ZTAP 3,8,69. OSHA Standard: Air: TWA 200 ppm (SCP-H) FEREAC 39,23540,74. "NIOSH Manual of Analytical Methods" VOL 3 S110. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FEREAC 45,13646,80.

THR: MOD ori ipr.

Disas
tox

trans-

CAS F
mf: C₂Colorle
p: 36°Pd: 1.27
d: 3.34SYNS:
TRANS-I

TOXIC

ihl-hmn 7
10M:C

ipr-rat LI

ihl-mus L

ipr-mus L

ihl-cat LC

Reported

THR: H

sure to

weakn

promp

may re

Fire Haz

or oxid

Spontane**Explosion**

posed t

Disaster H

orously

To Fight

ACETYLE

CAS RN:

mf: C₂H₂E

Colorless t

d: 2.9638 (

SYNS:

MUTHMANN'S

1,1,2,2-TETRA

(GERMAN)

TETRABROMO

1,1,2,2-TETRA

(ITALIAN)

TOXICITY

skn-rbt 500 m

eye-rbt 100 m

dnr-esc 10 uL

skn-mus TDLo

1:NEO

ori-rbt LD50:1

TLV: Air: 1

TWA 1

ORM-A, 2

Manual of

in EPA T

Disaster Hazard: When heated to decomp it emits highly tox fumes of Cl^- .

trans-ACETYLENE DICHLORIDE

CAS RN: 156605 NIOSH #: KV 9400000
mf: $\text{C}_2\text{H}_2\text{Cl}_2$; mw: 96.94

Colorless liquid, pleasant odor. mp: -50° , bp: 48° , flash p: 36°F , autoign. temp.: 860°F , $\text{Iel} = 9.7\%$, $\text{uel} = 12.8\%$, d: 1.2743 @ $25^\circ/4^\circ$, vap. press: 400 mm @ 30.8° , vap. d: 3.34.

SYNS:

TRANS-1,2-DICHLOROETHYLENE

TOXICITY DATA: 3-2-1 CODEN:
ihl-hmn TCLo: 4800 mg/m³/10M: CNS AHBAAM 116,131,36
ipr-rat LD50: 7536 mg/kg TXCYAC 7(2),141,77
ihl-mus LCLo: 75000 mg/m³/2H AHBAAM 116,131,36
ipr-mus LD50: 4019 mg/kg TXCYAC 7(2),141,77
ihl-cat LCLo: 43000 mg/m³/6H AHBAAM 116,131,36

Reported in EPA TSCA Inventory, 1980.

THR: HIGH hmn chl (CNS). MOD ihl; LOW ipr. Exposure to high conc of vapor can cause nausea, vomiting, weakness, tremor and cramps. Recovery is usually prompt following removal from exposure. Dermatitis may result from de-fatting action on skin.

Fire Hazard: Dangerous when exposed to heat, flame or oxidizers.

Spontaneous Heating: No.

Explosion Hazard: Mod, in the form of vapor when exposed to flame.

Disaster Hazard: Dangerous; see chlorides; can react vigorously with oxidizing materials.

To Fight Fire: Water, foam; CO_2 , dry chemical.

ACETYLENE TETRABROMIDE

CAS RN: 79276 NIOSH #: KI 8225000
mf: $\text{C}_2\text{H}_2\text{Br}_4$; mw: 345.68

Colorless to yellow liquid. bp: 151° @ 54 mm, fp: -1° , d: 2.9638 @ $20^\circ/4^\circ$, autoign. temp.: 635°F .

SYNS:

MUTHMANN'S LIQUID 5-TETRABROMOETHANE
1,1,2,2-TETRABROMOETHAN 1,1,2,2-TETRABROMOETHANE
(GERMAN) 1,1,2,2-TETRABROMOETHAN
TETRABROMOACETYLENE (DUTCH)
1,1,2,2-TETRABROMOETANO
(ITALIAN)

TOXICITY DATA: 3 CODEN:
skn-rbt 500 mg/24H MOD AIHAAP 24,28,63
eye-rbt 100 mg MLD AIHAAP 24,28,63
dnr-esc 10 uL/disc MUREAV 41,61,76
skn-mus TDLo: 130 gm/kg/74W- JJINDS 63,1433,79
1: NEO
ori-ro: LD50: 400 mg/kg AMIHC 2,407,50

TLV: Air: 1 ppm DTLVS* 4.7,80. OSHA Standard: Air: TWA 1 ppm (SCP-I) FEREAC 39,23540,74. DOT: ORM-A, Label: None FEREAC 41,57018,76. "NIOSH Manual of Analytical Methods" VOL 3 S117. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Pre-

liminary Assessment Information Proposed Rule FER-REAC 45,13646,80. EPA TSCA 8E No. 10780254—Submission Received as of April, 1979.

THR: HIGH via ori and inh. It is irr and narcotic. An exper NEO. MUT data.

Fire Hazard: Low.

To Fight Fire: Water foam, fog, CO_2 , dry chemical.

Disaster Hazard: Dangerous; when heated it emits highly tox fumes of carbonyl bromide.

ACETYLENE TETRACHLORIDE

CAS RN: 79345 NIOSH #: KI 8575000
mf: $\text{C}_2\text{H}_2\text{Cl}_4$; mw: 167.84

Heavy, colorless, mobile liquid, chloroform-like odor. mp: -43.8° , bp: 146.4° , d: 1.600 @ $20^\circ/4^\circ$.

SYNS:

1,1,2,2-CZTEROCHLOROETAN 1,1,2,2-TETRACHLOROETHANE
(POLISH) (FRENCH)
1,1-DICHLORO-2,2-DICHLORO- SYM-TETRACHLOROETHANE
ETHANE 1,1,2,2-TETRACHLOROETHANE
NCI-C03554 1,1,2,2-TETRACHLOROETANO
(DUTCH) (ITALIAN)
1,1,2,2-TETRACHLORAETHAN TETRACHLORURE D'ACETYLENE
(GERMAN) (FRENCH)

TOXICITY DATA: 3 CODEN:
dnr-esc 10 uL/plate EVHPAZ 21,79,77
ori-rat TDLo: 42 gm/kg/78W-1:ETA NCITR* NCI-CG-TR-
27,78
ori-mus TDLo: 55 gm/kg/78W-1: CAR NCITR* NCI-CG-TR-
27,78
ori-mus TD: 110 gm/kg/78W-1: CAR NCITR* NCI-CG-TR-
27,78
ori-hmn TDLo: 30 mg/kg: CNS PCOC** -1110,66
ihl-hmn TCLo: 1000 mg/m³/30M: CNS AHBAAM 116,131,36
ihl-rat LCLo: 1000 ppm/4H JIHTAB 31,343,49
ihl-mus LCLo: 9000 mg/m³/40M AHBAAM 116,131,36
ipr-mus LDLo: 30 mg/kg CBCCI* 4,378,52
ori-dog LDLo: 300 mg/kg AJHYA2 16,325,32
ivn-dog LDLo: 56 mg/kg QJPPAL 7,205,34
ihl-cat LCLo: 19000 mg/m³/45M AHBAAM 116,131,36
scu-rbt LDLo: 500 mg/kg QJPPAL 7,205,34

Carcinogenic Determination: Animal positive IARC** 20,477,79. *Toxicology Review:* AIHAAP 40,A46,79; 27ZTAP 3,139,69. OSHA Standard: Air: TWA 5 ppm (skin) (SCP-I) FEREAC 39,23540,74. Occupational Exposure to 1,1,2,2-Tetrachloroethane recm std: Air: TWA 1 ppm NTIS**. NCI Carcinogenesis Bioassay Completed; Results positive: Mouse (NCITR* NCI-CG-TR-27,78). NCI Carcinogenesis Bioassay Completed; Results indefinite: Rat (NCITR* NCI-CG-TR-27,78). "NIOSH Manual of Analytical Methods" VOL 2 S124. NIOSH Current Intelligence Bulletin 27, 1978. Reported in EPA TSCA Inventory, 1980.

THR: HIGH via oral and inhal routes; MOD via dermal route. This is generally considered the most toxic of the common chlorinated HC. It has a fairly strong irritant action on mu mem of the eyes and upper respiratory tract; a conc of 3 ppm produces a detectable odor, thus an initial warning effect. Its narcotic action is stronger than that of chloroform, but because of

DICHLORODIPROPYLSTANNANE

CAS RN: 867367 NIOSH #: WH 7255000
mf: $C_6H_{14}Cl_2Sn$; mw: 275.79

Colorless crystals. Sol in organic solvents. mp. 81°.

SYNS:

DICHLORODIPROPYL TIN
DIPROPYL TIN CHLORIDE

DI-N-PROPYL TIN DICHLORIDE
DIPROPYL TIN DICHLORIDE

TOXICITY DATA: 3 CODEN:
ori-rat LDLo: 160 mg/kg BJIMAG 15.15.58

OSHA Standard: Air: TWA 100 ug(Sn)/m³ (skin)
(SCP-X) FEREAC 39,23540,74. Occupational Exposure
to Organotin Compounds recm sid: Air: TWA
0.1 mg(Sn)/m³ NTIS**.

THR: HIGH ori. See also tin compounds and chlorides.
Disaster Hazard: When heated to decomp it emits tox
fumes of Cl⁻.

1,4-DICHLORO-2,3-EPOXYBUTANE

CAS RN: 3583479 NIOSH #: EJ 8050000
mf: $C_4H_6Cl_2O$; mw: 141.00

SYN: BUTAN-1,4-DICHLORO-2,3-EPOXY

TOXICITY DATA: 2 CODEN:
mmo-klp 5 mmol/L MUREAV 89,269,81
skn-rbt 10 mg/24H open MLD AIHAAP 23,95,62
mma-sat 1 mmol/L ARTODN 41,249,79
ori-rat LDLo: 710 mg/kg AIHAAP 23,95,62
skn-rbt LDLo: 2830 mg/kg AIHAAP 23,95,62

THR: An irr in rbt skn. MUT data. MOD via oral, inhal
and dermal routes.

Disaster Hazard: Dangerous; see chlorides.

DICHLOROETHANE

CAS RN: 1300216 NIOSH #: KH 9800000
mf: $C_2H_4Cl_2$; mw: 98.96

Lel = 5.6%; uel = 11.4%.

TOXICITY DATA: 2 CODEN:
ori-rat LD50: 1120 mg/kg HYSAAY 32,349,67
ori-mus LD50: 625 mg/kg HYSAAY 32,349,67
ihl-mus LCLo: 10 gm/m³ GISAAA 20(8),19,55
skn-rbt LD50: 3890 mg/kg UCDS** 3/23/70
ihl-rat TCLo: 6000 ppm (6-15D preg) TXAPA9 28,452,74
TER
ihl-rat TCLo: 6000 ppm (6-15D preg) TXAPA9 28,452,74

THR: MOD ori in rat, mus. MOD skn in rbt.

Disaster Hazard: When heated to decomp it emits very
tox fumes of Cl⁻.

1,2-DICHLOROETHANE

mf: $C_2H_4Cl_2$; mw: 98.96

Lel = 6.2%; uel = 15.9%; flash p: 55.4°F.

Incomp: Dinitrogen tetraoxide; metals.

For further information see Vol. 1, No. 4 of DPIM Report.

2,2-DICHLOROETHANOL

CAS RN: 598389 NIOSH #: KK 4100000
mf: $C_2H_4Cl_2O$; mw: 114.96

TOXICITY DATA: CODEN:
mmo-om: 80 uL/plate CBINA8 30,9,80
mmo-asn 20 uL/plate/2H GBINA8 30,9,80

Reported in EPA TSCA Inventory, 1980.

Disaster Hazard: When heated to decomp it emits tox
fumes of Cl⁻.

2,2-DICHLOROETHENYL DIETHYL
PHOSPHATE

mf: $C_6H_{11}Cl_2O_4P$; mw: 249.04 NIOSH #: TC 0280000

SYNS:

DICHLOROVOS-ETHYL
2,2-DICHLOROVINYL DIETHYL
PHOSPHATE

O-(2,2-DICHLOROVINYL)-O,O-DI-
ETHYLPHOSPHAT (GERMAN)

TOXICITY DATA: 3 CODEN:
mmo-sat 5 uL/plate MUREAV 28,405,75
ipr-mus LD50: 12 mg/kg ARZNAD 5,746,55

THR: MUT data. HIGH ipr. See also esters.

Disaster Hazard: When heated to decomp it emits very
tox fumes of Cl⁻ and PO₂.

DICHLORO(4-ETHOXY-O-PHENYLENE)DI-
AMMINE)PLATINUM (II)

mf: $C_8H_{12}Cl_2N_2OPt$; mw: 418.21 NIOSH #: TP 2497050

TOXICITY DATA: CODEN:
mmo-sat 2500 nmol/L JMCMA9 23,459,80
mma-sat 2500 nmol/L JMCMA9 23,459,80

THR: MUT data. See also platinum compounds.

Disaster Hazard: When heated to decomp it emits very
tox fumes of Cl⁻ and NO₂.

DI(2-CHLOROETHYL) ACETAL

CAS RN: 14689975 NIOSH #: KI 3600000
mf: $C_6H_{12}Cl_2O_2$; mw: 187.08

SYN: 1,1'-(ETHYLIDENE)BIS(OXY)BIS(2-CHLOROETHANE)

TOXICITY DATA: 3 CODEN:
ori-rat LD50: 310 mg/kg AIHAAP 30,470,69
skn-rbt LD50: 200 mg/kg AIHAAP 30,470,69

THR: HIGH ori. HIGH skn.

Disaster Hazard: When heated to decomp it emits tox
fumes of Cl⁻.

4-DI(2'-CHLOROETHYLAMINO)AZOBENZENE-
2'-CARBOXYLIC ACID

mf: $C_{17}H_{17}Cl_2N_3O_2$; mw: 366.27 NIOSH #: DG 7450000

SYN: 2-CP
TOXICIT
aln-dmg-par
THR: MI
Disaster H
tox fum

9-(2-DIC2
ETHYL
ACRID

CAS RN:
mf: $C_{20}H_{12}$

SYNS:
ICR-45B
NSC-34372

TOXICITY
ipr-mus TDL

THR: An
Disaster H
tox fume

DICHLOR

CAS RN: 5
mf: C_2H_3As

Colorless liq
156° decomp
21.5° vap.

SYNS:
ARSENIC DICHL
DICK (GERMAN)

TOXICITY
ihl-hmr LCLo:
ihl-mus LCLo:
ihl-rat LCLo:
scu-cat LDLo:

Aquatic To
WQCHM*

THR: VERY
via oral ro
Used as a
Disaster Haze
fumes it em
will react w
sive fumes.

2,2-DICHLOR
ESTER

CAS RN: 67
mf: $C_8H_9Cl_2$

TOXICITY
ipr-mus LDLo:
scu-rat LDLo:
par-frg LDLo:

ihl-mus TC:55 ppm/43W-I:ETA
ihl-hmn TCLO:25 ppm:SYS
ori-rat LD50:200 mg/kg
ihl-rat LCLO:10000 ppm/24H
ihl-mus LC50:98 ppm/22H
ori-dog LDLo:5750 mg/kg
ivn-dog LDLo:225 mg/kg
scu-rbt LDLo:3700 mg/kg

JTEHD6 4,15,78
CHINAG 11,463,76
DCTODJ 1,63,77
EXMPA6 20,187,74
JTEHD6 3(5-6),913,77
QJPPAL 7,205,34
QJPPAL 7,205,34
QJPPAL 7,205,34

Aquatic Toxicity Rating: TLM96:1000-100 ppm
WQCHM* 3,-,74. Carcinogenic Determination: Animal Positive IARC** 19,439,79.

TLV: Air: 10 ppm DTLVS* 4,432,80. *Toxicology Review:* CTXAO 8,633,75; CMTVAS 10(3),49,73; NTIS** ORNL/TIRC-77/3. Occupational Exposure to Vinyl Halides recm std: Air: TWA 1 ppm; CL 5 ppm/15M NTIS**. NTP Carcinogenesis Bioassay Completed as of December 1980. "NIOSH Manual of Analytical Methods" VOL 4 266*. NIOSH Current Intelligence Bulletin 28, 1978. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FERREAC 45,13646,80.

THR: An exper MUT, ETA, NEO, CARC. HIGH acute ori, ihl. See also vinyl chloride.

Fire Hazard: Highly dangerous, when exposed to heat or flame.

Explosion Hazard: Mod, in the form of gas, when exposed to heat or flame. Also can explode spontaneously; reacts violently with chlorosulfonic acid, HNO₃, oleum.

Disaster Hazard: Highly dangerous; see chlorides; can react vigorously with oxidizing materials.

To Fight Fire: Alcohol foam, CO₂, dry chemical.

Incomp: Air; chlorotri-fluoroethylene; ozone; perchloryl fluoride.

cis-DICHLOROETHYLENE

CAS RN: 156592 NIOSH #: KV 9420000
mf: C₂H₂Cl₂; mw: 96.94

Colorless liquid, pleasant odor. mp: -80.5°, bp: 59°, lel = 9.7%, uel = 12.8%, flash p: 39°F, d: 1.2743 @ 25°/4°, vap. press: 400 mm @ 41.0°, vap. d: 3.34.

SYNS:

1,2-DICHLOROETHYLENE

ACETYLENE DICHLORIDE

TOXICITY DATA: 1

CODEN:

ihl-mus LCLo:65000 mg/m3/2H

AHBAAM 116,131,36

ihl-cat LCLo:20000 mg/m3/6H

AHBAAM 116,131,36

Reported in EPA TSCA Inventory, 1980.

THR: LOW via oral route. In high conc it is irr and narcotic. Has produced liver and kidney injury in exper animals.

Fire Hazard: Dangerous, when exposed to heat or flame. Reacts violently with N₂O₄, KOH, Na, NaOH.

Spontaneous Heating: No.

Explosion Hazard: Mod, in the form of vapor when exposed to flame.

Disaster Hazard: Dangerous; see chlorides; can react vigorously with oxidizing materials.

To Fight Fire: Water spray, foam, CO₂, dry chemical.

cis, 1,2-DICHLOROETHYLENE

mf: C₂H₂Cl₂; mw: 96.94

Flash p: 42.8°F, lel = 3.3%; uel = 15%

trans-1,2-DICHLOROETHYLENE

mf: C₂H₂Cl₂; mw: 96.94

Flash p: 35.6°F; lel = 9.7%; uel = 12.8%.

Can cause fire hazard.

Incomp: Alkalies; difluoromethylene dihypofluorite; nitrogen tetraoxide.

1,2-DICHLOROETHYLENE CARBONATE

CAS RN: 3967553

NIOSH #: JH 7400000

mf: C₃H₂Cl₂O₃; mw: 156.95

TOXICITY DATA: 3

CODEN:

scu-mus TDLo:645 mg/kg/54W-I:ETA

JNCIAM 48,1431,72

THR: An exper ETA.

Disaster Hazard: When heated to decomp it emits tox fumes of Cl⁻.

DICHLORO(ETHYLENEDIAMMINE)-PLATINUM(II)

CAS RN: 14096516

NIOSH #: TP 2497100

mf: C₂H₄Cl₂N₂Pt; mw: 326.11

TOXICITY DATA: 3

CODEN:

mmo-sat 2 ug/plate

MUREAV 77,45,80

mna-sat 2 ug/plate

MUREAV 77,45,80

ipr-mus LDLo:14 mg/kg

BICHBX 2,187,73

THR: MUT data. HIGH ipr. See also platinum compounds.

Disaster Hazard: When heated to decomp it emits very tox fumes of Cl⁻ and NO₂.

DI-2-CHLOROETHYL MALEATE

CAS RN: 63917066

NIOSH #: ON 1050000

mf: C₈H₁₀Cl₂O₄; mw: 241.08

TOXICITY DATA: 3

CODEN:

ori-rat LD50:71 mg/kg

TXAPA9 28,313,74

skn-rbt LD50:140 mg/kg

TXAPA9 28,313,74

THR: HIGH ori, skn.

Disaster Hazard: When heated to decomp it emits tox fumes of Cl⁻.

2,3-DICHLORO-N-ETHYLMALAEINIMIDE

CAS RN: 20198770

NIOSH #: ON 5175000

mf: C₆H₅Cl₂NO₂; mw: 194.02

SYN: N-ETHYL-DICHLOROMALAEINIMIDE

TOXICITY DATA: 3

CODEN:

ipr-mus TDLo:6200 ug/kg/9SD

ARTODIN 37,15,76

preg:TER

ipr-mus LD50:15 mg/kg

ARTODN 37,15,76

ivn-mus LD50:5600 ug/kg

CSLNX* NX=63644

ipr-mus TL
preg:TH
ipr-mus TL
preg)

THR: A
Disaster
tox fun

2-(1,2-DI
DIOXO

CAS RN:
mf: C₈H₁₀

TOXICIT
skn-rbt 10 m
ori-rat LD50
skn-rbt LD5

THR: M
Disaster I
fumes o

DICHLOR

CAS RN:
mf: C₈H₁₀

Liquid.

SYN: ETHY

TOXICIT

Aquatic To

4,-,74. I

FEREA

tory. 19

THR: HIC

and inha

Disaster H

emits hi

react wit

fumes; c

DICHLOR

CAS RN:
mf: C₂H₆Cl

Liquid. vap

SYN: ETHY

TOXICIT

Aquatic To

4,-,74.

DOT: Fla

FEREA

tory. 198

THR: HIC

and inha

Fire Hazar

or power

Disaster H

THR: MOD orl. A skin irr. See also aldehydes.
Disaster Hazard: When heated to decomp it emits acrid smoke and fumes.

TOLUENE

CAS RN: 108883 NIOSH #: XS 5250000
 mf: C₇H₈; mw: 92.15

Colorless liquid, benzol-like odor. Flammable. mp: -95° to -94.5°, bp: 110.4°, flash p: 40°F (CC), ulc: 75-80, lcl = 1.27%, ucl = 7%, d: 0.866 @ 20°/4°, autoign. temp.: 896°F, vap. press: 36.7 mm @ 30°, vap. d: 3.14. Insol in water; sol in acetone; misc in absolute alc, ether, chloroform.

SYNS:

METHYLBENZENE
 METHYLBENZOL
 NCI-C07272
 PHENYLMETHANE

TOLUEN (DUTCH)
 TOLUEN (CZECH)
 TOLUOL
 TOLUOLO (ITALIAN)

TOXICITY DATA:

3
 cycl-rat-scu 12 gm/kg/12D-1
 ihl-rat TCLo: 1500 mg/m³/24H (1-8D
 pregl)
 ihl-rat TCLo: 1000 mg/m³/24H (7-
 14D pregl)
 ori-mus TDLo: 9 gm/kg (6-15D pregl)
 ori-mus TDLo: 15 gm/kg (6-15D pregl)
 ori-mus TDLo: 30 gm/kg (6-15D pregl)
 ihl-mus TCLo: 500 mg/m³/24H (6-
 13D pregl)
 unk-rat LD50: 6900 mg/kg
 unk-mus LD50: 2000 mg/kg
 eye-hmn 300 ppm
 skin-rbt 435 mg MLD
 eye-rbt 870 ug MLD
 eye-rbt 2 mg/24H SEV
 cycl-rat-ihl 610 mg/m³/16W-1
 ihl-hmn TCLo: 200 ppm/CNS
 ihl-hmn TCLo: 100 ppm/PSY
 ori-rat LD50: 5000 mg/kg
 ihl-rat LCLo: 4000 ppm/4H
 ipr-rat LDLo: 800 mg/kg
 ihl-mus LC50: 5320 ppm/8H
 ipr-mus LD50: 1120 ug/kg
 skin-rbt LD50: 14 gm/kg
 scu-frg LDLo: 920 mg/kg
 CODEN:
 GTPZAB 17(3),24,73
 TXCYAC 11,55,78
 FMORAO 28,286,80
 TJADAB 19,41A,79
 TJADAB 19,41A,79
 TJADAB 19,41A,79
 TXCYAC 11,55,78
 GISAAA 45(12),64,80
 GISAAA 45(12),64,80
 JIHTAB 25,282,43
 UCDS** 7/23/70
 UCDS** 7/23/70
 28ZPAK -23,72
 GISAAA 42(1),32,77
 JAMAAP 123,1106,43
 WEHSAL 9,131,72
 AMIHAB 19,403,59
 AIHAAP 30,470,69
 TXAPA9 1,156,59
 JIHTAB 25,366,43
 AGGHAR 18,109,60
 UCDS** 7/23/70
 AEPPAE 130,250,28

Aquatic Toxicity Rating: TLM96: 100-10 ppm WQCHM* 4,-,74.

TLV: Air: 100 ppm DTLVS* 4,400,80. *Toxicology Review:* AEHLAU 22,373,71; CTOXAO 11(5),549,77; FNSCA6 2,67,73; MUREAV 47(2),75,78; CTOXAO 11(5),549,77; 27ZTAP 3,144,69. OSHA Standard: Air: TWA 200 ppm; CL 300; Pk 500/10M (SCP-V) FEREAC 39,23540,74. DOT: Flammable Liquid, Label: Flammable Liquid FEREAC 41,57018,76. Occupational Exposure to Toluene recm std: Air: TWA 100 ppm; CL 200 ppm/10M NTIS**. Currently Tested by NTP for Carcinogenesis by Standard Bioassay Protocol as of December 1980. Reselected by NTP Carcinogenesis Bioassay as of December 1980. "NIOSH Manual of Analytical Methods" VOL 1 127, VOL 3 5343. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed

Rule FERREAC 45,13646,80. EPA TSCA, 8E No. 02780079P-Followup Sent as of April, 1979.

THR: MUT data. A skin, eye irr. A hmn CNS, PSY. MOD ihl, ipr, scu; HIGH ipr; LOW orl, skin. Toluene is derived from coal tar, and commercial grades usually contain small amounts of benzene as an impurity. Acute poisoning, resulting from exposures to high conc of the vapors, are rare with toluene. Inhal of 200 ppm of toluene for 8 hrs may cause impairment of coordination and reaction time; with higher conc (up to 800 ppm) these effects are increased and are observed in a shorter time. In the few cases of acute toluene poisoning reported, the effect has been that of a narcotic, the workman passing through a stage of intoxication into one of coma. Recovery following removal from exposure has been the rule. An occasional report of chronic poisoning describes an anemia and leucopenia, with biopsy showing a bone marrow hypoplasia. These effects, however, are less common in people working with toluene, and they are not as severe.

Exposure to conc up to 200 ppm produces few symptoms. At 200-500 ppm, headache, nausea, eye irr, loss of appetite, a bad taste, lassitude, impairment of coordination and reaction time are reported, but are not usually accompanied by any laboratory or physical findings of significance. With higher conc, the above complaints are increased and in addition, anemia, leucopenia and enlarged liver may be found in rare cases.

A common air contaminant.

Fire Hazard: Slight, when exposed to heat, flame or oxidizers.

Explosion Hazard: Mod, when exposed to flame or reacted with (H₂SO₄ + HNO₃), N₂O₄, AgClO₄, BrF₃, UF₆.

Disaster Hazard: Mod dangerous; when heated it emits irr fumes; can react vigorously with oxidizing materials.

To Fight Fire: Foam, CO₂, dry chemical.

For further information see Vol. 2, No. 1 of *DPIM Report*.

p-TOLUENEBORONIC ACID, CYCLIC-2-METHYL-2-PROPYLTRIMETHYLENE ESTER

CAS RN: 2430468 NIOSH #: XS 7875000
 mf: C₁₄H₂₂BO₂; mw: 232.16

SYNS:

DIOSSOBORONO
 2-METHYL-2-PROPYL-1,3-PROPANEDIOL-P-METHYLBENZENE-BORONATE

5-METHYL-5-PROPYL-2-(P-TOLYL)-1,3,2-DIOXABORINANE

TOXICITY DATA:

2
 ipr-rat LD50: 1600 mg/kg
 ipr-mus LD50: 3350 mg/kg
 CODEN:
 27ZQAG -319,72
 27ZQAG -319,72

THR: MOD ipr. See also boron compounds and esters.
Disaster Hazard: When heated to decomp it emits acrid smoke and fumes.

TOLUENEBORONIC ACID, CYCLIC NEOPENTANETETRYL ESTER

CAS RN: 7091410 NIOSH #: XS 7950000
 mf: C₁₅H₂₂B₂O₄; mw: 336.03

SYNS:

DI-(P-METHYLBENZYL) DE PENTAN-3-OL
 (FRENCH)
 DI-(P-METHYLBENZYL) DE PENTAN-3-OL

TOXICITY D.

ori-rat LD50: 1130
 ipr-rat LD50: 570
 ori-mus LD50: 181
 ipr-mus LD50: 866

THR: MOD o

ters.

Disaster Hazard: smoke and f

TOLUENEDI

CAS RN: 253

TOXICITY E

DOT-ORM-A L

FEREAC 41,

Reported in E

THR: No dat

TOLUENE-2

CAS RN: 951

mf: C₇H₁₀N₂;

Prisms. mp: 6

SYNS:

C.I. OXIDATION
 M-TOLYLENEDIA
 3-AMINO-P-TOLU
 5-AMINO-O-TOLU
 C.I. 76035
 1,3-DIAMINOTOLU
 2,4-DIAMINO-1-A
 2,4-DIAMINOTOLU
 DIAMINOTOLU
 2,4-DIAMINOTOLU
 2,4-DIAMINO-1-A
 2,4-DIAMINOTOLU
 4-METHYL-1,3-E

TOXICITY

skin-rbt 500 mg
 eye-rbt 100 mg
 mma-sat 100 u
 sin-dmg-par 5
 sin-dmg-ori 15
 otr-ham: emb 5
 ori-rat TDLo:
 C:CAR
 ori-mus TDLo:
 C:CAR
 ori-mus TDLo:
 ori-rat TDLo:

ori-rat TDLo:
 ori-rat LD50:
 scu-rat LDLo:
 scu-coq LDLo:
 scu-rat LDLo:

4,5,7-TRICHLOROBENZTHIADIAZOLE-2,1,3

CAS RN: 1982554 NIOSH #: DL 0175000
 mf: $C_6HCl_3N_2S$; mw: 239.50

SYN: 4,5,7-TRICHLORO-2,1,3-BENZOTHIADIAZOLE

TOXICITY DATA: 2 CODEN:
 ori-rat LD50: 1620 mg/kg WRPAC2 9,119,70
 ori-mus LD50: 1500 mg/kg 3120AD 1,423,68

THR: MOD orl.

Disaster Hazard: When heated to decomp it emits very tox fumes of NO_x and SO_x .

TRICHLOROBENZYL CHLORIDE

CAS RN: 1344327 NIOSH #: XT 8575000
 mf: $C_7H_4Cl_4$; mw: 229.91

SYN: TCWC

TOXICITY DATA: 2 CODEN:
 ori-rat LD50: 3075 mg/kg 28ZEAL 4,359,69

Toxicology Review: 27ZTAP 3,146,69. Reported in EPA TSCA Inventory, 1980.

THR: MOD orl.

Disaster Hazard: When heated to decomp it emits tox fumes of Cl^- .

3,4,4'-TRICHLOROCARBANILIDE

CAS RN: 101202 NIOSH #: FE 1250000
 mf: $C_{13}H_9Cl_3N_2O$; mw: 315.59

SYN: N-(3,4-DICHLOROPHENYL)-N'-(4-CHLOROPHENYL)UREA

TOXICITY DATA: 3 CODEN:
 ipr-mus LD50: 2100 mg/kg LPPTAK 27,306,79

Toxicology Review: 27ZTAP 3,146,69. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FERREAC 45,13646,80.

THR: MOD ipr.

Disaster Hazard: When heated to decomp it emits very tox fumes of Cl^- and NO_x .

4,5,6-TRICHLORO-2-(2,4-DICHLOROPHENOXY) PHENOL

mf: $C_{12}H_3Cl_5O_2$; mw: 358.42 NIOSH #: SL 0532000

SYN: 2-(2,4-DICHLOROPHENOXY)-4,5,6-TRICHLOROPHENOL

TOXICITY DATA: CODEN:
 sli-mus-ipr 140 umol/L MUREAV 46,202,77

THR: MUT data.

Disaster Hazard: When heated to decomp it emits tox fumes of Cl^- .

1,1,2-TRICHLORO-2,2-DIFLUOROETHANE

CAS RN: 354212 NIOSH #: KI 1435000
 mf: $CHCl_2F_2$; mw: 157.37

SYN: UCON FLUOROCARBON 122

TOXICITY DATA: 2 CODEN:
 ori-rat LDLo: 7500 mg/kg 16CZAC 20,459,66
 ihi-rat LCLo: 4000 ppm/4H UCMH** 11,15,62

THR: MOD orl, ihi.

Disaster Hazard: When heated to decomp it emits very tox fumes of F^- and Cl^- .

TRICHLORODINITROBENZENE

CAS RN: 8003461 NIOSH #: CZ 7960000
 mf: $C_6HCl_3N_2O_4$; mw: 271.44

SYNS:

BRASSISAN (GERMAN)

DINITROTRICHLOROBENZENE
 ISOMERIC MIXTURE

TOXICITY DATA: 2 CODEN:
 ori-rat LD50: 425 mg/kg GUCHAZ 6,516,73
 skn-rat LD50: 425 mg/kg GUCHAZ 6,516,73

THR: MOD, via oral and dermal routes. See also benzene and nitrobenzene. A pesticide.

Fire Hazard: Mod, when exposed to heat or flame. See nitrates.

Explosion Hazard: See nitrates.

Disaster Hazard: Dangerous; when heated to decomp it emits highly tox fumes of NO_x and Cl^- ; can react vigorously with reducing materials.

TRICHLORO ESTERTIN

NIOSH #: WH 8240000

SYN: ESTERTRICHLOROSTANNANE

TOXICITY DATA: 1 CODEN:
 unk-rat LD50: 5500 mg/kg TUSAD 10*,1,76

Occupational Exposure to Organotin Compounds recm std: Air: TWA 0.1 mg(Sn)/m³ NTIS**.

THR: LOW unk. See also tin compounds and esters.

Disaster Hazard: When heated to decomp it emits tox fumes of Cl^- .

1,1,1-TRICHLOROETHANE

CAS RN: 71556 NIOSH #: KJ 2975000
 mf: $C_2H_3Cl_3$; mw: 133.40

Colorless liquid. bp: 74.1°, fp: -32.5°, flash p: none, d: 1.3376 @ 20°/4°, vap. press: 100 mm @ 20.0°. Insol in water; sol in acetone, benzene, carbon tetrachloride, methanol, ether.

SYNS:

CHLOROETHENE
 CHLOROTHANE NU
 CHLOROTHENE
 METHYL CHLOROFORM
 METHYLTRICHLOROMETHANE
 NCI-C04626
 1,1,1-TRICHLOROETHAAN
 (DUTCH)

1,1,1-TRICHLORAETHAN (GERMAN)
 TRICHLORO-1,1,1-ETHANE
 (FRENCH)
 ALPHA-TRICHLOROETHANE
 1,1,1-TRICLOROETANO (ITALIAN)

TOXICITY DATA: 2-1 CODEN:
 ihi-rat TCLo: 2100 ppm/24H (14D) TONID* 1,25,80
 pre/i-20D preg)
 eye-man 450 ppm/8H
 skn-rat 5 gm/12D-1 MLD
 BJMAG 28,256,71
 AIHAAP 19,252,58

skn-rbt 500 mg/24H MOD
eye-rbt 100 mg MLD
eye-rbt 2 mg/24H SEV
ihl-man LCLo: 27 gm/m³/10M
ihl-man TCLo: 350 ppm/PSY
ori-hmn TDLo: 670 mg/kg/GIT
ihl-hmn TCLo: 920 ppm/70M: CNS
ori-rat LD50: 10300 mg/kg
ihl-rat LCLo: 1000 ppm
ipr-rat LD50: 5100 mg/kg
ori-mus LD50: 11240 mg/kg
ihl-mus LCLo: 11000 ppm/2H
ipr-mus LD50: 4700 mg/kg
ori-dog LD50: 750 mg/kg
ipr-dog LD50: 3100 mg/kg
ivn-dog LDLo: 95 mg/kg
ori-rbt LD50: 5660 mg/kg
scu-rbt LDLo: 500 mg/kg
ori-gpg LD50: 9470 mg/kg

28ZPAK -28.72
AIHAAP 19,353.58
28ZPAK -28.72
JOCMA7 8,358.66
WEHSAL 10,82.73
NTIS** PB257-185
AIHAAP 19,353.58
NTIS** PB257-185
FMCHA2 -D317.80
NTIS** PB257-185
HBTXAC 5,72.59
TXAPA9 13,287.68
FMCHA2 -D317.80
TXAPA9 10,119.67
HBTXAC 5,72.59
AIHAAP 19,353.58
HBTXAC 5,72.59
AIHAAP 19,353.58

Aquatic Toxicity Rating: TLM96: 100-10 ppm WQCHM*
3,-,74. Carcinogenic Determination: Indefinite IARC**
20,515,79.

TLV: Air: 350 ppm DTLVS* 4,269.80. Toxicology Review: FAZMAE 18,365.74; EATR** EB-TR-75047; AIHAAP 40,A46.79. OSHA Standard: Air: TWA 350 ppm (SCP-J) FEREAC 39,23540.74. DOT: ORM-A, Label: None FEREAC 41,57018.76. Occupational Exposure to 1,1,1-Trichloroethane recm std: Air: CL 350 ppm/15M NTIS**. NCI Carcinogenesis Bioassay Completed; Results Negative (NCITR* NCI-CG-TR-3,77). Currently Tested by NTP for Carcinogenesis by Standard Bioassay Protocol as of December 1980. "NIOSH Manual of Analytical Methods" VOL 1 127, VOL 3 S328. NIOSH Current Intelligence Bulletin 27, 1978. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FERREAC 45,13646.80.

THR: In hmn it causes PSY, GIT, CNS effects. A MOD skn irr, a SEV eye irr in rbt. LOW ori, ipr, ihl in rat, mus. MOD ori, ipr dog; Narcotic in high conc. Causes a proarrhythmic activity which sensitizes the heart to epinephrine-induced arrhythmias. This sometimes will cause a cardiac arrest particularly when this material is massively inhaled as in drug abuse for euphoria. Reacts violently with N₂O₄, O₂, O₂ liquid, Na, NaOH, Na-K alloy.

Disaster Hazard: Dangerous; see chlorides.

For further information see Vol. 2, No. 1 of DPIM Report.

1,1,2-TRICHLOROETHANE

CAS RN: 79005 NIOSH #: KJ 3150000
mf: C₂H₃Cl₃; mw: 133.40

Liquid, pleasant odor. bp: 114°, fp: -35°, d: 1.4416 @ 20°/4°, vap. press: 40 mm @ 35.2°.

SYNS:

ETHANE TRICHLORIDE
NCI-C04579
BETA-TRICHLOROETHANE
1,1,2-TRICHLOROETHANE

TRICHLOROETAN(1,1,2) (POL-
ISH)
VINYL TRICHLORIDE

TOXICITY DATA: 3

skn-rbt 500 mg open MLD
skn-rbt 810 mg/24H SEV
eye-rbt 162 mg MLD
skn-gpg 1440 mg/15M
cyt-gpg-skn 2880 ug/kg
ori-mus TDLo: 76 gm/kg/78W-
I: CAR
ori-mus TD: 152 gm/kg/78W-I: CAR
ori-rat LD50: 1140 mg/kg
ihl-rat LCLo: 500 ppm/8H
ipr-mus LD50: 994 mg/kg
scu-mus LD50: 227 mg/kg
ori-dog LDLo: 500 mg/kg
ipr-dog LD50: 450 mg/kg
ivn-dog LDLo: 95 mg/kg
ihl-cat LCLo: 13100 mg/m³/4.5H
scu-rbt LDLo: 500 mg/kg

Aquatic Toxicity Rating: TLM96: 100-10 ppm WQCHM*
3,-,74. Carcinogenic Determination: Animal Positive
IARC** 20,533,79.

TLV: Air: 10 ppm (skin) DTLVS* 4,406.80. Toxicology Review: FAZMAE 18,365.74; AIHAAP 40,A46.79; 27ZTAP 3,146.69. OSHA Standard: Air: TWA 10 ppm (skin) (SCP-J) FEREAC 39,23540.74. NCI Carcinogenesis Bioassay Completed; Results Positive: Mouse (NCITR* NCI-CG-TR-74,78). NCI Carcinogenesis Bioassay Completed; Results Negative: Rat (NCITR* NCI-CG-TR-74,78). "NIOSH Manual of Analytical Methods" VOL 1 127, VOL 2 S134. NIOSH Current Intelligence Bulletin 27, 1978. Reported in EPA TSCA Inventory, 1980. EPA TSCA 8(a) Preliminary Assessment Information Proposed Rule FERREAC 45, 13646.80.

THR: HIGH ivn, scu and MOD ori, ihl, ipr and dermal. MOD skn irr and SEV eye irr in rbt. Trichloroethane has narcotic properties and acts as a local irr to the eyes, nose and lungs. It may also be injurious to the liver and kidneys. A fumigant. An exper CARC. MLT data.

Disaster Hazard: Dangerous; see chlorides.

Incomp: K.

For further information see Vol. 2, No. 6 and Vol. 3, No. 2 of DPIM Report.

1,1,1-TRICHLOROETHANE mixed with TETRACHLOROETHYLENE (3:1)

NIOSH #: KJ 3950000

SYNS:

DOWCLENE

EC CLEANER

TOXICITY DATA: 2-1

ori-rat LD50: 15 gm/kg
ihl-rat LC50: 3700 ppm/7H
ori-mus LD50: 10 gm/kg
ori-rbt LD50: 15 gm/kg
ori-gpg LD50: 6 gm/kg

CODEN:

AIHAAP 24,541.63
AIHAAP 24,541.63
AIHAAP 24,541.63
AIHAAP 24,541.63
AIHAAP 24,541.63

THR: LOW ori, ihl in rat; LOW ori in mus; ori in rbt and ori in gpg.

Disaster Hazard: When heated to decomp it emits very tox fumes of Cl⁻.

TRICHLOR

CAS RN: 11
mf: C₂H₃Cl₃

Liquid mp: 1
4°, vap. press:

SYNS:

2,2,2-TRICHLORO
TRICHLOROETHANE

TOXICITY

mmo-asn 5 uL/L
ori-rat LD50: 60
ipr-rat LDLo: 30
ivn-mus LD50: 2
ivn-rbt LDLo: 10

Reported in 1
THR: HIGH

An anesthetic
Disaster Hazard

TRICHLOR

CAS RN: 75
mf: C₂H₃Cl₃S

Fuming liquid
16°F.

SYNS:

TRICHLORO(VINYL)
TRICHLORO(VINYL)

TOXICITY I

skn-rbt 1 mg/24H
skn-rbt 625 mg c
eye-rbt 50 ug SE
ori-rat LD50: 120
ihl-rat LCLo: 500
ori-mus LD50: 30
ihl-mus LC50: 30
skn-rbt LD50: 60

Aquatic Toxic
4,-,74. DO

Liquid FER
Inventory,

THR: MOD c
lanes.

Fire Hazard:
moist air.

Disaster Hazard
fumes of Cl⁻
tox and cor

2,2,2-TRICHL

CAS RN: 515
mf: C₂H₃Cl₃C

Crystals, less
organic solvent

SYNS:

CHLORAL ALCOHOL
CHLORAL ETHYL

REF. 4

GENESCO

Employee and Environmental Safety

May 21, 1985

Mr. Tom Tiesler
Director
Division of Solid Waste Management
Department of Health and Environment
4th Floor, Custom House
701 Broadway
Nashville, Tennessee 37219-5403

Dear Tom:

The purpose of this letter is to advise you of a chemical waste site once used by a division of Genesco Inc. (the "Company" or "Genesco") and to solicit the assistance and approval of the Tennessee Department of Health and Environment (the "Department") with respect to certain actions the Company proposes to take.

The Company is a Tennessee corporation with its executive offices located at Genesco Park, Nashville, Tennessee. Genesco operates in two major industry segments - footwear and men's apparel - and employs approximately 3,900 persons in the State of Tennessee. General Adhesives, formerly known as General Adhesives and Chemical Company, is a division of Genesco's footwear segment which operates a manufacturing plant at 6100 Centennial Boulevard in Nashville, Tennessee. General Adhesives manufactures and sells specialty industrial and consumer products, which include adhesives, sealants and coatings utilizing solvent based, thermoplastic and water based technologies. It is a generator (EPA I.D. Number TND 001981240) and transporter (EPA I.D. Number TND 001367549) of hazardous waste currently disposed of at either the Stauffer Chemical Company, Mt. Pleasant, Tennessee or Chemical Waste Management Company, Emelle, Alabama.

It has recently been brought to the attention of Genesco's corporate management that for a limited period of time during the summer and/or fall of 1978, approximately eight hundred 55-gallon barrels of waste material from General Adhesives were disposed of in a rural area in Williamson County, Tennessee. Preliminary indications are that some of the waste

Genesco Inc.
Genesco Park
Nashville TN 37202

615 367 8417

Mr. Tom Tiesler
May 21, 1985
Page 2

(approximately 50-80 barrels) was buried in the barrels and the remainder was poured from barrels into phosphate pits or earthen trenches. The disposal site is an approximately two acre section of a 146 acre farm owned by Emmett N. Kennon located in the fifteenth civil district of Williamson County, Tennessee on the east side of Wilson Pike between Moores Lane and Split Log Road (the "Kennon Property"). Enclosed is a copy of a map showing the location of the Kennon Property and the approximate location of the disposal site.

The exact amount and contents of the waste material are unknown; however, it is believed that it contained water based adhesives and may have contained acetone; ethyl acetate; hexane; methylene chloride; methyl ethyl ketone; rubber solvent; toluene; 1,1,1-trichloroethane; trichloroethylene and organic fillers. A large portion of the organic solvents that was poured into the phosphate pits and earthen trenches may have evaporated, but it is believed that approximately 50-80 barrels were buried on the Kennon Property and may still contain waste material.

Having been informed of the reported waste disposal, corporate management immediately instructed its counsel to undertake an investigation of this matter. Based on the preliminary findings of that investigation, the Company developed the general plan of action outlined herein and arranged for a meeting with you. The plan has been developed in consultation with Mr. V. Wayne McCoy of Resource Consultants Inc. of Brentwood, Tennessee. Implementation of the plan calls for the employment of hydrogeologists, soil geologists and other experts, possibly including a waste disposal firm.

The details of the plan and the retention of experts and others to carry out the plan are subject to the Department's approval, and representatives of the Department are invited to observe or participate in all aspects of its implementation.

The first phase of the plan, as proposed by Genesco, is designed, through hydrogeological study, to:

1. Identify more specifically the area and volume of the land area on the Kennon Property that has been used for disposal of waste generated by General Adhesives;
2. Determine the extent to which chemical waste generated by General Adhesives is still present in the soil in and around the disposal site;

Mr. Tom Tiesler
May 21, 1985
Page 3

3. Determine the existence and direction of possible surface water flows and subsurface aquifers in and around the disposal site;
4. Determine if any of the chemicals generated by General Adhesives is present in any surface water or groundwater in and around the disposal site; and
5. Develop a report regarding the environmental impact and preliminary recommendations for any corrective action indicated.

Subject to Department approval, Genesco proposes to retain the services of Resource Consultants and Geologic Associates Inc. of Franklin, Tennessee, as soon as possible to perform the initial surveys, tests and analyses to define the nature and extent of any environmental problem that may exist on the Kennon Property and surrounding area.


Genesco will meet with appropriate Department representatives to review the results of the surveys, tests and analyses and to more fully develop any preliminary plan for any remedial action.

If waste removal and site cleanup is required, the Company will retain the services of a Department-approved firm to excavate, exhume, analyze, transport and dispose of contaminated material. Any cleanup and removal required will be subject to necessary pre-closure site tests and analyses conducted by Geologic Associates Inc. or other approved firms.

Sincerely,



Ralph Mosely
Director



4001
2.94 AC

4202
15 AC

1204
205

4207
2034 AC

4206
1026 AC

420
12 AC

42
34.3 AC

3905
502 AC

3904
501 AC

38
112.5 AC

3701
3527 AC

37
165.5 AC

3704
53 AC

APPROXIMATE LOCATIONS
OF DISPOSAL SITES

REVISU 8-1-55

"KENNEDY PROPERTY"

DIST

RAILROAD

REF. 5

GEOLOGIC MAP FRANKLIN QUADRANGLE TENNESSEE GM 63-NE

Leipers and Catheys Formations

Limestone, argillaceous nodular and shaly, medium dark gray to brownish-gray, fine-grained, thin-bedded, fossiliferous, limestone, dark gray (weathers to pale yellowish-brown), fine-grained, thin- to medium-bedded; calcarenite, medium light-gray to brownish-gray, coarse-grained, medium-bedded, crossbedded, phosphatic, weathers to brown phosphatic residuum; and thin zones of limestone, clayey, medium-gray (weathers to light-gray surface), cryptocrystalline, medium-bedded, breaks with conchoidal fracture, present only in the north. At base of formation is shaly limestone or calcareous shale, olive-gray to yellowish-brown, fine-grained, which typically contains large numbers of bryozoans (*Constellaria* zone). Thickness 120 to 200 feet.

Obc

Bigby-Cannon Limestone

The Bigby-Cannon Limestone in the Franklin quadrangle consists of three facies—the Cannon limestone, Dove-colored limestone, and Bigby limestone—which replace each other laterally and vertically. The Bigby comprises the upper and lower parts of the formation, whereas the middle part includes all three facies. The formation ranges in thickness from 70 to 130 feet.

Cannon limestone facies is medium dark-gray to brownish-black, microcrystalline to medium-grained, thin- to medium-bedded, evenly bedded. Composite thickness 10 to 40 feet.

Dove-colored limestone facies is medium light-gray to medium-gray (weathers to a characteristic light-gray surface), cryptocrystalline, medium and evenly bedded, brittle, breaks with pronounced conchoidal fracture, contains specks and stringers of clear calcite. Composite thickness 5 to 30 feet.

Bigby limestone facies is calcarenite, medium light-gray to brownish-gray, coarse-grained, medium-bedded, crossbedded, contains brown phosphate pellets, weathers to brown phosphatic residuum. Composite thickness 60 to 100 feet.

Oh

Hermitage Formation

Coquina facies at top is limestone with disseminated silt and shale partings, medium-gray to brownish-gray, medium-bedded, characterized by numerous shells of the brachiopod *Resserella fertilis* (formerly *Dalmanella fertilis*). Thickness 10 to 20 feet.

Laminated argillaceous limestone facies is silty to sandy, medium-gray to dark-gray (weathers to pale to dark yellowish-brown), very fine- to medium-grained, laminated to thin-bedded with thin shale partings. Thickness about 40 to 75 feet.

Curdsville Limestone Member at base is medium- to dark-gray, fine- to medium-grained, thin-bedded with thin shale partings, fossiliferous. Thickness 0 to 5 feet.

Thickness of formation 50 to 100 feet.

Oc

Carters Limestone

Upper member is limestone, medium light-gray to brownish-gray and yellowish-brown, very fine-grained to cryptocrystalline, thin-bedded with thin shale partings. Thickness 5 to 10 feet.


Bentonite (T-3 bed), green when fresh but weathers to white and greenish-yellow sticky clay, 6 to 12 inches thick; occurs between upper and lower members, but rarely seen in natural outcrops. (This is the "Pencil Cave" of drillers' terminology in Central Tennessee.)

Lower member is limestone, medium light-gray to brownish-gray and yellowish-brown, cryptocrystalline to very fine-grained with some beds ranging up to coarse-grained, medium- to thick-bedded, with minor amounts of saccharoidal magnesian limestone as small irregular mottlings, and thin bands and lenses of chert locally. Thickness about 60 to 70 feet.

Olb

Lebanon Limestone

Limestone, medium- to medium dark-gray and brownish-gray to yellowish-brown, cryptocrystalline to very fine-grained with some beds ranging up to coarse-grained, thin-bedded with thin calcareous shale partings, fossiliferous. Maximum exposed thickness about 30 feet.



REF.6

BEDROCK GEOLOGY OF THE NASHVILLE AND MIDDLE TENNESSEE AREA

Copyright 1977
BEAVER ENGINEERING, INC.
Hendersonville, Tennessee

SYSTEM	GROUP	FORMATION	ROCK STRATA	AVERAGE THICKNESS ft.	RANGE OF THICKNESS ft.	GENERALIZED DESCRIPTION OF ROCKS OUTCROPPING IN NASHVILLE AND MIDDLE TENNESSEE.
MISSISSIPPIAN		STE. GENEVIEVE (MONTEAGLE)		250	180-350	STE. GENEVIEVE LIMESTONE: Gray to white limestone, variable bedding thickness, oolitic layers, gray chert near base. Weathers to present ground water table, very cavernous, develops karst topography, weathers to reddish brown clay 20-40 feet thick. Outcrops on Northern Highland Rim.
		ST. LOUIS		180	100-280	ST. LOUIS FORMATION: Brownish gray cherty limestone, thick bedded to massive, numerous gray to black chert beds and nodules. Weathers deep to present ground water table, develops karst topography, weathers to reddish brown clay about 20 feet thick. Outcrops on Highland Rim.
		WARSAW		100	40-150	WARSAW LIMESTONE: Gray, cross bedded limestone, massive, line grained, some chert. Weathers deep but sinkhole development not as intense as St. Louis Formation. Sandy and shaly facies near base. Weathers to reddish brown clay about 20 feet deep. Outcrops on Highland Rim.
		FT. PAYNE		250	200-400	FORT PAYNE FORMATION: Dark gray siltstone, shale, and cherty limestone. Thin beds of crinoidal limestone, green shale at base (Maury Shale), contains phosphate nodules. Weathers to residual cherty clay about 15 feet deep. Outcrops along Highland Rim and higher hills within Central Basin. Excellent road metal. CHATTANOOGA SHALE: Dark grayish black fissile, carbonaceous shale, thin sandstone at base. Weathers to light buff clay. Outcrops on Highland Rim and on higher hills within Central Basin. Widely used by geologists as a mapping unit, both in surface and subsurface. PEGRAM FORMATION: Light gray limestone, massive. Minor amounts of light gray shale and sandstone in lower portion. Outcrops mainly in the Kingston Springs area. CAMDEN FORMATION: Thin to medium bedded blue gray, shaly limestone containing nodules and bands of chert. Chert beds average 6 to 12 inches thick and are separated by white clay partings. Weathers to thin residual soil less than three feet thick then a thicker weathered layer of angular blocks and sharp fragments of chert rubble. Very difficult to drill or excavate with conventional excavation equipment. Outcrops mainly in Benton, Decatur, and Perry counties. Chert beds are used locally as road metal and ballast.
DEVONIAN		CHATTANOOGA		20	10-70	FLAT GAP LIMESTONE: Light gray and pink limestone, occasionally glauconitic in upper part. Outcrops in extreme western counties of Highland Rim. Very good concrete aggregate.
		PEGRAM		17	0-30	ROSS FORMATION: Alternating facies of thin limestone and thick shales. Shales are blue or greenish gray. Limestones weather to glades and shales generally do not have slope stability on steep road cuts.
		CAMDEN		95	0-220	SILURIAN SYSTEM: Extremely variable in outcrop and thickness. Major unconformity extends from base of Mississippian System through Devonian and Silurian Systems. Silurian is predominantly limestone and shaly limestone. See Tennessee Division Geology Bulletin 56 for complete description.
		FLAT GAP		20	0-55	SEQUATCHIE FORMATION: Greenish gray, massive mudstone with some sand, shale, and limestone. Contains Mannie Shale facies which is a green calcareous shale that weathers into laminated cobbles of green silt. Outcrops mostly in Lincoln, Franklin, and Marion Counties. Contains Fernvale Limestone facies, which is an irregular bedded massive limestone containing enough limonite to be a low grade iron ore.
		ROSS		45	0-110	LEIPERS FORMATION: Dark blue gray, earthy, nodular limestone. Thin beds of limestone separated by shale mudstone and siltstone beds from a few inches to 10 feet thick. Weathers to light brown silty clay soil 3 to 5 feet thick. Weathering along fractures and faults can penetrate 20 feet into rock mass. Outcrops mostly along edge of Central Basin.
SILURIAN		DECATUR		VARIABLE	0-250	INMAN FORMATION: Greenish gray calcareous shale interbedded with thin beds of dense limestone. Weathers to thin clay soil. Outcrops in southeastern part of Middle Tennessee is a very restricted outcrop belt.
		BROWNSPORT				CATHEYS FORMATION: A complex mixture of shaly limestone units. Typically it is thin bedded, blue gray nodular limestone interbedded with thin partings of shale and siltstone. Weathers to thin silty clay soil usually 3 to 4 feet thick. Outcrops extensively in Central Basin.
ORDOVICIAN		WAYNE		VARIABLE	0-250	BIGBY CANNON LIMESTONE: Composed of 3 facies: (1) the Bigby facies is blue gray, massive, granular, cross bedded, and phosphatic. (2) Dove facies is a light gray (Dove colored) dense fine grained limestone. (3) Cannon facies is blue gray limestone, massive but non-phosphatic. All facies weather to reddish-brown clay usually less than 10 feet thick. Some sinkhole development and considerable deep weathering along vertical fractures. Outcrops in Central Basin. Mined for phosphate in several counties of Central Basin.
		BRASSFIELD				HERMITAGE FORMATION: Variable rock units consisting of thin-bedded, dark blue-gray shaly limestone and sandy limestone in northwest part of Central Basin. Persistent layer of shale and phosphatic shale in central part of Central Basin. Silty shale and nodular limestone in south part of Central Basin. Weathers to a silty and sandy clay up to 20 feet thick. Outcrops extensively in Central Basin.
		SEQUATCHIE		55	0-275	CARTERS LIMESTONE: Contains upper and Lower member separated by T ¹ bentonite clay. Upper member is thin bedded, light gray shaly limestone about 10 feet thick. Lower member is massive, light gray, line grained limestone about 50 feet thick and contains T ¹ and T ¹ bentonite clays. Weathers to brown plastic clay about 4 feet thick with some sink holes. Outcrops extensively in Central Basin.
	MAYSVILLE	LEIPERS		70	0-160	LEBANON LIMESTONE: Blue-gray, dense, fine-grained, thin-bedded limestone. Bedding planes contain thin shale layers, weathers to loose slabs of limestone with very little residual soil. Forms cedar glades and has worm-eaten appearance. Outcrops in central part of Central Basin.
	EDEN	INMAN		50	0-70	
	NASHVILLE	CATHEYS		130	10-250	
		BIGBY CANNON		80	50-100	
		HERMITAGE		120	70-180	
		CARTERS		60	37-93	

REF. 7



United States Department of the Interior

GEOLOGICAL SURVEY
Water Resources Division
Tennessee District

A-413 Federal Bldg.
U.S. Courthouse
Nashville, TN 37203
February 19, 1987

CNP-2/23/87
DAS 2123
File
SCA-426

Mr. Todd Hughes
Tennessee Department of Health
and Environment
Customs House - 4th Floor
701 Broadway
Nashville, TN 37219-5403

94-508(1)

Dear Todd:

We have completed observation well installations and logging for the Genesco Hazardous Waste Site Investigation. Enclosed please find tables of data on the new wells and a sample resistivity log. We are completing a first draft of a basic data report on the site study, but we thought that both you and Geraghty and Miller would like to have preliminary copies of this data. If you approve, let me know and I'll route copies to Don Brice of Geraghty and Miller.

Sincerely yours,

FOR THE DISTRICT CHIEF

Roger W. Lee
Roger W. Lee

Enclosure

LOCAL WELL NUMBER	LATITUDE (DEGREES)	LONGITUDE (DEGREES)	ALTITUDE OF LAND SURFACE (FEET)	DATE WELL CONSTRUCTED	DEPTH OF WELL, (FEET)
WM:N-020	355809	0864626	740	10-18-84	350
WM:N-022	355805	0864627	710	05-01-81	158
WM:N-023	355756	0864625	720	08-14-85	1050
WM:N-024	355724	0864617	750	06-27-84	240
WM:N-033	355707	0864509	830	08-17-74	150
WM:N-038	355706	0864431	890	--	175
WM:N-039	355712	0864539	766.9	11-03-78	220
WM:N-040	355723	0864614	760	--	350
WM:N-041	355700	0864544	780.1	06-23-86	45.0
WM:N-041A	355700	0864544	780	09-23-86	225
WM:N-042	355701	0864557	754.0	06-23-86	35.0
WM:N-042A	355701	0864557	753.8	09-22-86	193
WM:N-043	355720	0864606	737.6	06-24-86	28.0
WM:N-043A	355720	0864606	738.4	10-07-86	102
WM:N-044	353718	0864610	744.1	06-25-86	34.1
WM:N-044A	353718	0864610	738.8	10-07-86	102
WM:N-045	355723	0864533	812.6	06-26-86	49.0
WM:N-045A	355723	0864532	812.6	10-10-86	167
WM:N-046	355732	0864602	758.0	06-30-86	30.0
WM:N-046A	355732	0864602	758.7	10-09-86	135
WM:N-047	355738	0864551	762.4	07-01-86	20.0
WM:N-047A	355738	0864551	759.9	10-09-86	162
WM:N-048	355733	0864540	806.4	07-01-86	45.0
WM:N-048A	355733	0864540	808.8	10-10-86	152
WM:N-050	355748	0864551	785.9	07-04-86	45.0
WM:N-050A	355748	0864551	786.8	10-08-86	162
WM:N-051	355745	0864601	754.1	07-05-86	25.0
WM:N-051A	355745	0864601	754.8	10-08-86	137
WM:N-052	355715	0864621	791.8	07-07-86	35.0
WM:N-052A	355715	0864621	792.9	10-06-86	132
WM:N-053	355654	0864550	795.8	07-08-86	55.0
WM:N-053A	355654	0864550	798.4	09-24-86	203
WM:N-054	355710	0864541	759.8	07-10-86	30.0
WM:N-054A	355710	0864541	760.3	10-13-86	139
WM:N-055	355714	0864545	757.8	07-11-86	30.0
WM:N-055A	355714	0864545	758.6	10-13-86	177
WM:N-056	355729	0864618	775	01-09-87	45.0
WM:N-056A	355729	0864618	775	01-12-87	175
WM:N-057	355713	0864552	795	01-07-87	57.0
WM:N-057A	355713	0864552	795	01-08-87	204
WM:N-058	355711	0864631	760	01-08-87	35.0
WM:N-058A	355711	0864631	760	01-09-87	165

LOCAL WELL NUMBER	DEPTH OF WELL (FEET)	BOTTOM OF CASING (FEET)	WATER- LEVEL, DATE	WATER LEVEL, (FEET)	
WM:N-020	350	21.0	--	--	WM:N-020
WM:N-022	158	20.0	--	--	<i>to</i>
WM:N-023	1050	20.0	--	--	<i>040</i>
WM:N-024	240	21.0	--	--	are domestic wells.
WM:N-033	150	--	--	--	
WM:N-038	175	--	--	--	
WM:N-039	220	20.0	--	--	NO W/L Data
WM:N-040	350	--	--	--	obtained
WM:N-041	45.0	10.0	02-05-87	10.05	
WM:N-041A	225	62.0	02-05-87	39.13	
WM:N-042	35.0	10.7	02-05-87	16.06	
WM:N-042A	193	34.0	02-05-87	15.76	
WM:N-043	28.0	5.00	02-05-87	25.53	
WM:N-043A	102	15.0	02-05-87	9.27	
WM:N-044	34.1	5.00	02-05-87	10.06	
WM:N-044A	102	20.0	02-05-87	9.57	
WM:N-045	49.0	--	02-05-87	30.94	
WM:N-045A	167	59.0	02-05-87	71.46	
WM:N-046	30.0	4.50	02-05-87	4.98	
WM:N-046A	135	15.0	02-05-87	29.57	
WM:N-047	20.0	3.10	02-05-87	5.92	
WM:N-047A	162	17.0	02-05-87	35.83	
WM:N-048	45.0	6.00	--	--	
WM:N-048A	152	41.0	02-05-87	71.81	
WM:N-050	45.0	10.0	02-05-87	11.70	
WM:N-050A	162	55.0	02-05-87	80.82	
WM:N-051	25.0	8.70	02-05-87	11.63	
WM:N-051A	137	34.0	02-05-87	36.46	
WM:N-052	35.0	19.5	02-05-87	19.50	
WM:N-052A	132	33.0	02-05-87	57.94	
WM:N-053	55.0	10.0	02-05-87	35.09	
WM:N-053A	203	41.0	02-05-87	63.79	
WM:N-054	30.0	4.50	02-05-87	2.69	
WM:N-054A	139	32.0	02-05-87	17.85	
WM:N-055	30.0	5.80	02-05-87	14.32	
WM:N-055A	177	26.0	02-05-87	18.03	
WM:N-056	775	20.0	02-05-87	22.54	
WM:N-056A	775	67.0	02-05-87	113.29	
WM:N-057	795	9.0	02-05-87	--	
WM:N-057A	795	57.0	02-05-87	50.74	
WM:N-058	760	12.5	02-05-87	16.51	
WM:N-058A	760	35.0	02-05-87	16.97	

WM:N-020
to
040
are domestic wells.

NO W/L Data
obtained

W/L referenced to
depth below land
surface.

WM:N-057 is a
Flowing well w/
head 7'10" above
land surface.

TABLE 1

CONSTRUCTION & STATUS OF DOMESTIC WELLS

WELL OWNER	DATE COMPLETED	CASING DIAM. (IN)	DEPTH OF CASING (FT)	TOTAL DEPTH (FT)	OPEN INTERVAL FORMATION	PRINCIPLE WATER BEARING ZONE (DEPTH FT)	STATUS	DRILLER
Allen				68-80			Residential	
Beyer	04/05/69	7	20	200	B,H,C	195	Residential	
Boswell	08/14/85	6.25	20	1050	H, L, R, P, M, K	1020	Residential	Henry Drilling Co.
Denny	10/18/84	6.25	21	350	H, C, L	277	Residential	Henry Drilling Co.
Fischer	06/27/84	6.25	21	240	H, C, L	70, 110	Residential	Henry Drilling Co.
Fletcher (1)				200	H, C, L	115-117	Residential	Henry Drilling Co.
Fletcher (2)				198	H, C, L	23, 115-116	Residential	Henry Drilling Co.
Foster (1)	08/08/85	6.25	20	260	H, C, L	146	Heat Pump	Henry Drilling Co.
Foster (2)	05/22/84	6.25	21	450	H, C, L, R	230	Residential	Henry Drilling Co.
Gore	06/04/70	6	20	75	H	65	Residential	
Holt		6	25	36	B	36	Residential	
Hall	03/03/86	6.25	24	400	H, C, L	80	Residential	Henry Drilling Co.
Howe				220	H, C, L	130	Residential	
Johnson	12/30/72	6	20	198	H, C	184	Residential	
Levine (1)	08/17/74	6	22	1235	H, C, L, R, P, M, K	1170	Residential	
Levine (2)				2200	H, C, L, R, P, M, K			
Myatt				73	H	18	Residential	
Legieza						28	Residential	
Mallory				350	H, C, L, R	112	Non-Potable	
Pewitt	09/16/81	6.25	21	105	H, C	105	Residential	Herman Clark Water Wells
Sullivan						28	Residential	
Wilson	02/28/84	6.25	21	260	B, H, C	160	Residential	Henry Drilling Co.

B = Bigby-Cannon Formation R = Ridley Formation
 H = Hermitage Formation P = Pierce Formation
 C = Carters Formation M = Murfreesboro Formation
 L = Lebanon Formation K = Knox Group

Information Provided by TUE, Division of Ground Water Protection.

REF.8


Uncontrolled Hazardous Waste Site Ranking System

A Users Manual
(HW-10)

Originally Published in
the July 16, 1982, *Federal Register*


United States
Environmental Protection
Agency

1984



Source: Climatic Atlas of the United States, U.S. Department of Commerce, National Climatic Center, Asheville, N.C., 1979.

FIGURE 4
MEAN ANNUAL LAKE EVAPORATION
(IN INCHES)



Source: Climatic Atlas of the United States, U.S. Department of Commerce, National Climatic Center, Asheville, N.C., 1979.

FIGURE 5
NORMAL ANNUAL TOTAL PRECIPITATION (INCHES)

TABLE 2

PERMEABILITY OF GEOLOGIC MATERIALS*

look at least permeable layer

Type of Material	Approximate Range of Hydraulic Conductivity	Assigned Value
Clay, compact till, shale; unfractured metamorphic and igneous rocks	$<10^{-7}$ cm/sec	0 (impermeable)
Silt, loess, silty clays, silty loams, clay loams; less permeable limestone, dolomites, and sandstone; moderately permeable till	$10^{-5} - 10^{-7}$ cm/sec	1
Fine sand and silty sand; sandy loams; loamy sands; moderately permeable limestone, dolomites, and sandstone (no karst); moderately fractured igneous and metamorphic rocks, some coarse till	$10^{-3} - 10^{-5}$ cm/sec	2
Gravel, sand; highly fractured igneous and metamorphic rocks; permeable basalt and lavas; karst limestone and dolomite	$>10^{-3}$ cm/sec	3

*Derived from:

Davis, S. N., Porosity and Permeability of Natural Materials in Flow-Through Porous Media, R.J.M. DeWiest ed., Academic Press, New York, 1969

Freeze, R.A. and J.A. Cherry, Groundwater, Prentice-Hall, Inc., New York, 1979

substance used in rating waste characteristics. Where the total inventory of substances in a facility is known, only those present in amounts greater than the reportable quantity (see CERCLA Section 102 for definition) may be evaluated.

Toxicity and Persistence have been combined in the matrix below because of their important relationship. To determine the overall value for this combined factor, evaluate each factor individually as discussed below. Match the individual values assigned with the values in the matrix for the combined rating factor. Evaluate several of the most hazardous substances at the facility independently and enter only the highest score in the matrix on the work sheet.

Value for Toxicity	Value for Persistence			
	0	1	2	3
0	0	0	0	0
1	3	6	9	12
2	6	9	12	15
3	9	12	15	18

Persistence of each hazardous substance is evaluated on its biodegradability as follows:

<u>Substance</u>	<u>Assigned Value</u>
Easily biodegradable compounds	0
Straight chain hydrocarbons	1
Substituted and other ring compounds	2
Metals, polycyclic compounds and halogenated hydrocarbons	3

more specific information is given in Tables 4 and 5.

Toxicity of each hazardous substance being evaluated is given a value using the rating scheme of Sax (Table 6) or the National Fire Protection Association (NFPA) (Table 7) and the following guidance:

<u>5th ed.</u>	<u>Toxicity</u>	<u>Assigned Value</u>
None	Sax level 0 or NFPA level 0	0
Low	Sax level 1 or NFPA level 1	1
moderate	Sax level 2 or NFPA level 2	2
high	Sax level 3 or NFPA level 3 or 4	3

*Sax is preferred
5th Edition*

Table 4 presents values for some common compounds.

Hazardous waste quantity includes all hazardous substances at a facility (as received) except that with a containment value of 0. *NOT DEPENDENT UPON CONCENTRATION - dilution is not the solution to pollution.*

Do not include amounts of contaminated soil or water; in such cases, the amount of contaminating hazardous substance may be estimated.

On occasion, it may be necessary to convert data to a common unit to combine them. In such cases, 1 ton = 1 cubic yard = 4 drums and for the purposes of converting bulk storage, 1 drum = 50 gallons. Assign a value as follows:

<u>Tons/Cubic Yards</u>	<u>No. of Drums</u>	<u>Assigned Value</u>
0	0	0
1-10	1-40	1
11-62	41-250	2
63-125	251-500	3
126-250	501-1000	4
251-625	1001-2500	5
626-1250	2501-5000	6
1251-2500	5001-10,000	7
>2500	>10,000	8

TABLE 4
WASTE CHARACTERISTICS VALUES
FOR SOME COMMON CHEMICALS

CHEMICAL/COMPOUND	<div style="display: flex; justify-content: space-around; transform: rotate(-45deg);"> 1234 </div>			
	1	2	3	4
Acetaldehyde	3	0	3	2
Acetic Acid	3	0	2	1
Acetone	2	0	3	0
Aldrin	3	3	1	0
Ammonia, Anhydrous	3	0	1	0
Aniline	3	1	2	0
Benzene	3	1	3	0
Carbon Tetrachloride	3	3	0	0
Chlordane	3	3	0 ^a	0 ^a
Chlorobenzene	2	2	3	0
Chloroform	3	3	0	0
Cresol-O	3	1	2	0
Cresol-M&P	3	1	1	0
Cyclohexane	2	2	3	0
Dieldrin	3	3	1	0
Ethyl Benzene	2	1	3	0
Formaldehyde	3	0	2	0
Formic Acid	3	0	2	0
Hydrochloric Acid	3	0	0	0
Isopropyl Ether	3	1	3	1
Lindane	2	3	1	0
Methane	1	1	3	0
Methyl Ethyl Ketone	2	0	3	0
Methyl Parathion in Xylene Solution	3	0 ^d	3	2
Naphthalene	2	1	2	0
Nitric Acid	3	0	0	0
Parathion	3	0 ^d	1	2
PCB	3	3	0 ^d	0 ^d
Petroleum, Kerosene (Fuel Oil No. 1)	3	1	2	0
Phenol	3	1	2	0
Sulfuric Acid	3	0	0	2
Toluene	2	1	3	0
Trichlorobenzene	2	3	1	0
m-Trichlorobenzene	2	2	1	0
Xylene	2	1	3	0

¹ Sax, N. I., Dangerous Properties of Industrial Materials, Van Nostrand Reinhold Co., New York, 4th ed., 1975. The highest rating listed under each chemical is used.

² JEB Associates, Inc., Methodology for Rating the Hazard Potential of Waste Disposal Sites, May 1, 1980.

³ National Fire Protection Association, National Fire Codes, Vol. 13, No. 49, 1977.


^a Professional judgment based on information contained in the U.S. Coast Guard CHRIS hazardous Chemical Data, 1978.

^d Professional judgment based on existing literature.

TABLE 5

PERSISTENCE (BIODEGRADABILITY) OF
SOME ORGANIC COMPOUNDS*

VALUE = 3 HIGHLY PERSISTENT COMPOUNDS		VALUE = 1 SOMEWHAT PERSISTENT COMPOUNDS	
aldrin	heptachlor	acetylene dichloride	limonene
benzopyrene	heptachlor epoxide	benzoic acid, methyl ester	methyl ester of lignoceric acid
benzothiazole	1,2,3,4,5,7,7-heptachloronothornene	benzene	methane
benzothiofene	hexachlorobenzene	benzene sulfonic acid	2-methyl-5-ethyl-pyridine
benzyl butyl phthalate	hexachloro-1,3-butadiene	butyl benzene	methyl naphthalene
bromochlorobenzene	hexachlorocyclohexane	butyl bromide	methyl palmitate
bromofenr butanal	hexachloroethane	n-caproic acid	methyl phenyl carbinol
bromophenyl phynyl ether	methyl benzothiazole	carbon-disulfide	methyl stearate
chlordane	pentachlorobiphenyl	n-cresol	naphthalene
chlorohydroxy benzophenone	pentachlorophenol	decane	nonane
bis-chlorodiphenyl ether	1,1,3,3-tetrachloroacetone	1,2-dichloroethane	octane
m-chloronitrobenzene	tetrachlorobiphenyl	1,2-dimethoxy benzene	octyl chloride
DDE	thiomethylbenzothiazole	1,3-dimethyl naphthalene	pentane
DDT	trichlorobenzene	1,4-dimethyl phenol	phenyl benzoate
dibromobenzene	trichlorobiphenyl	diethyl adipate	phthalic anhydride
diethyl phthalate	trichlorofluoromethane	n-dodecane	propylbenzene
1, 4-dichlorobenzene	2,4,6-trichlorophenol	ethyl benzene	1-terpineol
dichlorodifluoroethane	triphenyl phosphate	2-ethyl-n-hexane	toluene
dieldrin	bromochloromethane	n-ethyltoluene	vinyl benzene
diethyl phthalate	bromofenr	isododecane	xylene
di(2-ethylhexyl)phthalate	carbon tetrachloride	isopropyl benzene	
diethyl phthalate	chloroform		
di-isobutyl phthalate	chloromethylmethane		
dimethyl phthalate	dibromodichloroethane		
4,6-dinitro-2-naphthanol	tetrachloroethane		
dipropyl phthalate	1,1,2-trichloroethane		
endrin			
VALUE = 2 PERSISTENT COMPOUNDS		VALUE = 0 NONPERSISTENT COMPOUNDS	
acrophthylene	cis-2-ethyl-4-methyl-1,3-dioxolene	acetaldehyde	methyl benzoate
atrazine	trans-2-ethyl-4-methyl-1,3-dioxolane	acetic acid	3-methyl butanol
(diethyl) atrazine	guaiacol	acetone	methyl ethyl ketone
barbital	2-hydroxydipentitrile	acetophenone	2-methylpropanol
benzene	isophenone	benzoic acid	octadecane
benzobenzene	indene	di-isobutyl carbinol	pentadecane
camphor	isoborneol	dicosane	pentanol
chlorobenzene	isopropenyl-r-isopropyl benzene	tricosane	propanol
1,2-bis-chloroethoxy ethane	2-methoxy biphenyl	ethanol	propylamine
b-chloromethyl methyl ether	methyl biphenyl	ethylamine	tetradecane
chloromethyl ether	methyl chloride	hexadecane	n-tridecane
chloromethyl ethyl ether	methylindene	methanol	n-undecane
3-chloropyridine	methylene chloride		
di-t-butyl-p-benzoquinone	nitroanisole		
dichloromethyl ether	nitrobenzene		
dihydrocarvone	1,1,2-trichloroethylene		
dimethyl sulfide	trimethyl-trioxo-hexahydro-triazine		
2,6-dinitrotoluene	isomer		



Source: Rainfall Frequency Atlas of the United States, Technical Paper No. 40, U.S. Department of Commerce, U.S. Government Printing Office, Washington, D.C., 1963.

FIGURE 8
1-YEAR 24-HOUR RAINFALL
(INCHES)

DRAFT
01-14-87

Table I is the listing of EPA Hazard Ranking System (HRS) Waste Characteristics Values (Toxicity/Persistence matrix) used by the NPL quality assurance team. These rating factor values are based on the criteria specified in the HRS (toxicity rating assigned to each substance in Sax, Dangerous Properties of Industrial Chemicals, 4th, 5th and 6th editions). The listing shows the matrix values for ground water and surface water and the toxicity value for air. The values shown are "post multiplier" for use on the HRS worksheets. Changes to this list are made, albeit infrequently, as a result of response to public comment and changes in the reference material. Questions should be directed to the NPL quality assurance team via Mr. Steve Caldwell, EPA Headquarters, (202) 475-8103.

TABLE I

EPA Hazard Ranking System Waste Characteristics Values
(Toxicity/Persistence Matrix)

Chemical/Compound	Ground Water and Surface Water Pathway Values	Air Pathway Values
Acenaphthene	9	3
Acetaldehyde	6	6
Acetic Acid	6	6
Acetone	6	6
2-Acetylaminoflourene	18	9
Aldrin	18	9
Ammonia	9	9
Aniline	12	9
Anthracene	15	9
Arsenic	18	9
Arsenic Acid	18	9
Arsenic Trioxide	18	9
Asbestos	15	9
Barium	18	9
Benzene	12	9
Benzidine	18	9
Benzoapylene	18	9
Benzopyrene, NOS	18	9
Beryllium & Compounds		
NOS	18	9
Beryllium Dust, NOS	18	9
Bis (2-Chloroethyl) Ether	15	9
Bis (2-Ethylhexyl Phthalate	12	3
Bromodichloromethane	15	6
Bromoform	15	6
Bromomethane	15	9
Cadmium	18	9
Carbon Tetrachloride	18	9
Chlordane	18	9
Chlorobenzene	12	6
Chloroform	18	6
3-Chlorophenol	12	6
4-Chlorophenol	15	9
2-Chlorophenol	12	6
Chromium	18	9
Chromium, Hexavalent (Cr ⁺⁶)	18	9

Table I (cont.)

Chemical/Compound	Ground Water and Surface Water Pathway Values	Air Pathway Values
Chromium, Trivalent (Cr ⁺³)	15	6
Copper & Compounds, NOS	18	9
Creosote	15	6
Cresols	9	6
4-Cresol	12	9
Cupric chloride	18	9
Cyanides (soluble salts), NOS	12	9
Cyclohexane	12	6
DDE	18	9
DDT	18	9
Diaminotoluene	18	6
Dibromochloromethane	15	6
1, 2-Dibromo, 3- chloropropane	18	9
Di-N-Butyl-Phthalate	18 12	6
1, 4-Dichlorobenzene	18 12	6
Dichlorobenzene, NOS	18	6
1, 1-Dichloroethane	12	6
1, 2-Dichloroethane	12	9
1, 1-Dichloroethene	15	9
1, 2-cis-Dichloro- ethylene	12	3
1, 2-trans-Dichloro- ethylene	12	3
Dichloroethylene, NOS	12	3
2, 4-Dichlorophenol	18	6
2, 4-Dichlorophenoxyacetic Acid	18	9
Dicyclopentadiene	18	9
Dieldrin	18	9
2, 4-Dinitrotoluene	15	9
Dioxin	18	9
Endosulfan	18	9
Endrin	18	9
Ethylbenzene	9	6
Ethylene Dibromide	18	9
Ethylene Glycol	9	6
Ethyl Ether	15	3
Ethylmethacrylate	12	6

Table I (cont.)

Chemical/Compound	Ground Water and Surface Water Pathway Values	Air Pathway Values
Fluorine	18	9
Formaldehyde	9	9
Formic Acid	9	6
Heptachlor	18	9
Hexachlorobenzene	15	6
Hexachlorobutadiene	18	9
Hexachlorocyclohexane, NOS	18	9
Hexachlorocyclopentadiene	18	9
Hydrochloric Acid	9	6
Hydrogen Sulfide	18	9
Indene	12	6
Iron & Compounds, NOS	18	9
Isophorone	12	6
Isopropyl Ether	9	3
Kelthane	15	6
Kepone	18	9
Lead	18	9
Lindane	18	9
Magnesium & Compounds, NOS	15	6
* Manganese & Compounds, NOS	18 12	9
Mercury	18	9
Mercury Chloride	18	9
Methoxychlor	15	6
4, 4'-Methylene-Bis-(2- Chloroaniline)	18	9
Methylene Chloride	12	6
Methyl Ethyl Ketone	6	6
Methyl Isobutyl Ketone	12	6
4-Methyl-2-Nitroaniline	12	6
Methyl Parathion	9	6
2-Methylpyridine	12	6
Mirex	18	9

* Subject to EPA HQ approval

NOTE: Iron is not a CERCLA listed hazardous waste

Table I (cont.)

Chemical/Compound	Ground Water and Surface Water Pathway Values	Air Pathway Values
Naphthalene	9	6
* Nickel & Compounds, NOS	18 12	9
Nitric Acid	9	9
Nitroaniline, NOS	18	9
Nitrogen Compounds, NOS	12	0
Nitroguanidine	12	9
Nitrophenol, NOS	15	9
m-Nitrophenol	15	
o-Nitrophenol	12	
p-Nitrophenol	15	
Nitrosodiphenylamine	12	6
Parathion	9	9
Pentachlorophenol (PCP)	18	9
Pesticides, NOS	18	9
Phenanthrene	15	9
Phenol	12	9
Phosgene	9	9
Polybrominated Biphenyl (PBB), NOS	18	9
Polychlorinated Biphenyls (PCB), NOS	18	9
Potassium Chromate	18	9
Radium & Compounds, NOS	18	9
Radon & Compounds, NOS	15	9
RDX (Cyclonite)	15	
2, 4-D, Salts & Esters	18	9
* Selenium	18 12	9
Sevin (Carbaryl)	18	9
Sodium Cyanide	12	9
Styrene	9	6
Sulfate	9	0
Sulfuric Acid	9	9
2, 4, 5-T	18	9
1, 1, 2, 2-Tetrachloro- ethane	18	9
Tetrachloroethane, NOS	18	9
1, 1, 2, 2-Tetrachloro- ethene	12	6

* Subject to EPA HQ approval

Table I (cont.)


Chemical/Compound	Ground Water and Surface Water Pathway Values	Air Pathway Values
Tetraethyl Lead	18	9
Tetrahydrofuran	15	6
Thorium & Compounds, NOS	18	9
Toluene	9	6
TNT	12	
Toxaphene	18	9
Tribromomethane	18	9
1, 2, 4-Trichlorobenzene	15	6
1, 3, 5-Trichlorobenzene	15	6
1, 1, 1-Trichloroethane	12	6
1, 1, 2-Trichloroethane	15	6
Trichloroethane, NOS	15	6
Trichloroethene	12	6
1, 1, 1-Trichloropropane	12	6
1, 1, 2-Trichloropropane	12	6
1, 2, 2-Trichloropropane	12	6
1, 2, 3-Trichloropropane	15	9
Uranium & Compounds, NOS	18	9
Varsol	12	6
Vinyl Chloride	15	9
Xylene	9	6
* Zinc & Compounds, NOS	12 12	9
Zinc Cyanide	18	9

* Subject to EPA HQ approval

REF. 9

SOIL SURVEY

Williamson County Tennessee



UNITED STATES DEPARTMENT OF AGRICULTURE
Soil Conservation Service
In cooperation with
TENNESSEE AGRICULTURAL EXPERIMENT STATION

Series 1961, No. 5

Issued August 1964

easy to work and are suited to all commonly grown crops and pasture.

Stiversville silt loam, 5 to 12 percent slopes, eroded (SIC2).—This well-drained soil is on the uplands of the outer Central Basin. It has formed from phosphatic sandy limestone interbedded with shale. Small fragments of soft, sandy limestone are generally scattered throughout the soil. The depth to bedrock ranges from about 2 to 5 feet.

Representative profile:

0 to 8 inches, dark-brown, very friable silt loam with granular structure.

8 to 20 inches, reddish-brown or yellowish-brown, friable silty clay loam with blocky structure.

20 to 40 inches, dark-brown or reddish-brown, friable silty clay loam or clay loam with blocky structure; common fragments of sandy limestone increase in size and amount with increasing depth.

This soil is medium to high in phosphorus, is medium acid to strongly acid, and is moderate in available moisture capacity. Permeability is moderately rapid to rapid. The soil has a deep root zone and generally is in good tilth.

Nearly all areas of this soil have been cleared, but a considerable acreage is now idle. The soil is easy to work and is suited to many kinds of crops and pasture. Crops grown on it respond to good management, especially to additions of lime. The soil can be cultivated every 3 or 4 years if it is well managed and special practices are used to control water. (Capability unit IIIe-1)

Stiversville silt loam, 2 to 5 percent slopes, eroded (SIB2).—This deep, well-drained soil is on gently sloping uplands in the eastern half of the county. It has formed from interbedded, phosphatic, sandy limestone and shale and contains highly weathered, sandy fragments in the lower subsoil. The surface layer is dark-brown silt loam, about 8 inches thick. The subsoil is yellowish-brown or reddish-brown silty clay loam or clay loam. In places small fragments of weathered siltstone or sandy limestone are on the surface. A few patches of this soil are severely eroded and have a plow layer of clay loam. Bedrock is at a depth of 2½ to 5 feet.

The soil is medium to high in phosphorus, is medium acid to strongly acid, and is moderate to moderately high in available moisture capacity. It is moderately rapid in permeability.

Many kinds of crops and pasture are suited to this soil. It is easy to work and to conserve and can be used moderately intensively. (Capability unit IIe-1)

Stiversville silt loam, 12 to 20 percent slopes, eroded (SID2).—This phosphatic soil is on short slopes of rolling hills. The surface layer of brown or dark-brown silt loam is about 4 to 6 inches thick and is underlain by a subsoil of yellowish-brown or reddish-brown silty clay loam or clay loam. In most places a few fragments of weathered siltstone or sandy limestone are on the surface. These sandy fragments are more common in the lower subsoil. Bedrock is generally at a depth of 2½ to 5 feet.

The soil is medium to high in phosphorus and is medium acid to strongly acid. It has a moderate to moderately low available moisture capacity. Permeability is moderately rapid to rapid.

Nearly all of this soil has been cleared and cultivated. Most of it is now used for pasture, but a considerable acreage is used for crops. Although the soil is suited to all

common crops, it is too sloping for frequent cultivation. Plants respond especially well if lime is added to the soil. (Capability unit IVe-1)

Stiversville clay loam, 5 to 12 percent slopes, severely eroded (SIC3).—This soil has a surface layer of brown or yellowish-brown clay loam, 3 to 5 inches thick. Most of this layer is yellowish-brown or reddish-brown silty clay loam or clay loam from the subsoil. In most places fragments of weathered siltstone or sandy limestone are on the surface. Many shallow gullies or a few deep ones are common, and in places there are a few outcrops of bedrock. The average depth to bedrock, however, is between 2 and 4 feet.

This soil is medium to high in phosphorus and is medium acid to strongly acid. Although not especially droughty, the soil is generally in poor tilth. Because of the fine-textured surface layer and the strong slopes, further erosion is likely and frequent cultivation is not practical. With careful management that includes intensive conservation practices, the soil can be cultivated every 4 or 5 years. It is fairly well suited to the commonly grown crops and pasture. Crops respond to good management, especially to additions of lime and nitrogen. (Capability unit IVe-1)

Stiversville clay loam, 12 to 20 percent slopes, severely eroded (SID3).—This severely eroded, phosphatic soil is on strongly sloping uplands of the outer Central Basin. The surface layer is brown or yellowish-brown clay loam. This layer is 3 to 5 inches thick and consists mostly of yellowish-brown or reddish-brown silty clay loam or clay loam from the subsoil. Many shallow gullies or a few deep ones are common. In most places fragments of weathered siltstone or sandy limestone, ½ to 3 inches across, are on the surface. These sandy fragments generally are throughout the soil and increase in size and amount with increasing depth. Bedrock of phosphatic sandy limestone is at a depth of 2 to 4 feet.

The soil has lost much of its natural fertility and most of its organic matter. It has low available moisture capacity.

All of this soil has been cleared and cultivated. About 25 percent of the acreage is still in crops, 50 percent is in pasture, and 25 percent is idle or is in sparse stands of trees. Because of the fine-textured surface layer and steep slopes, runoff is rapid and the hazard of further erosion is great. Therefore, the soil is best suited to permanent pasture or hay. (Capability unit VIe-1)


Sulphura Series

In the Sulphura series are steep soils on high hills and knobs. These soils have developed in residuum of shale, which in most places is mantled by 2 to 14 inches of cherty creep that drifted down from higher soils.

Sulphura soils have a surface layer of dark grayish-brown cherty silt loam about 6 inches thick, and a subsoil of dark-brown shaly silt loam or shaly silty clay loam. Shale bedrock generally is at a depth of 18 to 24 inches, but it crops out on the steeper slopes. Slopes range from 12 to 50 percent but are generally greater than 20 percent.

These soils are medium acid to strongly acid and low in available moisture capacity.

The Sulphura soils are between the Bodine soils and Dellrose soils on hillsides. They are below the Bodine



REF. 10



FEB 21 1986

City of Brentwood

P.O. BOX 788, 116 WILSON PIKE

BRENTWOOD, TENNESSEE 37027

TELEPHONE (615) 273-8041 371-0060

T. MACK BLACKBURN
MAYOR

PHILLIP HARDEMAN
VICE MAYOR

FRANK W. CLIFTON, JR.
CITY MANAGER

COMMISSIONERS

T. MACK BLACKBURN
PHILLIP HARDEMAN
HAROLD J. McMURTRY
BRIAN J. SWEENEY
RICHARD L. VAUGHN

February 19, 1986

Mr. Donald Shackleford
Tennessee Department of Health and Environment
701 Broadway, 4th floor Customs House
Nashville, TN 37219-5403

Dear Mr. Shackleford:

Based on our previous conversations and our meeting with Dr. Bruner and Mayor Blackburn, the following cost estimates are provided:

Alternative 1

6" Ductile Iron Pipe from Alamo Drive to the intersection of Split Log Road and Wilson Pike and east on Split Log Road to the existing city limits and south on Wilson Pike to the existing city limits.

17,000 L.F. of 6" DI Pipe at \$14/LF	\$ 238,000
37 6" Gate Valves at \$400 each	14,800
24 Fire Hydrants at \$1,100 each	26,400
Railroad Crossing (Tunnelled)	20,000
Pavement Repairs 300 LF at \$12/LF	3,600
Crushed Stone 8,000 LF at \$1/LF	8,000
Meters/Boxes 25 at \$200 each	5,000
Service Lines 625 LF at \$4/LF	2,500
Engineering (6%)	19,100
Inspection (4%)	12,700
Contingency (10%)	31,400

Total Estimated Cost

\$ 382,000

Mr. Donald Shackelford
February 19, 1986
Page two

Alternative 2

Instead of 6" Ductile Iron Pipe use Class 200 PVC Pipe at an estimated cost of \$7/LF instead of \$14/LF for Ductile Iron. All other factors remain the same, a savings of \$119,000 is realized. Total revised project cost will be \$263,000.

Alternative 3

Replacing the proposed minimum 6" Ductile Iron Pipe with a 12" Ductile Iron Pipe to provide adequate water supply for future growth. A revised cost estimate is as follows:

16,000 L.F. of 12" Ductile Iron Pipe at \$28/LF	\$ 448,000
500 L.F. of 6" Ductile Iron Pipe at \$14/LF	7,000
12" Gate Valves--13 at \$900 each	11,700
6" Gate Valves--24 at \$400 each	9,600
Fire Hydrants--24 at \$1,100 each	26,400
Railroad Crossing (Tunnelled)	20,000
Pavement Repairs--300 L.F. at \$12/LF	3,600
Crushed Stone--8,000 L.F. at \$1/LF	8,000
Meters/Boxes--25 at \$200 each	5,000
Service Lines 625 L.F. at \$4/LF	2,500
Engineering (6%)	33,400
Inspection (4%)	22,300
Contingency (10%)	55,700
Total Estimated Cost	\$ 668,000

Alternative 4

Instead of 12" Ductile Iron Pipe Use Class 200 PVC Pipe at an estimated cost of \$14/LF instead of \$28/LF for Ductile Iron. All other factors remain consistent, a savings of \$227,500 is realized. Total revised project cost will be \$440,500.

In addition to one of the above options the City will be required to bring a second feeder line into the new proposed line. This second feeder will come down Wilson Pike from Concord Road to the new connection off of Alamo Drive. The approximate length of this additional line is estimated to be 4,500 L.F. This second feeder line will cost additionally above alternatives 1-4 (depending on the option selected) as follows:

Mr. Donald Shackelford
February 19, 1986
Page three

- 6" Ductile Iron Pipe	\$ 97,000
- 6" Class 200 PVC	64,800
- 12" Ductile Iron Pipe	180,000
- 12" Class 200 PVC	115,600

Summarizing

To effectively get a reliable source of public water to area in question would cost a minimum of \$327,800 and under the most desirable conditions, using 12" PVC Class 200 Pipe, \$556,500. These estimates would be subject to actual bids.

If Class 200 PVC Pipe is allowable under these conditions, I feel the City would want to install the 12" line as a minimum, understanding that the City would have to pick up the cost difference between the 12" and 6" pipe and the second feeder to the area in question.

Based on the above calculations, I feel a reasonable estimate of cost sharing on this project would be:

Local Sources	\$ 293,100
State and/or Pollution Offenders	<u>263,000</u>
Total Estimated Cost	\$ 556,100

Please recognize that these figures include no cost for right-of-way acquisition or condemnation expenses.


This information is being provided the Brentwood City Commission for their review and knowledge. We will await further contact from your office with regards to proceeding with any additional action.

Respectfully,


Frank W. Clifton, Jr.
City Manager

cc: Mayor and City Commission
City Attorney Robert H. Jennings, Jr.

FWC:NS



REF. 11

JGA 8/1
OR-8/4
AUG 01 1986
OHP-8/6
File

Employee and Environmental Safety

Mr. Frank W. Clifton, Jr.
City Manager
City of Brentwood
P.O. Box 788
Brentwood, TN 37027

RE: SERVICE CONNECTIONS

July 28, 1986

Dear Frank:

As we discussed with you and with John Grissom, an estimate of the cost of each service connection prior to installation would probably be the best method of insuring we are in agreement of the costs involved.

To facilitate the cost estimates, we asked Bill Griggs of Barge, Waggoner, Sumner and Cannon, to meet with John Grissom, Manager of Water Service of the City of Brentwood, to estimate distances and size of service line needed, etc. Attached is his report.

Bill's basic assumption on sizes, etc. was to assume that your storage tank would be 50% full, a residual pressure of 20 psi would be maintained, and that 10 GPM would be adequate for each residence.

There are questions we have involving three service connections that we would like to ask either John Grissom or the contractor to clarify:

It would appear to be much more cost effective to combine the service lines to the three residences on the Sharp property, and to extend the service connection to Mr. Reese Smith's house back down the hill to connect to Woodrow Shaw's residence (Mr. Smith's tenant). If a common service line is not applicable, we would still prefer a common trench.


If you could have someone clarify this before we proceed further, it would expedite the cost estimating process.

As quickly as the cost estimates are submitted, we will have a prompt review, so we could proceed without undue delay.

Mr. Frank W. Clifton
July 28, 1986
Page two

Thank you for your assistance.

Sincerely,

A handwritten signature in dark ink, appearing to read "R. Mosely", written over the printed name.

Ralph E. Mosely
Director
Employee and Environmental Safety

RM/bb

cc: Mr. John Grissom - City of Brentwood
Mr. Bill Griggs - Barge, Waggoner, Sumner & Cannon
Mr. Don Shackelford - Tennessee Dept. of Health & Environment

RECOMMENDED SERVICE LINE SIZES
BREWING WATER LINE
FILE 9035

1 MILE RADIUS
Jan 3/3/87
Charles B. B. - Superfund Field Coordinator

Name	Address	Parcel	Elev.	Estimated Dist. from Road, Ft.	Service Line Size, In.	Available GPM	Remarks
[REDACTED]	[REDACTED]	54-39.15	730	200	3/4	13	
[REDACTED]	[REDACTED]	54-39.14	720	400	3/4	10	
[REDACTED]	[REDACTED]	54-39.13	720	200	3/4	14	
[REDACTED]	[REDACTED]	54-39.11	725	175	3/4	14	
[REDACTED]	[REDACTED]	54-39.10	725	175	3/4	14	
[REDACTED]	[REDACTED]		730	150	3/4	15	
[REDACTED]	[REDACTED]		730	300	3/4	10	
[REDACTED]	[REDACTED]		750	600	1	14	1
[REDACTED]	[REDACTED]		750	600	1	14	
[REDACTED]	[REDACTED]	54-39.04	760	600	1	13	
[REDACTED]	[REDACTED]	54-39.05	770	600	1	12	
[REDACTED]	[REDACTED]	54-42.01	760	200	3/4	11	
[REDACTED]	[REDACTED]	54-42.02	760	500	1	15	
[REDACTED]	[REDACTED]	54-40	760	600	1	14	
[REDACTED]	[REDACTED]	54-40	820	2,000	2	25	
[REDACTED]	[REDACTED]	54-40	780	1,800	1-1/2	18	
[REDACTED]	[REDACTED]	61-5	830	1,500	2	25	

¹John Gilson was unsure of exact location.

³In les head loss through meter, minimal loss through 12" main, tank 50% full, and 20 psi residual pressure.

<u>Name</u>	<u>Address</u>	<u>Parcel</u>	<u>Elev.</u>	<u>Estimated Dist. from Road, Ft.</u>	<u>Service Line Size, In.</u>	<u>Available GPM³</u>	<u>Remarks</u>
[REDACTED]	[REDACTED]	61-5	830	1,700	2	23	
[REDACTED]	[REDACTED]	61-5	810	1,200	1-1/2	17	2
[REDACTED]	[REDACTED]		770	250	1	20	
[REDACTED]	[REDACTED]		780	250	1	19	
[REDACTED]	[REDACTED]		765	600	1	13	
[REDACTED]	[REDACTED]		760	200	3/4	11	
[REDACTED]	[REDACTED]		790	400	1	13	
[REDACTED]	[REDACTED]		785	400	1	14	
[REDACTED]	[REDACTED]		790	700	1	10	
[REDACTED]	[REDACTED]		800	150	3/4	10	
[REDACTED]	[REDACTED]		825	600	1-1/2	20	
[REDACTED]	[REDACTED]		765	500 ⁴	1	14	
[REDACTED]	[REDACTED]		790	400	1	13	
[REDACTED]	[REDACTED]		720	600	1	16	

Summary - 3/4" - 2,150 LF
 - 1" - 7,600 LF
 - 1-1/2" - 3,600 LF
 - 2" - 5,200 LF

²Served from Split Log Road.

³Includes head loss through meter, minimal loss through 12" main, tank 50% full, and 20 psi residual pressure.

⁴No existing house, assumed distance.

REF. 12

REF. 13 + 14

OVERSIZED

DOCUMENT

REF.15

REF.16

DEC 20 1985



TENNESSEE WILDLIFE RESOURCES AGENCY

ELLINGTON AGRICULTURAL CENTER
P. O. BOX 40747
NASHVILLE, TENNESSEE 37204

December 19, 1985

Mr. Gordon Caruthers
Solid Waste Management Division
Department of Health & Environment
701 Broadway
Nashville, TN 37219

Dear Gordon:

In response to your call of December 19, I am happy to enclose descriptions of critical wildlife habitat of Tennessee, as designated by the U.S. Fish and Wildlife Service.

Please advise if I can be of further assistance.

Sincerely,

TENNESSEE WILDLIFE RESOURCES AGENCY

Robert M. Hatcher, Coordinator
Nongame/Endangered Species


RME/ch
enc.

8/85

Proposed Rules (Region 4)

(E = Endangered; T = Threatened; CH = Critical Habitat; S/A = Classified under similarity of appearance provision)

<u>SPECIES</u>	<u>LOCATION</u>	<u>DETERMINATION</u>	<u>FEDERAL REGISTER</u>
Trispot Darter (<u>Etheostoma trisella</u>)	Conasauga River, Coahulla Creek, TN, GA	E, CH	07/13/84
Prickly-ash (<u>Zanthoxylum thomsonianum</u>)	PR, VI	E	02/11/85
Dismal Swamp Southeastern Snrew (<u>Sorex longirostris</u> <u>fisheri</u>)	VA and NC	T	07/16/85
Short's Goldenrod (<u>Solidago shortii</u>)	Robertson, Nicholas, Fleming Co., KY	E	10/11/84
Key Largo Cotton Mouse and Woodrat	N. Key Largo, FL	CH	02/09/84, 08/31/84, 11/21/84
Prickly Apple Cactus (<u>Cereus eriophorus</u> var. <u>traprans</u>)	St. Lucie Co., FL	E	03/06/85
Longspurred Balm (<u>Dicerandra cornutissima</u>)	Marion Co., FL	E	
Scrub Balm (<u>Dicerandra frutescens</u>)	Highlands Co., FL	E	03/26/85
Canby's Dropwort (<u>Oxybolis canbyi</u>)	Burke, Lee, Sumter Co., GA; Scotland Co., NC; Bamberg, Colleton Co., SC; MD	E	03/28/85
Florida Golden Aster (<u>Oenysopsis floridana</u>)	Hillsborough and Pinellas Counties, FL	E	08/05/85
Pondberry (<u>Lindera melissifolia</u>)	AR: Clay Co. MS: Sharkey Co. MO: Ripley Co. NC: Bladen Co. SC: Berkeley Co. GA: Wheeler Co.	E	08/13/85



ENDANGERED AND THREATENED WILDLIFE AND PLANTS

JULY 20, 1964

50 CFR 17.11 and 17.12

Department of the Interior
U.S. Fish and Wildlife Service

DEPARTMENT OF THE INTERIOR

Fish and Wildlife Service

50 CFR Part 17

Republication of the Lists of Endangered and Threatened Species

AGENCY: Fish and Wildlife Service, Interior.

ACTION: Final rule.

SUMMARY: The Service republishes the U.S. Lists of Endangered and Threatened Wildlife and Plants. The last complete republication was May 20, 1980 (45 FR 33768-33781). Minor changes, principally in names of the species, are incorporated in this republication.

DATES: This rule is effective on July 27, 1983.

ADDRESSES: Comments concerning this republication should be sent to the Associate Director—Federal Assistance, Fish and Wildlife Service, U.S. Department of the Interior, Washington, D.C. 20240.

FOR FURTHER INFORMATION CONTACT: Mr. John L. Spinks, Jr., Chief, Office of Endangered Species, U.S. Fish and Wildlife Service, Washington, D.C. 20240 (703/235-5771).

SUPPLEMENTARY INFORMATION:

Background

These lists contain the names of species officially listed as Endangered or Threatened under the Endangered Species Act of 1973, as amended (16 U.S.C. 1531, *et seq.*) through the date of this republication. The listing regulations promulgated under that Act are found at 50 CFR Part 424 and are under revision to conform to the Endangered Species Act Amendments of 1982 (Pub. L. 97-304, 96 Stat. 1411). The previous compilation of these lists appears in the 1982 edition of the Code of Federal Regulations for Title 50, which was actually issued in early 1983. That compilation was effective through October 1, 1982. This republication of §§ 17.11 and 17.12 incorporates all subsequent changes (i.e., additions, reclassifications, and deletions) published as Final Rules in the Federal Register.

In addition to those changes, the Service has made extensive revisions on some of the entries. Most of these changes reflect current nomenclature. The entries for the common and scientific names of many plants and animals are amended by adding synonyms, indicated by the use of (=). Synonyms aid law enforcement officials, importers, exporters, and many others

who routinely use these names by identifying alternative names that may appear in documents and other references.

The species named in these lists were placed there either by the U.S. Fish and Wildlife Service, Department of the Interior, or jointly by that Service and the National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce. References to "Services" in the text of §§ 17.11 and 17.12 refer to those two agencies. The Fish and Wildlife Service maintains the lists through republications and other administrative practices.

No entry to these lists has been added, deleted, or significantly altered by this republication. Such actions must be published as separate documents in the Federal Register.

Minor changes are made in §§ 17.11(d) and 17.12(d) to clarify that some of the data in these lists are provided for the information of the reader and may now be changed without public notice when the annual (October 1) compilation of Title 50 is being done. This procedure will annually save the government several thousand dollars in publication costs in the daily Federal Register by permitting such changes of a nonregulatory nature.

The Service finds for good cause that this document shall be effective upon publication and that notice and public comment are unnecessary. This action is merely a republication of existing, and previously published, requirements. By bringing earlier lists up to date, it will provide more timely guidance to the public. Readers are requested to advise the Service of any errors or omissions, particularly with regard to historic ranges and alternative names in these lists.

Authors

This document was compiled by the staff of the Office of Endangered Species, U.S. Fish and Wildlife Service, Washington, D.C. 20240 (703/235-1575).

List of Subjects in 50 CFR Part 17

Endangered and threatened species.

Dated: July 21, 1983.

J. Craig Potter,

Acting Assistant Secretary for Fish and Wildlife and Parks.

Regulations Promulgation

PART 17—[AMENDED]

Accordingly, the Service amends Part 17 of Title 50 of the Code of Federal Regulations as follows:

1. The authority citation for Part 17 reads as follows:

Authority: Pub. L. 93-205, 87 Stat. 884; Pub. L. 95-632, 92 Stat. 3751; Pub. L. 96-159, 93 Stat. 1241; and Pub. L. 97-304, 96 Stat. 1411 (16 U.S.C. 1531, *et seq.*).

2. Revise Subpart B of 50 CFR Part 17 to read as follows:

Subpart B—Lists

§ 17.11 Endangered and threatened wildlife.

(a) The list in this section contains the names of all species of wildlife which have been determined by the Services to be *Endangered* or *Threatened*. It also contains the names of species of wildlife treated as *Endangered* or *Threatened* because they are sufficiently similar in appearance to *Endangered* or *Threatened* species (see § 17.50 *et seq.*).

(b) The columns entitled "Common Name," "Scientific Name," and "Vertebrate Population Where Endangered or Threatened" define the species of wildlife within the meaning of the Act. Thus, differently classified geographic populations of the same vertebrate subspecies or species shall be identified by their differing geographic boundaries, even though the other two columns are identical. The term "Entire" means that all populations throughout the present range of a vertebrate species are listed. Although common names are included, they cannot be relied upon for identification of any specimen, since they may vary greatly in local usage. The Services shall use the most recently accepted scientific name. In cases in which confusion might arise, a synonym(s) will be provided in parentheses. The Services shall rely to the extent practicable on the *International Code of Zoological Nomenclature*.

(c) In the "Status" column the following symbols are used: "E" for *Endangered*, "T" for *Threatened*, and "E (or T) (S/A)" for similarity of appearance species.

(d) The other data in the list are nonregulatory in nature and are provided for the information of the reader. In the annual revision and compilation of this Title, the following information may be amended without public notice: the spelling of species' names, historical range, footnotes, references to certain other applicable portions of this Title, synonyms, and more current names. In any of these revised entries, neither the species, as defined in paragraph (b) of this section, nor its status may be changed without following the procedures of Part 424 of this Title.

(e) The "Historic Range" indicates the known general distribution of the

species or subspecies as reported in the current scientific literature. The present contribution may be greatly reduced from this historic range. This column does not imply any limitation on the application of the prohibitions in the Act or implementing rules. Such prohibitions apply to all individuals of the species, wherever found.

(f)(1) A footnote to the Federal Register publication(s) listing or reclassifying a species is indicated under the column "When Listed." Footnote numbers to §§ 17.11 and 17.12 are in the same numerical sequence, since plants and animals may be listed in the same Federal Register document. That document, at least since 1973, includes a statement indicating the basis

for the listing, as well as the effective date(s) of said listing.

(2) The "Special Rules" and "Critical Habitat" columns provide a cross reference to other sections in Parts 17, 222, 226, or 227. The term "NA" (not applicable) appearing in either of these two columns indicates that there are no special rules and/or Critical Habitat for that particular species. However, all other appropriate rules in Parts 17, 217-227, and 402 still apply to that species. In addition, there may be other rules in this Title that relate to such wildlife, e.g., port-of-entry requirements. It is not intended that the references in the "Special Rules" column list all the regulations of the two Services which might apply to the species or to the

regulations of other Federal agencies or State or local governments.

(g) The listing of a particular taxon includes all lower taxonomic units. For example, the genus *Hylobates* (gibbons) is listed as Endangered throughout its entire range (China, India, and SE Asia); consequently, all species, subspecies, and populations of that genus are considered listed as Endangered for the purposes of the Act. In 1978 (43 FR 6230-6233) the species *Haliaeetus leucocephalus* (bald eagle) was listed as Threatened in "USA (WA, OR, MN, WI, WI, MI)" rather than its entire population; thus, all individuals of the bald eagle found in those five States are considered listed as Threatened for the purposes of the Act.

(h) The "List of Endangered and Threatened Wildlife" is provided below:

REF. 17

WATER QUALITY MANAGEMENT PLAN
FOR THE
LOWER CUMBERLAND RIVER BASIN

November, 1978

PRODUCED BY
TENNESSEE DEPARTMENT OF PUBLIC HEALTH
DIVISION OF WATER QUALITY CONTROL
309 CAPITOL TOWERS
NASHVILLE, TENNESSEE 37219

Authorization No. 0871 ; 150 copies printed. This document was printed at a cost of 3399.50 , or 22.66 each, to fulfill a requirement of EPA Grant No. P004193010 to the State of Tennessee and Section 208 of the Federal Water Pollution Control Act Amendments of 1972.

Printed by Enviro-Printers, Franklin, Tennessee

TABLE III - 2
Domestic Surface Water Supplies In The Lower Cumberland River Basin

<u>Municipality or Water Company</u>	<u>Water Source</u>	<u>River Mile</u>	<u>Intake Location</u>		<u>Average Daily Use (l)</u>
			<u>Latitude</u>	<u>Longitude</u>	
Woodbury	East Fork Stones River	44.3	35°49'36"	86°04'28"	0.3
Ashland City	Big Marrowbone Creek, Cumberland River	1.1 160.0	36°15'41"	87°03'33"	0.4
Pleasant View Utility District	Sycamore Creek	-	36°19'36"	87°03'30"	0.3
River Road Utility District	Brush Creek Cumberland River	1.1 160.7	36°16'14"	87°03'07"	0.0
South Cheatham Utility District	Harpeth River	36.1	36°06'38"	86°06'48"	0.
Cumberland Utility District	Cumberland River	207.6	36°12'30"	86°38'30"	
Harpeth Valley Utility District	Cumberland River- Cheatham Lake	172.5	36°08'10"	86°55'15"	2.7230
Madison Suburban Utility District	Cumberland River	200.3	36°14'22"	86°12'52"	7.1290
Nashville-Plant No. 1	Cumberland River	193.8	-	-	63.502
Nashville-Plant No. 2	Cumberland River	206.3	-	-	35.000
Old Hickory Utility District	Cumberland River	218.8	36°15'40"	86°38'30"	0.5790
Dickson	Impounded Reservoir	-	36°04'48"	87°24'14"	0.6500
Turnbull Utility District	Turnbull Creek	11.1	36°03'30"	87°12'15"	1.2000
Erin	Cumberland River	108.3	36°25'25"	87°34'33"	0.4131
Clarksville	Cumberland River Big West Fork Creek	132.8 5.5	-	-	9.1710

Adams-Cedar Hill	Red River	34.1	36°05'20"	87°35'55"	0.0960
Greenbrier	Impounded Reservoir	-	-	-	0.2810
Springfield	Sulphur Fork Creek	-	36°31'36"	86°52'54"	-
White House Utility District	Cumberland River- Old Hickory Lake	216.5	36°17'50"	86°38'00"	2.0200
Murfreesboro	East Fork Stones River (Spring)	12.3	-	-	5.3050
Smyrna	Stones River (Percy Priest Reservoir)	-	35°59'55"	86°28'45"	1.7230
Carthage	Cumberland River	309.0	36°14'36"	85°56'45"	0.3710
Dover	Cumberland River	88.8	36°29'27"	37°50'22"	0.1360
Gallatin	Cumberland River	239.1	36°20'25"	86°26'25"	2.3900
Hendersonville Utility District	Drakes Creek Cumberland River	3.7 222.1	36°17'45"	86°37'50"	2.1510
Portland	Impounded Reservoir	-	-	-	0.4330
Westmoreland	Impoundment		36°36'23"	86°29'23"	0.1640
Hartsville	Cumberland River	278.6	36°22'25"	86°10'44"	0.2810
Franklin	Harpeth River	81.5	35°54'30"	86°51'30"	1.9630
Lebanon	Cumberland River	263.0	36°17'57"	86°15'47"	2.718
West Wilson Utility District	Cumberland River	225.6	36°16'32"	86°33'35"	0.8000

Ref 18

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 42
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - SITE MAINTENANCE FORM

* ACTION: _

EPA ID : TND981473515

SITE NAME: KENNON SITE (GENESCO) SOURCE: T * _ _ _ _ _ *

STREET : WILSON PIKE CONG DIST: 06 * _ _ _ _ _ *

CITY : BRENTWOOD ZIP: 37027 * _ _ _ _ _ *

CNTY NAME: WILLIAMSON CNTY CODE : 187 * _ _ _ _ _ *

LATITUDE : 35/57/20.0 LONGITUDE : 086/45/47.0 * _ _ / _ _ / _ _ . _ *

LL-SOURCE: G LL-ACCURACY: * _ _ _ _ _ *

SMSA : 5360 HYDRO UNIT: 05130204 * _ _ _ _ _ *

INVENTORY IND: Y REMEDIAL IND: Y REMOVAL IND: N FED FAC IND: N * _ _ _ _ _ *

NPL IND: N NPL LISTING DATE: NPL DELISTING DATE: * _ _ _ _ _ *

SITE/SPILL IDS: * _ _ _ _ _ *

RPM NAME: SHAVER RPM PHONE: 404-347-2234 * _ _ _ _ _ *

SITE CLASSIFICATION: SITE APPROACH: * _ _ _ _ _ *

DIOXIN TIER: REG FLD1: REG FLD2: * _ _ _ _ _ *

RESP TERM: PENDING () NO FURTHER ACTION () * PENDING (_) NO FURTHER ACTION (_) *

ENF DISP: NO VIABLE RESP PARTY () VOLUNTARY RESPONSE () * _ _ _ _ _ *

ENFORCED RESPONSE () COST RECOVERY () * _ _ _ _ _ *

SITE DESCRIPTION:

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 43
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - PROGRAM MAINTENANCE FORM

SITE: KENNON SITE (GENESCO)

EPA ID: TND981473515 PROGRAM CODE: H01 PROGRAM TYPE:

PROGRAM QUALIFIER: ALIAS LINK :

PROGRAM NAME: SITE EVALUATION

DESCRIPTION:

* ACTION: _

*

*

*

*

*

*

*

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 44
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - EVENT MAINTENANCE FORM

SITE: KENNON SITE (GENESCO)
PROGRAM: SITE EVALUATION

EPA ID: TND981473515 PROGRAM CODE: H01

EVENT TYPE: DS1

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: E

EVENT NAME: DISCOVERY

STATUS:

DESCRIPTION:

* ACTION: _

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

ORIGINAL

CURRENT

ACTUAL

START:

START:

START:

* _/_/_ _/_/_ _/_/_ *

COMP :

COMP :

COMP : 02/28/86

* _/_/_ _/_/_ _/_/_ *

HQ COMMENT:

* _ _ _ _ _ *

RG COMMENT:

* _ _ _ _ _ *

COOP AGR #

AMENDMENT #

STATUS

STATE %

0

* _ _ _ _ _ *

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 45
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - EVENT MAINTENANCE FORM

SITE: KENNON SITE (GENESCO)
PROGRAM: SITE EVALUATION

EPA ID: TND981473515 PROGRAM CODE: H01

EVENT TYPE: PA1

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: S

EVENT NAME: PRELIMINARY ASSESSMENT

STATUS:

DESCRIPTION:

* ACTION: _

* _ _ _ *

* _ _ _ *

* _ _ _ *

* _ _ _ *

* _ _ _ *

* _ _ _ *

ORIGINAL

CURRENT

ACTUAL

START:

START:

START: 06/13/86

* _/_/_ _/_/_ _/_/_ *

COMP :

COMP :

COMP : 06/13/86

* _/_/_ _/_/_ _/_/_ *

HQ COMMENT:

* _ _ _ *

RG COMMENT:

* _ _ _ *

COOP AGR #

AMENDMENT #

STATUS

STATE %

0

* _ _ _ *

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 46
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - EVENT MAINTENANCE FORM

SITE: KENNON SITE (GENESCO)
PROGRAM: SITE EVALUATION

EPA ID: TND981473515 PROGRAM CODE: H01

EVENT TYPE: SI1

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: S

EVENT NAME: SITE INSPECTION

STATUS:

DESCRIPTION:

* ACTION: _

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

ORIGINAL

CURRENT

ACTUAL

START:

START:

START:

* _/_/_ _/_/_ _/_/_ *

COMP :

COMP :

COMP : 03/29/87

* _/_/_ _/_/_ _/_/_ *

HQ COMMENT:

* _ _ _ _ _ *

RG COMMENT:

* _ _ _ _ _ *

COOP AGR #

AMENDMENT #

STATUS

STATE %

0

* _ _ _ _ _ *

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 48
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - COMMENT MAINTENANCE FORM

SITE: KENNON SITE (GENESCO)

EPA ID: TND981473515

COM
NO COMMENT

ACTION

013 BOTTLED WATER AND A PUBLIC WATER SU
PPLY IS ABOUT TO BE CONTRUCTED TO T
014 HEM AT GENESCO'S EXPENSE.

*	—	_____	*
*		_____	*
*	—	_____	*
*		_____	*

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 49
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - REGIONAL UTILITY MAINTENANCE FORM

SITE: KENNON SITE (GENESCO)

EPA ID: TND981473515

REG CODE: HSCH-01

DESCRIPTION: HEAVY METALS

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

*

*

* _/_/_

* _/_/_

* _/_/_

* _

*

REG CODE: HSCS-01

DESCRIPTION: SOLVENTS

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

*

*

* _/_/_

* _/_/_

* _/_/_

* _

*

REG CODE: HSC1-01

DESCRIPTION: ORGANICS

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

*

*

* _/_/_

* _/_/_

* _/_/_

* _

*

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 50
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - REGIONAL UTILITY MAINTENANCE FORM

SITE: KENNON SITE (GENESCO)

EPA ID: TND981473515

REG CODE: HTDO-01

DESCRIPTION: DRINKING WATER CONTAMINATION OBSERVED

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

*

*

* _/_/_

* _/_/_

* _/_/_

* _

*

REG CODE: HTGO-01

DESCRIPTION: GROUND WATER CONTAMINATION OBSERVED

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

*

*

* _/_/_

* _/_/_

* _/_/_

* _

*

REG CODE: OPD4-01

DESCRIPTION: PIT

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

*

*

* _/_/_

* _/_/_

* _/_/_

* _

*

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 51
RUN DATE: 04/29/87
RUN TIME: 13:14:37

M.2 - REGIONAL UTILITY MAINTENANCE FORM

SITE: KENNON SITE (GENESCO)

EPA ID: TND981473515

REG CODE: 4C85-01

DESCRIPTION: CERCLA FY85 COOP. AG., PA

DATE1:

DATE2:

DATE3:

FREE FIELD:

* ACTION: _

*

*

* _/_/_

* _/_/_

* _/_/_

*

*

REG CODE: 4PHR-01

DESCRIPTION: PRELIMINARY HAZARD RANKING

DATE1:

DATE2:

DATE3:

FREE FIELD: 29.19

* ACTION: _

*

*

* _/_/_

* _/_/_

* _/_/_

*

*

*

*

*

*

*

*

*

*

*

*

*

*



Rec'd
6/13/86

TENNESSEE DEPARTMENT OF HEALTH AND ENVIRONMENT
CUSTOMS HOUSE
701 BROADWAY
NASHVILLE, TENNESSEE 37219-5403

June 10, 1986

Mr. Joel Veater, Project Director
Site Screening and Investigations Unit
CERCLA 104 Program
Region IV, U.S. Environmental Protection Agency
345 Courtland Street
Atlanta, GA 30365


Dear Mr. Veater:

As requested by your office I am enclosing the completed Preliminary Assessment for the Kennon (Genesco) Site, Brentwood, Tennessee.

Because of the nature of this site it was necessary for us to proceed expeditiously under our State program. We have issued a Commissioner's Order and the Remedial Investigation is well underway.

If the enclosed is not complete, please advise.

Sincerely,


James C. Ault, Director
Division of Superfund

JCA/ah/SPF-ddl

Enclosure

KENNON SITE (GENESCO)

On May 21, 1985 the Tennessee Department of Health & Environment Superfund Section was informed of a potential chemical waste site once used by a division of Genesco, Inc. (General Adhesives). The site is located on a farm in rural Williamson County owned by Emmett N. Kennon. From the date of this first notification, responsible parties have cooperated fully. Genesco has hired a professional consultant firm to do a complete Remedial Investigation/Feasibility Study (to date this has included 30 on site monitoring wells, a geophysical study with both electromagnetic and ground penetrating radar and test pits on site to determine the extent and nature of the dumping).

The Remedial Investigation/Feasibility Study and all other work at the site is being performed in an accelerated manner by the responsible parties. State efforts have concentrated on determining the extent of off site migration of contaminants and supervising on site work by the responsible parties. A Commissioners Order has been issued by the State of Tennessee to insure that adequate, timely, and appropriate actions be initiated to address any environmental and health concerns that may arise due to this site.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

IDENTIFICATION
01 STATE TN 02 SITE NUMBER

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or historical name of site)

Kennon Site (Genesco)

02 STREET, ROUTE NO. OR SPECIFIC LOCATION IDENTIFIER

Wilson Pike

03 CITY

Brentwood

04 STATE

TN

05 ZIP CODE

37027

06 COUNTY

Williamson

07 COUNTY CODE

187

08 CONG DIST

06

09 COORDINATES LATITUDE

35° 57' 20"

LONGITUDE

86° 45' 47"

10 DIRECTIONS TO SITE (Starting from nearest public road)

Take I-65 South from Nashville to Moore's Lane exit, turn left on Moore's Lane and follow it to Wilson Pike intersection. Turn right on Wilson Pike and go approx. 1½ mi. until you go under a railroad overpass. Entrance to site is about 30 yds. on left after

III. RESPONSIBLE PARTIES railroad overpass - steel gate at entrance.

01 OWNER (if known)

Emmett Kennon

02 STREET (Business, mailing, residential)

2934 Sidco Drive

03 CITY

Nashville

04 STATE

TN

05 ZIP CODE

37216

06 TELEPHONE NUMBER

(615) 242-1667

07 OPERATOR (if known and different from owner)

Same

08 STREET (Business, mailing, residential)

Same

09 CITY

Same

10 STATE

Same

11 ZIP CODE

Same

12 TELEPHONE NUMBER

() Same

13 TYPE OF OWNERSHIP (Check one)

☒ A. PRIVATE ☐ B. FEDERAL:

(Agency name)

☐ C. STATE

☐ D. COUNTY

☐ E. MUNICIPAL

☐ F. OTHER:

(Specify)

☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)

☐ A. RCRA 3001 DATE RECEIVED:

MONTH DAY YEAR

☒ B. UNCONTROLLED WASTE SITE (RCRA 103 c)

DATE RECEIVED: 5/21/85

☐ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON-SITE INSPECTION

☒ YES

DATE

7/2/85

☐ NO

MONTH DAY YEAR

BY (Check all that apply)

☐ A. EPA

☐ B. EPA CONTRACTOR

☒ C. STATE

☐ D. OTHER CONTRACTOR

☐ E. LOCAL HEALTH OFFICIAL

☐ F. OTHER:

(Specify)

1-22-86

CONTRACTOR NAME(S):

02 SITE STATUS (Check one)

☐ A. ACTIVE

☒ B. INACTIVE

☐ C. UNKNOWN

03 YEARS OF OPERATION

1976

1976

UNKNOWN

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

Approximately 800 55 gallon barrels of waste materials from General Adhesives, a division of Genesco Inc., waste on site is volatile organics, heavy metals, and base-neutral extractable organics.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

Waste was disposed of in abandoned phosphate pits and earthen trenches. Site is covered and migration at this time would be through groundwater. There are wells and springs in the area. There is not any potential of fire, explosion, air or direct contact while the site is covered.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If higher or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents)

☒ A. HIGH

(Inspection required promptly)

☐ B. MEDIUM

(Inspection required)

☐ C. LOW

(Inspection on time available basis)

☐ D. NONE

(No further action needed, complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT

James C. Ault

02 OF (Agency, Organization)

Director - Division of Superfund

03 TELEPHONE NUMBER

(615) 741-3424

04 PERSON RESPONSIBLE FOR ASSESSMENT

James C. Ault

05 AGENCY

State

06 ORGANIZATION

TDH&E Div. of Superfund

07 TELEPHONE NUMBER

(615) 741-3424

08 DATE

5/20/86



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 2 - WASTE INFORMATION

IDENTIFICATION
01 STATE 02 SITE NUMBER
TN

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES (check all that apply) <input checked="" type="checkbox"/> A SOLID <input checked="" type="checkbox"/> B POWDER FINES <input type="checkbox"/> C SLUDGE <input type="checkbox"/> D OTHER (Specify) _____ <input type="checkbox"/> E SLURRY <input checked="" type="checkbox"/> F LIQUID <input type="checkbox"/> G GAS	02 WASTE QUANTITY AT SITE (Measures of waste quantities must be independent) TONS _____ CUBIC YARDS _____ NO OF DRUMS approx. 800 55 gal.	03 WASTE CHARACTERISTICS (check all that apply) <input checked="" type="checkbox"/> A TOXIC <input type="checkbox"/> B CORROSIVE <input type="checkbox"/> C RADIOACTIVE <input checked="" type="checkbox"/> D PERSISTENT <input checked="" type="checkbox"/> E SOLUBLE <input type="checkbox"/> F INFECTIOUS <input type="checkbox"/> G FLAMMABLE <input checked="" type="checkbox"/> H IGNITABLE <input checked="" type="checkbox"/> I HIGHLY VOLATILE <input type="checkbox"/> J EXPLOSIVE <input type="checkbox"/> K REACTIVE <input type="checkbox"/> L INCOMPATIBLE <input type="checkbox"/> M NOT APPLICABLE
--	---	---

III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE	X		800 55 gal. drums of mixed waste mostly organic solvents
CLW	OILY WASTE			
SOL	SOLVENTS	X		
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
	Arsenic		soil	18	ppm
	toluene		soil	6200	ppm
	1,1,1 - trichlorethane		soil	160	ppm
	trichloroethane		soil	6.9	ppm
	Bis (2-ethylhexyl) phthalate		trenches	940	ppm
	lead		soil	7.6	ppm
	chromium		soil	14	ppm
	naphthalene		trenches	110	ppm
	1,2 - dichlorethane		soil	11.11	ppm
	ethyl benzene		soil	19.19	ppm
	tetrachloroethane		soil	220	ppm

V. FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Letter from the Genesco Company, Inc. (5/21/85) informing state of the site. On site inspection and investigation by state personnel.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A GROUNDWATER CONTAMINATION 1 to 100 02 ☐ OBSERVED (DATE 1-22-86) 03 ☐ POTENTIAL ☒ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: a 3 mile radius 04 NARRATIVE DESCRIPTION

Initial sampling of groundwater has indicated that 2 wells and 1 spring are contaminated. Sampling is still on going.

01 ☒ B SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE:) 03 ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

None- Sampling in the area has not shown any contaminants migrating off site by way of surface water.

01 ☒ C CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE:) 03 ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

None - Site is covered with soil at this time.

01 ☒ D FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE:) 03 ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

None - Site is covered with soil at this time.

01 ☒ E DIRECT CONTACT 02 ☐ OBSERVED (DATE:) 03 ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

None - Site is covered with soil at this time.

01 ☒ F CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE:) ☒ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: (Acres) 04 NARRATIVE DESCRIPTION

There is a potential for migration off site to contaminate soil in the surrounding area due to position on landscape.

01 ☒ G DRINKING WATER CONTAMINATION 1 to 100 02 ☐ OBSERVED (DATE: 1-22-86) 03 ☐ POTENTIAL ☒ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 3 mile radius 04 NARRATIVE DESCRIPTION

Groundwater in this area was being used for drinking water. People in the area are on bottled water and public water lines are under construction.

01 ☐ H WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE:) 03 ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

Not Applicable

01 ☒ POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE:) 03 ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

None - Site is covered with soil at this time.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES
(Spills/runoffs/standing liquids/leaking drums)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____

04 NARRATIVE DESCRIPTION

None

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

None

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☒ ALLEGED

Dumping occurred in 1978 without state approval.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

None

III. TOTAL POPULATION POTENTIALLY AFFECTED: 1 - 100

IV. COMMENTS

A full site investigation is on going. An alternate drinking water source has been supplied. A State Commissioners Order has been issued and is being implemented.

V. SOURCES OF INFORMATION (Cite specific references e.g., state files, sample analysis, reports)

State files, Reports from Responsible parties and their contractor, Site Investigations and interviews with residents.

37.04
53 AC.

37
165.5 AC
140.5 AC

06
AC

3703
489 AC.

3701
3527 AC.

38
112.5 AC.

"KENNON PROPERTY"

APPROXIMATE LOCATIONS
OF BUILDING SITES

REVISED 8-1-85

3904
501 AC.

3905
502 AC.

42
34.3 AC

42.0
12 AC

40.0
8.94 AC

42.02
15 AC

42.04
42.05

42.06
1026 AC

42.07
2034 AC

CT-22-36

416

67

91

DIST

15


515

19

18

17

16



POOR LEGIBILITY

**PORTIONS OF THIS DOCUMENT
MAY BE UNREADABLE, DUE TO
THE QUALITY OF THE
ORIGINAL**

STATE OF TENNESSEE
DEPARTMENT OF HEALTH AND ENVIRONMENT

IN THE MATTER OF:)	
)	
GENESCO INC.)	DIVISION OF SUPERFUND
EMMETT N. KENNON)	
AND)	
ROSE S. KENNON)	NO. 86-2013
)	
RESPONDENTS)	

COMMISSIONER'S ORDER

Comes now, James E. Word, Commissioner of the Tennessee Department of Health and Environment, and states that:

PARTIES

I.

James E. Word is the duly appointed Commissioner of the Tennessee Department of Health and Environment (the "Department").

II.

Respondent, Genesco Inc., is a domestic corporation qualified to do business in Tennessee. Its agent for service of process is W. C. O'Connor whose mailing address is Genesco Park, Nashville, TN 37202.

III.

Respondents, Emmett N. Kennon, and wife, Rose S. Kennon are husband and wife and both are residents of the state of Tennessee. Their mailing address is 2934 Sidco Drive, Nashville, TN 37204.

JURISDICTION

IV.

Pursuant to T.C.A. Section 68-46-206, the Commissioner is authorized to issue an order to any liable party requiring such party to investigate, identify, contain, and clean-up, including monitoring and maintenance, inactive hazardous substance sites which pose or may pose a danger to public health, safety or the environment because of the release or threatened release of hazardous substances. Pursuant to T.C.A. Section 68-46-215 the Commissioner may issue an Order for correction to the appropriate person, who will then comply with the Order within the time limit specified in the Order.

V.

Respondents are "persons" within the meaning of T.C.A. Section 68-46-104 and each is also a "liable party" within the meaning of T.C.A. Section 68-46-202.

FACTS

VI.

Respondent, Genesco Inc. (hereinafter "Genesco"), is a Tennessee corporation with its executive offices located at Genesco Park, Nashville, TN. Genesco operates in two major industry segments which are footwear and men's apparel. It employs approximately 3,900 persons in Tennessee.

VII.

General Adhesives, formerly known as General Adhesives and Chemical Company, is a division of Genesco Inc. which operates a manufacturing plant at 6100 Centennial Boulevard in Nashville, TN. It manufactures and sells specialty industrial and consumer products which includes adhesives, sealants, and coatings utilizing solvent-based thermoplastic and water-based technologies. It is a hazardous waste generator utilizing the EPA installation identification number TND 001981240. It is a permitted hazardous waste transporter utilizing the EPA installation identification number TND 001367549.

VIII.

Emmett N. Kennon and Rose S. Kennon are owners of certain property described herein. They have owned the property since at least 1976. A portion of said property was used for a period of time in approximately 1978 for the disposal of certain hazardous substances. To the knowledge of the Department it has not been operated as a disposal site since that time and, therefore, said property is an inactive hazardous substance disposal site, (hereinafter, the "site").

IX.

The site is within a 146.8 acre tract located along Wilson Pike in Williamson County, Tennessee, and all of said tract is located within the city limits of Brentwood, Tennessee. The site is approximately two (2) acres.

X.

The site was operated by Respondents, Kennons, as a disposal site for construction waste and for certain other waste described herein which were hazardous substances. At least one or more of the trenches used in the disposal operation were already in existence from the excavation for phosphate mining.

XI.

Genesco notified the Department on or about August 19, 1981 that it was a generator of hazardous waste. It reported that it generated hazardous waste which were described as being "waste, cement and solvents, N.O.S.". The waste was further described as being ignitable (as described in Division rule 1200-1-11-02 promulgated under the Hazardous Waste Management Act). The waste was reported to be generated at an average rate of 7,400 kilograms per month. The major compounds of the waste were described as being acetone, hexane, toluene, methyl ethyl ketone, and 1, 1, 1 trichloroethylene.

XII.

On or about May 21, 1985 Genesco reported in a letter to the Department, that during the summer and/or fall of 1978, General Adhesives had disposed of approximately eight hundred (800) 55 gallon barrels of waste material in a rural area of Williamson County, Tennessee". The rural disposal area is now known to be the property of Respondents Emmett N. Kennon and Rose S. Kennon. To the knowledge and belief of the Department, the waste was transported to the site by Respondent Genesco and/or by Respondents Kennon.

XIII.

In the same letter referenced above, it was stated that approximately 50 to 80 barrels were buried and the remainder of the waste was poured from the barrels into earthen trenches at the site.

XIV.

It was further stated in the same letter, that the exact amount and contents of the waste material were unknown; however, Genesco believed that the waste contained water-based adhesives and may have contained acetone, ethyl acetone, hexane, methylene chloride, methyl ethyl ketone, rubber solvent, toluene, 1, 1, 1 - trichloroethane, trichloroethylene, and organic fillers.

XV.

On or about August 9, 1985 Genesco submitted a plan of investigation of the site to the Department. The plan was revised according to Department comments and resubmitted on September 25, 1985. The plan was approved by the Department on or about October 2, 1985. Genesco then began to investigate the extent of any environmental impact including the sampling of waste, soil, and water in and around the site. Water samples included samples of leachate at the site, springs, a seep, and water wells in the vicinity.

XVI.

Laboratory analysis of certain samples reveal the presence of hazardous substances including, but not limited to: arsenic, lead, chromium, trans-1, 2-dichloroethene, 1,1,1 trichloroethane, 1, 1-dichloroethane, 1, 2-dichloroethane, toluene, bis (2-ethyl hexyl) phthalate, naphthalene, ethylbenzene and trichloroethane. The location of a spring and a seep and the laboratory analysis of the same indicate that the contaminants are migrating from the site. The exact analysis results and sampling locations are listed in Tables A, B, C and D of this Order.

TABLE A
 Samples Collected January 28, 1986 by Department Staff
 at an On-Site Seep Approximately 500 feet Southeast
 of the Site

<u>Hazardous Substance</u>	<u>Level of Contamination</u>	<u>Type of Sample</u>
Arsenic	.217 ppm	water
Arsenic	18.0 ppm	soil
Lead	.12 ppm	water
Lead	7.6 ppm	soil
Chromium	.15 ppm	water
Chromium	9.3 ppm	soil

TABLE B
 Samples Collected February 7, 1986 by Department Staff
 at an Off-Site Spring (Hackett Spring)
 Approximately 1200 Feet Southeast
 of the Site

<u>Hazardous Substances</u>	<u>Level of Contamination</u>	<u>Type of Sample</u>
Trans -1, 2-dichloroethene	.07 ppm	water
1, 1, 1 trichloroethane	.013 ppm	water
1, 1-dichloroethane	.026 ppm	water

TABLE C
Sample Collected January 22, 1986 by Department
Staff at Pit A from the Disposal Site

<u>Hazardous Substance</u>	<u>Level of Contamination</u>	<u>Type of Sample</u>
Arsenic	9 ppm	soil
Chromium	14 ppm	soil
Lead	8 ppm	soil
1, 1-dichloroethane	4.3 ppm	soil
1, 2-dichloroethane	1.2 ppm	soil
Trans -1, 2-dichloroethane	3.3 ppm	soil
Toluene	120 ppm	soil
1, 1, 1-trichloroethane	2.2 ppm	soil

TABLE D
Samples Collected January 22, 1986 by Department
Staff from PIT B from the Disposal Site

<u>Hazardous Substance</u>	<u>Level of Contamination</u>	<u>Type of Sample</u>
Chromium	14 ppm	waste
Bis (2-ethyl hexyl) phthalate	940 ppm	waste
Naphthalene	110 ppm	waste
Chromium	14 ppm	soil
1, 2-dichlorethane	11.11 ppm	soil
Ethyl benzene	19.19 ppm	soil
Tetrachloroethene	220 ppm	soil
Toluene	6,200 ppm	soil
1, 1, 1-trichloroethane	160 ppm	soil
Trichloroethane	6.9 ppm	soil

XVII.

Based on the laboratory analysis and the location of these samples, it is the opinion of the Department that hazardous substances have been disposed of at the site, migrated from the site, and that the substances have contaminated ground water. Immediate remedial measures are necessary and appropriate because of potential harm to the public health and environment.

CLAIMS FOR RELIEF

XVIII.

By owning and operating a hazardous substance disposal site and by being the generator of the hazardous substances who at the time of disposal caused such substance to be disposed at the site, each of the Respondents is a "liable party" as defined at T.C.A. Section 68-46-202 which is defined as:

- "(a) The owner or operator of an inactive hazardous substance site;
- (b) Any person who at the time of disposal was the owner or operator of an inactive hazardous substance site;
- (c) Any generator of hazardous substance who at the time of disposal caused such substance to be disposed of at an inactive hazardous substance site; or
- (d) Any transporter of hazardous substances which is disposed of at an inactive hazardous substance site who, at the time of disposal, selected the site of disposal of such substances."

This site is an inactive hazardous substance site within the meaning of T.C.A. Section 68-46-202 which is defined as "any site or area where hazardous substance disposal has occurred."

XIX.

PREMISES CONSIDERED, I, James E. Word, hereby ORDER the Respondents to comply with the following:

- A. The Respondents shall conduct certain IMMEDIATE REMEDIAL MEASURES which must include the following:

1. The Respondents must submit a plan to the Department within fifteen (15) days of the receipt of this Order describing how the Respondents will provide a permanent adequate, and potable water source for human consumption and household use to the residents potentially impacted by the site. Until such time as a permanent water supply is provided, the Respondents shall supply adequate drinking water to those persons in the vicinity of the site that they are presently supplying and others deemed appropriate by the Department.
2. The Respondents will define the potentially impacted area within the above referenced plan and said plan will include a proposed chronology of activities and a schedule for the completion of activities. The plan will describe how the Respondents will provide and install said water source including any agreements with public utility districts. The plan will further include a well water monitoring program for sampling and testing specified existing wells outside the perimeter of the "potentially impacted area."
3. The Respondents will submit a separate plan to the Department within thirty (30) days of the receipt of this Order which will describe how the Respondents will control the source of release of the contaminants to prevent migration of the same. Said plan will define the scope of the source and provide a proposal of activities for immediate remedial measures and a schedule for completion of said activities. The Respondent will implement the plan upon the approval and notice to proceed of the Department.
4. The Department will review said plans and may require revisions as deemed necessary. Respondents shall implement all immediate remedial action plans as they are approved by the Department.

B. INITIAL ASSESSMENT

1. Within sixty (60) days of receipt of this Order, the Respondents shall submit to the Department any existing data available to the

Respondents which is pertinent to the assessment of the hazard that the specified site may pose to public health and the environment. This information shall include available data listed in paragraph XIX C2 of this Order and shall be submitted in duplicate.

2. Following receipt of this information, the Department will schedule an initial assessment conference which the Respondents shall attend in the Nashville Office of the Department, Division of Superfund. The Respondents shall be given seven (7) days notice prior to this meeting. The purpose of this conference will be to discuss existing data and determine the need for further investigation, remedial action and/or long term monitoring and maintenance. A schedule for future activities, deemed necessary by the Department, shall be established at this conference. Depending on existing data, the Department may determine that no further action is necessary. In all other cases, the schedule established in this conference will provide the dates by which the activities enumerated herein must be completed.

C. INVESTIGATION PROGRAM

1. According to the schedule established in the initial assessment conference, the Respondents shall submit to the Department a proposed Investigation Plan.
2. In order to provide an accurate assessment of the hazard posed by the site to public health and the environment and to develop design data for remedial action, the Investigation Plan shall include, but not be limited to, assessment of the following factors:
 - a. Types and quantities of hazardous substances disposed at the site.
 - b. Physical state, analytical summary, toxicological characteristics and other pertinent data defining hazardous substances present at the site.

- c. Methods and extent of the disposal operation including containment methods used, plans and/or photographs of site operation, perimeter and depth of disposal area, and type of disposal operation conducted (open burning, trench, surface impoundment, etc.).
- d. Observed release of contaminants to ground water, surface water or air, including sampling, to determine contaminant concentrations and extent of contaminant migration.
- e. Hydrogeologic factors to determine depth to groundwater, permeability of the unsaturated zone, distance to nearest surface water and slope of the disposal area and intervening terrain.
- f. Population and environment potentially affected:
 - (1.) Ground water use and population served by ground water sources within a three (3) mile radius of the perimeter of contaminant migration.
 - (2.) Surface water use and population served within a three (3) mile reach downstream of the perimeter of contaminant migration.
 - (3.) Population potentially affected by contaminant releases to the air within a four (4) mile radius of the perimeter of contaminant migration.
 - (4.) Distance from the site to sensitive environments such as a natural wetland, critical habitat for an endangered species or a National Wildlife Refuge.
- g. Fire and explosion hazard assessment of the site.
- h. Direct contact hazard assessment of the site.

3. The Investigation Plan must include cost estimates and a proposed schedule for completion of activities involved in the investigation. Following a review of the Plan, the Department may schedule a meeting which Respondents shall attend to discuss any revisions required by the Department. The Respondents will be given seven (7) days notice prior to the meeting. On or before a deadline date established in this review meeting, a revised Investigation Plan shall be submitted by the Respondents to the Department. Upon approval by the Department of the revised Investigation Plan, the Respondents shall begin required activities according to the revised Investigation Plan.

D. REMEDIAL ACTION SELECTION AND IMPLEMENTATION

1. Following completion of the investigation activities, a report providing an assessment of the hazard posed by the site to public health and the environment and proposing remedial action alternatives shall be submitted by the Respondents to the Department according to the Investigation Plan schedule. One of the alternatives that shall be addressed in the report shall be the removal of the source of contamination. This report will be referred to as a Hazard Evaluation/Remedial Action report (herein after referred to as "HE/RA"). Remedial action alternatives must include cost estimates and proposed schedules for completion of activities involved in remedial action implementation.
2. Assessment of each remedial action alternative must include consideration of the following factors:
 - a. The technological feasibility of each alternative;
 - b. The cost-effectiveness of each alternative;
 - c. The nature of the danger to the public health, safety, and the environment posed by the hazardous substances at the site; and


- d. The extent to which each alternative would achieve the goal of T.C.A. Section 68-46-206(d) which states, in part, "... The goal of any such action shall be cleanup and containment of the site through the elimination of the threat to public health, safety and the environment posed by the hazardous substance."
3. Following the Department's review of the HE/RA Report, the Department may schedule a meeting which the Respondents shall attend, to discuss any revisions required by the Department. The Respondents will be given seven (7) days notice prior to the meeting. On or before a deadline date established in this review meeting, a final HE/RA Report shall be submitted to the Department. Upon receipt of approval by the Department of the final HE/RA Report, the Respondents shall begin activities required by the final HE/RA Report, unless the Department determines no further action is necessary.
4. The HE/RA activities shall not be considered complete until the Department has reviewed these activities and issued a letter of acceptance to the Respondents.

E. SITE MONITORING AND MAINTENANCE

1. Where the Department determines a need for site monitoring and maintenance, the Respondents shall provide a Site Monitoring and Maintenance Plan (herein after referred to as "M/M Plan") which shall include a proposed schedule for completion of required activities and cost estimates within ninety (90) days of receipt of a request for said Plan by the Department.
2. Within forty-five (45) days of receipt of this M/M Plan by the Department, the Respondents shall attend a meeting with the Department to discuss any required revisions. On or before a deadline established in this review meeting, a revised M/M Plan shall be submitted by the Respondents to the Department. Upon receipt of approval by the Department, the revised M/M Plan will go into effect.

- F. To the extent practicable, any investigation, identification, containment and clean-up, including monitoring and maintenance, shall be consistent with the national contingency plan promulgated pursuant to Section 105 of Public Law 96-510.
- G. Certain activities may be deemed critical by the Department and shall require observation by the Department. The Respondents shall provide sufficient notice to the Department to allow scheduling of personnel for these activities. The Department also reserves the right to observe any other activities required pursuant to this Order.
- H. Any failure to comply with approved schedules of activities required under this Order shall be a failure to comply with this Order.
- I. In this Order, any reference to the singular includes the plural.
- J. Further, I, James E. Word, do not waive any rights or authority available to me to assess the Respondents for liability for costs, expenditures, civil penalties or damages incurred by the State pursuant to this Order. I also reserve the right to order such further remedial action to be completed by the Respondents where it is determined that further remedial action is needed.

Issued in this office of the Commissioner of the Tennessee Department of Health and Environment this 5th day of March, 1986.



JAMES E. WORD, Commissioner
Tennessee Department of Health
and Environment

NOTICE OF RIGHTS

Respondents are hereby advised that in accordance with T.C.A. Section 68-46-215 they may secure a review of the necessity for or reasonableness of this Order by filing with the Commissioner, a written petition setting forth the grounds and reasons for objection and asking for a hearing in the matter involved before the Solid Waste Disposal Control Board. The Order shall become final and not subject to review unless the person or persons named herein shall file such petition for a

hearing no later than thirty (30) days after the date such Order is secured.
Hearings will be conducted in accordance with the Tennessee Uniform
Administrative Procedures Act.

Correspondence regarding this Order should be addressed to Mary E. Johnston,
TERRA Bldg. 6th Floor, Assistant General Counsel, 150 Ninth Avenue, North,
Nashville, Tennessee 37203 or telephone (615)741-0657.


Mary E. Johnston
Assistant General Counsel

MEJ/djv
SWM Order - Genesco

SITE DISCOVERY FORM

Joel - What is the status of this?
Be

Part 1: Information necessary to add a site to CERCLIS

ACTION: A

EPA ID: 777

SITE NAME: General Adhesives

STREET: Wilkes Pike COI

CITY: Brentwood ZII

CNTY NAME: Williamson CNT

LATITUDE: / / LONGITUDE:

INVENTORY IND: Y REMEDIAL IND: Y REMOVAL

RPM NAME: Joe Young RPM PHONE:

SITE DESCRIPTION: (optional)

- Dichloromethane, trichloroethylene and other chemicals are buried in about 2 or 3 covered trenches in pastureland owned by a Emmett Kennon. This is over about a 2-acre area.
- Wastes are from General adhesives, Nashville, Tenn. - a division of Genesco, Inc. Nashville. Genesco is willing to clean up the site. The site is now being investigated by a contractor for Genesco and TN superfund.

Part 2: Other site information

DATE SITE FIRST

REPORTED: 02/28/84

REPORTED BY: Mike Norman, EPA

REASON FOR LISTING:

- Two family drinking wells and a spring in the area are known to be contaminated. The families are being furnished bottled water, and a public water supply is about to be constructed to them at Genesco's expense.

To: See file - General Adhesiver,
Brentwood, Tenn. 5/15/86

From Joe Young

- Michael Norman of Emerg Response, EPA heard about the site when he received an informal inquiry via EPA Congressional of Public Affairs from Tenn. Congressman Bill Bonner (Brier). ~~Mr. Norman~~ ~~then called the state of Tenn.~~ ~~Long.~~ Bonner wanted to know what EPA knew about the site and/or what involvement EPA had with it. This inquiry was on or about 2/28/86.
- See attached Norman memo of 2/28/86.
- Joe Young of CERCLA site screening called Bill Forester of Tenn. CERCLA about the site on or about 5/13/86. He said I should call James Ault of Tenn. Superfund for information.

I called Mr. Ault on 5/14/86. See the information on site ~~of~~ discovery

form. He gave other information as follows:

- Emmett Kennon owns the site property. His mailing address is: 2934 Cidero Drive, Nashville, Tenn. 37204.
- W. C. Conner is Genesco's attorney. Ralph Moseley is their environmental person.
- U S G S is going to do a groundwater investigation of that site.
- Genesco's address is 6 Genesco Park, Nashville, Tenn. 37202
- General Adhesives is still in business. Their address is 6100 Centennial Blvd., Nashville, Tenn.
- Genesco of Tenn Superfund's ongoing site invt. includes sampling of the site.

SITE DISCOVERY FORM

Part 1: Information necessary to add a site to CERCLIS

ACTION: A

EPA ID: TN

SITE NAME: General Adhesives

SOURCE: T (R=EPA, T=STATE)

STREET: Wilson Pike

CONG DIST: (optional)

CITY: Brentwood

ZIP: -

CNTY NAME: Williamson

CNTY CODE: (optional)

LATITUDE: / /

LONGITUDE: / / (optional)

INVENTORY IND: Y REMEDIAL IND: Y REMOVAL IND: N FED FAC IND: N

RPM NAME: Joe Young

RPM PHONE: 404 - 347 - 2234 (EPA Project Office)

SITE DESCRIPTION: (optional)

- Dichloroethane, trichloroethylene and other chemicals are buried in about 2 or 3 covered trenches in pastureland owned by a Emmett Kennon. This is over about a 2 acre area.
- Wastes are from General adhesives, Nashville, Tenn. - a division of Genesco, Inc. Nashville. Genesco is willing to clean up the site. The site is now being investigated by a contractor for Genesco and TN superfund.

Part 2: Other site information

DATE SITE FIRST

REPORTED: 02 / 28 / 86

REPORTED BY: Mike Norman, EPA

REASON FOR LISTING:

- Two family drinking wells and a spring in the area are known to be contaminated. The families are being furnished bottled water, and a public water supply is about to be constructed to them at Genesco's expense.

SITE DISCOVERY FORM

Part 1: Information necessary to add a site to CERCLIS

ACTION: A

EPA ID: TND

SITE NAME: General Adhesives SOURCE: T (R=EPA, T=STATE)

STREET: Wilson Pike CONG DIST: (optional)

CITY: Brentwood ZIP: -

CNTY NAME: Williamson CNTY CODE: (optional)

LATITUDE: / / LONGITUDE: / / (optional)

INVENTORY IND: Y REMEDIAL IND: Y REMOVAL IND: N FED FAC IND: N

RPM NAME: Joe Young RPM PHONE: 404 - 347 - 2234 (EPA Project Office)

SITE DESCRIPTION: (optional)

- Dichloroethane, trichloroethylene and other chemicals are buried in about 2 or 3 covered trenches in pastureland owned by a Emmatt Kennon. This is over about a 2 acre area.
- Wastes are from General adhesives, Nashville, Tenn. - a division of Genesco, Inc. Nashville. Genesco is willing to clean up the site. The site is now being investigated by a contractor for Genesco and TN superfund.

Part 2: Other site information

DATE SITE FIRST REPORTED: 02 / 28 / 86 REPORTED BY: Mike Norman, EPA

REASON FOR LISTING:

- Two family drinking wells and a spring in the area are known to be contaminated. The families are being furnished bottled water, and a public water supply is about to be constructed to them at Genesco's expense.

SITE DISCOVERY FORM

Part 1: Information necessary to add a site to CERCLIS

ACTION: A

EPA ID: TND

SITE NAME: General Adhesives SOURCE: T (R=EPA, T=STAT)

STREET: Wilson Pike CONG DIST: (optional)

CITY: Brentwood ZIP: - -

CNTY NAME: Williamson CNTY CODE: (optional)

LATITUDE: / / LONGITUDE: / / (optional)

INVENTORY IND: Y REMEDIAL IND: Y REMOVAL IND: N FED FAC IND: N

RPM NAME: Joe Young RPM PHONE: 404 - 347 - 2234 (EPA Project Office)

SITE DESCRIPTION: (optional)

- Dichloroethane, trichloroethylene and other chemicals are buried in about 2 or 3 covered trenches in pastureland owned by a Emmatt Kennon. This is over about a 2 acre area.
- Wastes are from General adhesives, Nashville, Tenn. - a division of Genesco, Inc. Nashville. Genesco is willing to clean up the site. The site is now being investigated by a contractor for Genesco and TN superfund.

Part 2: Other site information

DATE SITE FIRST

REPORTED: 02 / 28 / 86

REPORTED BY: Mike Norman, EPA

REASON-FOR-LISTING:

- Two family drinking wells and a spring in the area are known to be contaminated. The families are being furnished bottled water, and a public water supply is about to be constructed to them at Genesco's expense.

5/15/86

To: Site file - General Adhesiver,
Brentwood, Tenn.

From Joe Young

- Michael Norman of Emery Response, EPA heard about the site when he received an informal inquiry via EPA Congressman of Public Affairs from Tenn. Congressman Bill Bonner (Brier). ~~Mr. Norman~~ then called the state of ~~Tenn.~~ ~~Mr.~~ Congr. Bonner wanted to know what EPA knew about the site and/or what involvement EPA had with it. This inquiry was on or about 2/28/86.
- See attached Norman memo of 2/28/86.
- Joe Young of CERCLA site screening called Bill Forester of Tenn. CERCLA about the site on or about 5/13/86. He said I should call James Ault of Tenn. Superfund for information.
- I called Mr. Ault on 5/14/86. See the information on site ~~of~~ discovery.

GENESCO
BRENTWOOD, TN

2/28/86

PER CONVERSATION WITH ^{James} M.C. AULT, DIRECTOR
OF THE DIVISION OF SUPERFUND FOR
TENNESSEE [(615) 741-3424] :

- TN IS PREPARING AN ORDER REQUIRING GENESCO TO DO A REMEDIAL INVESTIGATION AND WILL BASE ADDITIONAL REQ'MENTS ON THE FINDINGS OF THAT RI.
- CHEMICALS PRESENT: DICHLOROETHANE
TRICHLOROETHYLENE
AMONG OTHERS
- THERE ARE 2 OR 3 DUMPS OVER A 2-ACRE AREA. THE PLANT OCCUPIES A MUCH LARGER AREA.
- PEOPLE IN THE AREA WHO ARE ON WELLS HAVE BEEN AND ARE BEING SUPPLIED BOTTLED WATER.
- MR. AULT DID NOT KNOW EXACT CONCENTRATIONS; HOWEVER THEY DID NOT SEEM TO BE TREMENDOUSLY HIGH IN THE SOIL (OR GROUNDWATER).

Richard C. Nolan

form, He gave the information as follows:

- Emmett Kemmer owns the site property. His mailing address is: 2934 Cider Drive, Nashville, Tenn. 37204
- W. C. Conner is Genesco's attorney. Ralph Moorely is their environmental person.
- USGS is going to do a groundwater investigation of that site.
- Genesco's address is 6 Genesco Park, Nashville, Tenn. 37202
- General Altheimer is still in business. Their address is 6100 Centennial Blvd., Nashville, Tenn.
- Genesco & Tenn Superfund's ongoing site invt. includes sampling of the site.

(PHOTOGRAPHS)

MEDIA

UNSCANNABLE